

**Final
Site Inspection Prioritization**

**International Harvester Landfill
Memphis, Shelby County, Tennessee
EPA ID N° TND007024516
WasteLAN N° 03631**

Prepared Under:
Contract N° 68-W9-0055

For The:
**U.S. Environmental Protection Agency
Waste Management Division
Region IV**

Prepared By:
**BLACK & VEATCH Waste Science Inc.
BVWS Project N° 52012.145**

August 15, 1994

REC'D


AUG 15 1994

U.S. E.P.A.

Prepared by:


Dane G. Pehrman
Site Manager

Reviewed by:


Bryan J. Williams
Technical Reviewer

Approved by:


Hubert Wieland
Project Manager

Table of Contents

| <u>Section</u> | <u>Page</u> |
|--|-------------|
| 1.0 Introduction | 1 |
| 2.0 Site Location, Description, Operational History, and Waste Characteristics | 1 |
| 2.1 Location | 1 |
| 2.2 Site Description | 3 |
| 2.3 Operational History and Waste Characteristics | 3 |
| 3.0 Groundwater Pathway | 6 |
| 3.1 Hydrogeologic Setting | 6 |
| 3.2 Groundwater Targets | 9 |
| 4.0 Surface Water Pathway | 10 |
| 4.1 Hydrologic Setting | 10 |
| 4.2 Surface Water Targets | 11 |
| 5.0 Soil Exposure and Air Pathways | 11 |
| 5.1 Physical Conditions | 11 |
| 5.2 Soil and Air Targets | 12 |
| 6.0 Summary and Conclusions | 12 |
| 7.0 References | 13 |

List of Tables

| | |
|---|----|
| Table 1. Water Usage in 4 Mile Radius | 10 |
|---|----|

List of Figures

| | <u>Following Page</u> |
|-----------------------------------|-----------------------|
| Figure 1. Site Location Map | 1 |
| Figure 2. Site Layout Map | 3 |

**Site Inspection Prioritization Report
International Harvester Landfill
Memphis, Shelby County, Tennessee
EPA ID N° TND007024516
WasteLAN N° 03631**

1.0 Introduction

B&V Waste Science and Technology Corp. (BVWST) was tasked by the U.S. Environmental Protection Agency (EPA) to perform a Site Inspection Prioritization (SIP) for the International Harvester Landfill Site in Memphis, Shelby County, Tennessee. This study was performed under the authorization of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) and the Superfund Amendment Reauthorization Act of 1986 (SARA).

A Preliminary Assessment was conducted at the International Harvester Landfill Site by the Tennessee Department of Environment and Conservation, Division of Solid Waste Management (TSWM) for the United States Environmental Protection Agency (USEPA). The Preliminary Assessment was performed in May 1987-1984. A Site Inspection was performed by USEPA in July 1980. An off-site investigation was performed by BVWST on July 27, 1993. Additional sources of information used in this evaluation were EPA CERCLA, TSWM, and Tennessee Division of Superfund file material as well as documentation generated via telephone contacts and letters. Agencies contacted were: the United States Environmental Protection Agency (USEPA) Region IV Atlanta Offices, the Tennessee Department of Environment and Conservation, and local utilities. This SIP will quantify threats posed by the site and provide documentation in order for decisions to be made about a future course of action at the site.

2.0 Site Location, Description, Operational History, and Waste Characteristics

2.1 Location. The International Harvester Landfill Site is located southeast of the confluence of the Loosahatchie and Mississippi Rivers at 3003 Harvester Avenue in Memphis, Tennessee at North latitude 35°08'10.6" and West longitude 89°47'50.4" (Ref. 1). The site location is shown in Figure 1. The climate in this area is characterized by relatively mild winters, hot summers, and abundant rainfall (Ref. 2, p. 2). The average annual precipitation is 50 inches (Ref. 3, p. 1). Mean lake pan evaporation in this area is 41 inches (Ref. 3, p. 2), yielding a net annual rainfall of 9 inches. The 2-year, 24-hour rainfall in the area is approximately 4.0 inches (Ref. 4, p. B-4).

DWC# HARVEST.DWG

9-3-93/1100



International Harvester Landfill

Figure 1




WASTE SCIENCE AND TECHNOLOGY CORP.
PHILADELPHIA, PA

Site Inspection Prioritization
International Harvester Landfill
Memphis, Shelby County, Tennessee

2.2 Site Description. The International Harvester Landfill Site is in an heavily developed industrial area at 3003 Harvester Avenue, Memphis, Tennessee (Ref. 5, 6). The former landfill area is inactive and is covered with grasses and some small shrubs. The landfill areas appears to be mowed and well maintained (Ref. 6). There are lightly wooded areas around the base of the landfill, primarily to the south and west. These forested areas and a gravel road, separate the landfill from the Memphis Shelby County Airport, located adjacent to the west and south (Ref. 6). The landfill is east and adjacent to the former International Harvester plant, now occupied by Mastercraft and Center City Float Factory (Ref. 6). The landfill is bounded to the north by Harvester Lane (Ref. 6). Access to the landfill is unrestricted from the north; however, there is thick vegetation that must be traversed to enter the landfill (Ref. 6). Access from the east and south is restricted by a six-foot high, barbed-wire, chain-link fence (Ref. 6). Access from the west is restricted by a three-foot high, wire fence (Ref. 6).

No stressed vegetation was observed during the August 27, 1993 site investigation (Ref. 6). The landfill occupies an irregular-shaped area a maximum of 650 feet wide and 1,300 feet long (Refs. 5; 6), encompassing approximately 10 acres (Ref. 7). A sketch illustrating the site layout is shown in Figure 2.

2.3 Operational History and Waste Characteristics. The International Harvester Landfill Site is an inactive, closed landfill that was used for the deposition of various industrial wastes by International Harvester Corp. (Ref. 7). International Harvester is no longer operating at the site but had produced farm equipment at the facility since 1947 (Ref. 7). Manufacturing processes included casting, shearing, machining, assembly, washing, plating and painting of farm equipment components (Ref. 8). Wastes from these manufacturing operations were placed into the landfill by International Harvester and included: wood, paper, foundry sand, glass, metal scraps, cardboard, household trash, paint and paint sludge, washing machine sludge, oils, greases, coolants, wastewater treatment sludge, spent transformer oil, varnish, sealing compounds, caustics and acids, electroplating treatment sludge, and other miscellaneous industrial solid wastes (Ref. 8). The landfill was operated from 1947 to November 1983, when landfilling was discontinued (Ref. 8). The landfill is currently covered with a cap of 6 inches of clay and an additional 12 inches of clean soil (Ref. 9). Because of the time when landfilling was started at the site (1947) and the fact that there was no removal of contaminants prior to closure (Ref. 9), we have assumed that there is no liner under the landfill. Closure of the landfill was completed by early 1987, when the maintenance and monitoring program began (Ref. 10). During a Tennessee Division of Superfund inspection performed on June 29, 1989, areas of exposed waste and erosion were observed (Ref. 11). The site is presently being evaluated under monitoring and maintenance program.



DWG#HARVEST.DWG

9--3--93/1100

Site Layout Map

Figure 2

The site was originally discovered during a preliminary inspection by USEPA - Region IV personnel in May of 1980 (Ref. 12, p. 1). Wood, pallets, crates, metal, paper, trash, glass, and drums were observed in the landfill (Ref. 12, p. 1). On October 20 and 21, 1980, a site investigation was performed at the site by USEPA - Region IV personnel (Ref. 12, p. 1). During this investigation, four sediment, one soil, and two surface water samples were collected and analyzed from the landfill and surrounding areas (Ref. 12, p. 1). The soil sample (IH-5) was a composite of four samples obtained from the top of the landfill (Ref. 12, Figure 2). Locations of these samples is shown in Figure 2. This soil sample indicated the presence of the following compounds in the landfill above naturally occurring levels in soil: **3,4-benzofluoranthene, chromium, copper, nickel, lead, zinc, manganese, cyanide, and PCBs** (Refs. 12, Table 2; 13).

The sediment and surface water samples were not accompanied by background samples and therefore, could not be used to determine if there was contamination of the surface water pathway.

On March 14, 1984, the Tennessee Department of Health and Environment issued a commissioners order requiring International Harvester Corp. to prepare a Hazard Assessment and a Remedial Action Plan for closure of the landfill at the site (Ref. 8).

Additional sampling of the landfill and surrounding areas was performed by The Pickering Firm, Inc. on June 15, 1984 on behalf of International Harvester (Ref. 14). This sampling included the collection and analysis of three sediment, two water, and two soil samples. The soil sample "D" was a composite of four samples taken at the same general locations as EPA October 1980 sample number IH-5 (Refs. 12; 14). Locations for these samples are shown in Figure 2. The analytical results for the soil sample were generally similar with the EPA sampling results and did not indicate any additional hazardous source constituents in the landfill (Refs. 12; 14).

The monitoring and maintenance program was initiated in 1987 by International Harvester. As part of this program four groundwater monitoring wells were installed into the surficial aquifer. The depth of these four wells is as follows: Well 1, 41.5 feet; Well 2, 24.8 feet; Well 3, 25.0 feet; and Well 4, 25.0 feet (Ref. 10). Well 1 was used to measure background groundwater conditions because it is at a higher groundwater elevation (Ref. 15). The location of these wells is shown in Figure 2. Tennessee Department of Health and Environment sampled Well 1 and Well 4 on December 4, 1987 (Ref. 16). Analysis of these samples indicated an observed release of nickel, 21 ug/l (12.6 times background); lead, 141 ug/l (4.5 times background); copper, 207 ug/l (23.0 times background); arsenic, 41 ug/l (13.7 times background); cadmium, 13 ug/l (13 times background); zinc, 656 ug/l (32.8 times background); aluminum, 116,240 ug/l (12.2 times background); and barium, 2,129 ug/l (18.5 times background) (Ref. 16). Of these observed releases of hazardous substances, only **nickel, lead, copper, and zinc** can be attributed to the landfill.

Additional analytical data from these wells, obtained during the monitoring and maintenance program, was used to determine if chromium and lead from the landfill had migrated into the groundwater. Chromium and lead were not detected in groundwater above background concentrations in any of the post-closure sampling (Refs. 10, 17, 18, 19).

3.0 Groundwater Pathway

3.1 Hydrogeologic Setting. The International Harvester Landfill Site is situated in the Gulf Coastal Plain Physiographic Province of western Tennessee. The topography of the study area is characterized by loess covered bluffs rising above the Mississippi River Alluvial Plain (Ref. 20, pp. 4-6; Figure 1). The Memphis area is located in the north-central portion of the Mississippi Embayment, a broad structural trough or syncline that plunges south along an axis that parallels the Mississippi River (Ref. 20, p. 6). Formations in the area dip westward towards the embayment and southward on the axis (Ref. 20, p. 6). Topography in the area ranges from 205 feet National Geodetic Vertical Datum (NGVD) to 280 feet NGVD. The International Harvester Landfill Site is located approximately 250 feet NGVD. (Ref. 5).

The major hydrogeologic units found in the Memphis area in descending order are as follows: the loess, alluvium and fluvial deposits that comprise the shallow water-table aquifer, the Jackson, Cockfield and Cook Mountain Formations which together comprise the Jackson-Upper Claibourne confining unit, the Memphis Sand which comprises the Memphis aquifer, the Flour Island Formation and the Fort Pillow Sand (Ref. 20, p. 7).

The soil underlying the facility is classified as Graded land (Gr), Falaya silt loam (Fm) and Memphis silt loam (MeF3) (Ref. 2, Sheet 41). Graded land is characterized by areas where the original soil has been graded for commercial, industrial, and residential development. These materials in these areas are generally silty (Ref. 2, p. 22). Falaya silt loam is characterized by poorly drained, acidic, silt loam soils formed on bottomlands (Ref. 2, p. 16). Memphis silt loam is characterized by well-drained, deep silt loam soils on hillsides (Ref. 2, p. 32). The water table is ranges from 1 foot below land surface (bls) during winter and spring in the Falaya soil to over 6 feet bls in the Memphis sand.. Some areas of the Falaya soil are flooded for short periods in winter and spring (Ref. 2, p. 14).

Alluvial deposits occur both beneath the Mississippi Alluvial Plain and the alluvial plains of the streams which drain the Gulf Coastal Plain and range in thickness from 100 to 150 feet in the Mississippi River Alluvial Plain to less than 50 feet in the alluvial plains of streams in the Gulf Coastal area. The alluvial deposits consist of fine sand, silt, and clay in the upper part and sand and gravel in the lower part (Ref. 20, p. 7). The region was blanketed by a 20 to 50 foot layer of loess during the Pleistocene. Loess consists of wind-blown silt, silty clay, and sand. Recent erosion has thinned or removed the loess deposits along streams. Fluvial deposits underlie alluvium and loess and consist primarily

of sand, gravel and minor clay lenses. Locally, the sand and gravel are cemented with iron oxide to form thin layers of sandstone or conglomerate in the basal portions of the unit (Ref. 20, p. 7). The regional range of thickness of these fluvial deposits is 0 to 100 feet depending on the local erosional surface (Ref. 20, p. 6). The total thickness of the alluvial and fluvial deposits in the vicinity of the site is approximately 50 feet (Ref. 20, pp. 13, Table 2).

The Jackson Formation, which consists of fine sand or sandy clay, occurs only beneath the higher hills and ridges in the northern part of the Memphis area (Ref. 20, p. 7). Since the International Harvester Landfill Site is located in the central part of the Memphis area, the Jackson Formation is probably absent beneath the site (Refs. 5; 20). The Cockfield Formation occurs in the subsurface in most of the Memphis area and consists of fine sand, silt, clay and local lenses of lignite. Underlying the Cockfield Formation is the Cook Mountain Formation, which consists primarily of clay (Ref. 20, p. 7). Due to the probable absence of the Jackson Formation, the Cockfield and Cook Mountain formations comprise the Jackson-Upper Claiborne confining unit in the area of the site. The thickness of this confining unit in the vicinity of the International Harvester Landfill Site is approximately 268 feet (Ref. 20, Table 2, Plate 1). Estimated hydraulic conductivity of the Jackson-Upper Claiborne clay unit based on information from Freeze and Cherry (1979) as well as Dr. William S. Parks, ranges from 1×10^{-7} to 1×10^{-5} cm/sec (Refs. 21, p. 29, 22).

The Memphis Sand underlies the Jackson-Upper Claiborne confining unit and is comprised of a thick body of sand that includes subordinate lenses of clay and silt at various horizons (Ref. 20, p. 9). The Memphis Sand ranges in thickness from about 500 to 900 feet. The Memphis Sand is thickest in the southwestern part of the Memphis area and thinnest in the northeastern part (Ref. 20, Table 1). Beneath the site, the Memphis Sand is approximately 800 feet thick (Ref. 20, p. 9 Figure 2, Table 2). In the area of the facility the top of the Memphis Sand occurs approximately 328 feet below land surface (bls) (Ref. 20, Table 2). The potentiometric surface within the Memphis Sand near the International Harvester Landfill Site is approximately 100 feet bls (Ref. 20, Plate 3). This would indicate that the water in the Memphis Sand in the vicinity of the site is under artesian conditions.

According to well logs from the Memphis Defense Depot, the Paleocene-aged Flour Island Formation underlies the Memphis Sand. The top of this formation is located approximately 1,000 to 1,100 feet bls and consists primarily of silty clays and sandy silts. The Flour Island Formation acts as a lower confining unit for the Memphis Sand and an upper confining unit for the Fort Pillow Sand, and it ranges in thickness from 200 to 300 feet (Ref. 20, Figure 2).

The Fort Pillow Sand is the middle sand unit of the Paleocene Wilcox group, and it underlies the Flour Island Formation. This sand ranges from fine sandy textures to coarse

sand, and it ranges in thickness from 150 to 300 feet in the Memphis area (Ref. 20, Figure 2)

Groundwater beneath the site is present in the sediments of the loess, alluvium and fluvial deposits, the Memphis Sand aquifer, and in the Fort Pillow Sand. The surficial aquifer consists of the saturated portions of the loess, alluvium and fluvial deposits. The combined thickness of these deposits in the area of the site is approximately 60 feet. The surficial aquifer may be utilized for a few domestic, agricultural, and industrial supplies (Ref. 20, pp. 7). The depth to the water table beneath the site is estimated to be approximately 20 to 35 feet below land surface (bls) (Ref. 10, p. 5).

The Memphis Sand Unit is the primary source of groundwater in the Memphis area. It is confined below by the Flour Island Formation and above by the Jackson Upper Claiborne Confining Unit (Cook Mountain Formation). Recharge to the Memphis Sand aquifer occurs predominantly via percolation of precipitation in outcrop areas 30 to 60 miles east of Memphis. Seepage from the overlying surficial aquifer and the Mississippi River also contribute to the recharge of the Memphis Sand Aquifer (Ref. 23, p. 30). In the last several years, the Memphis Sand has been contaminated due to discontinuity of the Jackson-Upper Claiborne confining unit, heavy pumpage of wellfields in the area, and interconnection of aquifers through drilled wells (Ref. 20, pp. 5-9, 34). Hydraulic conductivities in the Memphis Sand Aquifer are approximately 1×10^{-2} cm/sec (Ref. 21, p. 29).

Underlying the Flour Island Formation is the Fort Pillow Sand. This unit is the second principal aquifer in the Memphis area and supplies about 10 percent of the water there. Hydraulic conductivity for the Fort Pillow Sand is approximated at 1×10^{-2} (Ref. 21, p. 29).

The 1990 document Hydrogeology and Preliminary Assessment of the Potential for Contamination of the Memphis Aquifer in the Memphis Area, Tennessee has extensively outlined the Jackson-Upper Claiborne confining unit. The report indicates the presence of the confining unit beneath the site at approximately 60 feet bls with a thickness of 268 feet (Ref. 20, pp. 6-9, Plate 1). Parks (1990) states that the Jackson-Upper Claiborne confining unit is thin, locally absent, and may contain sand "windows" which could provide "pathways" for contaminants to reach the Memphis Sand aquifer. Parks also indicates that downward leakage from the water-table aquifer to the Memphis Sand aquifer is widespread in the Memphis area. Evidence of downward leakage, as discussed by Parks, includes: (Ref. 20, pp. 1, 2, 34-37)

- confining layer absence
- hydraulic head differences between the water table aquifer and the Memphis Sand aquifer
- local water table surface depressions

- long-term declines and reduced seasonal fluctuations in the water table observation wells
- stream water loss based on discharge measurements
- Carbon-14 and tritium concentrations present in the Memphis Sand aquifer indicating "recent" leakage
- water-quality anomalies in the Memphis Sand indicating downward leakage
- volatile organic compounds present in the Memphis Sand aquifer

The presence of organic compounds in the Memphis Sand aquifer indicates that a hydraulic connection between the surficial aquifer and the Memphis Sand aquifer exists. Volatile organic compounds have been detected in Allen wellfield wells (numbers Sh: J-119, Sh: J-120, and Sh: J-121) at depths ranging from 398 to 436 feet bls (Ref. 20, p. 35). These wells are located in an area where the confining unit is approximately 68 feet thick. The nearest known potential source of contamination in the water table aquifer is 650 feet from the Allen wellfield (Ref. 20, pp. 34-36, Plate 1, Table 6). The migration pathway for the contaminants has not been established. Throughout Memphis the Jackson-Upper Claiborne confining unit is variable in its thickness and lithology. Generally the unit is thick under Memphis and it pinches out to the east; however, in localized zones beneath Memphis, the confining unit is very thin and is potentially absent. The nearest documented location where the confining unit is thin or absent is 9 miles southeast where the unit is absent (Ref. 20, Plate 1).

3.2 Groundwater Targets. There is one Memphis Light, Gas and Water Division (MLGW) wellfield within four miles of the site, the Mallory Station wellfield, located between 3.0 and 4.0 miles south of the site (Ref. 24, p. 11). There are also 18 private wells across the Mississippi River in Arkansas located between 3.0 and 4.0 miles from the site (Ref. 5). In the vicinity of the Mallory wellfield, groundwater in the Memphis Aquifer flows radically toward the pumping wells due to the large cone of depression created by the wellfield (Ref. 20, Plate 1).

The majority of potable water for the residents within four miles of the International Harvester Landfill Site is supplied by MLGW, which operates a blended system serving approximately 565,274 people (Refs. 24, 25, 26). MLGW obtains its water from 162 wells: 143 wells are screened in the Memphis Sand aquifer and 19 wells are screened in the Fort Pillow Sand aquifer (Ref. 24). Thirteen of these municipal wells are located within four miles of International Harvester Landfill Site: 10 of these wells are screened in the Memphis Sand aquifer and 3 wells are screened in the Fort Pillow Sand (Refs. 5, 24). The closest Memphis Sand aquifer well is approximately 3.1 miles southeast of the site (Refs. 5, 24).

Approximately 52 persons located across the Mississippi River in Crittendon County, Arkansas (Ref. 5, 27) obtain water from 18 private wells. These wells have been assumed to be screened in the surficial aquifer because depths to the Memphis sand make it unlikely that private wells utilize it as a drinking water source. The closest alluvial

aquifer well is approximately 3.6 miles west of the site (Ref. 5). A more detailed analysis of groundwater targets in the Memphis Sand and Fort Pillow Sand aquifers is provided in Table 1.

TABLE 1
Potable Groundwater Usage within
4 miles of International Harvester Landfill Site

| Distance from Site | Wells Counted | Aquifer | Percent of Population Supplied | Apportioned Population | Total Target Population |
|--------------------|---------------|------------------|--------------------------------|------------------------|-------------------------|
| 0-¼ mile | 0 | n/a ¹ | 0 | 0 | 0 |
| ¼-½ mile | 0 | n/a | 0 | 0 | 0 |
| ½-1 mile | 0 | n/a | 0 | 0 | 0 |
| 1-2 miles | 0 | n/a | 0 | 0 | 0 |
| 2-3 miles | 0 | n/a | 0 | 0 | 0 |
| 3-4 miles | 18 | Surficial | 100% ⁴ | 52 ³ | 45,413 |
| | 10 | Memphis Sand | 6.17% ² | 34,893 ³ | |
| | 3 | Fort Pillow Sand | 1.85% | 10,468 | |
| Total | 18 | Surficial | 100% | 52 | 45,413 |
| | 10 | Memphis Sand | 6.17% | 34,893 | |
| | 3 | Fort Pillow Sand | 1.85% | 10,468 | |

¹Where there are no wells, there are no target aquifers.

²The MLGW system has 162 wells. Since no individual well provides more than 40% of the total system production, each well service population is apportioned equally. Each well provides 0.617% of the total production.

³Population based on a household average of 2.65 persons/house (Ref. 26).

⁴These private wells provide all drinking water for each residence.

⁵Population based on a household average of 2.89 persons/house (Ref. 27).

4.0 Surface Water Pathway

4.1 Hydrologic Setting. Surface water run-off from approximately 10 acres flows from the International Harvester Landfill and overland to two intermittent ditches: one located west and one located south of the landfill. These ditches each flow west for approximately 1,500 feet where they converge into one intermittent ditch. This intermittent ditch continues to flow west for approximately 800 feet, where it enters the

Mississippi River (Ref. 5). This point is the probable point of entry (PPE) for contaminants into the surface water pathway. Flow continues south through the Mississippi River to the termination of the 15-mile surface water pathway, at Mississippi River Mile 725.4, near its confluence with Lake McKellar in Memphis, Tennessee (Ref. 5).

The average annual flow rate in the Mississippi River is approximately 580,000 cubic feet per second (cfs) (Ref. 28, p. 2). Portions of the International Harvester Landfill are located within the 100-year floodplain of the Mississippi (Ref. 29).

4.2 Surface Water Targets. There are no surface drinking water intakes along the surface water pathway (Ref. 30). Recreational fishing, swimming, and boating are known to occur on the Mississippi River (Ref. 31). There has been a commercial ban on fishing and recreational fishermen are advised not to eat fish taken from the Mississippi River (Refs. 31, 32). In spite of these advisories, fish are still caught and eaten from the Mississippi River (Ref. 31). Since there is no annual fishing harvest data from these fisheries, the fishery has been assumed to have an average annual yield of greater than one pound.

Forested wetlands are present along the surface water pathway. The closest wetlands are forested located across the Mississippi River, approximately 0.8 miles west of the site. The total in-flow length of wetlands along the surface water pathway is 9.6 miles (Ref. 33).

There is one state threatened fish species, blue sucker, (*Cycleptus elongatus*), located approximately 3.3 miles downstream of the site in the Mississippi River (Refs. 5, 34).

5.0 Soil Exposure and Air Pathways

5.1 Physical Conditions. The International Harvester Landfill is inactive and is covered with grasses and some small shrubs. The landfill areas appears to be mowed and well maintained (Ref. 6). There are lightly wooded areas around the base of the landfill, primarily to the south and west. These forested areas and a gravel road, separate the landfill from the Memphis Shelby County Airport, located adjacent to the west and south (Ref. 6). Access to the landfill is unrestricted from the north; however, there is thick vegetation that must be traversed to enter the landfill (Ref. 6). Access from the east and south is restricted by a six-foot high, barbed-wire, chain-link fence (Ref. 6). Access from the west is restricted by a three foot high, wire fence (Ref. 6). No stressed vegetation was observed during the August 27, 1993 site investigation (Ref. 6). The surrounding are is heavily industrialized (Ref. 6).

5.2 Soil and Air Targets. The site is currently inactive and is therefore not subject to contact by workers. There are no schools, residences, or daycare facilities within 200 feet of the site (Ref. 5). The nearest residences are located approximately 0.5 mile east of the site (Ref. 5; 35). The nearest school is the Westside School, located approximately 1 mile northeast of the site (Ref. 5).

There are no known occurrences of threatened or endangered species on the site; however, the Mississippi Kite (*Ictinia mississippiensis*), a state endangered avian species, is located approximately 0.9 mile north of the site (Refs. 5; 34). Approximately 30 acres of forested and emergent wetland are located between $\frac{1}{4}$ and $\frac{1}{2}$ mile of the site (Ref. 33). Approximately 70 acres of forested, emergent, and scrub-scrub wetland are located between $\frac{1}{2}$ and 1 mile of the site (Ref. 33).

Population in the area within four miles of the site is approximately 60,563 persons, excluding employees, and is detailed as follows: 0 to $\frac{1}{4}$ mile, 0 persons; $\frac{1}{4}$ to $\frac{1}{2}$ mile, 0 persons; $\frac{1}{2}$ to 1 mile, 2,599 persons; 1 to 2 miles, 6,128 persons; 2 to 3 miles, 20,234 persons; and 3 to 4 miles, 31,602 persons (Refs. 35).

6.0 Summary and Conclusions

Background information and sample data suggests the presence of 3,4-benzofluoranthene, chromium, copper, nickel, lead, zinc, manganese, cyanide, and PCBs in the landfill at International Harvester. The landfill encompasses approximately 10 acres of area.

The aquifers of concern are the Memphis and Fort Pillow Sands based on the high number of potential drinking water targets approximately 3 to 4 miles southeast of the site. The surficial aquifer provides drinking water to very few residents 3.5 to 4.0 miles west of the site, across the Mississippi River in Arkansas. It is unlikely that contamination in the surficial aquifer would migrate under the Mississippi River because the Mississippi River probably acts as an aquiclude, preventing flow of groundwater to these wells.

Potential contamination of the surface water pathway poses minimal to no threat human health and the environment. There are no drinking water intakes along the pathway, therefore, there is no threat to drinking water targets. While fishing is common along the surface water pathway, high flow rates in the Mississippi River dilute the effect of, contamination on fish and sensitive environments in the surface water pathway, minimizing the threat to human food chain and environmental targets.

Potential exposure to contaminated soil and air contamination poses a little threat to humans and the environments within the target distance limits if the site. There are no residents, schools, or day care facilities within 200 feet of the site. Additionally the population nearby is relatively low within 2 miles of the site. Threats to residents beyond

this point are minimal due to air dispersal and the low possibility of contact with site contaminants.

Based on the findings of this report, no further investigations are recommended for the International Harvester Landfill Site.

7.0 References

1. U.S. Environmental Protection Agency, "Standard Operating Procedure to Determine Site Latitude and Longitude Coordinates", 1991. Modified calculation worksheet for the International Harvester Landfill Site.
2. U.S. Department of Agriculture, Soil Conservation Service, Soil Survey of Shelby County, Tennessee, Sheet 49, June 1989.
3. U.S. Department of Commerce, Climatic Atlas of the United States (Washington, DC: GPO, June 1968), Reprint: 1983, National Oceanic and Atmospheric Administration.
4. Urban Hydrology for Small Watersheds, United States Department of Agriculture, Soil Conservation Service Engineering Division, Technical Release 55, June 1986.
5. U.S. Geological Survey, 7.5 minute series, Topographic Quadrangle Maps of Tennessee: Millington, TENN, 1971 (Photorevised 1983); Locke, TENN.-ARK, 1970; Northwest Memphis, TENN.-ARK., 1965 (Photorevised 1973); Northeast Memphis, TENN., 1965 (Photorevised 1983); scale 1:24,000.
6. B&V Waste Science and Technology Corp., Field Logbook for the International Harvester Landfill Site., Project 52012.145. Documentation of Off-site Reconnaissance conducted on July 27, 1993.
7. Tennessee Department of Health and Environment, "Potential Hazardous Waste Site Preliminary Assessment", International Harvester, Memphis, Shelby County, Tennessee, TND007024516, May 13, 1987.
8. William L. Penny, Assistant General Counsel, Tennessee Department of Public Health, letter with enclosure to International Harvester Company dated March 14, 1984. Subject: Flow rates in Mississippi, Loosahatchie, and Wolf Rivers near Memphis, Tennessee.
9. James C. Ault, Director, Superfund Division, Tennessee Department of Health and Environment, Statement of Hazardous Substance Site Disposition, executed and notarized February 29, 1988.

10. Hess Environmental Services, Inc., "Report of Post Closure Monitoring at the International Harvester Landfill Site - Third Quarter, First Year", Memphis, Tennessee, October 6, 1987.
11. Wm. Jordan English, Geologist, Tennessee Division of Superfund, letter to Dr Sheldon Kelman, P.E., Vice President, The Pickering Firm, dated July 10, 1989. Subject: Deficiencies at the International Harvester Landfill Site.
12. United States Environmental Protection Agency, "Hazardous Waste Site", International Harvester Company, Memphis, Tennessee, March 1981.
13. Hansford T. Shacklette and Josephine G. Boerngen, U.S. Geological Survey, *Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States*, USGS Professional Paper 1270, USGPO, Washington, 1984.
14. Sheldon Kelman, Ph.D., P.E., Pickering, Wooten, Smith & Weiss, Inc., letter to Mr. Danny Brewer, Environmental Engineer, Superfund Division, Tennessee Department of Health and Environment, dated July 18, 1984. Subject: Sampling and laboratory analyses of water and soil samples collected from the International Harvester Site.
15. Sheldon Kelman, Ph.D., P.E., Pickering Environmental Consultants, Inc., letter to Mr. Jordan English, Geologist, Tennessee Department of Superfund, dated September 20, 1989. Subject: Establishment of Well #1 as a background groundwater monitoring well.
16. Tennessee Department of Health and Environment, Report of Analyses, Groundwater samples from Wells 1 and 4 at the International Harvester Site, January 4, 1988.
17. Hess Environmental Services, Inc., "Report of Groundwater Monitoring, Well Development, and Post Closure Monitoring at the International Harvester Landfill Site - Second Quarter, Second Year", Memphis, Tennessee, July 17, 1988.
18. Hess Environmental Services, Inc., "Report of Post Closure Monitoring at the International Harvester Landfill Site - Second Quarter, Third Year", Memphis, Tennessee, June 26, 1989.
19. Pickering Environmental Consultants, Inc., "Annual Report of Post Closure Monitoring at the International Harvester Landfill Site", Memphis, Tennessee, Second Quarter, Sixth Year, December 1992.
20. William S. Parks, *Hydrogeology and Preliminary Assessment of the Potential for Contamination of the Memphis Aquifer in the Memphis Area, Tennessee*, U.S. Geological Survey, Water-Resources Investigations Report 90-4092, 1990.

21. R. Allan Freeze and John A. Cherry, Prentice-Hall, *Groundwater*, Englewood Cliffs, NJ, 1979.
22. Carter Helm, B&V Waste Science and Technology Corp., telephone conversation with Dr. William S. Parks, USGS Water Investigations, March 3, 1992. Subject: Hydraulic conductivity of Jackson-Upper Claiborne clay confining unit.
23. J.H. Criner, P-C; P. Sun; and D.J. Nyman, *Hydrology of Aquifer Systems in the Memphis Area, Tennessee*, U.S. Geological Survey, Water-Resources Investigations Report, 1964.
24. Memphis Light, Gas, and Water Division, "MLGW Water Production", Memphis, Tennessee, 1990.
25. Paula Payne, Vice President, Memphis Light, Gas and Water Division, letter to Christian J. Lavalley, B&V Waste Science and Technology Corporation, dated June 28, 1993. Subject: City of Memphis Water Production.
26. U.S. Department of Commerce, *Summary Population and Housing Characteristics - Tennessee*, 1990 Census of Population and Housing, 1990-CPH-1-44.
27. U.S. Department of Commerce, *Summary Population and Housing Characteristics - Arkansas*, 1990 General Population Characteristics, 1990-CP-15.
28. Dewey L. Jones, Chief - Hydraulics and Hydrology Branch, U.S. Army Corps of Engineers, Memphis District, letter to Laura J. Morrison, Project Scientist, B&V Waste Science dated April 1, 1992. Subject: Flow rates in Mississippi, Loosahatchie, and Wolf Rivers near Memphis, Tennessee.
29. Federal Emergency Management Agency, Flood Insurance Rate Map, City of Memphis, Tennessee, Shelby County, Panel 10 of 80, Community Panel No. 470177 0010 B, December 1, 1982.
30. Laura Morrison, B&V Waste Science, telephone conversation with Jerry Collins, Memphis Department of Public Works, October 18, 1991. Subject: Surface water intakes on the Mississippi River.
31. Paul Delphos, B&V Waste Science, telephone conversation with John Rayfield, TN Wildlife Resource Agency, July 1, 1992. Subject: Fisheries on the Mississippi, Loosahatchie, and Wolf Rivers; Nonconnah Creek; and Lake McKellar.
32. Laura Morrison, B&V Waste Science, telephone conversation with John Condor, Wildlife Manager, Wildlife Resources Agency, December 23, 1991. Subject: Ban on commercial fishing in the Mississippi River.

33. U.S. Fish and Wildlife Service, 7.5 minute series, National Wetlands Inventory Maps of Tennessee: Northwest Memphis, TENN.-ARK., 1988, West Memphis, ARK.-TENN., 1988; and Fletcher Lake, TENN.-ARK., 1988, scale 1:24,000
34. Tennessee Department of Environment & Conservation, List of Rare and Endangered Species for Shelby County, July 22, 1993
35. U.S. Environmental Protection Agency, *Graphical Exposure Modelling System (GEMS) Data Base*, Data compiled from U.S. Bureau of Census data (1990) by Dane G. Pehrman, B&V Waste Science, September 2, 1993.

CONFIDENTIAL
Hazard Ranking System Preliminary Score
for the
International Harvester Landfill
Memphis, Shelby County, Tennessee

The preliminary scores were calculated using the SI worksheets and the HRS Rule of December 1990. Pathways evaluated include air, soil exposure, surface water, and groundwater. The International Harvester Landfill Site is an inactive, closed landfill that was used for the deposition of various industrial wastes by International Harvester Corp. Manufacturing processes included casting, shearing, machining, assembly, washing, plating and painting of farm equipment components. Wastes from these manufacturing operations were placed into the landfill by International Harvester and included: wood, paper, foundry sand, glass, metal scraps, cardboard, household trash, paint and paint sludge, washing machine sludge, oils, greases, coolants, wastewater treatment sludge, spent transformer oil, varnish, sealing compounds, caustics and acids, electroplating treatment sludge, and other miscellaneous industrial solid wastes (Ref. 8). Samples from the landfill indicated the presence of the following compounds: **3,4-benzofluoranthene, chromium, copper, nickel, lead, zinc, manganese, cyanide, and PCBs.**

Three scenarios were evaluated during this investigation: Scenario #1, which is BVWST's "best professional judgement" based on the available data; Scenario #2, which is based on an assumed interconnection between the surficial and Memphis Sand aquifers; and Scenario #3, which is based on an assumed observed release of PCBs in a sediment sample taken in the surface water pathway in the Mississippi River fishery.

The closed, capped, landfill encompasses 10 acres. Based on this information and SI Table 1, a hazardous waste quantity score of 100 was calculated for each scenario summarized below.

Scenario #1

This scenario represents BVWST's best professional judgement of how the conditions at the International Harvester Landfill will score under the HRS program based on the available data.

The worksheets indicate the Memphis and Fort Pillow Sand aquifers are the aquifer of concern due primarily to its depth and number of potential targets. While there is an observed release of hazardous contaminants to the surficial aquifer, there are too few targets to outscore the potential targets in the Memphis and Fort Pillow Sand aquifers. The depth to the aquifer of concern is large enough to minimize the potential of release significantly enough to indicate that there is little potential of impacting groundwater targets. The groundwater pathway is the most significant pathway scored and is responsible for most of the overall site score.

The worksheets indicate that there is a moderate potential for a release to surface water. There are no surface water intakes along the pathway; therefore, there is no drinking water threat. There are fisheries and sensitive environments along the pathway but the Mississippi River has an extremely high flow rates that dilutes the impact of hazardous substances on food chain and environmental targets. There is little threat to human food chain resources or sensitive

environments.

The worksheets indicate a low likelihood of exposure to hazardous substances at the site to residents because the site is relatively inaccessible. There are no resident targets on or within 200 feet of the site. The nearby population is also relatively low, resulting a low soil exposure score. There is little threat of exposure to hazardous contaminants through soil contact.

The worksheets indicate a low potential of air contamination because there is no population within ½ mile of the site and areas within 4 miles of the site are only moderately populated. While PCBs have a high air mobility/toxicity, the potential effects of contamination are minimized by dispersal factors prior to reaching populated areas and sensitive environments.

This scenario indicates the overall site score is low and does not indicate the need to further investigate this site under the HRS process.

Scenario #2

Documentation gathered in the SIP investigation indicates the possibility that there is an interconnection between the overlying surficial aquifer and the Memphis Sand aquifer, although the same documentation indicates that the nearest interconnection is 9 miles to the southeast. This scenario is identical to Scenario #1, except BVWST examined the effect that aquifer interconnection would have on the site score.

This scenario results in a higher groundwater pathway and overall site score than Scenario #1 because of the addition of the MLGW drinking water targets to the observed release; however, the overall site score remains low and does not indicate the need to further investigate this site under the HRS process.

Scenario #3

Sediment and water sampling in the 1980 EPA Site Investigation indicated PCB contamination in the drainage ditch from the landfill. This data could not be used because there were no background samples and the samples were not on the surface water pathway (the ditches are intermittent). However, we feel that there is a possibility that a sediment sample, taken at the mouth of the ditch in the Mississippi could indicate a PCB "hit". Since the Mississippi is a fishery, this sample would allow the human food chain targets to be scored as Level II targets.

This scenario increases the surface water pathway score by one order of magnitude; however, it not significantly affect the overall site score. This scenario does not indicate the need to further investigate this site under the HRS process.

Conclusions

Scenarios #1, #2, and #3 indicate that the site will not score over the HRS threshold of 28.5 based on the current data available. Based on this information, no further action is recommended for the International Harvester Landfill Site.

| Pathway | Scenario #1 | Scenario #2 | Scenario #3 |
|---------------|-------------|-------------|-------------|
| Groundwater | 4.57 | 27.93 | 4.57 |
| Surface Water | 0.037 | 0.037 | 96.065 |
| Soil Exposure | 0.01 | 0.01 | 0.01 |
| Air | 3.44 | 3.44 | 3.44 |
| Overall Score | 2.86 | 14.07 | 48.12 |

HRS Scoresheets

Scenario #1

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

GROUNDWATER MIGRATION PATHWAY SCORESHEET

| <u>Likelihood of Release to an Aquifer</u> | <u>Maximum Value</u> | <u>Aquifer 1 Assigned Value</u> | <u>Aquifer 2 Assigned Value</u> | <u>Aquifer 3 Assigned Value</u> |
|---|----------------------|---------------------------------|---------------------------------|---------------------------------|
| 1. Observed Release | 550 | 550 | 0 | 0 |
| 2. Potential to Release | | | | |
| 2a. Containment | 10 | 10 | 10 | 10 |
| 2b. Net Precipitation | 10 | 3 | 3 | 3 |
| 2c. Depth to Aquifer | 5 | 5 | 1 | 1 |
| 2d. Travel Time | 35 | 25 | 5 | 5 |
| 2e. Potential to Release (lines 2a x (2b+2c+2d)) | 500 | 330 | 90 | 90 |
| 3. Likelihood of Release (higher of lines 1 and 2e.) | 550 | 550 | 90 | 90 |

Waste Characteristics

| | | | | |
|-----------------------------|-----|-----|-----|-----|
| 4. Toxicity/Mobility | a | 100 | 100 | 100 |
| 5. Hazardous Waste Quantity | a | 100 | 100 | 100 |
| 6. Waste Characteristics | 100 | 10 | 10 | 10 |

Targets

| | | | | |
|---------------------------------|----|-----|-----|-----|
| 7. Nearest Well | 50 | 2 | 2 | 2 |
| 8. Population | | | | |
| 8a. Level I Concentrations | b | 0 | 0 | 0 |
| 8b. Level II Concentrations | b | 0 | 0 | 0 |
| 8c. Potential Contamination | b | 0.4 | 417 | 417 |
| 8d. Population (lines 8a+8b+8c) | b | 0.4 | 417 | 417 |
| 9. Resources | 5 | 0 | 0 | 0 |
| 10. Wellhead Protection Area | 20 | 0 | 0 | 0 |
| 11. Targets (lines 7+8d+9+10) | b | 2.4 | 419 | 419 |

Groundwater Migration Score for an Aquifer

| | | | | |
|--|-----|------|------|------|
| 12. Aquifer Score [(lines 3 x 6 x 11)/82,500] | 100 | 0.16 | 4.57 | 4.57 |
|--|-----|------|------|------|

Groundwater Migration Pathway Score

| | | | | |
|---|-----|--|--|--|
| 13. Pathway Score (Sgw) – Highest value for all aquifers evaluated | 100 | | | |
|---|-----|--|--|--|

4.57

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE SHEET

DRINKING WATER THREAT

| <u>Likelihood of Release</u> | <u>Maximum Value</u> | <u>Watershed 1 Assigned Value</u> | <u>Watershed 2 Assigned Value</u> |
|---|----------------------|-----------------------------------|-----------------------------------|
| 1. Observed Release | 550 | 0 | n/a |
| 2. Potential Release by Overland Flow | | | |
| 2a. Containment | 10 | 9 | |
| 2b. Runoff | 25 | 1 | |
| 2c. Distance to Surface Water | 25 | 6 | |
| 2d. Potential to Release by Overland Flow lines 2a x (2b + 2c) | 500 | 63 | 0 |
| 3. Potential to Release by Flood | | | |
| 3a. Containment | 10 | 10 | |
| 3b. Flood Frequency | 50 | 25 | |
| 3c. Potential to Release by Flood (Lines 3a x 3b) | 500 | 250 | 0 |
| 4. Potential to Release (lines 2d + 3c) | 500 | 313 | 0 |
| 5. Likelihood of Release (Higher of lines 1 and 4) | 550 | 313 | 0 |

Waste Characteristics

| | | | |
|-----------------------------|-----|-------|--|
| 6. Toxicity/Persistence | a | 10000 | |
| 7. Hazardous Waste Quantity | a | 100 | |
| 8. Waste Characteristics | 100 | 32 | |

Targets

| | | | |
|---|----|---|---|
| 9. Nearest Intake | 50 | 0 | |
| 10. Population | | | |
| 10a. Level I Concentrations | b | 0 | |
| 10b. Level II Concentrations | b | 0 | |
| 10c. Potential Contamination | b | 0 | |
| 10d. Population (lines 10a + 10b + 10c) | b | 0 | 0 |
| 11. Resources | 5 | 0 | |
| 12. Targets (lines 9 + 10d + 11) | b | 0 | 0 |

Drinking Water Threat Score

| | | | |
|---|-----|------|---|
| 13. Drinking Water Threat Score [(lines 5 x 8 x 12)/82500] | 100 | 0.00 | 0 |
|---|-----|------|---|

- a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET
 (continued)

HUMAN FOOD CHAIN THREAT

| | Maximum Value | Watershed 1 Assigned Value | Watershed 2 Assigned Value |
|---|------------------|----------------------------------|----------------------------------|
| <u>Likelihood of Release</u> | | | |
| 14. Likelihood of Release (Same as line 5) | <u>550</u> | <u>313</u> | <u>0</u> |
| <u>Waste Characteristics</u> | | | |
| 15. Toxicity/Persistence/Bioaccumulation | <u>a</u> | <u>500000000</u> | |
| 16. Hazardous Waste Quantity | <u>a</u> | <u>100</u> | |
| 17. Waste Characteristics | <u>1000</u> | <u>320</u> | |
| <u>Targets</u> | | | |
| 18. Food Chain Individual | <u>50</u> | <u>0</u> | |
| 19. Population | | | |
| 19a. Level I Concentrations | <u>b</u> | <u>0</u> | |
| 19b. Level II Concentrations | <u>b</u> | <u>0</u> | |
| 19c. Potential Human Food Chain Contamination | <u>b</u> | <u>0.03</u> | |
| 19d. Population (lines 19a + 19b + 19c) | <u>b</u> | <u>0.03</u> | <u>0</u> |
| 20. Targets (lines 18 + 19d) | <u>b</u> | <u>0.03</u> | <u>0</u> |
| <u>Human Food Chain Threat Score</u> | | | |
| 21. Human Food Chain Threat Score [(lines 14 x 17 x 20)/(82500)] | <u>100</u> | <u>0.0364</u> | <u>0</u> |

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND FLOOD MIGRATION COMPONENT SCORE SHEET (continued)

ENVIRONMENTAL THREAT

| | Maximum Value | Watershed 1 Assigned Value | Watershed 2 Assigned Value |
|---|------------------|----------------------------------|----------------------------------|
| <u>Likelihood of Release</u> | | | |
| 22. Likelihood of Release (Same as line 5) | <u>550</u> | <u>313</u> | <u>0</u> |

Waste Characteristics

| | | | |
|--|-------------|------------------|--|
| 23. Ecosystem Toxicity/Persistence/Bioaccumulation | <u>a</u> | <u>500000000</u> | |
| 24. Hazardous Waste Quantity | <u>a</u> | <u>100</u> | |
| 25. Waste Characteristics | <u>1000</u> | <u>320</u> | |

Targets

| | | | |
|--|----------|---------------|----------|
| 26. Sensitive Environments | | | |
| 26a. Level I Concentrations | <u>b</u> | <u>0</u> | |
| 26b. Level II Concentrations | <u>b</u> | <u>0</u> | |
| 26c. Potential Environmental Contamination | <u>b</u> | <u>0.0003</u> | |
| 26d. Population (lines 26a + 26b + 26c) | <u>b</u> | <u>0.0003</u> | <u>0</u> |
| 27. Targets (value on lines 26d) | <u>b</u> | <u>0.0003</u> | <u>0</u> |

Environmental Threat Score

| | | | |
|--|-----------|----------------|----------|
| 28. Environmental Threat Score [(lines 22 x 25 x 27)/82500] | <u>60</u> | <u>0.00036</u> | <u>0</u> |
|--|-----------|----------------|----------|

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE – WATERSHED

| | | | |
|---|------------|--------------|----------|
| 29. Watershed Score (Lines 13 + 21 + 28) | <u>100</u> | <u>0.037</u> | <u>0</u> |
|---|------------|--------------|----------|

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE – WATERSHED

| | | | |
|--|------------|---------------|--|
| 30. Watershed Score (Highest of all watersheds) | <u>100</u> | 0.0368 | |
|--|------------|---------------|--|

- a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SOIL EXPOSURE PATHWAY SCORE SHEET

RESIDENT POPULATION THREAT

Likelihood of Exposure

1. Likelihood of Exposure

| Maximum Value | Assigned Value |
|---------------|----------------|
| 50 | 50 |

Waste Characteristics

2. Toxicity
 3. Hazardous Waste Quantity
 4. Waste Characteristics

| | |
|-----|-------|
| a | 10000 |
| a | 100 |
| 100 | 32 |

Targets

5. Resident Individual
 6. Resident Population
 6a. Level I Concentrations
 6b. Level II Concentrations
 6c. Resident Population (lines 6a + 6b)
 7. Workers
 8. Resources
 9. Terrestrial Sensitive Environments
 10. Targets (lines 5+6c+7+8+9)

| | |
|----|---|
| 50 | 0 |
| b | 0 |
| b | 0 |
| b | 0 |
| 15 | 0 |
| 5 | 0 |
| c | 0 |
| b | 0 |

Resident Population Threat Score

11. Resident Population Threat
 [(lines 1 x 4 x 10)/82500]

| | |
|---|---|
| b | 0 |
|---|---|

a Maximum value applies to waste characteristics category

b Maximum value not applicable

c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a max. of 60.

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SOIL EXPOSURE PATHWAY SCORESHEET (continued)

NEARBY POPULATION THREAT

| <u>Likelihood of Exposure</u> | <u>Maximum Value</u> | <u>Assigned Value</u> |
|----------------------------------|----------------------|-----------------------|
| 12. Attractiveness/Accessibility | <u>100</u> | <u>8</u> |
| 13. Area of Contamination | <u>100</u> | <u>80</u> |
| 14. Likelihood of Exposure | <u>500</u> | <u>25</u> |

Waste Characteristics

| | | |
|------------------------------|------------|--------------|
| 15. Toxicity | <u>a</u> | <u>10000</u> |
| 16. Hazardous Waste Quantity | <u>a</u> | <u>100</u> |
| 17. Waste Characteristics | <u>100</u> | <u>32</u> |

Targets

| | | |
|--------------------------------|----------|----------|
| 18. Nearby Individual | <u>1</u> | <u>1</u> |
| 19. Population Within One Mile | <u>b</u> | <u>1</u> |
| 20. Targets (lines 18+19) | <u>b</u> | <u>1</u> |

Nearby Population Threat Score

| | | |
|--|----------|-------------|
| 21. Nearby Population Threat [(lines 14 x 47 x 20)/82500] | <u>b</u> | <u>0.01</u> |
|--|----------|-------------|

SOIL EXPOSURE PATHWAY SCORE

| | | |
|---|------------|-------------|
| 22. Soil Exposure Pathway Score (Ss) (Lines 11 + 21) | <u>100</u> | 0.01 |
|---|------------|-------------|

- a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a maximum of 10.

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

AIR MIGRATION PATHWAY SCORESHEET

| <u>Likelihood of Release</u> | Maximum Value | Assigned Value |
|---|---------------|----------------|
| 1. Observed Release | 500 | |
| 2. Potential to Release | | |
| 2a. Gas Potential to Release | 500 | 500 |
| 2b. Particulate Potential to Release | 500 | 500 |
| 2c. Potential to Release (Higher of lines 2a and 2b) | 500 | 500 |
| 3. Likelihood of Release (higher of lines 1 and 2c.) | a | 500 |
| <u>Waste Characteristics</u> | | |
| 4. Toxicity/Mobility | a | 10000 |
| 5. Hazardous Waste Quantity | a | 100 |
| 6. Waste Characteristics | 100 | 32 |
| <u>Targets</u> | | |
| 7. Nearest Individual | 50 | 1 |
| 8. Population | | |
| 8a. Level I Concentrations | b | 0 |
| 8b. Level II Concentrations | b | 0 |
| 8c. Potential Contamination | b | 16.4 |
| 8d. Population (lines 8a+8b+8c) | b | 16.4 |
| 9. Resources | 5 | 0 |
| 10. Sensitive Environments | | |
| 10a. Actual Contamination | c | 0 |
| 10b. Potential Contamination | c | 0 |
| 10c. Sensitive Environments (lines 10a+10b) | c | 0.335 |
| 11. Targets (lines 7+8d+9+10c) | b | 17.74 |
| <u>Groundwater Migration Pathway Score</u> | | |
| 12. Pathway Score (Sa) [(lines 3 x 6 x 11)/82500] | 100 | 3.44 |

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. No specific maximum value applies to factor. However, pathway score based solely on sensitive environments cannot be greater than 100

HRS Scoresheets

Scenario #1

Site Name: International Harvester Landfill
Location: Memphis, Tennessee

SITE SCORING SUMMARY

| | |
|---------------------------------------|-------|
| Groundwater Migration Pathway Score | 4.57 |
| | |
| Surface Water Migration Pathway Score | 0.037 |
| | |
| Soil Exposure Migration Pathway Score | 0.01 |
| | |
| Air Migration Pathway Score | 3.44 |
| | |
| Overall Site Score | 2.86 |

HRS Scoresheets

Scenario #2

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

GROUNDWATER MIGRATION PATHWAY SCORESHEET

| <u>Likelihood of Release to an Aquifer</u> | <u>Maximum Value</u> | <u>Aquifer 1 Assigned Value</u> | <u>Aquifer 2 Assigned Value</u> | <u>Aquifer 3 Assigned Value</u> |
|---|----------------------|---------------------------------|---------------------------------|---------------------------------|
| 1. Observed Release | 550 | 550 | 0 | n/a |
| 2. Potential to Release | | | | |
| 2a. Containment | 10 | 10 | 10 | 0 |
| 2b. Net Precipitation | 10 | 3 | 3 | 0 |
| 2c. Depth to Aquifer | 5 | 5 | 1 | 0 |
| 2d. Travel Time | 35 | 25 | 5 | 0 |
| 2e. Potential to Release (lines 2a x (2b+2c+2d)) | 500 | 330 | 90 | 0 |
| 3. Likelihood of Release (higher of lines 1 and 2e.) | 550 | 550 | 90 | 0 |

Waste Characteristics

| | | | | |
|-----------------------------|-----|-----|-----|---|
| 4. Toxicity/Mobility | a | 100 | 100 | 0 |
| 5. Hazardous Waste Quantity | a | 100 | 100 | 0 |
| 6. Waste Characteristics | 100 | 10 | 10 | 0 |

Targets

| | | | | |
|---------------------------------|----|-----|-----|---|
| 7. Nearest Well | 50 | 2 | 2 | 0 |
| 8. Population | | | | |
| 8a. Level I Concentrations | b | 0 | 0 | 0 |
| 8b. Level II Concentrations | b | 0 | 0 | 0 |
| 8c. Potential Contamination | b | 417 | 417 | 0 |
| 8d. Population (lines 8a+8b+8c) | b | 417 | 417 | 0 |
| 9. Resources | 5 | 0 | 0 | 0 |
| 10. Wellhead Protection Area | 20 | 0 | 0 | 0 |
| 11. Targets (lines 7+8d+9+10) | b | 419 | 419 | 0 |

Groundwater Migration Score for an Aquifer

| | | | | |
|--|-----|-------|------|------|
| 12. Aquifer Score [(lines 3 x 6 x 11)/82,500] | 100 | 27.93 | 4.57 | 0.00 |
|--|-----|-------|------|------|

Groundwater Migration Pathway Score

13. Pathway Score (Sgw) – Highest value for all aquifers evaluated 100

27.93

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND FLOOD MIGRATION COMPONENT SCORE SHEET

DRINKING WATER THREAT

| <u>Likelihood of Release</u> | <u>Maximum Value</u> | <u>Watershed 1 Assigned Value</u> | <u>Watershed 2 Assigned Value</u> |
|--|----------------------|-----------------------------------|-----------------------------------|
| 1. Observed Release | 550 | 0 | n/a |
| 2. Potential Release by Overland Flow | | | |
| 2a. Containment | 10 | 9 | |
| 2b. Runoff | 25 | 1 | |
| 2c. Distance to Surface Water | 25 | 6 | |
| 2d. Potential to Release by Overland Flow lines 2a x (2b + 2c) | 500 | 63 | 0 |
| 3. Potential to Release by Flood | | | |
| 3a. Containment | 10 | 10 | |
| 3b. Flood Frequency | 50 | 25 | |
| 3c. Potential to Release by Flood (Lines 3a x 3b) | 500 | 250 | 0 |
| 4. Potential to Release (lines 2d + 3c) | 500 | 313 | 0 |
| 5. Likelihood of Release (Higher of lines 1 and 4) | 550 | 313 | 0 |

Waste Characteristics

| | | | |
|-----------------------------|-----|-------|--|
| 6. Toxicity/Persistence | a | 10000 | |
| 7. Hazardous Waste Quantity | a | 100 | |
| 8. Waste Characteristics | 100 | 32 | |

Targets

| | | | |
|---|----|---|---|
| 9. Nearest Intake | 50 | 0 | |
| 10. Population | | | |
| 10a. Level I Concentrations | b | 0 | |
| 10b. Level II Concentrations | b | 0 | |
| 10c. Potential Contamination | b | 0 | |
| 10d. Population (lines 10a + 10b + 10c) | b | 0 | 0 |
| 11. Resources | 5 | 0 | |
| 12. Targets (lines 9 + 10d + 11) | b | 0 | 0 |

Drinking Water Threat Score

| | | | |
|--|-----|------|---|
| 13. Drinking Water Threat Score [(lines 5 x 8 x 12)/82500] | 100 | 0.00 | 0 |
|--|-----|------|---|

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET (continued)

HUMAN FOOD CHAIN THREAT

| | Maximum Value | Watershed 1 Assigned Value | Watershed 2 Assigned Value |
|---|------------------|----------------------------------|----------------------------------|
| <u>Likelihood of Release</u> | | | |
| 14. Likelihood of Release (Same as line 5) | 550 | 313 | 0 |
| <u>Waste Characteristics</u> | | | |
| 15. Toxicity/Persistence/Bioaccumulation | a | 500000000 | |
| 16. Hazardous Waste Quantity | a | 100 | |
| 17. Waste Characteristics | 1000 | 320 | |
| <u>Targets</u> | | | |
| 18. Food Chain Individual | 50 | 0 | |
| 19. Population | | | |
| 19a. Level I Concentrations | b | 0 | |
| 19b. Level II Concentrations | b | 0 | |
| 19c. Potential Human Food Chain Contamination | b | 0.03 | |
| 19d. Population (lines 19a + 19b + 19c) | b | 0.03 | 0 |
| 20. Targets (lines 18 + 19d) | b | 0.03 | 0 |
| <u>Human Food Chain Threat Score</u> | | | |
| 21. Human Food Chain Threat Score [(lines 14 x 17 x 20)/82500] | 100 | 0.0364 | 0 |

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE SHEET 1
 (continued)

ENVIRONMENTAL THREAT

| | Maximum Value | Watershed 1 Assigned Value | Watershed 2 Assigned Value |
|---|------------------|----------------------------------|----------------------------------|
| <u>Likelihood of Release</u> | | | |
| 22. Likelihood of Release (Same as line 5) | <u>550</u> | <u>313</u> | <u>0</u> |

Waste Characteristics

| | | | |
|--|-------------|------------------|--|
| 23. Ecosystem Toxicity/Persistence/Bioaccumulation | <u>a</u> | <u>500000000</u> | |
| 24. Hazardous Waste Quantity | <u>a</u> | <u>100</u> | |
| 25. Waste Characteristics | <u>1000</u> | <u>320</u> | |

Targets

| | | | |
|--|----------|---------------|----------|
| 26. Sensitive Environments | | | |
| 26a. Level I Concentrations | <u>b</u> | <u>0</u> | |
| 26b. Level II Concentrations | <u>b</u> | <u>0</u> | |
| 26c. Potential Environmental Contamination | <u>b</u> | <u>0.0003</u> | |
| 26d. Population (lines 26a + 26b + 26c) | <u>b</u> | <u>0.0003</u> | <u>0</u> |
| 27. Targets (value on lines 26d) | <u>b</u> | <u>0.0003</u> | <u>0</u> |

Environmental Threat Score

| | | | |
|--|-----------|----------------|----------|
| 28. Environmental Threat Score {(lines 22 x 25 x 27)/82500} | <u>60</u> | <u>0.00036</u> | <u>0</u> |
|--|-----------|----------------|----------|

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE – WATERSHED

| | | | |
|---|------------|--------------|----------|
| 29. Watershed Score (Lines 13 + 21 + 28) | <u>100</u> | <u>0.037</u> | <u>0</u> |
|---|------------|--------------|----------|

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE – WATERSHED

| | | | |
|--|------------|---------------|--|
| 30. Watershed Score (Highest of all watersheds) | <u>100</u> | <u>0.0368</u> | |
|--|------------|---------------|--|

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SOIL EXPOSURE PATHWAY SCORESHEET

RESIDENT POPULATION THREAT

| <u>Likelihood of Exposure</u> | Maximum Value | Assigned Value |
|--|---------------|----------------|
| 1. Likelihood of Exposure | 550 | 550 |
| <u>Waste Characteristics</u> | | |
| 2. Toxicity | a | 10000 |
| 3. Hazardous Waste Quantity | a | 100 |
| 4. Waste Characteristics | 100 | 32 |
| <u>Targets</u> | | |
| 5. Resident Individual | 50 | 0 |
| 6. Resident Population | | |
| 6a. Level I Concentrations | b | 0 |
| 6b. Level II Concentrations | b | 0 |
| 6c. Resident Population (lines 6a+6b) | b | 0 |
| 7. Workers | 15 | 0 |
| 8. Resources | 5 | 0 |
| 9. Terrestrial Sensitive Environments | c | 0 |
| 10. Targets (lines 5+6c+7+8+9) | b | 0 |
| <u>Resident Population Threat Score</u> | | |
| 11. Resident Population Threat [(lines 1 x 4 x 10)/82500] | b | 0 |

a Maximum value applies to waste characteristics category

b Maximum value not applicable

c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments cannot be greater than 0.

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SOIL EXPOSURE PATHWAY SCORE SHEET (continued)

NEARBY POPULATION THREAT

| | Maximum Value | Assigned Value |
|----------------------------------|---------------|----------------|
| <u>Likelihood of Exposure</u> | | |
| 12. Attractiveness/Accessibility | 100 | 5 |
| 13. Area of Contamination | 100 | 80 |
| 14. Likelihood of Exposure | 500 | 25 |

Waste Characteristics

| | | |
|------------------------------|-----|-------|
| 15. Toxicity | a | 10000 |
| 16. Hazardous Waste Quantity | a | 100 |
| 17. Waste Characteristics | 100 | 32 |

Targets

| | | |
|--------------------------------|---|---|
| 18. Nearby Individual | 1 | 0 |
| 19. Population Within One Mile | b | 1 |
| 20. Targets (lines 18+19) | b | 1 |

Nearby Population Threat Score

| | | |
|--|---|------|
| 21. Nearby Population Threat [(lines 14 x 47 x 20)/82500] | b | 0.01 |
|--|---|------|

SOIL EXPOSURE PATHWAY SCORE

| | | |
|---|-----|------|
| 22. Soil Exposure Pathway Score (Ss) (Lines 11 + 21) | 100 | 0.01 |
|---|-----|------|

a. Maximum value applies to waste characteristics category.
 b. Maximum value not applicable.
 c. No specific maximum value applies to factor. However, pathway score based solely on sensitive receptor population (max = 50).

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

AIR MIGRATION PATHWAY SCORESHEET

| <u>Likelihood of Release</u> | Maximum Value | Assigned Value |
|---|---------------|----------------|
| 1. Observed Release | 550 | 0 |
| 2. Potential to Release | | |
| 2a. Gas Potential to Release | 500 | 500 |
| 2b. Particulate Potential to Release | 500 | 500 |
| 2c. Potential to Release (Higher of lines 2a and 2b) | 500 | 500 |
| 3. Likelihood of Release (higher of lines 1 and 2c.) | a | 500 |
| <u>Waste Characteristics</u> | | |
| 4. Toxicity/Mobility | a | 10000 |
| 5. Hazardous Waste Quantity | a | 100 |
| 6. Waste Characteristics | 100 | 32 |
| <u>Targets</u> | | |
| 7. Nearest Individual | 50 | 1 |
| 8. Population | | |
| 8a. Level I Concentrations | b | 0 |
| 8b. Level II Concentrations | b | 0 |
| 8c. Potential Contamination | b | 16.4 |
| 8d. Population (lines 8a+8b+8c) | b | 16.4 |
| 9. Resources | 5 | 0 |
| 10. Sensitive Environments | | |
| 10a. Actual Contamination | c | 0 |
| 10b. Potential Contamination | c | 0 |
| 10c. Sensitive Environments (lines 10a+10b) | c | 0.335 |
| 11. Targets (lines 7+8d+9+10c) | b | 17.74 |
| <u>Groundwater Migration Pathway Score</u> | | |
| 12. Pathway Score (Sa) [(lines 3 x 6 x 11)/82500] | 100 | 3.44 |

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a maximum of 0.

HRS Scoresheets

Scenario #2

Site Name: International Harvester Landfill
Location: Memphis, Tennessee

SITE SCORING SUMMARY

| | |
|---------------------------------------|-------|
| Groundwater Migration Pathway Score | 27.93 |
| Surface Water Migration Pathway Score | 0.037 |
| Soil Exposure Migration Pathway Score | 0.01 |
| Air Migration Pathway Score | 3.44 |
| Overall Site Score | 14.07 |

HRS Scoresheets

Scenario #3

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

GROUNDWATER MIGRATION PATHWAY SCORESHEET

| <u>Likelihood of Release to an Aquifer</u> | <u>Maximum Value</u> | <u>Aquifer 1 Assigned Value</u> | <u>Aquifer 2 Assigned Value</u> | <u>Aquifer 3 Assigned Value</u> |
|---|----------------------|---------------------------------|---------------------------------|---------------------------------|
| 1. Observed Release | 550 | 550 | 0 | 0 |
| 2. Potential to Release | | | | |
| 2a. Containment | 10 | 10 | 10 | 10 |
| 2b. Net Precipitation | 10 | 3 | 3 | 3 |
| 2c. Depth to Aquifer | 5 | 5 | 1 | 1 |
| 2d. Travel Time | 35 | 25 | 5 | 5 |
| 2e. Potential to Release (lines 2a x (2b+2c+2d)) | 500 | 330 | 90 | 90 |
| 3. Likelihood of Release (higher of lines 1 and 2e.) | 550 | 550 | 90 | 90 |

Waste Characteristics

| | | | | |
|-----------------------------|-----|-----|-----|-----|
| 4. Toxicity/Mobility | a | 100 | 100 | 100 |
| 5. Hazardous Waste Quantity | a | 100 | 100 | 100 |
| 6. Waste Characteristics | 100 | 10 | 10 | 10 |

Targets

| | | | | |
|---------------------------------|----|-----|-----|-----|
| 7. Nearest Well | 50 | 2 | 2 | 2 |
| 8. Population | | | | |
| 8a. Level I Concentrations | b | 0 | 0 | 0 |
| 8b. Level II Concentrations | b | 0 | 0 | 0 |
| 8c. Potential Contamination | b | 0.4 | 417 | 417 |
| 8d. Population (lines 8a+8b+8c) | b | 0.4 | 417 | 417 |
| 9. Resources | 5 | 0 | 0 | 0 |
| 10. Wellhead Protection Area | 20 | 0 | 0 | 0 |
| 11. Targets (lines 7+8d+9+10) | b | 2.4 | 419 | 419 |

Groundwater Migration Score for an Aquifer

| | | | | |
|--|-----|------|------|------|
| 12. Aquifer Score [(lines 3 x 6 x 11)/82,500] | 100 | 0.16 | 4.57 | 4.57 |
|--|-----|------|------|------|

Groundwater Migration Pathway Score

| | | | | |
|--|-----|--|--|--|
| 13. Pathway Score (Sgw) – Highest value for all aquifers evaluated | 100 | | | |
|--|-----|--|--|--|

4.57

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE SHEET

DRINKING WATER THREAT

| <u>Likelihood of Release</u> | <u>Maximum Value</u> | <u>Watershed 1 Assigned Value</u> | <u>Watershed 2 Assigned Value</u> |
|---|----------------------|-----------------------------------|-----------------------------------|
| 1. Observed Release | 550 | 550 | n/a |
| 2. Potential Release by Overland Flow | | | |
| 2a. Containment | 10 | 0 | |
| 2b. Runoff | 25 | 1 | |
| 2c. Distance to Surface Water | 25 | 0 | |
| 2d. Potential to Release by Overland Flow lines 2a x (2b + 2c) | 500 | 63 | 0 |
| 3. Potential to Release by Flood | | | |
| 3a. Containment | 10 | 10 | |
| 3b. Flood Frequency | 50 | 25 | |
| 3c. Potential to Release by Flood (Lines 3a x 3b) | 500 | 250 | 0 |
| 4. Potential to Release (lines 2d + 3c) | 500 | 313 | 0 |
| 5. Likelihood of Release (Higher of lines 1 and 4) | 550 | 550 | 0 |

Waste Characteristics

| | | | |
|-----------------------------|-----|-------|--|
| 6. Toxicity/Persistence | a | 10000 | |
| 7. Hazardous Waste Quantity | a | 100 | |
| 8. Waste Characteristics | 100 | 32 | |

Targets

| | | | |
|---|----|---|---|
| 9. Nearest Intake | 50 | 0 | |
| 10. Population | | | |
| 10a. Level I Concentrations | b | 0 | |
| 10b. Level II Concentrations | b | 0 | |
| 10c. Potential Contamination | b | 0 | |
| 10d. Population (lines 10a + 10b + 10c) | b | 0 | 0 |
| 11. Resources | 5 | 0 | |
| 12. Targets (lines 9 + 10d + 11) | b | 0 | 0 |

Drinking Water Threat Score

| | | | |
|---|-----|------|---|
| 13. Drinking Water Threat Score [(lines 5 x 8 x 12)/82500] | 100 | 0.00 | 0 |
|---|-----|------|---|

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORESHEET (continued)

HUMAN FOOD CHAIN THREAT

| | Maximum Value | Watershed 1 Assigned Value | Watershed 2 Assigned Value |
|---|------------------|----------------------------------|----------------------------------|
| <u>Likelihood of Release</u> | | | |
| 14. Likelihood of Release (Same as line 5) | 550 | 550 | 0 |
| <u>Waste Characteristics</u> | | | |
| 15. Toxicity/Persistence/Bioaccumulation | a | 500000000 | |
| 16. Hazardous Waste Quantity | a | 100 | |
| 17. Waste Characteristics | 1000 | 320 | |
| <u>Targets</u> | | | |
| 18. Food Chain Individual | 50 | 45 | |
| 19. Population | | | |
| 19a. Level I Concentrations | b | 0 | |
| 19b. Level II Concentrations | b | 0 | |
| 19c. Potential Human Food Chain Contamination | b | 0.03 | |
| 19d. Population (lines 19a + 19b + 19c) | b | 0.03 | 0 |
| 20. Targets (lines 18 + 19d) | b | 45.03 | 0 |
| <u>Human Food Chain Threat Score</u> | | | |
| 21. Human Food Chain Threat Score [(lines 14 x 17 x 20)/82500] | 100 | 96.0640 | 0 |

a Maximum value applies to waste characteristics category
 b Maximum value not applicable
 c Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE SHEET
 (continued)

ENVIRONMENTAL THREAT

| | Maximum Value | Watershed 1 Assigned Value | Watershed 2 Assigned Value |
|--|------------------|----------------------------------|----------------------------------|
| <u>Likelihood of Release</u> | | | |
| 22. Likelihood of Release (Same as line 5) | 550 | 550 | 0 |
| <u>Waste Characteristics</u> | | | |
| 23. Ecosystem Toxicity/Persistence/Bioaccumulation | a | 500000000 | |
| 24. Hazardous Waste Quantity | a | 100 | |
| 25. Waste Characteristics | 1000 | 320 | |
| <u>Targets</u> | | | |
| 26. Sensitive Environments | | | |
| 26a. Level I Concentrations | b | 0 | |
| 26b. Level II Concentrations | b | 0 | |
| 26c. Potential Environmental Contamination | b | 0.0003 | |
| 26d. Population (lines 26a + 26b + 26c) | b | 0.0003 | 0 |
| 27. Targets (value on lines 26d) | b | 0.0003 | 0 |
| <u>Environmental Threat Score</u> | | | |
| 28. Environmental Threat Score [(lines 22 x 25 x 27)/82500] | 60 | 0.00064 | 0 |

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE – WATERSHED

| | | | |
|---|-----|--------|---|
| 29. Watershed Score (Lines 13 + 21 + 28) | 100 | 96.065 | 0 |
|---|-----|--------|---|

SURFACE WATER OVERLAND/FLOOD MIGRATION COMPONENT SCORE – WATERSHED

| | | | |
|--|-----|----------------|--|
| 30. Watershed Score (Highest of all watersheds) | 100 | 96.0646 | |
|--|-----|----------------|--|

- a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. Do not round to nearest integer

Site Name: International Harvester Landfill
 Location: Memphis Tennessee

SOIL EXPOSURE PATHWAY SCORESHEET

RESIDENT POPULATION THREAT

| <u>Likelihood of Exposure</u> | Maximum Value | Assigned Value |
|--|---------------|----------------|
| 1. Likelihood of Exposure | 550 | 550 |
| <u>Waste Characteristics</u> | | |
| 2. Toxicity | a | 10000 |
| 3. Hazardous Waste Quantity | a | 100 |
| 4. Waste Characteristics | 100 | 32 |
| <u>Targets</u> | | |
| 5. Resident Individual | 50 | 0 |
| 6. Resident Population | | |
| 6a. Level I Concentrations | b | 0 |
| 6b. Level II Concentrations | b | 0 |
| 6c. Resident Population (lines 6a+6b) | b | 0 |
| 7. Workers | 15 | 0 |
| 8. Resources | 5 | 0 |
| 9. Terrestrial Sensitive Environments | c | 0 |
| 10. Targets (lines 5+6c+7+8+9) | b | 0 |
| <u>Resident Population Threat Score</u> | | |
| 11. Resident Population Threat [(lines 1 x 4 x 10)/82500] | b | 0 |

a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a maximum of 0.

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

SOIL EXPOSURE PATHWAY SCORESHEET (continued)

NEARBY POPULATION THREAT

| <u>Likelihood of Exposure</u> | Maximum Value | Assigned Value |
|----------------------------------|---------------|----------------|
| 12. Attractiveness/Accessibility | 100 | 5 |
| 13. Area of Contamination | 100 | 80 |
| 14. Likelihood of Exposure | 500 | 25 |

Waste Characteristics

| | | |
|------------------------------|-----|-------|
| 15. Toxicity | a | 10000 |
| 16. Hazardous Waste Quantity | a | 100 |
| 17. Waste Characteristics | 100 | 32 |

Targets

| | | |
|--------------------------------|---|---|
| 18. Nearby Individual | 1 | 0 |
| 19. Population Within One Mile | b | 1 |
| 20. Targets (lines 18+19) | b | 1 |

Nearby Population Threat Score

| | | |
|--|---|------|
| 21. Nearby Population Threat [(lines 14 x 47 x 20)/82500] | b | 0.01 |
|--|---|------|

SOIL EXPOSURE PATHWAY SCORE

| | | |
|---|-----|------|
| 22. Soil Exposure Pathway Score (Ss) (Lines 11 + 21) | 100 | 0.01 |
|---|-----|------|

a. Maximum value applies to waste characteristics category
 b. Maximum value not applicable
 c. No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a maximum

Site Name: International Harvester Landfill
 Location: Memphis, Tennessee

AIR MIGRATION PATHWAY SCORESHEET

| <u>Likelihood of Release</u> | Maximum Value | Assigned Value |
|---|---------------|----------------|
| 1. Observed Release | 550 | |
| 2. Potential to Release | | |
| 2a. Gas Potential to Release | 500 | 500 |
| 2b. Particulate Potential to Release | 500 | 500 |
| 2c. Potential to Release (Higher of lines 2a and 2b) | 500 | 500 |
| 3. Likelihood of Release (higher of lines 1 and 2c.) | a | 500 |

Waste Characteristics

| | | |
|-----------------------------|-----|-------|
| 4. Toxicity/Mobility | a | 10000 |
| 5. Hazardous Waste Quantity | a | 100 |
| 6. Waste Characteristics | 100 | 32 |

Targets

| | | |
|---|----|-------|
| 7. Nearest Individual | 50 | 1 |
| 8. Population | | |
| 8a. Level I Concentrations | b | 0 |
| 8b. Level II Concentrations | b | 0 |
| 8c. Potential Contamination | b | 16.4 |
| 8d. Population (lines 8a + 8b + 8c) | b | 16.4 |
| 9. Resources | 5 | 0 |
| 10. Sensitive Environments | | |
| 10a. Actual Contamination | c | 0 |
| 10b. Potential Contamination | c | 0 |
| 10c. Sensitive Environments (lines 10a + 10b) | c | 0.335 |
| 11. Targets (lines 7 + 8d + 9 + 10c) | b | 17.74 |

Groundwater Migration Pathway Score

| | | |
|--|-----|------|
| 12. Pathway Score (Sa) [(lines 3 x 6 x 11)/82500] | 100 | 3.44 |
|--|-----|------|

a. Maximum value applies to waste characteristics category

b. Maximum value not applicable

c. No specific maximum value applies to factor. However, pathway score based solely on sensitive environments is limited to a maximum of 100

HRS Scoresheets

Scenario #3

Site Name: International Harvester Landfill
Location: Memphis, Tennessee

SITE SCORING SUMMARY

| | |
|---------------------------------------|--------|
| Groundwater Migration Pathway Score | 4.57 |
| | |
| Surface Water Migration Pathway Score | 96.065 |
| | |
| Soil Exposure Migration Pathway Score | 0.01 |
| | |
| Air Migration Pathway Score | 3.44 |
| | |
| Overall Site Score | 48.12 |

APPENDIX C

SITE INSPECTION WORKSHEETS

This appendix consists of worksheets that can be used to generate an SI site score. Completion of these worksheets is not required, but the SI investigator must evaluate an SI score, either by these worksheets, *PREscore*, or other Regional scoring tools.

The worksheets consist of instructions and data tables to be filled in with scores from HRS reference tables. The data tables may also call for Data Type and References.

DATA TYPE: The Data Type columns should be filled in with an H, Q, or + if the data are HRS quality and well documented. The Data Type column should be filled in with an E, X, or - if the data represent estimates, approximations, or are not fully documented. This type identifies data gaps for the expanded SI to investigate.

REFERENCES: The Reference columns should be filled in with coded reference numbers. The numbered reference list should be attached or the numbering should be cross-referenced to the SI Narrative Report.

The SI investigator will need the current Superfund Chemical Data Matrix (SCDM) OSWER Directive 9345.1-13 (revised semi-annually) to complete these worksheets.

SITE INSPECTION WORKSHEETS

| |
|-------------------------------|
| CERCLIS IDENTIFICATION NUMBER |
|-------------------------------|

| SITE LOCATION | | | |
|--|-------|------------------------------|------------------|
| SITE NAME: LEGAL, COMMON, OR DESCRIPTIVE NAME OF SITE | | | |
| STREET ADDRESS, ROUTE, OR SPECIFIC LOCATION IDENTIFIER | | | |
| CITY | STATE | ZIP CODE | TELEPHONE () |
| COORDINATES: LATITUDE and LONGITUDE | | TOWNSHIP, RANGE, AND SECTION | |

| OWNER/OPERATOR IDENTIFICATION | | | | | |
|-------------------------------|----------|------------------|------------------|----------|------------------|
| OWNER | | | OPERATOR | | |
| OWNER ADDRESS | | | OPERATOR ADDRESS | | |
| CITY | | | CITY | | |
| STATE | ZIP CODE | TELEPHONE () | STATE | ZIP CODE | TELEPHONE () |

| SITE EVALUATION | | |
|---------------------|-------|----------|
| AGENCY/ORGANIZATION | | |
| INVESTIGATOR | | |
| CONTACT | | |
| ADDRESS | | |
| CITY | STATE | ZIP CODE |
| TELEPHONE () | | |

GENERAL INFORMATION

Site Description and Operational History: Provide a brief description of the site and its operational history. State the site name, owner, operator, type of facility and operations, size of property, active or inactive status, and years of waste generation. Summarize waste treatment, storage, or disposal activities that have or may have occurred at the site; note whether these activities are documented or alleged. Identify all source types and prior spills, floods, or fires. Summarize highlights of the PA and other investigations. Cite references.

This image shows a single sheet of white paper with horizontal black ruling lines. The lines are evenly spaced and run across the width of the page. There is no handwriting or other markings on the paper.

GENERAL INFORMATION (continued)

Site Sketch: Provide a sketch of the site. Indicate all pertinent features of the site and nearby environments including sources of wastes, areas of visible and buried wastes, buildings, residences, access roads, parking areas, fences, fields, drainage patterns, water bodies, vegetation, wells, sensitive environments, and other features.

[Faint, illegible handwritten text]

GENERAL INFORMATION (continued)

Source Descriptions: Describe all sources at the site. Identify source type and relate to waste disposal operations. Provide source dimensions and the best available waste quantity information. Describe the condition of sources and all containment structures. Cite references.

SOURCE TYPES

Landfill: A man-made (by excavation or construction) or natural hole in the ground into which wastes have come to be disposed by backfilling, or by contemporaneous soil deposition with waste disposal.

Surface Impoundment: A natural topographic depression, man-made excavation, or diked area, primarily formed from earthen materials (lined or unlined) and designed to hold an accumulation of liquid wastes, wastes containing free liquids, or sludges not backfilled or otherwise covered; depression may be wet with exposed liquid or dry if deposited liquid has evaporated, volatilized or leached; structures that may be described as lagoon, pond, aeration pit, settling pond, tailings pond, sludge pit; also a surface impoundment that has been covered with soil after the final deposition of waste materials (i.e., buried or backfilled).

Drum: A portable container designed to hold a standard 55-gallon volume of wastes.

Tank and Non-Drum Container: Any device, other than a drum, designed to contain an accumulation of waste that provides structural support and is constructed primarily of fabricated materials (such as wood, concrete, steel, or plastic); any portable or mobile device in which waste is stored or otherwise handled.

Contaminated Soil: An area or volume of soil onto which hazardous substances have been spilled, spread, disposed, or deposited.

Pile: Any non-containerized accumulation above the ground surface of solid, non-flowing wastes; includes open dumps. Some types of waste piles are:

- **Chemical Waste Pile:** A pile consisting primarily of discarded chemical products, by-products, radioactive wastes, or used or unused feedstocks.
- **Scrap Metal or Junk Pile:** A pile consisting primarily of scrap metal or discarded durable goods (such as appliances, automobiles, auto parts, batteries, etc.) composed of materials containing hazardous substances.
- **Tailings Pile:** A pile consisting primarily of any combination of overburden from a mining operation and tailings from a mineral mining, beneficiation, or processing operation.
- **Trash Pile:** A pile consisting primarily of paper, garbage, or discarded non-durable goods containing hazardous substances.

Land Treatment: Landfarming or other method of waste management in which liquid wastes or sludges are spread over land and tilled, or liquids are injected at shallow depths into soils.

Other: Sources not in categories listed above.

GENERAL INFORMATION (continued)

Source Description: Include description of containment per pathway for ground water (see HRS Table 3-2), surface water (see HRS Table 4-2), and air (see HRS Tables 6-3 and 6-9).

10-2

Hazardous Waste Quantity (HWQ) Calculation: SI Tables 1 and 2 (See HRS Tables 2-5, 2-6, and 5-2).

10005

— 1 —

Attach additional pages, if necessary

HWQ - 100

SI TABLE 1: HAZARDOUS WASTE QUANTITY (HWQ) SCORES FOR SINGLE SOURCE SITES AND FORMULAS FOR MULTIPLE SOURCE SITES

| | | Single Source Sites (assigned HWQ scores) | |
|--|----------------------------------|---|--|
| (Column 1) TIER | (Column 2) Source Type | (Column 3) HWQ = 10 | (Column 4) HWQ = 100 |
| A Hazardous Constituent Quantity | N/A | HWQ = 1 if Hazardous Constituent Quantity data are complete HWQ = 10 if Hazardous Constituent Quantity data are not complete | >100 to 10,000 lbs |
| B Hazardous Wastestream Quantity | N/A | ≤ 500,000 lbs | >500,000 to 50 million lbs |
| C Volume | Landfill | ≤ 6.75 million ft ³ ≤ 250,000 yd ³ | >6.75 million to 675 million ft ³ >250,000 to 25 million yd ³ |
| | Surface impoundment | ≤ 6,750 ft ³ ≤ 250 yd ³ | >6,750 to 675,000 ft ³ >250 to 25,000 yd ³ |
| | Drums | ≤ 1,000 drums | >1,000 to 100,000 drums |
| | Tanks and non-drum containers | ≤ 50,000 gallons | >50,000 to 5 million gallons |
| | Contaminated soil | ≤ 6.75 million ft ³ ≤ 250,000 yd ³ | >6.75 million to 675 million ft ³ >250,000 to 25 million yd ³ |
| | Pile | ≤ 6,750 ft ³ ≤ 250 yd ³ | >6,750 to 675,000 ft ³ >250 to 25,000 yd ³ |
| | Other | ≤ 6,750 ft ³ ≤ 250 yd ³ | >6,750 to 675,000 ft ³ >250 to 25,000 yd ³ |
| D Area | Landfill | ≤ 340,000 ft ² ≤ 7.8 acres | >340,000 to 34 million ft ² >7.8 to 780 acres |
| | Surface impoundment | ≤ 1,300 ft ² ≤ 0.029 acres | >1,300 to 130,000 ft ² >0.029 to 2.9 acres |
| | Contaminated soil | ≤ 3.4 million ft ² ≤ 78 acres | > 3.4 million to 340 million ft ² > 78 to 7,800 acres |
| | Pile | ≤ 1,300 ft ² ≤ 0.029 acres | >1,300 to 130,000 ft ² >0.029 to 2.9 acres |
| | Land treatment | ≤ 27,000 ft ² ≤ 0.62 acres | >27,000 to 2.7 million ft ² >0.62 to 62 acres |

TABLE 1 (CONTINUED)

| Single Source Sites (assigned HWQ scores) | | Multiple Source Sites | | |
|--|---|--|----------------------------------|--|
| (Column 5) HWQ = 10,000 | (Column 6) HWQ = 1,000,000 | (Column 7) Divisors for Assigning Source WQ Values | (Column 2) Source Type | (Column 1) TIER |
| >10,000 to 1 million lbs | > 1 million lbs | lbs + 1 | N/A | A Hazardous Constituent Quantity |
| >50 million to 5 billion lbs | > 5 billion lbs | lbs + 5,000 | N/A | B Hazardous Wastestream Quantity |
| >675 million to 67.5 billion ft ³ >25 million to 2.5 billion yd ³ | > 67.5 billion ft ³ > 2.5 billion yd ³ | ft ³ + 67,500 yd ³ + 2,500 | Landfill | C Volume |
| >675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³ | > 67.5 million ft ³ > 2.5 million yd ³ | ft ³ + 67.5 yd ³ + 2.5 | Surface Impoundment | |
| >100,000 to 10 million drums | > 10 million drums | drums + 10 | Drums | |
| >5 million to 500 million gallons | > 500 million gallons | gallons + 500 | Tanks and non-drum containers | |
| >675 million to 67.5 billion ft ³ >25 million to 2.5 billion yd ³ | > 67.5 billion ft ³ > 2.5 billion yd ³ | ft ³ + 67,500 yd ³ + 2,500 | Contaminated Soil | |
| >675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³ | > 67.5 million ft ³ > 2.5 million yd ³ | ft ³ + 67.5 yd ³ + 2.5 | Pile | |
| >675,000 to 67.5 million ft ³ >25,000 to 2.5 million yd ³ | > 67.5 million ft ³ > 2.5 million yd ³ | ft ³ + 67.5 yd ³ + 2.5 | Other | |
| >34 million to 3.4 billion ft ² >780 to 78,000 acres | > 3.4 billion ft ² >78,000 acres | ft ² + 3,400 acres + 0.078 | Landfill | D Area |
| >130,000 to 13 million ft ² >2.9 to 290 acres | > 13 million ft ² > 290 acres | ft ² + 13 acres + 0.00029 | Surface Impoundment | |
| > 340 million to 34 billion ft ² > 7,800 to 780,000 acres | > 34 billion ft ² > 780,000 acres | ft ² + 34,000 acres + 0.78 | Contaminated Soil | |
| > 130,000 to 13 million ft ² > 2.9 to 290 acres | > 13 million ft ² > 290 acres | ft ² + 13 acres + 0.00029 | Pile | |
| >2.7 million to 270 million ft ² >62 to 6,200 acres | > 270 million ft ² > 6,200 acres | ft ² + 270 acres + 0.0062 | Land Treatment | |

HAZARDOUS WASTE QUANTITY (HWQ) CALCULATION

For each migration pathway, evaluate HWQ associated with sources that are available (i.e., incompletely contained) to migrate to that pathway. (Note: If *Actual Contamination Targets* exist for ground water, surface water, or air migration pathways, assign the calculated HWQ score or 100, whichever is greater, as the HWQ score for that pathway.) For each source, evaluate HWQ for one or more of the four tiers (SI Table 1; HRS Table 2-5) for which data exist: constituent quantity, wastestream quantity, source volume, and source area. Select the tier that gives the highest value as the source HWQ. Select the source volume HWQ rather than source area HWQ if data for both tiers are available.

Column 1 of SI Table 1 indicates the quantity tier. Column 2 lists source types for the four tiers. Columns 3, 4, 5, and 6 provide ranges of waste amount for sites with only one source, corresponding to HWQ scores at the tops of the columns. Column 7 provides formulas to obtain source waste quantity values at sites with multiple sources.

1. Identify each source type.
2. Examine all waste quantity data available for each source. Record constituent quantity and waste stream mass or volume. Record dimensions of each source.
3. Convert source measurements to appropriate units for each tier to be evaluated.
4. For each source, use the formulas in the last column of SI Table 1 to determine the waste quantity value for each tier that can be evaluated. Use the waste quantity value obtained from the highest tier as the quantity value for the source.
5. Sum the values assigned to each source to determine the total site waste quantity.
6. Assign HWQ score from SI Table 2 (HRS Table 2-6).

Note these exceptions to evaluate soil exposure pathway HWQ (see HRS Table 5-2):

- The divisor for the area (square feet) of a landfill is 34,000.
- The divisor for the area (square feet) of a pile is 34.
- Wet surface impoundments and tanks and non-drum containers are the only sources for which volume measurements are evaluated for the soil exposure pathway.

SI TABLE 2: HWQ SCORES FOR SITES

| Site WQ Total | HWQ Score |
|-----------------------|----------------|
| 0 | 0 |
| 1 ^a to 100 | 1 ^b |
| > 100 to 10,000 | 100 |
| > 10,000 to 1 million | 10,000 |
| > 1 million | 1,000,000 |

^a If the WQ total is between 0 and 1, round it to 1.

^b If the hazardous constituent quantity data are not complete, assign the score of 10.

References

Site Name: _____

| | | |
|----|----|----|
| 1. | 4. | 7. |
| 2. | 5. | 8. |
| 3. | 6. | 9. |

C-11

Ground Water Observed Release Substances Summary Table

On SI Table 4, list the hazardous substances associated with the site detected in ground water samples for that aquifer. Include only those substances directly observed or with concentrations significantly greater than background levels. Obtain toxicity values from the Superfund Chemical Data Matrix (SCDM). Assign mobility a value of 1 for all observed release substances regardless of the aquifer being evaluated. For each substance, multiply the toxicity by the mobility to obtain the toxicity/mobility factor value; enter the highest toxicity/mobility value for the aquifer in the space provided.

Ground Water Actual Contamination Targets Summary Table

If there is an observed release at a drinking water well, enter each hazardous substance meeting the requirements for an observed release by well and sample ID on SI Table 5 and record the detected concentration. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population using the well as a Level I target. If these percentages are less than 100% or all are N/A, evaluate the population using the well as a Level II target for that aquifer.

Describe Ground Water Use within 4 Miles of the Site:
Describe generalized stratigraphy, aquifers, municipal and private wells

Show Calculations of Ground Water Drinking Water Populations for each Aquifer:
Provide apportionment calculations for blended supply systems.
County average number of persons per household: 2.65 Reference 10

C-14

GROUND WATER PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE

| | Score | Data Type | Ref's |
|--|-------|-----------|-------|
| 1. OBSERVED RELEASE: If sampling data or direct observation support a release to the aquifer, assign a score of 550. Record observed release substances on SI Table 4 | | | |
| 2. POTENTIAL TO RELEASE: Depth to aquifer: _____ feet. If sampling data do not support a release to the aquifer, and the site is in karst terrain or the depth to aquifer is 70 feet or less, assign a score of 500; otherwise, assign a score of 340. Optionally, evaluate potential to release according to HRS Section 3. | | | |

LR = 250

TARGETS

| | | | |
|--|--|--|--|
| Are any wells part of a blended system? Yes _____ No _____ If yes, attach a page to show apportionment calculations. | | | |
| 3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates that any target drinking water well for the aquifer has been exposed to a hazardous substance from the site, evaluate the factor score for the number of people served (SI Table 5). Level I: _____ people x 10 = _____ Level II: _____ people x 1 = _____ Total = _____ | | | |
| 4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water wells for the aquifer or overlying aquifers that are not exposed to a hazardous substance from the site; record the population for each distance category in SI Table 6a or 6b. Sum the population values and multiply by 0.1. | | | |
| 5. NEAREST WELL: Assign a score of 50 for any Level I Actual Contamination Targets for the aquifer or overlying aquifer. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Targets exist, assign the Nearest Well score from SI Table 6a or 6b. If no drinking water wells exist within 4 miles, assign 0. | | | |
| 6. WELLHEAD PROTECTION AREA (WHPA): If any source lies within or above a WHPA for the aquifer, or if a ground water observed release has occurred within a WHPA, assign a score of 20; assign 5 if neither condition applies but a WHPA is within 4 miles; otherwise assign 0. | | | |
| 7. RESOURCES: Assign a score of 5 if one or more ground water resource applies; assign 0 if none applies. <ul style="list-style-type: none"> Irrigation (5 acre minimum) of commercial food crops or commercial forage crops Watering of commercial livestock Ingredient in commercial food preparation Supply for commercial aquaculture Supply for a major or designated water recreation area, excluding drinking water use | | | |

Sum of Targets T= 250

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER TARGET POPULATIONS

SI Table 6a: Other Than Karst Aquifers

| Distance from Site | Nearest Well (choose highest) | Population Served by Wells within Distance Category | | | | | | | | | | | | Pop. Value | Ref. |
|-------------------------------------|-------------------------------|---|----------|-----------|------------|-------------|--------------|----------------|------------------|-------------------|--------------------|----------------------|------------------------|------------|------|
| | | 1 to 10 | 11 to 30 | 31 to 100 | 101 to 300 | 301 to 1000 | 1001 to 3000 | 3001 to 10,000 | 10,001 to 30,000 | 30,001 to 100,000 | 100,001 to 300,000 | 300,001 to 1,000,000 | 1,000,000 to 3,000,000 | | |
| 0 to $\frac{1}{4}$ mile | 20 | 4 | 17 | 53 | 164 | 522 | 1,633 | 5,214 | 16,325 | 52,137 | 163,246 | 521,360 | 1,632,455 | | |
| $\frac{1}{4}$ to $\frac{1}{2}$ mile | 18 | 2 | 11 | 33 | 102 | 324 | 1,013 | 3,233 | 10,122 | 32,325 | 101,213 | 323,243 | 1,012,122 | | |
| $\frac{1}{2}$ to 1 mile | 9 | 1 | 5 | 17 | 52 | 167 | 523 | 1,669 | 5,224 | 16,684 | 52,239 | 166,835 | 522,385 | | |
| > 1 to 2 miles | 5 | 0.7 | 3 | 10 | 30 | 94 | 294 | 939 | 2,939 | 9,385 | 29,384 | 93,845 | 293,842 | | |
| > 2 to 3 miles | 3 | 0.5 | 2 | 7 | 21 | 68 | 212 | 678 | 2,122 | 6,778 | 21,222 | 67,777 | 212,219 | | |
| > 3 to 4 miles | (2) | 0.3 | 1 | (4) | 13 | 42 | 131 | 417 | 1,306 | 4,171 | 13,060 | 41,709 | 130,596 | | |
| Nearest Well = | 2 / 2 / 2 | | | | | | | | | | | | | Sum = | 14 |

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER
TARGET POPULATIONS (continued)

SI Table 6b: Karst Aquifers

| Distance from Site | Pop. | Nearest Well (choose highest) | Population Served by Wells within Distance Category | | | | | | | | | | | | Pop. Value | Ref. |
|-------------------------------------|------|-------------------------------|---|----------|-----------|------------|-------------|--------------|----------------|------------------|-------------------|--------------------|----------------------|------------------------|------------|------|
| | | | 1 to 10 | 11 to 30 | 31 to 100 | 101 to 300 | 301 to 1000 | 1001 to 3000 | 3001 to 10,000 | 10,001 to 30,000 | 30,001 to 100,000 | 100,001 to 300,000 | 300,001 to 1,000,000 | 1,000,000 to 3,000,000 | | |
| 0 to $\frac{1}{4}$ mile | | 20 | 4 | 17 | 53 | 164 | 522 | 1,633 | 5,214 | 16,325 | 52,137 | 163,246 | 521,360 | 1,632,455 | | |
| $\frac{1}{4}$ to $\frac{1}{2}$ mile | | 20 | 2 | 11 | 33 | 102 | 324 | 1,013 | 3,233 | 10,122 | 32,325 | 101,213 | 323,243 | 1,012,122 | | |
| $\frac{1}{2}$ to 1 mile | | 20 | 2 | 9 | 26 | 82 | 261 | 817 | 2,607 | 8,163 | 26,068 | 81,623 | 260,680 | 816,227 | | |
| > 1 to 2 miles | | 20 | 2 | 9 | 26 | 82 | 261 | 817 | 2,607 | 8,163 | 26,068 | 81,623 | 260,680 | 816,227 | | |
| > 2 to 3 miles | | 20 | 2 | 9 | 26 | 82 | 261 | 817 | 2,607 | 8,163 | 26,068 | 81,623 | 260,680 | 816,227 | | |
| > 3 to 4 miles | | 20 | 2 | 9 | 26 | 82 | 261 | 817 | 2,607 | 8,163 | 26,068 | 81,623 | 260,680 | 816,227 | | |
| Nearest Well = | | | Sum = | | | | | | | | | | | | | |

GROUND WATER PATHWAY WORKSHEET (concluded)

| WASTE CHARACTERISTICS | Score | Data Type | Does not Apply |
|--|-------|-----------|----------------|
| 8. If any Actual Contamination Targets exist for the aquifer or overlying aquifers, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if no Actual Contamination Targets exist, assign the hazardous waste quantity score calculated for sources available to migrate to ground water. | 100 | | |
| 9. Assign the highest ground water toxicity/mobility value from SI Table 3 or 4. | 100 | | |
| 10. Multiply the ground water toxicity/mobility and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below: (from HRS Table 2-7) | | | |

| Product | WC Score |
|---------------------|----------|
| 0 | 0 |
| >0 to <10 | 1 |
| 10 to <100 | 2 |
| 100 to <1,000 | 3 |
| 1,000 to <10,000 | 6 |
| 10,000 to <1E + 05 | 10 |
| 1E + 05 to <1E + 06 | 18 |
| 1E + 06 to <1E + 07 | 32 |
| 1E + 07 to <1E + 08 | 56 |
| 1E + 08 or greater | 100 |

WC =

Multiply LR by T and by WC. Divide the product by 82,500 to obtain the ground water pathway score for each aquifer. Select the highest aquifer score. If the pathway score is greater than 100, assign 100.

GROUND WATER PATHWAY SCORE:

$$\frac{LR \times T \times WC}{82,500}$$

(Maximum of 100)

SURFACE WATER PATHWAY

Sketch of the Surface Water Migration Route:

Label all surface water bodies. Include runoff route and drainage direction, probable point of entry, and 15-mile target distance limit. Mark sample locations, intakes, fisheries, and sensitive environments. Indicate flow directions, tidal influence, and rate.

SURFACE WATER PATHWAY

Surface Water Observed Release Substances Summary Table

On SI Table 7, list the hazardous substances detected in surface water samples for the watershed which can be attributed to the site. Include only those substances in observed releases (direct observation) or with concentration levels significantly above background levels. Obtain toxicity, persistence, bioaccumulation potential, and ecotoxicity values from SCDM. Enter the highest toxicity/persistence, toxicity/persistence/bioaccumulation, and ecotoxicity/persistence/ecobioaccumulation values in the spaces provided.

- TP = Toxicity x Persistence
- TPB = TP x bioaccumulation
- ETPB = EP x bioaccumulation (EP = ecotoxicity x persistence)

Drinking Water Actual Contamination Targets Summary Table

For an observed release at or beyond a drinking water intake, on SI Table 8 enter each hazardous substance by sample ID and the detected concentration. For surface water sediment samples detecting a hazardous substance at or beyond an intake, evaluate the intake as Level II contamination. Obtain benchmark, cancer risk, and reference dose concentrations for each substance from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages of the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population served by the intake as a Level I target. If the percentages are less than 100% or all are N/A, evaluate the population served by the intake as a Level II target.

SURFACE WATER PATHWAY LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET

LIKELIHOOD OF RELEASE- OVERLAND FLOOD MIGRATION

| | Score | Data Type | Refs | | | | | | | | | | | | |
|--|--------------------------------------|-----------|--|--|------------------------------------|-----|---------------------------|-----|---------------------------|-----|--------------------------------|-----|--|--|--|
| 1. OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7. | | | | | | | | | | | | | | | |
| 2. POTENTIAL TO RELEASE: Distance to surface water: _____ (feet) If sampling data do not support a release to surface water in the watershed, use the table below to assign a score from the table below based on distance to surface water and flood frequency. | | | | | | | | | | | | | | | |
| <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Distance to surface water <2500 feet</td> <td>500</td> </tr> <tr> <td>Distance to surface water >2500 feet, and:</td> <td></td> </tr> <tr> <td> Site in annual or 10-yr floodplain</td> <td>500</td> </tr> <tr> <td> Site in 100-yr floodplain</td> <td>400</td> </tr> <tr> <td> Site in 500-yr floodplain</td> <td>300</td> </tr> <tr> <td> Site outside 500-yr floodplain</td> <td>100</td> </tr> </table> | Distance to surface water <2500 feet | 500 | Distance to surface water >2500 feet, and: | | Site in annual or 10-yr floodplain | 500 | Site in 100-yr floodplain | 400 | Site in 500-yr floodplain | 300 | Site outside 500-yr floodplain | 100 | | | |
| Distance to surface water <2500 feet | 500 | | | | | | | | | | | | | | |
| Distance to surface water >2500 feet, and: | | | | | | | | | | | | | | | |
| Site in annual or 10-yr floodplain | 500 | | | | | | | | | | | | | | |
| Site in 100-yr floodplain | 400 | | | | | | | | | | | | | | |
| Site in 500-yr floodplain | 300 | | | | | | | | | | | | | | |
| Site outside 500-yr floodplain | 100 | | | | | | | | | | | | | | |
| Optionally, evaluate surface water potential to release according to HRS Section 4.1.2.1.2 | 200 | | | | | | | | | | | | | | |
| LR = | | 200 | | | | | | | | | | | | | |

LIKELIHOOD OF RELEASE GROUND WATER TO SURFACE WATER MIGRATION

| | Score | Data Type | Refs |
|--|-------|-----------|------|
| 1. OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7. | | | |
| <p>NOTE: Evaluate ground water to surface water migration only for a surface water body that meets all of the following conditions:</p> <p>1) A portion of the surface water is within 1 mile of site sources having a containment factor greater than 0.</p> <p>2) No aquifer discontinuity is established between the source and the above portion of the surface water body.</p> <p>3) The top of the uppermost aquifer is at or above the bottom of the surface water.</p> <p>Elevation of top of uppermost aquifer _____</p> <p>Elevation of bottom of surface water body _____</p> | | | |
| 2. POTENTIAL TO RELEASE: Use the ground water potential to release. Optionally, evaluate surface water potential to release according to HRS Section 3.1.2. | | | |
| LR = | | | |

**SURFACE WATER PATHWAY
LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET
(CONTINUED)**

| DRINKING WATER THREAT TARGETS | Score | Data Type | Refs | | | | | | | | | | | | | | | | |
|--|-----------------|-----------------|---------------|---------------|--|--|--|--|--|--|--|--|--|--|--|--|---|--|--|
| <p>Record the water body type, flow, and number of people served by each drinking water intake within the target distance limit in the watershed. If there is no drinking water intake within the target distance limit, assign 0 to factors 3, 4, and 5.</p> <table border="1" style="width: 100%; border-collapse: collapse; margin: 10px 0;"> <thead> <tr> <th style="text-align: left; padding: 2px;">Intake Name</th> <th style="text-align: left; padding: 2px;">Water Body Type</th> <th style="text-align: left; padding: 2px;">Flow</th> <th style="text-align: left; padding: 2px;">People Served</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table> <p>Are any intakes part of a blended system? Yes _____ No <input checked="" type="checkbox"/> If yes, attach a page to show apportionment calculations.</p> <p>3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates a drinking water intake has been exposed to a hazardous substance from the site, list the intake name and evaluate the factor score for the drinking water population (SI Table 8).</p> <hr/> <p>Level I: _____ people x 10 = _____ Level II: _____ people x 1 = _____ Total = 0</p> | Intake Name | Water Body Type | Flow | People Served | | | | | | | | | | | | | 0 | | |
| Intake Name | Water Body Type | Flow | People Served | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| <p>4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water intakes for the watershed that have not been exposed to a hazardous substance from the site. Assign the population values from SI Table 9. Sum the values and multiply by 0.1.</p> | 0 | | | | | | | | | | | | | | | | | | |
| <p>5. NEAREST INTAKE: Assign a score of 50 for any Level I Actual Contamination Drinking Water Targets for the watershed. Assign a score of 45 if there are Level II targets for the watershed, but no Level I targets. If no Actual Contamination Drinking Water Targets exist, assign a score for the Intake nearest the PPE from SI Table 9. If no drinking water intakes exist, assign 0.</p> | 0 | | | | | | | | | | | | | | | | | | |
| <p>6. RESOURCES: Assign a score of 5 if one or more surface water resource applies; assign 0 if none applies.</p> <ul style="list-style-type: none"> • Irrigation (5 acre minimum) of commercial food crops or commercial forage crops • Watering of commercial livestock • Ingredient in commercial food preparation • Major or designated water recreation area, excluding drinking water use | 0 | | | | | | | | | | | | | | | | | | |
| SUM OF TARGETS T= | 0 | | | | | | | | | | | | | | | | | | |

SI TABLE 9 (From HRS Table 4-14): DILUTION-WEIGHTED POPULATION VALUES FOR POTENTIAL CONTAMINATION FOR SURFACE WATER MIGRATION PATHWAY

| Type of Surface Water Body | Pop. | Nearest Intake | Number of people | | | | | | | | | | | Pop. Value |
|--|------|----------------|------------------|---------|----------|-----------|------------|--------------|----------------|-----------------|------------------|--|--|------------|
| | | | 0 | 1 to 10 | 11 to 30 | 31 to 100 | 101 to 300 | 301 to 1,000 | 1,001 to 3,000 | 3,001 to 10,000 | 10,001 to 30,000 | | | |
| Minimal Stream (<10 cfs) | | 20 | 0 | 4 | 17 | 53 | 164 | 522 | 1,633 | 5,214 | 16,325 | | | |
| Small to moderate stream (10 to 100 cfs) | | 2 | 0 | 0.4 | 2 | 5 | 16 | 52 | 163 | 521 | 1,633 | | | |
| Moderate to large stream (> 100 to 1,000 cfs) | | 0 | 0 | 0.04 | 0.2 | 0.5 | 2 | 5 | 16 | 52 | 163 | | | |
| Large Stream to river (>1,000 to 10,000 cfs) | | 0 | 0 | 0.004 | 0.02 | 0.05 | 0.2 | 0.5 | 2 | 5 | 16 | | | |
| Large River (> 10,000 to 100,000 cfs) | | 0 | 0 | 0 | 0.002 | 0.005 | 0.02 | 0.05 | 0.2 | 0.5 | 16 | | | |
| Very Large River (>100,000 cfs) | | 0 | 0 | 0 | 0 | 0.001 | 0.002 | 0.005 | 0.02 | 0.05 | 0.2 | | | |
| Shallow ocean zone or Great Lake (depth < 20 feet) | | 0 | 0 | 0 | 0.002 | 0.005 | 0.02 | 0.05 | 0.2 | 0.5 | 2 | | | |
| Moderate ocean zone or Great Lake (Depth 20 to 200 feet) | | 0 | 0 | 0 | 0 | 0.001 | 0.002 | 0.005 | 0.02 | 0.05 | 0.2 | | | |
| Deep ocean zone or Great Lake (depth > 200 feet) | | 0 | 0 | 0 | 0 | 0 | 0.001 | 0.003 | 0.008 | 0.03 | 0.08 | | | |
| 3-mile mixing zone in quiet flowing river (> 10 cfs) | | 10 | 0 | 2 | 9 | 26 | 82 | 261 | 817 | 2,607 | 8,163 | | | |
| Nearest Intake = | | | Sum = | | | | | | | | | | | |

References

SURFACE WATER PATHWAY

Human Food Chain Actual Contamination Targets Summary Table

On SI Table 10, list the hazardous substances detected in sediment, aqueous, sessile benthic organism tissue, or fish tissue samples (taken from fish caught within the boundaries of the observed release) by sample ID and concentration. Evaluate fisheries within the boundaries of observed releases detected by sediment or aqueous samples as Level II, if at least one observed release substance has a bioaccumulation potential factor value of 500 or greater (see SI Table 7). Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For FDAAL benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate this portion of the fishery as subject to Level I concentrations. If the percentages are less than 100% or all are N/A, evaluate the fishery as a Level II target.

Sensitive Environment Actual Contamination Targets Summary Table

On SI Table 11, list each hazardous substance detected in aqueous or sediment samples at or beyond wetlands or a surface water sensitive environment by sample ID. Record the concentration. If contaminated sediments or tissues are detected at or beyond a sensitive environment, evaluate the sensitive environment as Level II. Obtain benchmark concentrations from SCDM. For AWQC/AALAC benchmarks, determine the highest percentage of benchmark of the substances detected in aqueous samples. If benchmark concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage equals or exceeds 100%, evaluate that part of the sensitive environment subject to Level I concentrations. If the percentage is less than 100%, or all are N/A, evaluate the sensitive environment as Level II.

SURFACE WATER PATHWAY (continued) HUMAN FOOD CHAIN THREAT WORKSHEET

| HUMAN FOOD CHAIN THREAT TARGETS | Score | Data Type | Ref's | | | | | | | | | | |
|--|-------|-----------|-------------|-----------|---------|----|---------------|---|--|---|---|----|--|
| <p>Record the water body type and flow for each fishery within the target distance limit. If there is no fishery within the target distance limit, assign a score of 0 at the bottom of this page.</p> | | | | | | | | | | | | | |
| <p>Fishery Name _____ Water Body _____ Flow _____ cfs</p> <p>Species _____ Production _____ lbs/yr</p> <p>Species _____ Production _____ lbs/yr</p> | 0.03 | | | | | | | | | | | | |
| <p>Fishery Name _____ Water Body _____ Flow _____ cfs</p> <p>Species _____ Production _____ lbs/yr</p> <p>Species _____ Production _____ lbs/yr</p> | | | | | | | | | | | | | |
| <p>Fishery Name _____ Water Body _____ Flow _____ cfs</p> <p>Species _____ Production _____ lbs/yr</p> <p>Species _____ Production _____ lbs/yr</p> | | | | | | | | | | | | | |
| <p>FOOD CHAIN INDIVIDUAL</p> | | | | | | | | | | | | | |
| <p>7. ACTUAL CONTAMINATION FISHERIES:</p> <p>If analytical evidence indicates that a fishery has been exposed to a hazardous substance with a bioaccumulation factor greater than or equal to 500 (SI Table 10), assign a score of 50 if there is a Level I fishery. Assign 45 if there is a Level II fishery, but no Level I fishery.</p> | | | | | | | | | | | | | |
| <p>8. POTENTIAL CONTAMINATION FISHERIES:</p> <p>If there is a release of a substance with a bioaccumulation factor greater than or equal to 500 to a watershed containing fisheries within the target distance limit, but there are no Level I or Level II fisheries, assign a score of 20.</p> <p>If there is no observed release to the watershed, assign a value for potential contamination fisheries from the table below using the lowest flow at all fisheries within the target distance limit:</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <thead> <tr> <th style="text-align: left;">Lowest Flow</th> <th style="text-align: center;">FCI Value</th> </tr> </thead> <tbody> <tr> <td><10 cfs</td> <td style="text-align: center;">20</td> </tr> <tr> <td>10 to 100 cfs</td> <td style="text-align: center;">2</td> </tr> <tr> <td>>100 cfs, coastal tidal waters, oceans, or Great Lakes</td> <td style="text-align: center;">0</td> </tr> <tr> <td>3-mile mixing zone in quiet flowing river</td> <td style="text-align: center;">10</td> </tr> </tbody> </table> | | | Lowest Flow | FCI Value | <10 cfs | 20 | 10 to 100 cfs | 2 | >100 cfs, coastal tidal waters, oceans, or Great Lakes | 0 | 3-mile mixing zone in quiet flowing river | 10 | |
| Lowest Flow | | FCI Value | | | | | | | | | | | |
| <10 cfs | | 20 | | | | | | | | | | | |
| 10 to 100 cfs | | 2 | | | | | | | | | | | |
| >100 cfs, coastal tidal waters, oceans, or Great Lakes | 0 | | | | | | | | | | | | |
| 3-mile mixing zone in quiet flowing river | 10 | | | | | | | | | | | | |
| <p>FCI Value =</p> | | | | | | | | | | | | | |
| <p>SUM OF TARGETS T =</p> | | | 0.03 | | | | | | | | | | |

SURFACE WATER PATHWAY (continued) ENVIRONMENTAL THREAT WORKSHEET

When measuring length of wetlands that are located on both sides of a surface water body, sum both frontage lengths. For a sensitive environment that is more than one type, assign a value for each type.

ENVIRONMENTAL THREAT TARGETS

Record the water body type and flow for each surface water sensitive environment within the target distance (see SI Table 12). If there is no sensitive environment within the target distance limit, assign a score of 0 at the bottom of the page.

| Environment Name | Water Body Type | Flow |
|-------------------|-----------------|-----------------|
| 1. <i>Wetland</i> | <i>Wetland</i> | <i>1250</i> cfs |
| 2. <i>Wetland</i> | <i>Wetland</i> | <i>1250</i> cfs |
| | | cfs |
| | | cfs |
| | | cfs |

9. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: If sampling data or direct observation indicate any sensitive environment has been exposed to a hazardous substance from the site, record this information on SI Table 11, and assign a factor value for the environment (SI Tables 13 and 14).

| Environment Name | Environment Type and Value (SI Tables 13 & 14) | Multiplier (10 for Level I, 1 for Level II) | Product |
|------------------|--|---|---------|
| | | x | = |
| | | x | = |
| | | x | = |
| | | x | = |

Sum =

10. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS:

| Flow | Dilution Weight (SI Table 12) | Environment Type and Value (SI Tables 13 & 14) | Pot. Cont. | Product |
|-----------------|-------------------------------|--|--------------|----------------|
| <i>1250</i> cfs | <i>0.00001</i> x | <i>Wetland 1250</i> x | <i>0.1</i> = | <i>0.00001</i> |
| <i>1250</i> cfs | <i>0.00001</i> x | <i>Wetland 1250</i> x | <i>0.1</i> = | <i>0.00001</i> |
| cfs | x | x | 0.1 = | |
| cfs | x | x | 0.1 = | |
| cfs | x | x | 0.1 = | |

Sum =

T =

SI TABLE 12 (HRS Table 4-13):
SURFACE WATER DILUTION WEIGHTS

| Type of Surface Water Body | | Assigned Dilution Weight |
|---|--|--------------------------|
| Descriptor | Flow Characteristics | |
| Minimal stream | < 10 cfs | 1 |
| Small to moderate stream | 10 to 100 cfs | 0.1 |
| Moderate to large stream | > 100 to 1,000 cfs | 0.01 |
| Large stream to river | > 1,000 to 10,000 cfs | 0.001 |
| Large river | > 10,000 to 100,000 cfs | 0.0001 |
| Very large river | > 100,000 cfs | 0.00001 |
| Coastal tidal waters | Flow not applicable; depth not applicable | 0.001 |
| Shallow ocean zone or Great Lake | Flow not applicable; depth less than 20 feet | 0.001 |
| Moderate depth ocean zone or Great Lake | Flow not applicable; depth 20 to 200 feet | 0.0001 |
| Deep ocean zone or Great Lake | Flow not applicable; depth greater than 200 feet | 0.000005 |
| 3-mile mixing zone in quiet flowing river | 10 cfs or greater | 0.5 |

**SI TABLE 13 (HRS TABLE 4-23):
SURFACE WATER AND AIR SENSITIVE ENVIRONMENTS VALUES**

| SENSITIVE ENVIRONMENT | ASSIGNED VALUE |
|--|--|
| Critical habitat for Federal designated endangered or threatened species Marine Sanctuary National Park Designated Federal Wilderness Area Ecologically important areas identified under the Coastal Zone Wilderness Act Sensitive Areas identified under the National Estuary Program or Near Coastal Water Program of the Clean Water Act Critical Areas identified under the Clean Lakes Program of the Clean Water Act (subareas in lakes or entire small lakes) National Monument (air pathway only) National Seashore Recreation Area National Lakeshore Recreation Area | 100 |
| Habitat known to be used by Federal designated or proposed endangered or threatened species National Preserve National or State Wildlife Refuge Unit of Coastal Barrier Resources System Coastal Barrier (undeveloped) Federal land designated for the protection of natural ecosystems Administratively Proposed Federal Wilderness Area Spawning areas critical for the maintenance of fish/shellfish species within a river system, bay, or estuary Migratory pathways and feeding areas critical for the maintenance of anadromous fish species within river reaches or areas in lakes or coastal tidal waters in which the fish spend extended periods of time Terrestrial areas utilized by large or dense aggregations of vertebrate animals (semi-aquatic foragers) for breeding National river reach designated as recreational | 75 |
| Habitat known to be used by State designated endangered or threatened species Habitat known to be used by a species under review as to its Federal endangered or threatened status Coastal Barrier (partially developed) Federally designated Scenic or Wild River | 50 |
| State land designated for wildlife or game management State designated Scenic or Wild River State designated Natural Area Particular areas, relatively small in size, important to maintenance of unique biotic communities | 25 |
| State designated areas for the protection of maintenance of aquatic life under the Clean Water Act | 5 |
| Wetlands | See SI Table 14 (Surface Water Pathway) or SI Table 23 (Air Pathway) |

**SI TABLE 14 (HRS TABLE 4-24): SURFACE WATER
WETLANDS FRONTAGE VALUES**

| Total Length of Wetlands | Assigned Value |
|---------------------------------|-----------------------|
| Less than 0.1 mile | 0 |
| 0.1 to 1 mile | 25 |
| Greater than 1 to 2 miles | 50 |
| Greater than 2 to 3 miles | 75 |
| Greater than 3 to 4 miles | 100 |
| Greater than 4 to 8 miles | 150 |
| Greater than 8 to 12 miles | 250 |
| Greater than 12 to 16 miles | 350 |
| Greater than 16 to 20 miles | 450 |
| Greater than 20 miles | 500 |

SURFACE WATER PATHWAY (concluded)

WASTE CHARACTERISTICS, THREAT, AND PATHWAY SCORE SUMMARY

| WASTE CHARACTERISTICS | | | | Score |
|--|-----------------|-------|---------|---|
| 14. If an Actual Contamination Target (drinking water, human food chain, or environmental threat) exists for the watershed, assign the calculated hazardous waste quantity score, or a score of 100, whichever is greater. | | | | 000 |
| 15. Assign the highest value from SI Table 7 (observed release) or SI Table 3 (no observed release) for the hazardous substance waste characterization factors below. Multiply each by the surface water hazardous waste quantity score and determine the waste characteristics score for each threat. | | | | |
| | Substance Value | HWQ | Product | WC Score (from Table) (Maximum of 100) |
| Drinking Water Threat Toxicity/Persistence | 000 x | 100 - | 000 | 000 |
| Food Chain Threat Toxicity/Persistence Bioaccumulation | 000 x | 100 - | 000 | 000 |
| Environmental Threat Ecotoxicity/Persistence/ Ecobioaccumulation | 000 x | 100 - | 000 | 000 |

| Product | WC Score |
|---------------------|----------|
| 0 | 0 |
| >0 to <10 | 1 |
| 10 to <100 | 2 |
| 100 to <1,000 | 3 |
| 1,000 to < 10,000 | 6 |
| 10,000 to <1E + 05 | 10 |
| 1E + 05 to <1E + 06 | 18 |
| 1E + 06 to <1E + 07 | 32 |
| 1E + 07 to <1E + 08 | 56 |
| 1E + 08 to <1E + 09 | 100 |
| 1E + 09 to <1E + 10 | 180 |
| 1E + 10 to <1E + 11 | 320 |
| 1E + 11 to <1E + 12 | 560 |
| 1E + 12 or greater | 1000 |

SURFACE WATER PATHWAY THREAT SCORES

| Threat | Likelihood of Release (LR) Score | Targets (T) Score | Pathway Waste Characteristics (WC) Score (determined above) | Threat Score $\frac{LR \times T \times WC}{82,500}$ |
|------------------|----------------------------------|-------------------|---|--|
| Drinking Water | 013 | 0 | 000 | (maximum of 100) |
| Human Food Chain | 013 | 000 | 000 | (maximum of 100) 000 |
| Environmental | 012 | 00000 | 000 | (maximum of 60) 00000 |

SURFACE WATER PATHWAY SCORE
(Drinking Water Threat + Human Food Chain Threat + Environmental Threat)

(maximum of 100)

0036

00000 = 96.04

SOIL EXPOSURE PATHWAY

If there is no observed contamination (e.g., ground water plume with no known surface source), do not evaluate the soil exposure pathway. Discuss evidence for no soil exposure pathway.

Soil Exposure Resident Population Targets Summary

For each property (duplicate page 35 as necessary):

If there is an area of observed contamination on the property and within 200 feet of a residence, school, or day care center, enter on Table 15 each hazardous substance by sample ID. Record the detected concentration. Obtain cancer risk, and reference dose concentrations from SCDM. Sum the cancer risk and reference dose percentages for the substances listed. If cancer risk or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the residents and students as Level I. If both percentages are less than 100% or all are N/A, evaluate the targets as Level II.

SI TABLE 15: SOIL EXPOSURE RESIDENT POPULATION TARGETS

| Residence ID: | | Level I | | Level II | | Population | |
|---------------|---------------------|---------------|---------------------------|------------------------|-----------------|-----------------|------------|
| Sample ID | Hazardous Substance | Conc. (mg/kg) | Cancer Risk Concentration | % of Cancer Risk Conc. | RID | % of RID | References |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | Highest Percent | | Sum of Percents | Sum of Percents | |

| Residence ID: | | Level I | | Level II | | Population | |
|---------------|---------------------|---------------|---------------------------|------------------------|-----------------|-----------------|------------|
| Sample ID | Hazardous Substance | Conc. (mg/kg) | Cancer Risk Concentration | % of Cancer Risk Conc. | RID | % of RID | References |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | Highest Percent | | Sum of Percents | Sum of Percents | |

| Residence ID: | | Level I | | Level II | | Population | |
|---------------|---------------------|---------------|---------------------------|------------------------|-----------------|-----------------|------------|
| Sample ID | Hazardous Substance | Conc. (mg/kg) | Cancer Risk Concentration | % of Cancer Risk Conc. | RID | % of RID | References |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | Highest Percent | | Sum of Percents | Sum of Percents | |

SOIL EXPOSURE PATHWAY WORKSHEET RESIDENT POPULATION THREAT

LIKELIHOOD OF EXPOSURE

| | Score | Data Type | Refs |
|---|-------|-----------|------|
| 1. OBSERVED CONTAMINATION: If evidence indicates presence of observed contamination (depth of 2 feet or less), assign a score of 550; otherwise, assign a 0. Note that a likelihood of exposure score of 0 results in a soil exposure pathway score of 0. | | | |
| LE = 550 | | | |

TARGETS

| <p>2. RESIDENT POPULATION: Determine the number of people occupying residences or attending school or day care on or within 200 feet of areas of observed contamination (HRS section 5.1.3).</p> <p>Level I: _____ people x 10 = _____</p> <p>Level II: _____ people x 1 = _____</p> <p>Sum = _____</p> | | | | | | | | | | | | | |
|--|--|-------|---|---|----------|---|--------------|----|--------|----|--|--|--|
| <p>3. RESIDENT INDIVIDUAL: Assign a score of 50 if any Level I resident population exists. Assign a score of 45 if there are Level II targets but no Level I targets. If no resident population exists (i.e., no Level I or Level II targets), assign 0 (HRS Section 5.1.3).</p> | | | | | | | | | | | | | |
| <p>4. WORKERS: Assign a score from the table below for the total number of workers at the site and nearby facilities with areas of observed contamination associated with the site.</p> <table border="1"> <thead> <tr> <th>Number of Workers</th> <th>Score</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0</td> </tr> <tr> <td>1 to 100</td> <td>5</td> </tr> <tr> <td>101 to 1,000</td> <td>10</td> </tr> <tr> <td>>1,000</td> <td>15</td> </tr> </tbody> </table> | Number of Workers | Score | 0 | 0 | 1 to 100 | 5 | 101 to 1,000 | 10 | >1,000 | 15 | | | |
| Number of Workers | Score | | | | | | | | | | | | |
| 0 | 0 | | | | | | | | | | | | |
| 1 to 100 | 5 | | | | | | | | | | | | |
| 101 to 1,000 | 10 | | | | | | | | | | | | |
| >1,000 | 15 | | | | | | | | | | | | |
| <p>5. TERRESTRIAL SENSITIVE ENVIRONMENTS: Assign a value for each terrestrial sensitive environment (SI Table 16) in an area of observed contamination.</p> <table border="1"> <thead> <tr> <th>Terrestrial Sensitive Environment Type</th> <th>Value</th> </tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table> <p>Sum = _____</p> | Terrestrial Sensitive Environment Type | Value | | | | | | | | | | | |
| Terrestrial Sensitive Environment Type | Value | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| <p>6. RESOURCES: Assign a score of 5 if any one or more of the following resources is present on an area of observed contamination at the site; assign 0 if none applies.</p> <ul style="list-style-type: none"> • Commercial agriculture • Commercial silviculture • Commercial livestock production or commercial livestock grazing | | | | | | | | | | | | | |
| Total of Targets T= | | | | | | | | | | | | | |

SI TABLE 16 (HRS TABLE 5-5): SOIL EXPOSURE PATHWAY
TERRESTRIAL SENSITIVE ENVIRONMENT VALUES

| TERRESTRIAL SENSITIVE ENVIRONMENT | ASSIGNED VALUE |
|--|----------------|
| Terrestrial critical habitat for Federal designated endangered or threatened species National Park Designated Federal Wilderness Area National Monument | 100 |
| Terrestrial habitat known to be used by Federal designated or proposed threatened or endangered species National Preserve (terrestrial) National or State terrestrial Wildlife Refuge Federal land designated for protection of natural ecosystems Administratively proposed Federal Wilderness Area Terrestrial areas utilized by large or dense aggregations of animals (vertebrate species) for breeding | 75 |
| Terrestrial habitat used by State designated endangered or threatened species Terrestrial habitat used by species under review for Federal designated endangered or threatened status | 50 |
| State lands designated for wildlife or game management State designated Natural Areas Particular areas, relatively small in size, important to maintenance of unique biotic communities | 25 |

SOIL EXPOSURE PATHWAY WORKSHEET NEARBY POPULATION THREAT

| LIKELIHOOD OF EXPOSURE | | Score | Data Type | Ref. |
|--|-----------------|-----------|-----------|------|
| 7. Attractiveness/Accessibility (from SI Table 17 or HRS Table 5-6) | Value <u>5</u> | | | |
| Area of Contamination (from SI Table 18 or HRS Table 5-7) | Value <u>30</u> | | | |
| Likelihood of Exposure (from SI Table 19 or HRS Table 5-8) | | | | |
| LE = | | <u>25</u> | | |

| TARGETS | | Score | Data Type | Ref. |
|---|--|----------|-----------|------|
| 8. Assign a score of 0 if Level I or Level II resident individual has been evaluated or if no individuals live within 1/4 mile travel distance of an area of observed contamination. Assign a score of 1 if nearby population is within 1/4 mile travel distance and no Level I or Level II resident population has been evaluated. | | <u>0</u> | | |
| 9. Determine the population within 1 mile travel distance that is not exposed to a hazardous substance from the site (i.e., properties that are not determined to be Level I or Level II); record the population for each distance category in SI Table 20 (HRS Table 5-10). Sum the population values and multiply by 0.1. | | <u>1</u> | | |
| T = | | <u>1</u> | | |

**SI TABLE 17 (HRS TABLE 5-6):
ATTRACTIVENESS/ACCESSIBILITY VALUES**

| Area of Observed Contamination | Assigned Value |
|--|----------------|
| Designated recreational area | 100 |
| Regularly used for public recreation (for example, vacant lots in urban area) | 75 |
| Accessible and unique recreational area (for example, vacant lots in urban area) | 75 |
| Moderately accessible (may have some access improvements—for example, gravel road) with some public recreation use | 50 |
| Slightly accessible (for example, extremely rural area with no road improvement) with some public recreation use | 25 |
| Accessible with no public recreation use | 10 |
| Surrounded by maintained fence or combination of maintained fence and natural barriers | 5 |
| Physically inaccessible to public, with no evidence of public recreation use | 0 |

SI TABLE 18 (HRS TABLE 5-7): AREA OF CONTAMINATION FACTOR VALUES

| Total area of the areas of observed contamination (square feet) | Assigned Value |
|---|----------------|
| ≤ to 5,000 | 5 |
| > 5,000 to 125,000 | 20 |
| > 125,000 to 250,000 | 40 |
| > 250,000 to 375,000 | 60 |
| > 375,000 to 500,000 | 80 |
| > 500,000 | 100 |

SI TABLE 19 (HRS TABLE 5-8): NEARBY POPULATION LIKELIHOOD OF EXPOSURE FACTOR VALUES

| AREA OF CONTAMINATION FACTOR VALUE | ATTRACTIVENESS/ACCESSIBILITY FACTOR VALUE | | | | | |
|------------------------------------|---|-----|-----|-----|-----|----|
| | 100 | 75 | 50 | 25 | 10 | 5 |
| 100 | 500 | 500 | 375 | 250 | 125 | 50 |
| 80 | 500 | 375 | 250 | 125 | 50 | 25 |
| 60 | 375 | 250 | 125 | 50 | 25 | 5 |
| 40 | 250 | 125 | 50 | 25 | 5 | 5 |
| 20 | 125 | 50 | 25 | 5 | 5 | 5 |
| 5 | 50 | 25 | 5 | 5 | 5 | 5 |

SI TABLE 20 (HRS TABLE 5-10): DISTANCE-WEIGHTED POPULATION VALUES FOR NEARBY POPULATION THREAT

| Travel Distance Category (miles) | Pop. Value | Number of people within the travel distance category | | | | | | | | | | | | Pop. Value |
|---|------------|--|---------|----------|-----------|------------|--------------|----------------|-----------------|------------------|-------------------|--------------------|----------------------|------------|
| | | 0 to 10 | 1 to 10 | 11 to 30 | 31 to 100 | 101 to 300 | 301 to 1,000 | 1,001 to 3,000 | 3,001 to 10,001 | 10,001 to 30,000 | 30,001 to 100,000 | 100,001 to 300,000 | 300,001 to 1,000,000 | |
| Greater than 0 to $\frac{1}{4}$ | 0 | 0.1 | 0.4 | 1.0 | 4 | 13 | 41 | 130 | 408 | 1,303 | 4,081 | 13,034 | 13,034 | |
| Greater than $\frac{1}{4}$ to $\frac{1}{2}$ | 0 | 0.05 | 0.2 | 0.7 | 2 | 7 | 20 | 65 | 204 | 652 | 2,041 | 6,517 | 6,517 | |
| Greater than $\frac{1}{2}$ to 1 | 0 | 0.02 | 0.1 | 0.3 | 1 | 3 | 10 | 33 | 102 | 326 | 1,020 | 3,258 | 3,258 | |
| Reference(s) _____ | | | | | | | | | | | | | | Sum = |

SOIL EXPOSURE PATHWAY WORKSHEET (concluded)

WASTE CHARACTERISTICS

| 10. | Assign the hazardous waste quantity score calculated for soil exposure | | | | | | | | | | | | | | | | | | | | | | | |
|---------------------|---|---------|----------|---|---|-----------|---|------------|---|---------------|---|-------------------|---|--------------------|----|---------------------|----|---------------------|----|---------------------|----|--------------------|-----|---|
| 11. | Assign the highest toxicity value from SI Table 16 | | | | | | | | | | | | | | | | | | | | | | | |
| 12. | Multiply the toxicity and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below: <table border="1" style="margin: 10px auto; border-collapse: collapse; text-align: center;"> <thead> <tr> <th style="padding: 2px;">Product</th> <th style="padding: 2px;">WC Score</th> </tr> </thead> <tbody> <tr><td style="padding: 2px;">0</td><td style="padding: 2px;">0</td></tr> <tr><td style="padding: 2px;">>0 to <10</td><td style="padding: 2px;">1</td></tr> <tr><td style="padding: 2px;">10 to <100</td><td style="padding: 2px;">2</td></tr> <tr><td style="padding: 2px;">100 to <1,000</td><td style="padding: 2px;">3</td></tr> <tr><td style="padding: 2px;">1,000 to < 10,000</td><td style="padding: 2px;">6</td></tr> <tr><td style="padding: 2px;">10,000 to <1E + 05</td><td style="padding: 2px;">10</td></tr> <tr><td style="padding: 2px;">1E + 05 to <1E + 06</td><td style="padding: 2px;">18</td></tr> <tr><td style="padding: 2px;">1E + 06 to <1E + 07</td><td style="padding: 2px;">32</td></tr> <tr><td style="padding: 2px;">1E + 07 to <1E + 08</td><td style="padding: 2px;">56</td></tr> <tr><td style="padding: 2px;">1E + 08 or greater</td><td style="padding: 2px;">100</td></tr> </tbody> </table> | Product | WC Score | 0 | 0 | >0 to <10 | 1 | 10 to <100 | 2 | 100 to <1,000 | 3 | 1,000 to < 10,000 | 6 | 10,000 to <1E + 05 | 10 | 1E + 05 to <1E + 06 | 18 | 1E + 06 to <1E + 07 | 32 | 1E + 07 to <1E + 08 | 56 | 1E + 08 or greater | 100 | WC = 0 |
| Product | WC Score | | | | | | | | | | | | | | | | | | | | | | | |
| 0 | 0 | | | | | | | | | | | | | | | | | | | | | | | |
| >0 to <10 | 1 | | | | | | | | | | | | | | | | | | | | | | | |
| 10 to <100 | 2 | | | | | | | | | | | | | | | | | | | | | | | |
| 100 to <1,000 | 3 | | | | | | | | | | | | | | | | | | | | | | | |
| 1,000 to < 10,000 | 6 | | | | | | | | | | | | | | | | | | | | | | | |
| 10,000 to <1E + 05 | 10 | | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 05 to <1E + 06 | 18 | | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 06 to <1E + 07 | 32 | | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 07 to <1E + 08 | 56 | | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 08 or greater | 100 | | | | | | | | | | | | | | | | | | | | | | | |

RESIDENT POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 1;
Targets = Sum of Questions 2, 3, 4, 5, 6)

LEX TX WC
82,500

0

NEARBY POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 7;
Targets = Sum of Questions 8, 9)

LEX TX WC
82,500

0.01

SOIL EXPOSURE PATHWAY SCORE:

Resident Population Threat + Nearby Population Threat

0.01

(Maximum of 100)

AIR PATHWAY

Air Pathway Observed Substances Summary Table

On SI Table 21, list the hazardous substances detected in air samples of a release from the site. Include only those substances with concentrations significantly greater than background levels. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For NAAQS/NESHAPS benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate targets in the distance category from which the sample was taken and any closer distance categories as Level I. If the percentages are less than 100% or all are N/A, evaluate targets in that distance category and any closer distance categories that are not Level I as Level II.

AIR PATHWAY WORKSHEET

| LIKELIHOOD OF RELEASE | Score | Data Type | Refs |
|--|-------|-----------|------|
| 1. OBSERVED RELEASE: If sampling data or direct observation support a release to air, assign a score of 550. Record observed release substances on SI Table 21. | — | | |
| 2. POTENTIAL TO RELEASE: If sampling data do not support a release to air, assign a score of 500. Optionally, evaluate air migration gaseous and particulate potential to release (HRS Section 6.1.2). | 500 | — | |

LR = 500

TARGETS

| <p>3. ACTUAL CONTAMINATION POPULATION: Determine the number of people within the target distance limit subject to exposure from a release of a hazardous substance to the air.</p> <p style="margin-left: 40px;">a) Level I: _____ people x 10 = _____</p> <p style="margin-left: 40px;">b) Level II: _____ people x 1 = _____ Total = _____</p> | | | | | | | | | | | | | | | | | | | | | |
|--|----------------------------|-------|--|--|--|--|--|--|--|--|-----------------|-------|--|--|--|--|--|--|--|--|--|
| <p>4. POTENTIAL TARGET POPULATION: Determine the number of people within the target distance limit not subject to exposure from a release of a hazardous substance to the air, and assign the total population score from SI Table 22. Sum the values and multiply the sum by 0.1.</p> | | | | | | | | | | | | | | | | | | | | | |
| <p>5. NEAREST INDIVIDUAL: Assign a score of 50 if there are any Level I targets. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Population exists, assign the Nearest Individual score from SI Table 22.</p> | | | | | | | | | | | | | | | | | | | | | |
| <p>6. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: Sum the sensitive environment values (SI Table 13) and wetland acreage values (SI Table 23) for environments subject to exposure from the release of a hazardous substance to the air.</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <tr> <th style="text-align: left;">Sensitive Environment Type</th><th style="text-align: left;">Value</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr> <th style="text-align: left;">Wetland Acreage</th><th style="text-align: left;">Value</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table> | Sensitive Environment Type | Value | | | | | | | | | Wetland Acreage | Value | | | | | | | | | |
| Sensitive Environment Type | Value | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| Wetland Acreage | Value | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| <p>7. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS: Use SI Table 24 to evaluate sensitive environments not subject to exposure from a release.</p> | | | | | | | | | | | | | | | | | | | | | |
| <p>8. RESOURCES: Assign a score of 5 if one or more air resources apply within 1/2 mile of a source; assign a 0 if none applies.</p> <ul style="list-style-type: none"> • Commercial agriculture • Commercial silviculture • Major or designated recreation area | | | | | | | | | | | | | | | | | | | | | |

T = 17.74

SI TABLE 21: AIR PATHWAY OBSERVED RELEASE SUBSTANCES

| Sample ID: _____ | | Level I _____ | | Level II _____ | | Distance from Sources (mi) _____ | | References _____ | |
|---------------------------|------------------------------------|---------------------|------------------------------------|----------------|-------------------|----------------------------------|-----------------|------------------|--|
| Hazardous Substance | Conc. ($\mu\text{g}/\text{m}^3$) | Gaseous Particulate | Benchmark Conc. (NAAQS or NESHAPS) | % of Benchmark | Cancer Risk Conc. | % of Cancer Risk Conc. | RID | % of RID | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| Highest Toxicity/Mobility | | | Highest Percent | | Sum of Percents | | Sum of Percents | | |

| Sample ID: _____ | | Level I _____ | | Level II _____ | | Distance from Sources (mi) _____ | | References _____ | |
|---------------------------|------------------------------------|-------------------|------------------------------------|----------------|-------------------|----------------------------------|-----------------|------------------|--|
| Hazardous Substance | Conc. ($\mu\text{g}/\text{m}^3$) | Toxicity/Mobility | Benchmark Conc. (NAAQS or NESHAPS) | % of Benchmark | Cancer Risk Conc. | % of Cancer Risk Conc. | RID | % of RID | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| Highest Toxicity/Mobility | | | Highest Percent | | Sum of Percents | | Sum of Percents | | |

| Sample ID: _____ | | Level I _____ | | Level II _____ | | Distance from Sources (mi) _____ | | References _____ | |
|---------------------------|------------------------------------|-------------------|------------------------------------|----------------|-------------------|----------------------------------|-----------------|------------------|--|
| Hazardous Substance | Conc. ($\mu\text{g}/\text{m}^3$) | Toxicity/Mobility | Benchmark Conc. (NAAQS or NESHAPS) | % of Benchmark | Cancer Risk Conc. | % of Cancer Risk Conc. | RID | % of RID | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| Highest Toxicity/Mobility | | | Highest Percent | | Sum of Percents | | Sum of Percents | | |

SI TABLE 22 (From HRS TABLE 6-17): VALUES FOR POTENTIAL CONTAMINATION AIR TARGET POPULATIONS

| Distance from Site | Pop. | Nearest Individual (choose highest) | Number of People within the Distance Category | | | | | | | | | | | | | P.op. Value |
|-------------------------------------|-------|-------------------------------------|---|----------|-----------|------------|--------------|----------------|-----------------|------------------|-------------------|--------------------|----------------------|------------------------|--|-------------|
| | | | 1 to 10 | 11 to 30 | 31 to 100 | 101 to 300 | 301 to 1,000 | 1,001 to 3,000 | 3,001 to 10,000 | 10,001 to 30,000 | 30,001 to 100,000 | 100,001 to 300,000 | 300,001 to 1,000,000 | 1,000,000 to 3,000,000 | | |
| On a source | 0 | 20 | 4 | 17 | 53 | 164 | 522 | 1,633 | 5,214 | 16,325 | 52,137 | 163,246 | 521,360 | 1,632,455 | | |
| 0 to $\frac{1}{4}$ mile | 0 | * | 1 | 4 | 13 | 41 | 131 | 408 | 1,304 | 4,081 | 13,034 | 40,812 | 130,340 | 408,114 | | |
| $\frac{1}{4}$ to $\frac{1}{2}$ mile | 0 | 2 | 0.2 | 0.9 | 3 | 9 | 28 | 88 | 282 | 882 | 2,815 | 8,815 | 28,153 | 88,153 | | |
| $\frac{1}{2}$ to 1 mile | 2509 | 1 | 0.06 | 0.3 | 0.9 | 3 | 8 | 26 | 83 | 261 | 834 | 2,612 | 8,342 | 26,119 | | |
| > 1 to 2 miles | 1128 | 0 | 0.02 | 0.09 | 0.3 | 0.8 | 3 | 8 | 27 | 83 | 266 | 833 | 2,659 | 8,326 | | |
| > 2 to 3 miles | 20234 | 0 | 0.009 | 0.04 | 0.1 | 0.4 | 1 | 4 | 12 | 38 | 120 | 375 | 1,199 | 3,755 | | |
| > 3 to 4 miles | 2122 | 0 | 0.005 | 0.02 | 0.07 | 0.2 | 0.7 | 2 | 7 | 28 | 73 | 229 | 730 | 2,285 | | |
| Nearest Individual = | | 1 | Sum = | | | | | | | | | | | | | |

References

* Score = 20 if the Nearest Individual is within $\frac{1}{8}$ mile of a source; score = 7 if the Nearest Individual is between $\frac{1}{8}$ and $\frac{1}{4}$ mile of a source.

SI TABLE 23 (HRS TABLE 6-18): AIR PATHWAY VALUES FOR WETLAND AREA

| Wetland Area | Assigned Value |
|--------------------|----------------|
| < 1 acre | 0 |
| 1 to 50 acres | 25 |
| > 50 to 100 acres | 75 |
| > 100 to 150 acres | 125 |
| > 150 to 200 acres | 175 |
| > 200 to 300 acres | 250 |
| > 300 to 400 acres | 350 |
| > 400 to 500 acres | 450 |
| > 500 acres | 500 |

SI TABLE 24: DISTANCE WEIGHTS AND CALCULATIONS FOR AIR PATHWAY POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS

| Distance | Distance Weight | Sensitive Environment Type and Value (from SI Tables 13 and 20) | Product |
|----------------------------|-----------------|---|---------|
| On a Source | 0.10 | x | |
| | | x | |
| 0 to 1/4 mile | 0.025 | x | |
| | | x | |
| | | x | |
| 1/4 to 1/2 mile | 0.0054 | x | |
| | | x | |
| | | x | |
| 1/2 to 1 mile | 0.0016 | x | |
| | | x | |
| | | x | |
| 1 to 2 miles | 0.0005 | x | |
| | | x | |
| | | x | |
| 2 to 3 miles | 0.00023 | x | |
| | | x | |
| | | x | |
| 3 to 4 miles | 0.00014 | x | |
| | | x | |
| | | x | |
| > 4 miles | 0 | x | |
| Total Environments Score = | | | |

AIR PATHWAY (concluded)

WASTE CHARACTERISTICS

| <p>9. If any Actual Contamination Targets exist for the air pathway, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if there are no Actual Contamination Targets for the air pathway, assign the calculated HWQ score for sources available to air migration.</p> | <p>100</p> | | | | | | | | | | | | | | | | | | | | | | |
|---|---------------|----------|---|---|-----------|---|------------|---|---------------|---|-------------------|---|--------------------|----|---------------------|----|---------------------|----|---------------------|----|--------------------|-----|----------------|
| <p>10. Assign the highest air toxicity/mobility value from SI Table 21.</p> | <p>10,000</p> | | | | | | | | | | | | | | | | | | | | | | |
| <p>11. Multiply the air pathway toxicity/mobility and hazardous waste quantity scores. Assign the Waste Characteristics score from the table below:</p> <table border="1" style="margin: 10px auto; border-collapse: collapse; text-align: center;"> <thead> <tr> <th style="padding: 2px 10px;">Product</th> <th style="padding: 2px 10px;">WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td>0</td></tr> <tr><td>>0 to <10</td><td>1</td></tr> <tr><td>10 to <100</td><td>2</td></tr> <tr><td>100 to <1,000</td><td>3</td></tr> <tr><td>1,000 to < 10,000</td><td>6</td></tr> <tr><td>10,000 to <1E + 05</td><td>10</td></tr> <tr><td>1E + 05 to <1E + 06</td><td>18</td></tr> <tr><td>1E + 06 to <1E + 07</td><td>32</td></tr> <tr><td>1E + 07 to <1E + 08</td><td>56</td></tr> <tr><td>1E + 08 or greater</td><td>100</td></tr> </tbody> </table> | Product | WC Score | 0 | 0 | >0 to <10 | 1 | 10 to <100 | 2 | 100 to <1,000 | 3 | 1,000 to < 10,000 | 6 | 10,000 to <1E + 05 | 10 | 1E + 05 to <1E + 06 | 18 | 1E + 06 to <1E + 07 | 32 | 1E + 07 to <1E + 08 | 56 | 1E + 08 or greater | 100 | <p>WC = 12</p> |
| Product | WC Score | | | | | | | | | | | | | | | | | | | | | | |
| 0 | 0 | | | | | | | | | | | | | | | | | | | | | | |
| >0 to <10 | 1 | | | | | | | | | | | | | | | | | | | | | | |
| 10 to <100 | 2 | | | | | | | | | | | | | | | | | | | | | | |
| 100 to <1,000 | 3 | | | | | | | | | | | | | | | | | | | | | | |
| 1,000 to < 10,000 | 6 | | | | | | | | | | | | | | | | | | | | | | |
| 10,000 to <1E + 05 | 10 | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 05 to <1E + 06 | 18 | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 06 to <1E + 07 | 32 | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 07 to <1E + 08 | 56 | | | | | | | | | | | | | | | | | | | | | | |
| 1E + 08 or greater | 100 | | | | | | | | | | | | | | | | | | | | | | |

AIR PATHWAY SCORE:

$$\frac{LE \times T \times WC}{82,500}$$

3.44
(maximum of 100)

$$100 \times 10,000 \times 12$$

| SITE SCORE CALCULATION | | S | S ² |
|--|--|--|----------------|
| GROUND WATER PATHWAY SCORE (S _{GW}) | | | |
| SURFACE WATER PATHWAY SCORE (S _{SW}) | | 0.00 | 0.00 |
| SOIL EXPOSURE (S _S) | | 0.00 | 0.00 |
| AIR PATHWAY SCORE (S _A) | | 0.00 | 0.00 |
| SITE SCORE | | $\sqrt{\frac{S_{GW}^2 + S_{SW}^2 + S_S^2 + S_A^2}{4}} =$ | |
| | | I → 2.86 | |
| | | II → 14.07 | |
| | | I = 48.10 | |

COMMENTS

Scenario 1 is based on a conservative estimate of exposure and indicates a score of 2.86.

Scenario 3 is based on a conservative estimate of exposure and indicates a score of 2.86. The exposure assessment for PCBs is based on the highest available concentration of 5.59 mg/kg.

Scenario 2 is based on an intermediate exposure assessment and indicates a score of 14.07. The exposure assessment for PCBs is based on the highest available concentration of 5.59 mg/kg.

Reference 1

LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2
LI USING ENGINEER'S SCALE (1/60)SITE NAME: International Harvester CERCLIS #: TND 00700

AKA: _____ SSID: _____

ADDRESS: 3003 Harvester LaneCITY: Memphis STATE: TN ZIP CODE: 38127

SITE REFERENCE POINT: _____

USGS QUAD MAP NAME: Northwest Memphis TN-AR TOWNSHIP: _____ N/S RANGE: _____ E/WSCALE: 1:24,000 MAP DATE: 1965 ^{Photorevised} 1973 SECTION: _____ 1/4 _____ 1/4 _____ 1/4MAP DATUM: 1927 1983 (CIRCLE ONE) MERIDIAN: _____

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):

LONGITUDE: 90° 00' 00" LATITUDE: 35° 07' 30"

COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:

LONGITUDE: 90° 02' 30" LATITUDE: 35° 10' 00"

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 437B) MULTIPLY (A) BY $\frac{0.3247}{0.3304}$ TO CONVERT TO SECONDS:

$$A \times \frac{0.3247}{0.3304} = 144.08"$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 02' 24.08"D) ADD TO STARTING LATITUDE: 35° 10' 00.00" + 02' 24.08" =SITE LATITUDE: 35° 12' 24.08"

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)


A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 84B) MULTIPLY (A) BY $\frac{0.4005}{0.4170}$ TO CONVERT TO SECONDS:

$$A \times \frac{0.4005}{0.4170} = 33.64"$$

C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 00' 33.64"D) ADD TO STARTING LONGITUDE: 90° 02' 30.00" + 00' 33.64" = 90° 03' 03.64"SITE LONGITUDE: 90° 03' 03.64"INVESTIGATOR: Robert Martel DATE: 07/09/93

SOIL SURVEY

Shelby County Tennessee



SOIL CONSERVATION SERVICE
7777 Walnut Grove Rd., Box 98
Memphis, TN 38120

UNITED STATES DEPARTMENT OF AGRICULTURE
Soil Conservation Service
In cooperation with
TENNESSEE AGRICULTURAL EXPERIMENT STATION




Figure 2.—Highway I-40, 5 miles east of the city limits of Memphis. Superhighways like this take large areas that once were farms.

The 2,052 farms in Shelby County take up 273,387 acres, or 56.6 percent of the land area. The average acreage per farm is 133.2 acres. Farms 10 to 49 acres in size are the most common. There are 992 farms in this size range and 266 farms less than 10 acres in size. There are few farms more than 500 acres in size, but there are 394 farms between 100 and 500 acres in size.

Most of the farms in the county are listed as field-crop farms, with cotton farms and miscellaneous and unclassified farms following closely. Livestock, cash-grain, general, and dairy farms follow in the order given. Soybeans were grown on 51,393 acres; cotton, on 33,728 acres; and corn, on 12,135 acres, in 1964. Vegetable crops, though not extensive in acreage, are important.

Annual lespedeza and alfalfa are the leading hay crops. They generally are fed on the farm, not sold as hay.

Unimproved pastures consist mostly of common lespedeza. Improved pastures consist mostly of tall fescue, white clover, and common bermudagrass.

Shelby County has a complete drainage system. All of the surface runoff flows into the Mississippi River. Noncounah Creek and the Wolf River are the major drains in the southern part of the county. Big Creek and the Loosahatchie River are the major drains in the northern part of the county.

Climate¹

The climate of Shelby County, like that of much of Tennessee and of surrounding areas, is characterized by relatively mild winters, hot summers, and abundant rainfall. Although the county is well inland from large bodies of water, it lies in the path of cold air moving down from Canada and warm, moist air moving up from the Gulf of Mexico. Consequently, extreme and frequent changes in the weather, both from day to day and from season to season, are common.

Although the weather varies daily within the county, differences in altitude are not great enough to cause significant differences in climate. Therefore, the climate data for Memphis in table 1 are representative of the entire county, except that precipitation decreases slightly from east to west. The difference between the total annual precipitation in the eastern part of the county and that in the western part is about 2 inches.

TEMPERATURE.—The average annual temperature at Memphis is 62° F. Extremes of 106° and -11° occurred during the period 1931 through 1960. Prolonged periods of very cold or very hot weather are unusual. Occasional

¹ By JOHN VARKSNOTIS, State climatologist, U.S. Weather Bureau, Nashville, Tennessee.

APPENDIX 1. MAPPING UNITS


For a full description of a mapping unit, read both the description of the mapping unit and that of the soil series to which the mapping unit belongs. The capability units are not discussed separately. For discussion of the suitability of a given soil for crops and pasture, for woodland, for wildlife, and for lawn grasses and shrubs, see the discussion of the mapping unit. Other information is given in tables as follows:

Average and extent, table 1, page 11.
Estimated yields, table 3, page 13.

Engineering uses of the soils, table 4, page 14; table 5, page 14.

Recreational uses of the soils, table 6, page 15.

| Map symbol | Mapping unit | Described on page | Capability unit |
|---------------|--|-------------------------|--------------------|
| | | | Symbol |
| Ad | Adler silt loam----- | 1 | I-1 |
| Bc | Bonn silt loam----- | 12 | IW-1 |
| Pw | Bowdre silty clay----- | 1 | IW-1 |
| Ca | Calloway silt loam----- | 13 | IW-1 |
| Co | Collins silt loam----- | 14 | I-2 |
| Cr | Commerce silt loam----- | 14 | I-2 |
| Cs | Convent silt loam----- | 1 | IW-1 |
| Cu | Crevasse fine sand----- | 1 | IWs-1 |
| Cv | Crevasse silt loam----- | 14 | IWs-1 |
| Fm | Falaya silt loam----- | 14 | IW-1 |
| Fs | Filled land, silty----- | 17 | None |
| Fy | Filled land, sandy----- | 17 | None |
| GaA | Grenada silt loam, 0 to 2 percent slopes----- | 18 | IW-2 |
| GaB | Grenada silt loam, 2 to 5 percent slopes----- | 18 | Ile-2 |
| GaB2 | Grenada silt loam, 2 to 5 percent slopes, eroded----- | 18 | Ile-2 |
| GaC | Grenada silt loam, 5 to 8 percent slopes----- | 18 | Ile-2 |
| GaC3 | Grenada silt loam, 5 to 8 percent slopes, severely eroded----- | 18 | IWs-2 |
| GaD | Grenada silt loam, 8 to 12 percent slopes----- | 1 | IWs-2 |
| GaD2 | Grenada silt loam, 8 to 12 percent slopes, eroded----- | 1 | Ile-2 |
| GdD3 | Grenada complex, 5 to 12 percent slopes, severely eroded----- | 1 | IWs-2 |
| Gr | Graded land, silty materials----- | 1 | None |
| Gs | Gullied land, silty----- | 1 | IWs-2 |
| He | Henry silt loam----- | 1 | IWs-1 |
| Ib | Iberia silt loam----- | 1 | IWs-3 |
| Lb | Levees and borrow pits----- | 1 | Ile-3 |
| LoB | Loring silt loam, 2 to 5 percent slopes----- | 1 | Ile-1 |
| LoB2 | Loring silt loam, 2 to 5 percent slopes, eroded----- | 1 | Ile-1 |
| LoC2 | Loring silt loam, 5 to 8 percent slopes, eroded----- | 1 | Ile-1 |
| LoD | Loring silt loam, 8 to 12 percent slopes----- | 1 | IWs-1 |
| LoD2 | Loring silt loam, 8 to 12 percent slopes, eroded----- | 1 | IWs-1 |
| LoD3 | Loring silt loam, 5 to 12 percent slopes, severely eroded----- | 1 | IWs-1 |
| MeB | Memphis silt loam, 2 to 5 percent slopes----- | 1 | Ile-1 |
| MeB2 | Memphis silt loam, 2 to 5 percent slopes, eroded----- | 1 | Ile-1 |
| MeC2 | Memphis silt loam, 5 to 8 percent slopes, eroded----- | 1 | Ile-1 |
| MeD2 | Memphis silt loam, 8 to 12 percent slopes, eroded----- | 1 | IWs-1 |
| MeD3 | Memphis silt loam, 5 to 12 percent slopes, severely eroded----- | 1 | IWs-1 |
| MeE | Memphis silt loam, 12 to 20 percent slopes----- | 1 | Ile-1 |
| MeF3 | Memphis silt loam, 12 to 30 percent slopes, severely eroded----- | 1 | Ile-1 |
| MeG | Memphis silt loam, 30 to 65 percent slopes----- | 1 | IWs-1 |
| Rb | Robinsonville fine sandy loam----- | 1 | I-1 |
| Rn | Robinsonville silt loam----- | 1 | I-1 |
| Sh | Sharkey clay----- | 1 | IWs-3 |
| Sw | Swamp----- | 1 | IWs-1 |
| Tu | Tunica silty clay----- | 1 | IWs-3 |
| Wv | Waverly silt loam----- | 1 | IWs-1 |



(Joins sheet 42)



(Joins sheet 48)

acid to neutral in reaction. It is flooded every few years.

Only a small acreage has been cleared. Most of the cleared area is idle or in bermudagrass pasture. Droughtiness limits the choice of crops to small grain, pasture, and other crops that grow in winter and spring, when moisture is most plentiful.

About three-fourths of the acreage is woodland. The trees are mainly cottonwood, black willow, and hackberry. In places the stand is thin, although the site is moderately good for cottonwood and black willow. Because of droughtiness, the loss of a fourth to a half of the seedlings in both planted and natural stands is to be expected.

The droughty nature of this soil limits the choice of plants that can be grown to provide food for wildlife. Plants that grow in winter and spring when available moisture is most plentiful are suitable. Winter small grains grow well if flooding is not severe. Sunflowers and sorghum also grow well. (Capability unit IVs-1)

Crevasse silt loam (Cv).—This is an excessively drained soil that occurs along the Mississippi River, as tracts 10 to 80 acres in size. The surface layer is silt loam or loam 6 to 10 inches thick. The substratum is almost pure sand. It extends to a depth of 4 feet or more. The slope range is 0 to 3 percent. Most areas have an uneven surface.

Included in mapping were a few areas that have a slightly finer textured substratum.

Crevasse silt loam has a low available water capacity and is extremely droughty. It is slightly acid to neutral in reaction and does not need lime. It is flooded every 5 to 10 years.

This soil is suited to small grain, pasture, and other crops that grow in winter and spring when moisture is most plentiful. It is fairly well suited to deep-rooted crops, such as alfalfa, but is too droughty for cotton and soybeans.

Droughtiness is the main limitation. This limitation can be partly overcome by selecting plants that grow when moisture is most plentiful. Flooding is a minor limitation.

Very little of the acreage is woodland. The site is moderately good for cottonwood and black willow. Because of droughtiness, the loss of about a fourth of the seedlings in both planted and natural stands is to be expected.

The droughty nature of this soil limits the choice of plants that can be grown for wildlife. Plants that have deep root systems or plants that grow in winter and spring are best suited. Small grains, sorghum, and sunflowers can be grown to provide food for wildlife. (Capability unit IVs-1)

Falaya Series

This series consists of somewhat poorly drained, strongly acid, nearly level, silty soils on bottom lands.

Representative profile of Falaya silt loam, 100 feet north of Raines Road, three-fourths of a mile east of Outland Road:

Ap—0 to 6 inches, brown (10YR 4/3) silt loam; weak, fine, granular structure; very friable; strongly acid; clear, smooth boundary.

0 to 18 inches, brown (10YR 5/3) silt loam; common, medium, light, granular structure; friable; strongly acid; smooth boundary.

12 to 18 inches, light brown (10YR 6/3) silt loam; common, medium, light, granular structure; friable; strongly acid; smooth boundary.

12 to 18 inches, light brown (10YR 6/3) silt loam; common, medium, light, granular structure; friable; strongly acid; smooth boundary.

The color of the surface 1 per ranges from brown to dark grayish brown. The C horizon has a high content of silt. The content of sand is no more than 15 percent and is commonly less than 10 percent.

Falaya silt loam (Fa).—This is a somewhat poorly drained, very silty, nearly level soil on first bottoms. It occurs throughout the county, except on the Mississippi River bottoms. The surface layer is brown, friable silt loam about 6 inches thick. The underlying material is friable silt loam that contains brown and gray mottles. It extends to a depth of several feet.

Included in mapping were some areas, in the vicinity of Woodstock and Millington, that are underlain with very dark gray to black silt loam or silty clay loam at a depth of 18 to 30 inches. Also included were small sandy spots in the eastern part of the county.

In winter and early in spring, the water table is often within a foot of the surface. In summer and fall it is several feet below the surface. Floods cover most areas during winter and spring, but the floodwater seldom stands more than a few hours.

This soil is easy to work after it dries out in spring. The lowest areas, however, are wet fairly late in spring (fig. 7). The available water capacity is high. The reaction is medium acid or strongly acid, and the content of phosphorus and potassium is moderately high. Crops respond to lime and fertilizer.

If adequately limed and fertilized and otherwise well managed, this soil is well suited to nearly all the commonly grown crops. Small grains can be grown if surface drainage is good and if flooding is not severe. Because of wetness, stands of alfalfa are not long lived. Tall fescue, annual lespedeza, and bermudagrass are suitable pasture plants. The surface is too wet and too soft for grazing during much of winter and early in spring. Nearly all of the acreage is used to grow cotton, corn, soybeans (fig. 8), pasture plants, and truck crops. Plowing under crop residue helps to maintain the organic-matter content.

Excess water is the main limitation. This limitation can be largely overcome by using a system of drainage ditches or tile and by selecting plants that tolerate wetness in winter and spring.

Some of the acreage is woodland. The site is excellent for bottom-land oaks, sweetgum, cottonwood, and other bottom-land hardwoods. Plant competition is severe. Weeding is needed in existing stands to promote reproduction of desirable species and to eliminate cull trees. Weeding is needed in planted stands to insure survival of seedlings.

This soil is well suited to many summer annuals that furnish food and cover for bobwhite quail, doves, and rabbits. Wastes left when corn and soybeans are har-



Figure 9.—Severely eroded, strongly sloping Grenada soil. Light-colored areas show where the fragipan is exposed or is close to the surface.

Most of this soil is idle and is either bare of vegetation or has a scrubby growth of weeds, broomsedge, briars, and bushes. It is poorly suited to row crops because of the slope and the erosion hazard. Only a small acreage is cultivated. Grasses and legumes that have shallow root systems or roots that can penetrate the fragipan can be grown. These include tall fescue, sericea lespedeza, and annual lespedeza.

The slope and the compact subsoil make management difficult. Well-fertilized hay and pasture help to control runoff and erosion.

The site is fair for pine trees, but productivity varies greatly from place to place because of differences in erosion and thickness of root zone. Seedling mortality ranges from slight to severe. The hazard of erosion is severe.

Most of this soil has only a sparse cover that provides little food or cover for wildlife. Tall fescue, sericea lespedeza, and annual lespedeza are fairly well suited, and they furnish some food for wildlife. (Capability unit VIc-2)

Graded land, silty materials (Gg).—This land type consists of areas that have been graded in preparation for subdivisions (fig. 10) and for commercial and industrial building. The depth to which these areas have been graded varies from a few inches to 5 feet or more and is

most commonly about 3 feet. The slope, after grading, is generally between 1 and 5 percent.

Grenada, Loring, and Memphis soils were predominant in these areas before grading. In most areas the original soil profiles have been disturbed to such an extent that they no longer can be identified. The soil material is brown, yellowish brown, and dark brown in color and silty in texture.

The areas of this land type range in size from a few acres to about 400 acres. They are on the outer edges of the city of Memphis and in the county just outside the city. Included in some of the areas mapped were small areas of Filled land, silty.

Lawn grasses and ornamental plants and trees grow well if a good seedbed is prepared and enough fertilizer and water are applied. (Not in a capability unit)

Gullied land, silty (Gs).—This land type occurs as tracts 5 to 20 acres in size. It is mostly on hillsides where the slope ranges from 8 to 20 percent. Gullies make up 25 percent or more of each area. The gullies range from 3 to 15 feet in depth and from 5 to 80 feet in width. Except in small patches and narrow strips, the soil profiles have been destroyed. Between the gullies, sheet erosion has removed much of the original surface layer and subsoil. In some gullies sandy and gravelly Coastal Plain material is exposed.

clover, bermudagrass, and lespedeza are suitable hay and pasture plants. Many kinds of grasses and legumes grow well under good management. Grazing is possible during winter because the surface is not wet and soft.

This soil erodes easily if not protected. Control of runoff is the main management problem. Well-fertilized pastures of grasses and legumes, if not overgrazed or mowed too closely, help to reduce runoff and to limit erosion.

The wooded tracts are fairly small. The existing stands consist of many kinds of upland hardwoods. The site is good for white oak, red oak, yellow-poplar, black walnut, and other upland hardwoods and for loblolly pine. Plant competition is moderate. The hazard of erosion is severe. Because of a lack of suitable seed trees, natural regeneration cannot always be relied upon to provide adequate restocking of high-value trees. In natural stands it may be necessary to plant seedlings and remove cull trees, low-value trees, and bushes. Abandoned fields and openings where planting is needed may need site preparation, cultivation, and weeding. Unnecessary disturbance of the soil should be avoided.

Many annual and perennial plants that furnish food and cover for wildlife can be grown on this soil. Crops such as annual lespedeza contribute to the food supply. Autumn olive, sericea lespedeza, shrub lespedeza, and pyracantha are among the perennials that can be planted in odd-shaped fields and field borders. In wooded areas, oak, hickory, beech, black walnut, and dogwood trees provide some food and cover for wildlife, especially for squirrels. (Capability unit Vfc-1)

Memphis silt loam, 12 to 30 percent slopes, severely eroded (McF3).—This is a deep soil on hillsides. It occurs as tracts 10 to 50 acres in size, mostly in the western half of the county. Erosion has removed most of the original surface layer and much of the subsoil. The plow layer consists mostly of brown, friable silt loam that originally was subsoil material. It is about 4 inches thick. The uppermost 6 inches of the subsoil is brown, friable silty clay loam. Below this is brown silt loam that extends to a depth of several feet. In many places erosion has removed the silty clay loam layer, and the texture throughout the profile is silt loam. There are many rills and gullies, and the surface is uneven.

This soil is strongly acid to slightly acid in reaction and moderately high in natural fertility. The response to lime and fertilizer is good. Roots, water, and air penetrate readily. The available water capacity is high. If runoff is controlled, plants generally have a good supply of moisture.

Because of rapid runoff and the severe hazard of erosion, this soil is poorly suited to row crops. The slope and the uneven surface make the operation of farm machinery difficult. Most areas are idle and have a scrubby growth of briars, bushes, cedars, and volunteer grasses. Some areas are in pasture. Tall fescue, white clover, bermudagrass, and lespedeza are among the suitable hay and pasture crops. Many kinds of grasses and legumes grow well under good management. Grazing is possible during winter because the surface does not get too wet and too soft.

This soil erodes easily if not protected. Control of runoff is the main management problem. Well-fertilized pastures of grasses and legumes, if not overgrazed or

mowed too closely, help to reduce runoff and limit erosion.

The site is fairly good for loblolly pine, which can be used as a nurse crop to reestablish upland hardwoods. Plant competition is moderate. Abandoned fields where planting is needed may need site preparation and weeding. The slope is a moderate limitation on the use of equipment. If unprotected, the soil erodes rapidly. Gully erosion is especially likely. Because of the severe hazard of erosion, protection must be provided if roads and trails are built.

This soil is too steep and too eroded to be cultivated every year, but annual and perennial plants that provide food and cover for wildlife can be grown. The plants in idle areas furnish some food and cover. Autumn olive, sericea lespedeza, shrub lespedeza, and annual lespedeza are among the plants that can be grown to attract birds. (Capability unit Vfc 1)

Memphis silt loam, 30 to 65 percent slopes (McG).—This is a well-drained soil on hill-sides that form deep, narrow, meandering, V-shaped valleys as they slope from the narrow, winding ridgetops. The soil formed in loess 20 to 80 feet thick. It occurs as large tracts on the steep bluffs adjacent to the Mississippi River bottoms. The surface layer is brown, very friable silt loam 5 to 8 inches thick. In the uppermost 3 inches there are dark stains from decayed leaves. The subsoil is brown, friable silt loam several feet thick. The depth to alkaline loess ranges from 4 to 6 feet. A few gullies have formed in most areas. Included in mapping were a few areas where the soil is underlain by sand at a depth of 30 to 40 inches.

This soil is medium acid in reaction and moderately high in natural fertility. It is readily penetrated by roots, water, and air. The available water capacity is high, and the root zone is deep. Plants generally have a good supply of moisture.

Very little of this soil has been cleared. Because of the slope, it is unsuited to crops, pasture, or hay. Surface runoff is rapid, and the hazard of erosion is severe.

Most of the acreage is woodland. The existing stands consist mainly of upland hardwoods. The site is good to excellent for oak, hickory, yellow-poplar, and other upland hardwoods. Plant competition is moderate. The slope is a moderate to severe limitation on the use of equipment. The severe hazard of erosion must be considered if roads and trails are built.


Such trees as upland oaks, hickory, beech, black walnut, and dogwood furnish food and cover to many kinds of wildlife, including deer, wild turkey, and squirrels. (Capability unit VIIc 1)

Robinsonville Series

This series consists of deep, well-drained, neutral to moderately alkaline, level soils on young natural levees along the Mississippi River. These soils formed in recent deposits of loamy sediment.

Representative profile of Robinsonville silt loam, three-fourths of a mile east of the Mississippi River and 50 yards south of the Tipton County line:

Ap-0 to 11 inches, dark grayish-brown (10YR 4/2) silt loam; weak, fine, granular structure; very friable; mildly alkaline; abrupt, smooth boundary.



CLIMATIC ATLAS OF THE UNITED STATES




U.S. DEPARTMENT OF COMMERCE
C. R. Smith, Secretary

ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION
Robert M. White, Administrator

ENVIRONMENTAL DATA SERVICE
Woodrow C. Jacobs, Director

JUNE 1968


REPRINTED BY THE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
1983




SITE
≈ 50" / year

Caution should be used in interpolating on these generalized maps, particularly in mountainous areas.

SEA PROJECTION - STANDARD PARALLELS 29° AND 45°
BASED ON PERIOD 1931-60



LAKE EVAPORATION



United States
Department of
Agriculture

Soil
Conservation
Service

Engineering
Division

Technical
Release 55

June 1986



Urban Hydrology for Small Watersheds



REPRODUCED BY
U.S. DEPARTMENT OF COMMERCE
NATIONAL TECHNICAL
INFORMATION SERVICE
SPRINGFIELD, VA. 22161




Figure II-3.—Two-year, 24-hour rainfall.

OVERSIZED

DOCUMENT


Interpretation: Harvester

Reference 6

The paper in this book is made of 50% high grade rag stock with a WATER RESISTING surface sizing.

DISTANCES FROM SIDE STAKES FOR CROSS-SECTIONING

Rightway of any Width. Side Slopes 1½ to 1.
In the figure below, opposite 7 under "Cut or Fill" and under .3 read 11.0, the distance out from the side stake at left. Also, opposite 11 under "Cut or Fill" and under .1 read 16.7, the distance out from the side stake at right.



| Cut or Fill | Distance out from Side or Shoulder Stake | | | | | | | | | | Cut or Fill |
|-------------|--|------|------|------|------|------|------|------|------|------|-------------|
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | |
| 0 | 0.0 | 0.2 | 0.3 | 0.5 | 0.8 | 0.8 | 0.9 | 1.1 | 1.2 | 1.4 | 0 |
| 1 | 1.5 | 1.7 | 1.8 | 2.0 | 2.1 | 2.3 | 2.4 | 2.6 | 2.7 | 2.9 | 1 |
| 2 | 3.0 | 3.2 | 3.3 | 3.5 | 3.6 | 3.8 | 3.9 | 4.1 | 4.2 | 4.4 | 2 |
| 3 | 4.5 | 4.7 | 4.8 | 5.0 | 5.1 | 5.3 | 5.4 | 5.6 | 5.7 | 5.9 | 3 |
| 4 | 6.0 | 6.2 | 6.3 | 6.5 | 6.6 | 6.8 | 6.9 | 7.1 | 7.2 | 7.4 | 4 |
| 5 | 7.5 | 7.7 | 7.8 | 8.0 | 8.1 | 8.3 | 8.4 | 8.6 | 8.7 | 8.9 | 5 |
| 6 | 9.0 | 9.2 | 9.3 | 9.5 | 9.6 | 9.8 | 9.9 | 10.1 | 10.2 | 10.4 | 6 |
| 7 | 10.5 | 10.7 | 10.8 | 11.0 | 11.1 | 11.3 | 11.4 | 11.6 | 11.7 | 11.9 | 7 |
| 8 | 12.0 | 12.2 | 12.3 | 12.5 | 12.6 | 12.8 | 12.9 | 13.1 | 13.2 | 13.4 | 8 |
| 9 | 13.5 | 13.7 | 13.8 | 14.0 | 14.1 | 14.3 | 14.4 | 14.6 | 14.7 | 14.9 | 9 |
| 10 | 15.0 | 15.2 | 15.3 | 15.5 | 15.6 | 15.8 | 15.9 | 16.1 | 16.2 | 16.4 | 10 |
| 11 | 16.5 | 16.7 | 16.8 | 17.0 | 17.1 | 17.3 | 17.4 | 17.6 | 17.7 | 17.9 | 11 |
| 12 | 18.0 | 18.2 | 18.3 | 18.5 | 18.6 | 18.8 | 18.9 | 19.1 | 19.2 | 19.4 | 12 |
| 13 | 19.5 | 19.7 | 19.8 | 20.0 | 20.1 | 20.3 | 20.4 | 20.6 | 20.7 | 20.9 | 13 |
| 14 | 21.0 | 21.2 | 21.3 | 21.5 | 21.6 | 21.8 | 21.9 | 22.1 | 22.2 | 22.4 | 14 |
| 15 | 22.5 | 22.7 | 22.8 | 23.0 | 23.1 | 23.3 | 23.4 | 23.6 | 23.7 | 23.9 | 15 |
| 16 | 24.0 | 24.2 | 24.3 | 24.5 | 24.6 | 24.8 | 24.9 | 25.1 | 25.2 | 25.4 | 16 |
| 17 | 25.5 | 25.7 | 25.8 | 26.0 | 26.1 | 26.3 | 26.4 | 26.6 | 26.7 | 26.9 | 17 |
| 18 | 27.0 | 27.2 | 27.3 | 27.5 | 27.6 | 27.8 | 27.9 | 28.1 | 28.2 | 28.4 | 18 |
| 19 | 28.5 | 28.7 | 28.8 | 29.0 | 29.1 | 29.3 | 29.4 | 29.6 | 29.7 | 29.9 | 19 |
| 20 | 30.0 | 30.2 | 30.3 | 30.5 | 30.6 | 30.8 | 30.9 | 31.1 | 31.2 | 31.4 | 20 |
| 21 | 31.5 | 31.7 | 31.8 | 32.0 | 32.1 | 32.3 | 32.4 | 32.6 | 32.7 | 32.9 | 21 |
| 22 | 33.0 | 33.2 | 33.3 | 33.5 | 33.6 | 33.8 | 33.9 | 34.1 | 34.2 | 34.4 | 22 |
| 23 | 34.5 | 34.7 | 34.8 | 35.0 | 35.1 | 35.3 | 35.4 | 35.6 | 35.7 | 35.9 | 23 |
| 24 | 36.0 | 36.2 | 36.3 | 36.5 | 36.6 | 36.8 | 36.9 | 37.1 | 37.2 | 37.4 | 24 |
| 25 | 37.5 | 37.7 | 37.8 | 38.0 | 38.1 | 38.3 | 38.4 | 38.6 | 38.7 | 38.9 | 25 |
| 26 | 39.0 | 39.2 | 39.3 | 39.5 | 39.6 | 39.8 | 39.9 | 40.1 | 40.2 | 40.4 | 26 |
| 27 | 40.5 | 40.7 | 40.8 | 41.0 | 41.1 | 41.3 | 41.4 | 41.6 | 41.7 | 41.9 | 27 |
| 28 | 42.0 | 42.2 | 42.3 | 42.5 | 42.6 | 42.8 | 42.9 | 43.1 | 43.2 | 43.4 | 28 |
| 29 | 43.5 | 43.7 | 43.8 | 44.0 | 44.1 | 44.3 | 44.4 | 44.6 | 44.7 | 44.9 | 29 |
| 30 | 45.0 | 45.2 | 45.3 | 45.5 | 45.6 | 45.8 | 45.9 | 46.1 | 46.2 | 46.4 | 30 |
| 31 | 46.5 | 46.7 | 46.8 | 47.0 | 47.1 | 47.3 | 47.4 | 47.6 | 47.7 | 47.9 | 31 |
| 32 | 48.0 | 48.2 | 48.3 | 48.5 | 48.6 | 48.8 | 48.9 | 49.1 | 49.2 | 49.4 | 32 |
| 33 | 49.5 | 49.7 | 49.8 | 50.0 | 50.1 | 50.3 | 50.4 | 50.6 | 50.7 | 50.9 | 33 |
| 34 | 51.0 | 51.2 | 51.3 | 51.5 | 51.6 | 51.8 | 51.9 | 52.1 | 52.2 | 52.4 | 34 |
| 35 | 52.5 | 52.7 | 52.8 | 53.0 | 53.1 | 53.3 | 53.4 | 53.6 | 53.7 | 53.9 | 35 |
| 36 | 54.0 | 54.2 | 54.3 | 54.5 | 54.6 | 54.8 | 54.9 | 55.1 | 55.2 | 55.4 | 36 |
| 37 | 55.5 | 55.7 | 55.8 | 56.0 | 56.1 | 56.3 | 56.4 | 56.6 | 56.7 | 56.9 | 37 |
| 38 | 57.0 | 57.2 | 57.3 | 57.5 | 57.6 | 57.8 | 57.9 | 58.1 | 58.2 | 58.4 | 38 |
| 39 | 58.5 | 58.7 | 58.8 | 59.0 | 59.1 | 59.3 | 59.4 | 59.6 | 59.7 | 59.9 | 39 |
| 40 | 60.0 | 60.2 | 60.3 | 60.5 | 60.6 | 60.8 | 60.9 | 61.1 | 61.2 | 61.4 | 40 |

[illegible]

Robert C. Mactel 07/27/53
DBS arrived at 3003 Hawthorne Lane,
Searcy, Mo. 65, going to 100. The property is
now occupied by MASTERCRAFT, a division of
Rachels, Inc. (901) 353-8100. a 1100 occupied by
Center City Float Company. ²⁰⁷¹⁷¹⁵ Factory,
and Memphis in May where, and the
Memphis Polka Impound Lot.

Airport

۱۰۰

Not to scale

←

TH
many
31895

many
Bldgs

Rel. a

KLINIK

HARVEST CLONE


W: 5575:pp: K: 100

Robert C. Mantel 07/20/63

1000 Spoke with Joe Taylor at the Memphis Waste Water Treatment facility, which is located SE of the ~~101~~ 501 I-40 I-40 site. He was not sure where the IH landfill is, but he showed me where his facilities Sludge ponds are. They are located along the river. He also showed me an aerial photo of the area. Aerial photograph from Feb. 20, 1990 which includes the IH facility. He gave me a photocopy of it which helped locate the landfill.



1020 Photo #3 taken from WSWTP admin. Bldg. 1015 gained access to airport area. Photos 5, 6, 7, 8 taken near intersection of gravel road, behind hangers. Possible see MWS #17, (yellow with red lining. Photo #9 was taken from where the gravel road makes a 90° turn near the runway. Celso photo #10 from the middle of the turn. Photos #11, 12 taken from just past the corner. Photos 13, 14, 15, 16 were taken from the gravel road approx. near the runway #16, near the numbers themselves. Photos 17, 18, 19, and 20 were taken on the gravel road, even with the end of the runway. There seems to be no stressed vegetation and wildlife appears abundant.

Robert C. Mantel 07/20/63



MWS 15815-1001 River

07/20/63



Robert G. reported 07/20/63

1120 left airport field. (R 07/20/63)

There is a small stream that probably flows from the site to the Mississippi River. I could not get access to this area. The runoff from the site likely goes into this stream.

The landfill is grassy and mowed - saw well maintained from that stand. (R 07/20/63) started

port. There is a fence that separates the airport from the site. There is an area of street access to the landfill. (R 07/20/63) then

is an area along N. 2nd Street where there is no fence; also there is a section of fence at the corner of Whitney & N. Second St. that is open and not ~~guarded~~ guarded.

1120 left airport field.

1135 Arrive on Klinka ave. Took photo 21 and 22.

and 23. Took photo 24 of front of facility from corner of Klinka and Harvester lane. Also 25, 26.

There is another company occupying the site in addition to previously mentioned ones: Hi-

Speed Hoist and Crane Co. 2512 1/2 S. Inc @ 3015 Harvester lane; Phone 901-357-6231. One more

company - Farnsworth Armored @ 3045 Harvester. Took photo 27 from 2nd street → Took photo 28

of open gate mentioned earlier to show access. 1135 left area.

Robert G. Master





Potential Hazardous Waste Site

PRELIMINARY ASSESSMENT

INTERNATIONAL HARVESTER

MEMPHIS, SHELBY COUNTY, TENNESSEE

TND 007 02 4516

PRELIMINARY ASSESSMENT
INTERNATIONAL HARVESTER
TND 007 02 4516

I. HISTORY OF SITE

The International Harvester Company is located in Memphis, Tennessee, Shelby County approximately one-half mile from the Mississippi. The land in the area is mainly flat with some gently sloped hills.

This company manufactures farm equipment and the manufacturing process includes: casting shearing, machine, welding, assembly, washing, plating and painting.

International Harvester has been in operation since 1947. The company has been operating a disposal site on company property, adjacent to its manufacturing operation from the early 1940's to November 1983. At present the disposal site has been inactive four years, yet closure has not been documented or made available to state superfund file.

II. NATURE OF HAZARDOUS MATERIALS

According to the feasibility study of industrial waste fill site, a hazardous waste site investigation conducted by E.P.A. on October 20-21, 1980, at the International Harvester disposal site noted detectable quantities of lead, chromium and P.C.B's. chromium levels in water samples taken at the site noted the drinking water

standards for chromium limits its concentration to 0.05 mg/l. lead levels in water samples taken showed the concentration to be less than 0.04 mg. which is less than the DWS limits of 0.05 mg/l.

Soil and sediments samples taken at the site also indicate detectable levels of lead, chromium, and PCB's. Samples taken at five locations showed a chromium concentration range 30 to 278 mg/kg and a lead concentration ranging from 57 to 468 mg/kg. PCB's were detected in all soil and sediment samples with concentrations ranging from 180 ug/kg to 18,000 ug/kg quantity of hazardous waste is unknown at this time. International Harvester's landfill is located in a flood plain.

III. DESCRIPTION OF HAZARDOUS CONDITION, INCIDENTS, PERMIT VIOLATION

There is unstable containment due to the fact that the Landfill is located in a floodplain, and therefore requires protection from possible floodwaters.

IV. ROUTE'S FOR CONTAMINATION

Drainage ditches on site empty toward the Mississippi River.

The landfill lies in the flood plains of the Mississippi River and is not protected from possible flood waters.

The site drains also into fields that grow soybeans and wheat.

V. POSSIBLE AFFECTED POPULATION AND RESOURCES

There is a potential for surface water contamination due to possible floodwaters, possible groundwater contamination due to the aquifer of concern and possible food contaminations.

Approximately 2000,00 populus could be affected.

VI. RECOMMENDATION AND JUSTIFICATIONS

This site has become inactive as of November 1983. It is considered to be a RCRA facility. It should be noted for the DSWM that there exist the potential for existing irregularities in waste distribution and a determination of the potential harm of the hazardous waste alleged to be present should be looked into.

RCRA ASSESSMENT

In State Superfund estimation this site (International Harvester) is a RCRA facility.

Since the landfill was in full operation, storing hazardous waste over the allotted time and was considered an active site up until 1983.

The State Superfund Program has conducted remedial action, but at this time International Harvester is considered a RCRA facility and no further action will be taken on behalf of Site Investigation, Division of Superfund.

TH/lag SF #5

REFERENCES

1. Tennessee Department of Health and Environment State Superfund file # 79-525(1).
2. Tennessee Department of Health and Environment Solid Waste Management file # 79-525.
3. Feasibility study of industrial waste fill site. Prepared by: Environmental Management Planning & Engineering March 1982.
4. Tennessee Department of Health and Environment Division of Solid Waste Management Commissioners Orders.
5. Topographic Map of Northwest Memphis Quadrangle.

INTERNATIONAL HARVESTER
3003 HARVESTER AVENUE
MEMPHIS, TENNESSEE

I. Site Identification

- A. Name - International Harvester
- B. County - Shelby
- C. Nearest Urban Area - Memphis
- D. Water Supplies Potentially Affected
 - 1. Public - Not affected
 - 2. Private - Not affected
 - 3. Other
 - a) Drainage ditches on site empty towards the Mississippi River
 - b) The landfill lies in the floodplains of the Mississippi River and is not protected from possible floodwaters.
 - c) The site also drains into fields that grow soybeans and wheat.
- E. Acreage - 10 acres

II. Site History

- A. Owner - International Harvester Corp.
- B. Operator - International Harvester Corp., G. W. Beadles, Manager
- C. Hazardous Waste Data
 - 1. Source - International Harvester
 - 2. Volume - approximately 1000-2000 tons
 - 3. Types of Wastes - Wood, paper, foundry sand, glass, metal scraps, cardboard, trash, paint and paint sludge, washing machine sludge, oils, greases, coolants, wastewater treatment sludge, spent transformer oil, varnish, sealing compound, caustics and acids, electroplating treatment sludge and miscellaneous industrial solid waste
- D. Period of Operation - 1947 to present
- E. Current Status - Feasibility study for closure submitted to SWM Superfund.

III. Investigations

A. Sampling Data

On October 20-21, 1980, EPA conducted a hazardous waste site investigation. During this investigation five sediment or soil samples and two water samples were collected. Chromium and lead were below or slightly above drinking water limits in water, but were very high in sediment/soil; high levels of PCBs were found in all soil samples, and

moderate to low amounts of some extractable/purgeable organic compounds were also found in soil/sediment samples.

Although chromium and lead contamination may enter the Mississippi River, the flow of this river, 470,000 cu. ft/sec., is enough to dilute it. The metal, PCB and organic-contaminated soil may, however, be washed into adjacent fields, which grow food crops, and may also migrate in the event of flooding.

B. Other Investigating Work - None

C. Costs Incurred

| <u>Entity</u> | <u>Activity</u> | <u>Cost</u> |
|---------------|--------------------|-------------|
| EPA | Site Investigation | \$15,000 |

IV. Enforcement Action

1. TN

September 1, 1981 - (SWM & EPA) International Harvester informed that their landfill was out of compliance with the floodplain criteria and was on the EPA open dump inventory.

September 17, 1981 - March 17, 1982 - Extension granted for submittal of a feasibility study for correcting the floodplain problem. Feasibility study submitted March 17, 1982. International Harvester accepted recommendation to close the landfills but subsequently developed financial problems. SWM allowed sufficient time for them to recover financially before requiring closure.

May 6, 1983 (SWM) - Hazardous Waste inspection found no violations for hazardous waste generators.

November, 1983 SWM Superfund staff reviewed closure plan and developed recommendations.

2. EPA

October 20, 1980 - Conducted a hazardous waste site inspection.


October 23, 1981 - International Harvester informed of potential violations of RCRA.

3. Local - None

V. Remedial Action

| <u>Entity</u> | <u>Activity</u> | <u>Cost</u> |
|---------------|-----------------|-------------|
|---------------|-----------------|-------------|

None to date



LOCATION MAP
INTERNATIONAL HARVESTER



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

1. IDENTIFICATION
01 STATE 02 SITE NUMBER
TN 0007-02-4516

II. SITE NAME AND LOCATION

| | | | | |
|---|---|-------------|-----------|----------------|
| 01 SITE NAME (Name, location, or description of site) | 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER | | | |
| International Harvester Company EPIC #73 | 3003 Harvester Lane | | | |
| 03 CITY | 04 STATE | 05 ZIP CODE | 06 COUNTY | 07 COUNTY CODE |
| Memphis | TN | 38127 | Shelby | 57 |
| 08 COORDINATES | 09 LONGITUDE | | | |
| LATITUDE 35 12 23 | LONGITUDE 90 03 05 | | | |

10 DIRECTIONS TO SITE (Starting from nearest public road)

I-240 west until road forks, go north on Thomas, to Marsch, turn west on Marsch to Sunrise North to Frayer then west to Harvester.

III. RESPONSIBLE PARTIES

| | | | |
|---|---|-------------|---------------------|
| 01 OWNER (if owner) | 02 STREET (Business, Home, Residential) | | |
| International Harvester Corporation | 3003 Harvester Lane | | |
| 03 CITY | 04 STATE | 05 ZIP CODE | 06 TELEPHONE NUMBER |
| Memphis | TN | 38127 | (901) 357-5311 |
| 07 OPERATOR (if owner and operator from owner) | 08 STREET (Business, Home, Residential) | | |
| International Harvester Corporation | 3003 Harvester Lane | | |
| 09 CITY | 10 STATE | 11 ZIP CODE | 12 TELEPHONE NUMBER |
| Memphis | TN | 38127 | (901) 357-5311 |
| 13 TYPE OF OWNERSHIP (Check one) | | | |
| <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL | | | |
| <input type="checkbox"/> F. OTHER: _____ <input type="checkbox"/> G. UNKNOWN | | | |

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check at least one)

☐ A. RCRA 3001 DATE RECEIVED: _____ ☐ B. UNCONTROLLED WASTE SITE (RCRA 103 d) DATE RECEIVED: _____ ☒ C. NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

| | | | |
|--|--|--|--|
| 01 ON SITE INSPECTION | 02 BY (Check at least one) | | |
| <input checked="" type="checkbox"/> YES DATE 10/20/80 | <input checked="" type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR | | |
| <input type="checkbox"/> NO | <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ | | |
| CONTRACTOR NAME(S): _____ | | | |
| 03 SITE STATUS (Check one) | 04 YEARS OF OPERATION | | |
| <input type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input checked="" type="checkbox"/> C. UNKNOWN | 1947 1983 <input type="checkbox"/> UNKNOWN | | |

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Alleged chromium and lead, PCB's and some extractable/purgeable organic compounds.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION


Drainage ditches on site that empty toward the Mississippi River. The landfill lies in the flood plains of the Mississippi River and is not protected from possible flood water.

V. PRIORITY ASSESSMENT

| |
|---|
| 01 PRIORITY FOR INSPECTION (Check one, if high or medium is checked, complete Part 2 - Waste Information and Part 3 - Assessment of Hazardous Conditions and Remediation) |
| <input type="checkbox"/> A. HIGH <input checked="" type="checkbox"/> B. MEDIUM <input type="checkbox"/> C. LOW <input type="checkbox"/> D. NONE |

VI. INFORMATION AVAILABLE FROM

| | | |
|--------------------------------------|----------------------------|---------------------|
| 01 CONTACT | 02 OF Agency/ Organization | 03 TELEPHONE NUMBER |
| Z.S. Migut | International Harvester | (901) 357-5311 |
| 04 PERSON RESPONSIBLE FOR ASSESSMENT | 05 AGENCY | 06 ORGANIZATION |
| Robin Tanya Humphries | TDH&E | Superfund |
| 07 TELEPHONE NUMBER | | 08 DATE |
| (615) 741-3424 | | 05/13/87 |





POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

IDENTIFICATION
STATE: TN SITE NUMBER: 003-02-514

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 2000.00 04 NARRATIVE DESCRIPTION

Due to the variations of the Memphis sands, this aquifer has a possibility for ground water contamination.

01 ☒ B SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 2000.00 04 NARRATIVE DESCRIPTION

The landfill lies in the flood plains of the Mississippi River and is not protected from possible flood waters.

01 ☐ C CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ D FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☒ E DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 2000.00 04 NARRATIVE DESCRIPTION

Possible drinking water contamination.

01 ☒ F CONTAMINATION OF SOIL 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 AREA POTENTIALLY AFFECTED: 10 acres (ACRES) 04 NARRATIVE DESCRIPTION

Possible contamination of soil.

01 ☒ G DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: 2000.00 04 NARRATIVE DESCRIPTION

Alleged chromium and lead were below or slightly above drinking water limits.

01 ☐ H WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

01 ☐ I POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

| | |
|-------------------|----------------|
| 1. IDENTIFICATION | |
| 01 STATE | 02 SITE NUMBER |
| TN | 007-02-4516 |

II. HAZARDOUS CONDITIONS AND INCIDENTS (CONTINUE)

01 ☐ J. DAMAGE TO FLORA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ K. DAMAGE TO FAUNA 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION (INCLUDE NUMBER OF SPECIES)

01 ☒ L. CONTAMINATION OF FOOD CHAIN 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

Site drains into fields tht grow soybeans and wheat.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☒ ALLEGED
(Include specific location, quantity, and date)

03 POPULATION POTENTIALLY AFFECTED: 2000.00 04 NARRATIVE DESCRIPTION

Landfill is out of compliance with the flood plain criteria.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL OR ALLEGED HAZARDS

Chromium, lead, PCB's, other organic waste.


III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., State Dept. of Health records, etc.)

TDHE Superfund File

Feasibility study of industrial waste fill site prepared for International Harvester Co. by Environmental Management Planning and Engineering.



NORTHWEST MEMPHIS QUADRANGLE
TENNESSEE-ARKANSAS
7.5 MINUTE SERIES (TOPOGRAPHIC)
NE 1/4 MEMPHIS IS QUADRANGLE

Reference 8

U.S. DEPARTMENT OF JUSTICE
FEDERAL BUREAU OF INVESTIGATION
WASHINGTON, D.C. 20535
MARCH 14, 1934

March 14, 1934


International Harvester Company,
c/o C. T. Corporation, Inc.,
530 Clay Street,
Knoxville, Tennessee 37901

Dear Sir:

Enclosed please find a document entitled, "Confederate's Order Issued by James B. Wood against International Harvester Company." It is our particular direct your attention to the Notice of Rights within.

If you have any questions please call (615) 711-1111.

Sincerely,


William L. Perry
Assistant General Counsel

Enclosure

cc: Don Shackerford
Tom Blankenship, Jr.
Jean Immon

STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT

IN THE MATTER OF:)
)
THE INTERNATIONAL) DIVISION OF SOLID WASTE
HARVESTER COMPANY) MANAGEMENT
MEMPHIS, TENNESSEE) NO. 84-156
)
RESPONDENT)

COMMISSIONER'S ORDER

Comes now, James E. Word, Commissioner of the Tennessee Department of Health and Environment, and states that:

PARTIES

I.

James E. Word is the duly appointed Commissioner of the Tennessee Department of Health and Environment (the "Department").

II.

The International Harvester Company (the "Respondent") is a Maryland Corporation qualified to do business in Tennessee. It is doing business at 3003 Harvester Lane, Memphis, Tennessee 38127. Its registered agent for service of process is: C. T. Corporation Systems, 530 Gay Street, Knoxville, Tennessee 37902. The Company manufactures farm equipment and the manufacturing processes include casting, shearing, machining, welding, assembly, washing, plating and painting.

JURISDICTION

III.

Pursuant to T.C.A. Sections 68-46-111 and 68-46-206, the Commissioner is authorized to issue an order to any liable party requiring such party to investigate, identify, contain, and clean up, including monitoring and maintenance, inactive hazardous substance sites which pose or may pose a danger to public health, safety or the environment because of the release or threatened release of hazardous substances. Pursuant to T.C.A. Section 68-46-215 the Commissioner may issue an order for correction to the appropriate person, and this order shall be complied with within the time limit specified in the order.

IV.

Respondent is a "person" within the meaning of T.C.A. Section 68-46-104 and is also a "liable party" within the meaning of T.C.A. Section 68-46-202.

FACTS

V.

As part of the Respondents manufacturing process, it produces metal plating wastes containing lead, chromium and other elements. This liquid waste is a hazardous substance as defined in T.C.A. Section 68-46-202. The waste is also a listed hazardous waste as defined in the Tennessee Hazardous Waste Regulation 1200-1-11-.02(4).

VI.

The existence of this inactive hazardous substance site poses or may be reasonably anticipated to pose a danger to public health, safety, and environment. This inactive hazardous substance site appears on the proposed list of such sites (pursuant to T.C.A. Section 68-46-206) eligible for investigation, identification, containment and clean up.

VII.

The Respondent reported that it has disposed of hazardous waste at a disposal site owned by International Harvester Company and located at latitude and longitude coordinates 35°12'23" and 90°00'05" respectively. The Respondent has reported the disposal of wood, paper, foundry sand, glass metal scraps, cardboard, trash, paint and paint sludge, washing machine sludge, oils, grease, coolants, wastewater treatment sludge, spent transformer oil, varnishes, sealing compounds, caustics and acids, electroplating treatment sludge and miscellaneous industrial solid waste. The disposal site has been inactive since at least November, 1983.

VIII.

On October 20-21, 1980 EPA conducted a hazardous waste site investigation of International Harvester. Analysis of samples taken during this inspection revealed

that concentrations of chromium and lead were below only slightly above drinking water limits in water, but were very high in sediment/soil. High levels of PCB's were found in all soil samples, and moderate to low amounts of some extractable/purgeable organic compounds were also found in soil/sediment samples.

CLAIMS FOR RELIEF

IX.

By operating this disposal site and generating the hazardous substances disposed of in the site, Respondent is a "liable party" as defined in T.C.A. Section 68-46-202 which is defined as:

"(a.) the owner or operator of an inactive hazardous substance site;

(b.) Any person who at the time of disposal was the owner or operator of an inactive hazardous substance site;

(c.) Any generator of hazardous substance who at the time of disposal caused such substance to be disposed of at an inactive hazardous substance site; . . ."

This site is a hazardous substance site within the meaning of T.C.A. Section 68-46-202 which is defined as "any site or area where hazardous substance disposal has occurred."

X.

PREMISES CONSIDERED, I, James E. Word, hereby ORDER the Respondent, International Harvester Company to comply with the following:

A. INITIAL ASSESSMENT

1. Within sixty (60) days of receipt of this Order, the Respondent shall submit to the Department any existing data available to the Respondent which is pertinent to the assessment of the hazard that the specified site may pose to public health and the environment. This information shall include available data listed in paragraph X.B.2 of this Order and shall be submitted in duplicate.

2. Following receipt of this information, the Department will schedule an initial assessment conference which the Respondent shall attend in the Nashville Office of the Department Division of Solid Waste Management. The Respondent shall be given seven (7) days notice prior to this meeting. The purpose of this conference will be to discuss existing data and determine the need for further investigation, remedial action and/or long term monitoring and maintenance. A schedule for future activities, deemed necessary by the Department, shall be established at this conference. Depending on existing data, the Department may determine that no further action is necessary. In all other cases, the schedule established in this conference will provide the dates by which the activities enumerated herein must be completed.

B. INVESTIGATION PROGRAM

1. According to the schedule established in the initial assessment conference, the Respondent shall submit to the Department a proposed Investigation Plan.

2. In order to provide an accurate assessment of the hazard posed by the site to public health and the environment and to develop design data for remedial action, the Investigation Plan shall include, but not be limited to, assessment of the following factors:

- a. Types and quantities of hazardous substances disposed at the site.
- b. Physical state, analytical summary, toxicological characteristics and other pertinent data defining hazardous substances present at the site.
- c. Methods and extent of the disposal operation including containment methods used, plans and/or photographs of site operation, perimeter and depth of disposal area, and type of disposal operation conducted (open burning, trench, surface impoundment, etc.).
- d. Observed release of contaminants to groundwater, surface water or air, including sampling, to determine contaminant concentrations and extent of contaminant migration.

e. Hydrogeologic evaluation to determine depth to groundwater, permeability of the unsaturated zone, distance to nearest surface water and slope of the disposal area and intervening terrain.

f. Population and environment potentially affected:

(1.) Groundwater use and population served by groundwater sources within a three (3) mile radius of the perimeter of contaminant migration.

(2.) Surface water use and population served within a three (3) mile reach downstream of the perimeter of contaminant migration.

(3.) Population potentially affected by contaminant releases to the air within a four (4) mile radius of the perimeter of contaminant migration.

(4.) Distance from the site to sensitive environments such as a natural wetland, critical habitat for an endangered species or a National Wildlife Refuge.

g. Fire and explosion hazard assessment of the site.

h. Direct contact hazard assessment of the site.

3. The Investigation Plan must include cost estimates and a proposed schedule for completion of activities involved in the investigation. Following a review of the Plan, the Department may schedule a meeting which Respondent shall attend to discuss any revisions required by the Department. The Respondent will be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a revised Investigation Plan shall be submitted by the Respondent to the Department. Upon approval by the Department of the revised Investigation Plan, the Respondent shall begin required activities according to the revised Investigation Plan.

C. REMEDIAL ACTION SELECTION AND IMPLEMENTATION

1. Following completion of the investigation activities, a report providing an assessment of the hazard posed by the site to public health and the environment and proposing remedial action alternatives shall be submitted by the Respondent to the Department according to the Investigation Plan schedule. This report will be referred to as a Hazard Assessment/Remedial Action report (herein after referred to as "HA/RA"). Remedial action alternatives must include cost estimates and proposed schedules for completion of activities involved in remedial action implementation.

2. Assessment of each remedial action alternative must include consideration of the following factors:

- a. The technological feasibility of each alternative;
- b. The cost-effectiveness of each alternative;
- c. The nature of the danger to the public health, safety, and the environment posed by the hazardous substances at the site; and
- d. The extent to which each alternative would achieve the goal of T.C.A. Section 63-46-206(d) which states, in part, "... The goal of any such action shall be cleanup and containment of the site through the elimination of the threat to public health, safety and the environment posed by the hazardous substance."

3. Following the Department review of the HA/RA Report, the Department will schedule a meeting which the Respondent shall attend, to discuss any revisions required by the Department. The Respondent shall be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a revised HA/RA Report shall be submitted to the Department. Upon receipt of approval by the Department of the revised HA/RA Report, the Respondent shall begin activities required by the revised HA/RA Report, unless the Department determines no further action is necessary.

4. The HIA/RA activities shall not be considered complete until the Department has reviewed these activities and issued a letter of acceptance to the Respondent.

D. SITE MONITORING AND MAINTENANCE

1. Where the Department determines a need for site monitoring and maintenance, the Respondent shall provide a Site Monitoring and Maintenance Plan (herein after referred to as "M/M Plan") which shall include a proposed schedule for completion of required activities and cost estimates within ninety (90) days of receipt of a request for said Plan by the Department.

2. Within forty-five (45) days of receipt of this M/M Plan by the Department, the Respondent shall attend a meeting with the Department to discuss any required revisions. On or before a deadline established in this review meeting, a revised M/M Plan shall be submitted by the Respondent to the Department. Upon receipt of approval by the Department, the revised M/M Plan will go into effect.

E. To the extent practicable, any investigation, identification, containment and clean-up, including monitoring and maintenance, shall be consistent with the national contingency plan promulgated pursuant to Section 105 of Public Law 96-510.


F. Certain activities may be deemed critical by the Department and shall require observation by the Department. The Respondent shall provide sufficient notice to the Department to allow scheduling of personnel for these activities. The Department also reserves the right to observe any other activities required pursuant to this Order.

G. Any failure to comply with approved schedules of activities required under this Order shall be a failure to comply with this Order.

H. In this Order, any reference to the singular includes the plural.

I. Further, I, James E. Word, do not waive any rights or authority available to me to assess the International Harvester Company for liability for costs, expenditures, civil penalties or damages incurred by the State pursuant to this Order. I also reserve the right to order such further remedial action to be completed by the Respondent where it is determined that further remedial action is needed.


Issued in this office of the Commissioner of the Tennessee Department of Health and Environment this 14th day of March, 1984.


JAMES E. WORD, Commissioner
Tennessee Department of Health
and Environment

NOTICE OF RIGHTS

International Harvester Company is hereby advised that in accordance with T.C.A. Section 68-46-215 it may secure a review of the necessity for or reasonableness of this Order by filing with the Commissioner, a written petition setting forth the grounds and reason for objection and asking for a hearing in the matter involved before the Solid Waste Disposal Control Board. The Order shall become final and not subject to review unless the person or persons named herein shall file such petition for a hearing no later than thirty (30) days after the date such Order is secured. Hearings will be conducted in accordance with the Tennessee Uniform Administrative Procedures Act.

Correspondence regarding this Order should be addressed to William L. Penny, Assistant General Counsel, 150 9th Avenue, North, Nashville, Tennessee 37203 or telephone (615)741-3657.


William L. Penny
Assistant General Counsel

WLP/bec/Intern Harv

DIVISION OF SUPERFUND SITE IDENTIFICATION NUMBER: #79-525

STATEMENT OF HAZARDOUS SUBSTANCE SITE DISPOSITION:

From 1940's to 1982, International Harvester disposed of hazardous substances including oils, grease, spent transformer oil and paint sludge. The graded landfill is covered with a cap of 6 inches of clay and an additional one foot of clean soil. The site is in monitoring and maintenance phase. Many of the contaminants remain in place. The landfill area is located approximately 250 feet west of the main plant building and should not be disturbed without authorization from the Tennessee Department of Health and Environment, Division of Superfund.

Executed this 29th day of February, 1988.

TENNESSEE DEPARTMENT OF HEALTH AND ENVIRONMENT
JAMES E. WORD, COMMISSIONER

BY: James C. Ault

James C. Ault, Director
Superfund Division

Tennessee Department of Health and Environment
701 Broadway
4th Floor, Customs House
Nashville, Tennessee 37219-5403

STATE OF TENNESSEE

COUNTY OF DAVIDSON

Before me, the undersigned Notary Public in the State and County aforesaid, personally appeared James C. Ault, with whom I am personally acquainted, and who, upon oath acknowledged himself to be Director of the Division of Superfund, Tennessee Department of Health and Environment, and that he as such Director, executed the foregoing instrument by his signature for the purpose therein contained, by delegated authority from the Commissioner of the Department of Health and Environment.

WITNESS, my hand and Official Seal at office this 29th day of February, 1988.

Marion S. Thompson
NOTARY PUBLIC

My Commission Expires April 17, 1988

My Commission Expires: _____

Reference 10

RECEIVED

OCT 29 1987

REPORT OF POST CLOSURE MONITORING
AT THE
INTERNATIONAL HARVESTER LANDFILL SITE
MEMPHIS, TENNESSEE
-THIRD QUARTER, FIRST YEAR-

Prepared by
Hess Environmental Services, Inc.
Memphis, Tennessee

October 6, 1987



HESS ENVIRONMENTAL SERVICES, INC.
6890 HILLSHIRE DRIVE, SUITE 13
MEMPHIS, TENNESSEE 38134
(901) 377-9139

October 6, 1987

Dr. Sheldon Kelman
The Pickering Firm
821 Barksdale, South
Memphis, Tennessee 38114

Dear Dr. Kelman:

Hess Environmental Services, Inc. (HES) has prepared the enclosed "Report of Post Closure Monitoring at the International Harvester Landfill Site, Memphis, Tennessee, Third Quarter, First Year." If you have any questions or comments concerning this report, please feel free to contact me at your convenience.

Dr. Kelman, I have enjoyed working with you on this project and look forward to sampling this site again next quarter.

Sincerely,

Connie Hess, CHMM
President

mm

Enclosure

TABLE OF CONTENTS

| | Page No. |
|-------------------------|----------|
| Summary | 1 |
| I. Introduction | 2 |
| II. Sample Collection | 3 |
| III. Discussion of Data | 12 |
| IV. Conclusions | 14 |

Tables

| | |
|--|----|
| I. Monitoring Well Measurements | 5 |
| II. Analytical Methods | 8 |
| III. Location of Soil Composites Collected | 11 |
| IV. Summary of Data | 13 |

Figure

| | |
|------------------------------|---|
| International Harvester Site | 4 |
|------------------------------|---|

Appendix

| | |
|--------------------|--|
| Laboratory Reports | |
|--------------------|--|

SUMMARY

First year, third quarter groundwater, surface water, sediment and soil samples were collected and analyzed in compliance with post closure monitoring requirements set forth in International Harvester's Closure Plan as enforced by the State of Tennessee.

All water samples were analyzed for chromium and lead content. All sediment and soil samples were analyzed for chromium, lead and Polychlorinated Biphenyls (PCBs) content.

The downgradient well (#4) was found to be dry this quarter.

No metals were detected in any of the groundwater samples collected. Hence, the landfill can not be said to have impacted groundwater surrounding it.

No metals were detected in the surface water composite. Metals and PCBs were found in both soil composites, however these levels were comparable with levels previously found at this site.

Metals, but no PCBs were found in the sediment composite sample collected. The sediment chromium level was comparable with published soil levels referenced in table IV and the lead level in the sediment was below the average level found in a recent study of Memphis soils (HES 1986).

All data is displayed in Table IV of this report.

I. INTRODUCTION

To comply with post closure monitoring requirements set forth in the International Harvester (IH) Closure Plan and enforced by the State of Tennessee, Department of Health and Environment, Division of Superfund (the State), Hess Environmental Services, Inc. (HES) collected groundwater samples from three (3) groundwater monitoring wells (down gradient well #4 was dry), water and sediment samples from the National Pollutant Discharge Elimination System (NPDES) discharge point and soil samples from two (2) areas at the base of the landfill.

All samples were analyzed for chromium and lead content. The soil samples collected below the landfill and the sediment sample collected from the NPDES discharge point were also analyzed for PCB content.

This report addresses sampling, testing and chain-of-custody protocols followed to fulfill third quarter, first year, post closure monitoring requirements.

II. SAMPLE COLLECTION

On September 3 1987, HES provided a team to collect: groundwater, samples from three (3) downgradient wells (#2, #3, and #4) and one (1) upgradient well (#1); one (1) sediment composite and one (1) surface water composite from the (NPDES) discharge point ditch; and two (2) soil composites, the first from below the landfill on the north side, and the second from below the landfill on the south side; no groundwater sample was collected from well #4 this quarter, because it was found to be dry (no water was present in the well). All samples collected at the IH Landfill Site, parcel 4, are shown in Figure 1.

Present on site during sample collection were:

Connie Hess - Senior Chemist with HES
Larry Stewart - Senior Chemist with HES
Marolyn Howe - Chemical Engineer with HES
Bobby King - Environmental Engineer with the State
Bijan Haghtaleb - Environmental Engineer with the
State

Weather conditions were mild, sunny & 22° (72°F).

Groundwater Monitoring Wells

Each of the four (4) two inch ID groundwater monitoring wells had a metal outer well casing with a pad-locked lid. HES found all lids locked. Before sampling, the well depth and the depth to the surface of the groundwater was measured in each well containing water and the volume of the standing water calculated. A record of these measurements is shown in Table I. A Well Wizard, stainless steel portable positive gas displacement bladder pump, Model ST110P, with a Teflon bladder, Teflon tubing and a stainless steel intake screen,

TABLE I
MONITORING WELL
MEASUREMENTS

| WELL NUMBER | 1 | 2 | 3 | 4 |
|--|------|------|------|------|
| Total Depth of Well (Ft.) | 41.5 | 24.8 | 25.0 | 25.0 |
| Depth from MP* to Top of Water Column (Ft.) | 32.7 | 21.6 | 22.3 | 25.0 |
| Height of Water Column (Ft.) | 8.8 | 3.2 | 2.7 | 0.0 |

*MP = Measuring Point, an area (point) at the top of each PVC well casing used as a reference point for measurements.

was used to evacuate one (1) volume of standing water and three (3) volumes of recharge water in wells #1 and #2. Well #3 was bailed to dryness and then a sample collected using a Teflon bailer. This is in accordance with the protocol described in the Environmental Protection Agency's (EPA), Resource Conservation and Recovery Act (RCRA), Groundwater Monitoring Technical Enforcement Guidance Document. Well #4 was found to be dry, therefore no water was evacuated and no sample was taken. Groundwater to be sampled was then pumped into precleaned glass sample containers with Teflon lined lids.

Groundwater samples collected for chromium and lead analysis from well #1 and #2 were filtered using a 0.45 micron filter attached to the discharge tube of the ST 1100P pump. Groundwater samples from well #3 were filtered by the laboratory. Wells #2 and #3 exhibited very slow recharge rates which was consistent with first and second quarter findings.

Because of the lack of rainfall in recent months, the water column in each well was lower than levels measured during previous sampling events.

All groundwater samples were stored on ice (4°) immediately after collection (in the field). Groundwater from wells #1 and #2 to be analyzed for metals were pH adjusted with nitric acid to a pH of <2 and refrigerated (4°) along with the rest of the sample. Groundwater from well #3 was preserved at the laboratory, after filtering, with nitric acid to a pH of less <2.

All sampling equipment and sample container cleaning procedures, sample preservation procedures and analytical procedures were performed in accordance with "Methods for Chemical Analysis of Water and Wastes," EPA-600/4-79-020,

March, 1979, as referenced in the "Rules Governing Hazardous Waste Management in Tennessee." See Table II for the specific analytical method references for each parameter.

Environmental Testing & Consulting, Inc. (ETC), received samples from the three (3) wells. ETC is a laboratory certified by the State of Tennessee (Cert. #00210). Samples were delivered to ETC by HES van on September 3, 1987.

All samples arrived at the laboratory with seal intact.

Established chain-of-custody sample handling protocols were followed. A "Field Log Book" was kept, as required in the chain-of-custody protocol. Pertinent data concerning the site in general, weather conditions, and data collected during the sampling event were recorded. This log will be updated during each quarter's sampling event.

TABLE II
ANALYTICAL METHOD

| PARAMETER | WATER SAMPLES | SOIL/SEDIMENT SAMPLES |
|-----------|------------------|-----------------------|
| | METHOD REFERENCE | METHOD REFERENCE |
| Chromium | 302D*, 303A* | 302D*, 303A* |
| Lead | 302D*, 303A* | 302D*, 303A |
| PCBs | - | 3550, 8080** |

*Standard Methods for the Examination of Water and Wastewater, 16th Edition, American Public Health Association, Inc., New York, New York, 1985.

**Test Methods for Evaluating Solid Waste, Physical Chemical Methods, SW-846, third Edition, Revised, 1986 U.S. Environmental Protection Agency.

NPDES Discharge Point

Samples were collected at the NPDES discharge sampling point below the discharge of storm water located in the northwest area of parcel 4 (see Figure 1). A water and then a sediment composite were collected from this discharge point.

HES personnel collected grab samples of water from two (2) locations along the south bank in the vicinity of the NPDES discharge point. Water was scooped from each location via a clean glass sampling jar then added to a second jar to form the composite. Equal portions of water from each grab sample were poured into the composite accumulation jar; when all grabs were deposited into the accumulation jar the sample was pH adjusted to pH <2 with nitric acid, then covered with a Teflon lined lid.

There appeared to have been little if any flow in the NPDES discharge ditch. Only pools of standing water were present at the time of this sampling event.

Four (4) sediment grab samples were collected in the same area as the water grabs. Sediment grabs were scooped from the rocky stream bed by raking a sampler, comprised of a small stainless steel beaker attached to a stainless steel pole, across each area then pouring each scoop raked, into a glass sampling jar. The sediment accumulated in the jar was then stirred with a stainless steel spatula to form a uniform composite. The jar was then covered with a Teflon lined lid.

Both composite samples were sealed by placing a chain-of-custody seal across each jar lid and down the sides of the jar. The water sample was stored on ice (4°C) along with the groundwater samples. Both samples were delivered along with the monitoring well samples, to ETC, via HES van on September 3, 1987.

Soil Composites

Two (2) soil composite samples were collected at the landfill site, one north and the second south of the NPDES (and storm water) discharge point, below the west face of the landfill.

All areas sampled are shown in Figure I. A description of the soil areas sampled is provided in Table III.

The north and south soil composites were formed by collecting two (2) cores from each of two (2) locations and depositing them in a precleaned Pyrex glass mixing tray. The soil was then mixed in the tray with a stainless steel spatula to form as uniform a composite as possible then placed in a sample jar. The composite jars were then covered with a Teflon lined lid and sealed with a chain-of-custody seal.

Both soil composites were delivered to ETC, via HES van along with the water and sediment samples on September 3, 1987.

TABLE III
LOCATION OF SOIL COMPOSITES COLLECTED

| <u>Composites</u> | <u>Locations Sampled</u> |
|-------------------|--|
| South Composite: | |
| Grab S1 | 18 feet due west of well #2 |
| Grab S2 | 18 feet due west of well #3 |
| North Composite: | |
| Grab N1 | 15 feet due west of well #4 |
| Grab N2 | 51 feet north and 15 feet west of the north concrete retaining wall at the NPDES discharge point |

III. DISCUSSION OF DATA

As stipulated in the IH Closure Plan, all water, soil and sediment samples were analyzed for chromium and lead content. The soil and sediment samples were also analyzed for PCB content.

All soil and sediment sample data is reported on the basis of dry weight (mg/kg).

A summary of all second quarter laboratory data is presented in Table IV, the actual laboratory report is included in the Appendix of this report.

No chromium or lead was detected in groundwater from any of the wells. No metals were detected in the surface water composite. Chromium and lead were found in the sediment and soil composites. PCBs were found current soil composites, but not in the sediment composite.

Third quarter groundwater data for the downgradient wells was comparable with first and second quarter data. The absents of chromium in third quarter groundwater from upgradient well #1 may reflect normal variations in groundwater quality.

Current surface water data is comparable with first and second data. The variations in sediment data probably reflect variations in constituent concentrations at different points in the NPDES stream bed.

Third quarter (site) soil data was comparable with previous data. The relatively small variations in data probably reflect a combination of the ranges present in site soil and normal variations in laboratory data.

TABLE IV
SUMMARY OF DATA

| <u>Groundwater Monitoring Wells</u> | <u>Units</u> | <u>Chromium</u> | <u>Lead</u> | <u>PCBs</u> |
|---|--------------|-----------------|-------------|-------------|
| #1 | mg/l | <0.02 | <0.05 | - |
| #2 | mg/l | <0.02 | <0.05 | - |
| #3 | mg/l | <0.02 | <0.05 | - |
| <u>NPDES Discharge Pt.</u> | | | | |
| Surface Water Comp. | mg/l | <0.02 | <0.05 | - |
| Sediment Comp. | mg/Kg* | 144 | 144 | <0.05 |
| <u>Soils</u> | | | | |
| N. Landfill Comp. | mg/Kg* | 21.7 | 38.4 | 0.64 |
| S. Landfill Comp. | mg/Kg* | 11.9 | 15.9 | 0.24 |
| <u>Average Background Levels</u> | | | | |
| Soil | mg/Kg | 100(1) | 313(2)** | <1(3) |

References

- (1) Allaway, W. H. 1968. Agronomic controls over the environmental cycling of trace elements. Adv. Agron. 20: 235-274.
- (2) Final Report of Soil Sampling and Analysis for the North Hollywood Dump Health Effects Study, Hess Environmental Services, Inc., May 30, 1986.
- (3) Richardson, B. J. and Waid, J. S. (1982). Polychlorinated biphenyls (PCBs): An Australian viewpoint on a global problem. Search 13, 17.

*Dry Weight Basis

**Range 40.7 to 2002 mg/Kg.

IV. CONCLUSIONS

- * Because no metals were found in downgradient groundwater, the landfill can not be said to have impacted groundwater surrounding it.
- * Site surface water and soil composites do not contain contaminants of interest above published background levels.
- * The groundwater level in all wells was lower than, noted first and second quarter monitoring.
- * Most third quarter data is comparable with first and second quarter data with the following exceptions: the level of chromium in background groundwater decreased, the level of lead and PCBs in the sediment decreased and the level of chromium in the sediment increased slightly. The relatively minor variations in data reported to date probably reflect a combination of the ranges present in soil and sediments at the site and normal variations in laboratory data.

No actions beyond reporting the data contained in this report should be required until fourth quarter, first year, when monitoring will again be required.

APPENDIX
LABORATORY REPORT



ENVIRONMENTAL TESTING & CONSULTING INC.

2924 WALNUT GROVE RD. • MEMPHIS, TENN. 38111 • PHONE (901) 327-2750

September 18, 1987

RECEIVED SEP 23 1987

Ms. Connie Hess, President
Hess Environmental Services, Inc.
6890 Hillshire Drive, Suite 13
Memphis, Tenn. 38134

REF: ANALYTICAL TESTING - WATER SAMPLES
SAMPLE(S) DATE: 9/3/87
SAMPLE(S) I.D.: MUF (1,2,3 & 5)

Dear Ms. Hess:


The above referenced samples have been analyzed per your instructions. The tests were performed in our laboratory (#00210) in accordance with Standard Methods, 16th Edition, and the results are shown below.

| Tests | Results (mg/l) | | | | Standard Methods Page # | By | Date |
|----------|----------------|-------|-------|-------|-------------------------------|----|------|
| | #1 | #2 | #3 | #5 | | | |
| Chromium | <0.02 | <0.02 | <0.02 | <0.02 | 157 | JF | 9/4 |
| Lead | <0.05 | <0.05 | <0.05 | <0.05 | 157 | JF | 9/4 |

* Filtered through a 0.45 micron filter.
Analyses on filtrate.

If you have any questions please feel free to contact me.

Very truly yours,


Michael J. Cimbalo
President

MJC/mg

Attachment



ENVIRONMENTAL TESTING & CONSULTING INC.

2924 WALNUT GROVE RD. • MEMPHIS, TENN. 38111 • PHONE (901) 327-2750

September 18, 1987

Ms. Connie Hess, President
Hess Environmental Services, Inc.
6890 Hillshire Drive, Suite 13
Memphis, Tenn. 38134

REF: ANALYTICAL TESTING
SAMPLE(S) DATE: 9/3/87
SAMPLE(S) I.D.: MUF #1 & #2
SOIL & SEDIMENT SAMPLES

Dear Ms. Hess:

The above referenced samples have been analyzed per your instructions. The tests were performed in our laboratory (#00210) in accordance with Standard Methods, 16th Edition, and SW-846, Methods 8080/3550*(PCBs). The results are shown below.

| Tests | Soil Samples | | Sediment | Standard | By | Date |
|----------|-------------------|------|-----------|----------|----|------|
| | MUF Results (ppm) | | MUF (ppm) | Methods | | |
| | #1 | #2 | #1 | Page # | | |
| Chromium | 21.7 | 11.9 | 144 | 157 | JF | 9/8 |
| Lead | 38.4 | 15.9 | 144 | 157 | JF | 9/8 |
| PCBs | 0.64 | 0.24 | <0.05 | * | RR | 9/17 |

If you have any questions please feel free to contact me.

Very truly yours,

Michael J. Cimbalo
President

MJC/mg

Attachment

DSF, JFO, F...

Reference 11

STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT
SOUTHWEST TENNESSEE REGIONAL OFFICE
295 SUMMAR AVENUE
JACKSON, TENNESSEE 38301-3984

July 10, 1989

Dr. Sheldon Kelman, P. E.
Vice President
The Pickering Firm
Suite 500
1750 Madison Avenue
Memphis, TN 38104

Re: International Harvester Landfill Site, TDSF #79-525

Dear Dr. Kelman:

The International Harvester Site was inspected on 6/29,89 (see enclosed trip report). Although many problems have been corrected, there still exist some serious deficiencies at the site. In particular:

1. Many areas on the cap and slopes of the cap are eroded with waste visible at the surface.
2. Areas that have apparently been re-covered and seeded are eroding.
3. The gate erected at the Whitney Road entrance is secured only with a wire (a lock should be purchased and a key made available to the Division).
4. Mowing has been restricted to only the cap and access road. Mowing around the monitoring wells will also be required for obvious reasons.

If a joint site inspection is required to adequately define these problems please feel free to contact me at (901) 424-9200.

Sincerely,



Wm Jordan English
Geologist, TDSF

Enclosure

cc: Edith Ardiente

Reference 12

HAZARDOUS WASTE SITE INVESTIGATION INTERNATIONAL HARVESTER COMPANY MEMPHIS, TENNESSEE MARCH, 1981

INTRODUCTION

A hazardous waste site investigation was conducted at the International Harvester Company, Memphis, TN, during October 20-21, 1980 by J. S. Hall and Charles A. Till of the US Environmental Protection Agency (US-EPA), Region IV, Surveillance and Analysis Division (SAD). This investigation was initiated following a preliminary inspection by personnel of the US-EPA, Region IV, Enforcement Division in May 1980 (1). During the May 1980 inspection, US-EPA, investigators observed wood, pallets, crates, metal, paper, trash, glass, and drums in a landfill adjacent to the plant. The drums in the landfill were alleged to be empty (with the exception of some yellow drums filled with trash), and could not be sold or reconditioned. These drums were not accessible, so their contents or lack thereof were not verified by the US-EPA. The drums that were not sold or reconditioned were supposed to be crushed. There were also approximately 1000 empty drums stacked along the northeastern side of the landfill near the back entrance gate of the plant. The original contents of these drums were reported to be oil, paint, varnish, sealing compound, caustics, and hydrochloric acid.

STUDY AREA

The International Harvester Plant is located at 3003 Harvester Lane on the northwestern side of Memphis (see figure 1). The plant manufactures farm equipment. The manufacturing processes include casting, shearing, machining, welding, assembly, washing, plating, and painting. In addition to manufacturing complete pieces of equipment, the plant also manufactures parts to be shipped to other International Harvester Plants.

The subject landfill is located to the west of the plant. The landfill and adjacent area are situated on the Mississippi River floodplain. All runoff from the landfill drains toward the Mississippi River via a large drainage ditch. The soils around the landfill are floodplain alluvium that consist of materials formed from silts and clays washed from the adjacent uplands, and from silts, clays, sands and gravels deposited by the Mississippi River. The area immediately downgradient from the landfill is presently being farmed. The topography of the area consists of gently sloping uplands to nearly flat to flat bottom lands. (See figure 2 for site map)

During this investigation, four sediment, one soil, and two water samples were collected. Three sediment samples (IH-2, IH-3, IH-4) were collected in depositional areas downgradient from the landfill. A composite soil sample (IH-5) was collected from random locations on top of the landfill. The two water samples IH-6 and IH-001, and another sediment sample IH-7 were collected in the drainage ditch that conveys wastewater from the plant and surface runoff from the landfill to the Mississippi River (see figure 2 for sampling locations). All sampling points were located on International Harvester Company property.

DISCUSSIONS AND RESULTS

The soil and sediment samples were analyzed for organic compounds and metals. Water sample IH-6 was analyzed for organic compounds, metals, and cyanide. Water sample IH-001 was collected for an NPDES inspection so it was analyzed only for metals and other permitted parameters. Results of the NPDES investigation were forwarded January 29, 1981, and are not discussed in this report.

Sampling station locations are included in Table 1. All data included in tables 2 and 3 include only metals and organic compounds that were positively identified and quantified by laboratory analyses. Several organic compounds were tentatively identified and concentrations were estimated; also, some trace concentrations (below the minimum detection level (MDL) of organic compounds and metals were detected but were too low to be quantified. These data, along with all of the analytical results, are included with the analytical data sheets in Attachment 1. Attachment 2 contains all of the field data record sheets.

Extractable and Purgeable Organic Compounds

3,4-benzofluoranthene and/or 11,12-benzofluoranthene was detected at a concentration of 1,500 ug/kg in the sediment sample (IH-3) collected in the small drainage ditch on the western side of the landfill. This sample would have been affected by runoff from most of the landfill area except for the northwest portion. Trace concentrations of eight other extractable organic compounds were detected, but were too low to be quantified (<1,000 ug/kg), including: naphthalene, phenanthrene and/or anthracene, fluoranthene, pyrene, chrysene and/or 1,2-benzanthracene, 3,4-benzopyrene, 1,12-benzoperylene, and phenol (<2,200 ug/kg). Also, 13 other extractable organic compounds were tentatively identified in this sample with estimated concentrations or concentrations too low to be quantified. (See Attachment 1).

Sediment sample IH-2, collected in a depositional area collected at the southern part of the site, contained trace concentrations of nine extractable organic compounds but were too low to be quantified (<1000 ug/kg). These were: naphthalene, phenanthrene and/or anthracene, fluoranthene, pyrene, 1,2-benzanthracene, 3,4-benzofluoranthene and/or 11,12-benzofluoranthene, 3,4-benzopyrene, 1,12-benzoperylene, and phenol (<500 ug/kg). Ten other extractable organic compounds were tentatively identified with estimated concentrations or concentrations too low to be quantified.

Sediment sample IH-4, collected in a depositional area of the northern part of the site, contained a trace concentration of phenol (<1,000 ug/kg). There were also four other extractable organic compounds tentatively identified with estimated concentrations or concentrations too low to be quantified.

Soil sample IH-5 collected on the landfill, contained trace concentrations of fluoranthene (<15,000 ug/kg) and pyrene (<15,000 ug/kg). Also, one other extractable organic compound was tentatively identified in IH-5, but the concentration was too low to be quantified.

Sediment sample IH-7, collected from the large drainage ditch below the site, contained seven extractable organic compounds that were tentatively identified with estimated concentrations, or concentrations too low to be quantified.

The water sample IH-6, collected from the large drainage ditch below the site, contained no detectable extractable organic compounds.

The only purgeable organic compound detected in any of the soil and sediment or water samples collected during this investigation was dichlorodifluoromethane at a trace concentration (<5 ug/kg) in soil sample IH-4.

Chlorinated Organic Compounds

Polychlorinated biphenyls (PCB's) were detected in all of the soil and sediment samples. The concentrations and compounds were as follows: (IH-2), PCB (Aroclor 1248, 18,000 ug/kg); (IH-3), PCB (Aroclor 1248, 5,500 ug/kg); (IH-4), PCB (Aroclor 1248, 8,900 ug/kg); (IH-5), PCB (Aroclor 1254, 3,800 ug/kg); and (IH-7); PCB (Aroclor 1254, 180 ug/kg). These data indicate that PCB concentrations were higher in the landfill area than in the drainage ditch sediments downgradient from the landfill (see figure 2 and table 2). PCB's have been used in numerous commercial applications such as plasticizers, heat transfer fluids, hydraulic fluids, fluids in vacuum pumps and compressors, lubricants, and wax extenders. (2)

Metals

Iron was detected in all of the soil and sediment samples ranging in concentration from 21,360 ug/kg to 41,000 ug/kg. Sediment sample IH-3 contained lead at a concentration of 112 ug/kg, and zinc at a concentration of 147 ug/kg. Sediment sample IH-4 contained chromium, 141 ug/kg; lead, 468 ug/kg, and zinc, 175 ug/kg. Sediment sample IH-7 contained chromium, 278 ug/kg; lead 210 ug/kg; and zinc, 174 ug/kg. Soil sample IH-5 contained chromium at a concentration of 104 ug/kg. Chromium was detected in water sample IH-6 at a concentration of 104 ug/L. None of the other metals detected in the soil, sediment or water samples displayed high concentrations (3) (See table 2 for concentrations).

METHODOLOGY

All sampling and preservation methods used during this investigation were in accordance with the Water Surveillance Branch Standard Operating Procedures and Quality Assurance Manual, August 29, 1980 (4). Chain-of-custody was maintained from time of collection until samples were relinquished to Laboratory Services Branch (LSB) personnel at the North Treatment Plant in Memphis.

Analyses were conducted by the US-EPA, SAD, Laboratory Services Branch (LSB) and Mead Technology (contract laboratory). The soil, sediment and water samples were analyzed for organic compounds and metals by the (LSB). Water sample IH-6 was analyzed by Mead Technology for organic compounds. The (LSB) analyzed water sample IH-6 for metals and cyanide. Water sample IH-001 was analyzed by the (LSB) for NPDES parameters.

REFERENCES

1. "Report - Hazardous Waste Site Investigation - Memphis, Tennessee - First Phase", US Environmental Protection Agency, Region IV, Enforcement Division; June 1980.
2. Ambient Water Quality Criteria for Polychlorinated Biphenyls United States Environmental Protection Agency, EPA-440/5-80-068, 1980.
3. Hazardous Waste Site Investigation, Frayser Pond Site, Memphis, TN. US Environmental Protection Agency, Region IV, Surveillance and Analysis Division, September 17, 1980.
4. Water Surveillance Branch Standard Operating Procedures and Quality Assurance Manual. (Draft); US Environmental Protection Agency Region IV, Surveillance and Analysis Division, August 29, 1980.

Table 1
Sampling Locations
International Harvester Company
Memphis, Tennessee
March, 1981

| Field Identification | SAD No. | Date | Time | Description | Type Sample |
|----------------------|----------|-------|--------------|--|-------------|
| IH-2 | 81C 0103 | 10/20 | 1045 | Depositional area below the southern most part of landfill. | Sediment |
| IH-3 | 81C 0104 | 10/20 | 1100 | Depositional area below landfill in drainage ditch on western side of site | Sediment |
| IH-4 | 81C 0106 | 10/20 | 1120 | Area below landfill on northern most part of dump. | Sediment |
| IH-5 | 81C 0105 | 10/20 | 1130 1145 | Composite sample from several locations on top of landfill. | Soil |
| IH-6 | 81C 0108 | 10/20 | 1420 | Effluent ditch at culvert and field rd. Approx. 1000 ft. below NPDES discharge pipe. | Water |
| IH-7 | 81C 0107 | 10/20 | 1425 | Effluent ditch at culvert and field rd. Approx. 1000 ft. below NPDES discharge pipe. | Sediment |
| IH-001 | 81C 0150 | 10/21 | 0935 | NPDES outfall in ditch discharging from the plant. | Water |

Table 2
Analytical Results
Soil Samples
International Harvester Company
Memphis, Tennessee
March, 1981


| Parameter | Sample Locations | | | | |
|---|------------------|--------|--------|--------|--------|
| | IH-2 | IH-3 | IH-4 | IH-5 | IH-7 |
| 3,4 - benzofluoranthene and/or 11,12 - benzofluoranthene (ug/kg) | ND | 1500 | ND | ND | ND |
| Barium (mg/kg) | 111 | 199 | 316 | 68 | 221 |
| Cadmium (mg/kg) | ND | ND | ND | ND | 4 |
| Chromium (mg/kg) | 30 | 44 | 141 | 104 | 278 |
| Copper (mg/kg) | 26 | 40 | 74 | 50 | 37 |
| Nickel (mg/kg) | 18 | 31 | 35 | 29 | 33 |
| Lead (mg/kg) | 70 | 112 | 468 | 57 | 210 |
| Strontium (mg/kg) | 37 | 48 | 92 | 46 | 41 |
| Titanium (mg/kg) | 275 | 533 | 320 | 112 | 224 |
| Vanadium (mg/kg) | 19 | 49 | 27 | 17 | 55 |
| Yttrium (mg/kg) | 5 | 11 | 8 | 4 | 14 |
| Zinc (mg/kg) | 83 | 147 | 175 | 54 | 174 |
| Zirconium (mg/kg) | 4 | ND | 5 | ND | ND |
| Mercury (mg/kg) | ND | ND | ND | ND | 0.1 |
| Calcium (mg/kg) | 17,638 | 13,170 | 19,300 | 6,591 | 6,050 |
| Magnesium (mg/kg) | 5,176 | 7,497 | 6,800 | 2,977 | 5,350 |
| Aluminum (mg/kg) | 7,282 | 20,985 | 15,900 | 6,200 | 23,750 |
| Iron (mg/kg) | 21,360 | 30,990 | 41,100 | 29,680 | 31,050 |
| Manganese (mg/kg) | 502 | 786 | 665 | 426 | 875 |
| Sodium (mg/kg) | ND | ND | 545 | 390 | ND |
| PCB, (Aroclor 1248) (ug/kg) | 18,000 | 5,500 | 8,900 | ND | ND |
| PCB, (Aroclor 1254) (ug/kg) | ND | ND | ND | 3,800 | 180 |

Note: ND - Indicates material was analyzed for but not detected at or above the minimum detection limit.

Table 3
Analytical Results
Water Sample (IH-6) and NPDES Discharge Sample (IH-001)
International Harvester Company
Memphis, Tennessee
March, 1981

| Parameter | IH-6 | IH-001 |
|------------|--------|--------|
| | (ug/L) | (ug/L) |
| Barium | 41 | 38 |
| Chromium | 104 | 58 |
| Copper | 14 | 11 |
| Molybdenum | 215 | 68 |
| Strontium | 44 | 38 |
| Aluminum | 300 | 154 |
| Calcium | 13 | 13 |
| Magnesium | 5.9 | 6 |
| Iron | 1.0 | 0.6 |
| Sodium | 17.0 | 12 |

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE






FIGURE 2
SITE MAP & SAMPLING LOCATIONS
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

← DRAINAGE FLOW DIRECTION

 SAMPLING LOCATION
IH-2

ATTACHMENT 1

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RCN, IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr.

REC'D. 10-20-80 COMPL'D. 1-26-81

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C | C103 | | |
|--|--|------------------------|------------------------|------------------------|
| SOURCE & STATION | IH-2 Depositional area below So. most part of dump. | | | |
| DATE/TIME | 10-20-80 @ 1045 | | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA | NA |
| 61. N-nitrosodimethylamine | 34451 | NA | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 1000U | | |
| 26. 1,3-dichlorobenzene | 34569 | 1000U | | |
| 27. 1,4-dichlorobenzene | 34574 | 1000U | | |
| 18. bis(2-chloroethyl) ether | 34276 | 1000U | | |
| 12. hexachloroethane | 34399 | 1000U | | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 1000U | | |
| 63. N-nitrosodi-n-propylamine | 34431 | 2000U | | |
| 56. nitrobenzene | 34450 | 1000U | | |
| 52. hexachlorobutadiene | 39705 | 1000U | | |
| 8. 1,2,4-trichlorobenzene | 34554 | 1000U | | |
| 55. naphthalene | 34445 | 1000K | | |
| 43. bis(2-chloroethoxy) methane | 34281 | 1000U | | |
| 54. isophorone | 34411 | 2000U | | |
| 53. hexachlorocyclopentadiene | 34389 | 1000U | | |
| 20. 2-chloronaphthalene | 34584 | 1000U | | |
| 77. acenaphthylene | 34203 | 1000U | | |
| 1. acenaphthene | 34208 | 1000U | | |
| 71. dimethyl phthalate | 34344 | 1000U | | |
| 35. 2,4-dinitrotoluene | 34614 | 1000U | | |
| 36. 2,6-dinitrotoluene | 34629 | 1000U | | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 1000U | | |
| 80. fluorene | 34384 | 1000U | | |
| 70. diethyl phthalate | 34339 | 1000U | | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 1000U | | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 1000U | | |
| 9. hexachlorobenzene | 39701 | 1000U | | |
| 41. 4-bromophenyl phenyl ether | 34639 | 1000U | | |
| 81. phenanthrene 4/ | 34464 | | | |
| 78. anthracene 4/ | 34223 | 1000K | | |
| 68. di-n-butyl phthalate | 39112 | 1000U | | |
| 39. fluoranthene | 34379 | 1000K | | |
| 84. pyrene | 34472 | 1000K | | |
| 67. butyl benzyl phthalate | 34295 | 1000U | | |
| 5. benzidine | 39121 | 2000U | | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 1000U | | |
| 76. chrysene 2/ | 34323 | | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 1000K | | |
| 28. 3,3'-dichlorobenzidine | 34634 | 1000U | | |
| 69. di-n-octyl phthalate | 34599 | 1000U | | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | | |
| 75. 11,12-benzofluoranthene 6/ | 34243 | 1000K | | |
| 73. 3,4-benzopyrene | 34250 | 1000K | | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 1000U | | |
| 82. 1,2,3,6-dibenzanthracene | 34559 | 1000U | | |
| 79. 1,12-benzoperylene | 34524 | 1000K | | |
| 24. 2-chlorophenol | 34589 | 500U | | |
| 57. 2-nitrophenol | 34594 | 500U | | |
| 65a. phenol (GC/MS) | 34695 | 500K | | |
| 34. 2,4-dimethylphenol | 34609 | 500U | | |
| 31. 2,4-dichlorophenol | 34604 | 500U | | |
| 21. 2,4,6-trichlorophenol | 34624 | 500U | | |
| 22. parachlorometa cresol | 34455 | 500U | | |
| 59. 2,4-dinitrophenol | 34619 | 4000U | | |
| 60. 4,6-dinitro-o-cresol | 34660 | 500U | | |
| 64. pentachlorophenol | 39061 | 500U | | |
| 58. 4-nitrophenol | 34649 | 1000U | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/- Tentative identification.

2/- and/or azobenzene.

3/- and/or diphenylamine.

5/- Chrysene and/or 1,2-benzanthracene

6/- 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 4/80

RESULTS ON DRY WEIGHT BASIS

No other organic compounds detected with an estimated minimum detection limit of .1000 ug/kg

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected, The number is the Minimum Detection Limit.

1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RCN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E.W. Loy, Jr.

REC'D. 10-20-80 COMPT'D. 1-26-81

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | | 81C 0104 | | |
|--|-------|--|------------------------|------------------------|
| SOURCE & STATION | | IN-3 Area below dump ditch on Western side of site. | | |
| DATE/TIME | | 10-20-80 @ 1100 | | |
| Compounds on NRDC List of Priority Pollutants | | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 1000U | | |
| 26. 1,3-dichlorobenzene | 34569 | 1000U | | |
| 27. 1,4-dichlorobenzene | 34574 | 1000U | | |
| 18. bis(2-chloroethyl) ether | 34276 | 1000U | | |
| 12. hexachloroethane | 34399 | 1000U | | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 1000U | | |
| 63. N-nitrosodi-n-propylamine | 34431 | 2000U | | |
| 56. nitrobenzene | 34450 | 1000U | | |
| 52. hexachlorobutadiene | 39705 | 1000U | | |
| 8. 1,2,4-trichlorobenzene | 34554 | 1000U | | |
| 55. naphthalene | 34445 | 1000K | | |
| 43. bis(2-chloroethoxy) methane | 34281 | 1000U | | |
| 54. isophorone | 34411 | 2000U | | |
| 53. hexachlorocyclopentadiene | 34389 | 1000U | | |
| 20. 2-chloronaphthalene | 34584 | 1000U | | |
| 77. acenaphthylene | 34201 | 1000U | | |
| 1. acenaphthene | 34202 | 1000U | | |
| 71. dimethyl phthalate | 34344 | 1000U | | |
| 35. 2,4-dinitrotoluene | 34614 | 1000U | | |
| 36. 2,6-dinitrotoluene | 34629 | 1000U | | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 1000U | | |
| 80. fluorene | 34384 | 1000U | | |
| 70. diethyl phthalate | 34339 | 1000U | | |
| 37. 1,2-diphenylhydrazine ^{2/} | 34349 | 1000U | | |
| 62. N-nitrosodiphenylamine ^{3/} | 34436 | 1000U | | |
| 9. hexachlorobenzene | 39701 | 1000U | | |
| 41. 4-bromophenyl phenyl ether | 34639 | 1000U | | |
| 81. phenanthrene ^{4/} | 34464 | | | |
| 78. anthracene ^{5/} | 34223 | 1000K | | |
| 68. di-n-butyl phthalate | 39112 | 1000U | | |
| 39. fluoranthene | 34379 | 1000K | | |
| 84. pyrene | 34472 | 1000K | | |
| 67. butyl benzyl phthalate | 34295 | 1000U | | |
| 5. benzidine | 39121 | 2000U | | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 1000U | | |
| 76. chrysene ^{5/} | 34323 | | | |
| 72. 1,2-benzanthracene ^{2/} | 34529 | 1000K | | |
| 28. 3,3'-dichlorobenzidine | 34634 | 1000U | | |
| 69. di-n-octyl phthalate | 34599 | 1000U | | |
| 74. 3,4-benzofluoranthene ^{6/} | 34233 | | | |
| 75. 11,12-benzofluoranthene ^{6/} | 34245 | 1500 | | |
| 73. 3,4-benzopyrene | 34250 | 1000K | | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 1000U | | |
| 82. 1,2,3,6-dibenzanthracene | 34559 | 1000U | | |
| 79. 1,12-benzoperylene | 34524 | 1000K | | |
| 24. 2-chlorophenol | 34589 | 2200U | | |
| 57. 2-nitrophenol | 34594 | 2200U | | |
| 65a. phenol (GC/MS) | 34695 | 2200K | | |
| 34. 2,4-dimethylphenol | 34609 | 2200U | | |
| 31. 2,4-dichlorophenol | 34604 | 2200U | | |
| 21. 2,4,6-trichlorophenol | 34624 | 2200U | | |
| 22. parachlorometa cresol | 34655 | 2200U | | |
| 59. 2,4-dinitrophenol | 34619 | 11,000U | | |
| 60. 4,6-dinitro-o-cresol | 34660 | 2200U | | |
| 64. pentachlorophenol | 39061 | 2200U | | |
| 58. 4-nitrophenol | 34649 | 4400U | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

^{1/} - Tentative identification.

^{2/} - and/or azobenzene.

^{3/} - and/or diphenylamine.

^{5/} - Chrysene and/or 1,2-benzanthracene

^{6/} - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

ETA. SAG, RCN. TV
Athens, GA 4/8

CHEMIST E.W. Lov, Jr. REC'D. 10-20-30 COMPL'D. 1-2

[illegible]

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST F. W. Loy, Jr.

REC'D. 10-20-80 COMPL'D. 2-3-81

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | | 81C 0106 | | |
|--|-------|---|------------------------|------------------------|
| SOURCE & STATION | | 1H-4 Area below dump on Northern most part of dump | | |
| DATE/TIME | | 10-20-80 @ 1120 | | |
| Compounds on NRDC List of Priority Pollutants | | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloroethyl) ether | 34271 | NA | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 40000U | | |
| 26. 1,3-dichlorobenzene | 34569 | 40000U | | |
| 27. 1,4-dichlorobenzene | 34574 | 40000U | | |
| 18. bis(2-chloroethyl) ether | 34276 | 40000U | | |
| 12. hexachloroethane | 34399 | 40000U | | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 40000U | | |
| 63. N-nitrosodi-n-propylamine | 34431 | 80000U | | |
| 56. nitrobenzene | 34450 | 40000U | | |
| 52. hexachlorobutadiene | 39705 | 40000U | | |
| 8. 1,2,4-trichlorobenzene | 34554 | 40000U | | |
| 55. naphthalene | 34445 | 40000U | | |
| 43. bis(2-chloroethoxy) methane | 34281 | 40000U | | |
| 54. isophorone | 34411 | 80000U | | |
| 53. hexachlorocyclopentadiene | 34389 | 40000U | | |
| 20. 2-chloronaphthalene | 34554 | 40000U | | |
| 77. acenaphthylene | 34201 | 40000U | | |
| 1. acenaphthene | 34208 | 40000U | | |
| 71. dimethyl phthalate | 34341 | 40000U | | |
| 35. 2,4-dinitrotoluene | 34614 | 40000U | | |
| 36. 2,6-dinitrotoluene | 34629 | 40000U | | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 40000U | | |
| 80. fluorene | 34384 | 40000U | | |
| 70. diethyl phthalate | 34339 | 40000U | | |
| 37. 1,2-diphenylhydrazine 4/ | 34349 | 40000U | | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 40000U | | |
| 9. hexachlorobenzene | 39701 | 40000U | | |
| 41. 4-bromophenyl phenyl ether | 34639 | 40000U | | |
| 81. phenanthrene 4/ | 34464 | | | |
| 78. anthracene 4/ | 34223 | 40000U | | |
| 68. di-n-butyl phthalate | 39112 | 40000U | | |
| 39. fluoranthene | 34379 | 40000U | | |
| 84. pyrene | 34472 | 40000U | | |
| 67. butyl benzyl phthalate | 34295 | 40000U | | |
| 5. benzidine | 39121 | 80000U | | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 40000U | | |
| 76. chrysene 2/ | 34323 | | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 40000U | | |
| 28. 3,3'-dichlorobenzidine | 34634 | 40000U | | |
| 69. di-n-octyl phthalate | 34599 | 40000U | | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | | |
| 75. 11,12-benzofluoranthene 2/ | 34245 | 40000U | | |
| 73. 3,4-benzopyrene | 34250 | 40000U | | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 40000U | | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 40000U | | |
| 79. 1,12-benzoperylene | 34574 | 40000U | | |
| 24. 2-chlorophenol | 34589 | 7500U | | |
| 57. 2-nitrophenol | 34594 | 7500U | | |
| 65a. phenol (GC/MS) | 34695 | 7500U | | |
| 34. 2,4-dimethylphenol | 34609 | 7500U | | |
| 31. 2,4-dichlorophenol | 34604 | 7500U | | |
| 21. 2,4,6-trichlorophenol | 34624 | 7500U | | |
| 22. parachloromerc cresol | 34455 | 7500U | | |
| 59. 2,4-dinitrophenol | 34610 | 60000U | | |
| 60. 4,6-dinitro-cresol | 34660 | 7500U | | |
| 64. pentachlorophenol | 34061 | 7500U | | |
| 58. 4-nitrophenol | 34649 | 15000U | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

4/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine.

5/ - Chrysene and/or 1,2-benzanthr
6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, REN. IV
Athens, GA 4/5

CHEMIST E. W. Loy, Jr. REC'D. 12-20-60 COMPTON 3-1

[illegible]

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RCB
Athens, GA

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 11-1-80

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 810 Q105 | | |
|---|--|------------------------|------------------------|
| SOURCE & STATION | 1H-5 Composite of 4 sites from top of dump. 10-20-80 @ 1130 | | |
| DATE/TIME | 10-20-80 @ 1145 | | |
| Compounds on NRC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloroethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 15000U | |
| 26. 1,3-dichlorobenzene | 34549 | 15000U | |
| 27. 1,4-dichlorobenzene | 34574 | 15000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 15000U | |
| 12. hexachloroethane | 34399 | 15000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 15000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 30000U | |
| 56. nitrobenzene | 34450 | 15000U | |
| 52. hexachlorobutadiene | 39705 | 15000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 15000U | |
| 55. naphthalene | 34445 | 15000U | |
| 43. bis(2-chloroethoxy) methane | 34281 | 15000U | |
| 54. isophorone | 34411 | 30000U | |
| 53. hexachlorocyclopentadiene | 34389 | 15000U | |
| 20. 2-chloronaphthalene | 34584 | 15000U | |
| 77. acenaphthylene | 34203 | 15000U | |
| 1. acenaphthene | 34203 | 15000U | |
| 71. dimethyl phthalate | 34344 | 15000U | |
| 35. 2,4-dinitrotoluene | 34614 | 15000U | |
| 36. 2,6-dinitrotoluene | 34629 | 15000U | |
| 40. 4-chlorobenzyl phenyl ether | 34644 | 15000U | |
| 80. fluorene | 34384 | 15000U | |
| 70. diethyl phthalate | 34339 | 15000U | |
| 37. 1,2-diphenylhydrazine ^{4/} | 34349 | 15000U | |
| 62. N-nitrosodiphenylamine ^{3/} | 34436 | 15000U | |
| 9. hexachlorobenzene | 39701 | 15000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 15000U | |
| 81. phenanthrene ^{4/} | 34604 | | |
| 78. anthracene ^{5/} | 34223 | 15000U | |
| 68. di-n-butyl phthalate | 39112 | 15000U | |
| 39. fluoranthene | 34379 | 15000U | |
| 84. pyrene | 34472 | 15000U | |
| 67. butyl benzyl phthalate | 34295 | 15000U | |
| 5. benzidine | 39121 | 30000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 15000U | |
| 76. chrysene ^{5/} | 34323 | | |
| 72. 1,2-benzanthracene ^{2/} | 34529 | 15000U | |
| 28. 3,3'-dichlorobenzidine | 34634 | 15000U | |
| 69. di-n-octyl phthalate | 34599 | 15000U | |
| 74. 3,4-benzofluoranthene ^{6/} | 34233 | | |
| 75. 11,12-benzofluoranthene ^{6/} | 34245 | 15000U | |
| 73. 3,4-benzopyrene | 34250 | 15000U | |
| 83. indeno (1,2,3-cd) pyrene | 34404 | 15000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 15000U | |
| 79. 1,12-benzoperylene | 34524 | 15000U | |
| 24. 2-chlorophenol | 34589 | 500U | |
| 57. 2-nitrophenol | 34594 | 500U | |
| 65a. phenol (GC/MS) | 34625 | 500U | |
| 34. 2,4-dichlorophenol | 34609 | 500U | |
| 31. 2,4-dichlorophenol | 34604 | 500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 500U | |
| 22. p-chlorometa cresol | 34455 | 500U | |
| 59. 2,4-dinitrophenol | 34619 | 500U | |
| 60. 4,6-dinitro-p-cresol | 34660 | 500U | |
| 64. pentachlorophenol | 39061 | 500U | |
| 58. 4-nitrophenol | 34649 | 1000U | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

^{5/} - Chrysene and/or 1,2-benz.
^{6/} - 3,4-benzofluoranthene and
11,12-benzofluoranthene.

EPA, SAG, RCN. IV
Athens, GA 4/80

CHEMIST E. W. Loy, Jr.

REC'D. 10-20-80

COMPL'D. 1-26-

[illegible]

No other organic compounds detected with an estimated minimum detection limit of 15,000 ug/kg

- J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAG, RCN, 1
Athens, GA 4/3

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr.

REC'D. 10-20-80 MPL'D. 2-17

| | | RESULTS ON DRY WEIGHT BASIS | | |
|--|-------|---|------------------------|------------------------|
| SAD NO. | | 81C 0107 | | |
| SOURCE & STATION | | 1H-7 Eff. ditch at Culvert at field Rd. below pipe | | |
| DATE/TIME | | 10-20-80 @ 1426 | | |
| Compounds on NRDC List of Priority Pollutants | | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 5000U | | |
| 26. 1,3-dichlorobenzene | 34569 | 5000U | | |
| 27. 1,4-dichlorobenzene | 34574 | 5000U | | |
| 18. bis(2-chloroethyl) ether | 34776 | 5000U | | |
| 12. hexachloroethane | 34399 | 5000U | | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 5000U | | |
| 63. N-nitrosodi-n-propylamine | 34431 | 10000U | | |
| 56. nitrobenzene | 34450 | 5000U | | |
| 52. hexachlorobutadiene | 39705 | 5000U | | |
| 8. 1,2,4-trichlorobenzene | 34554 | 5000U | | |
| 55. naphthalene | 34445 | 5000U | | |
| 43. bis(2-chloroethoxy) methane | 34281 | 5000U | | |
| 54. isophorone | 34411 | 10000U | | |
| 53. hexachlorocyclopentadiene | 34389 | 5000U | | |
| 20. 2-chloronaphthalene | 34584 | 5000U | | |
| 77. acenaphthylene | 34203 | 5000U | | |
| 1. acenaphthene | 34205 | 5000U | | |
| 71. dimethyl phthalate | 34344 | 5000U | | |
| 35. 2,4-dinitrotoluene | 34614 | 5000U | | |
| 36. 2,6-dinitrotoluene | 34629 | 5000U | | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 5000U | | |
| 80. fluorene | 34384 | 5000U | | |
| 70. diethyl phthalate | 34339 | 5000U | | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 5000U | | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 5000U | | |
| 9. hexachlorobenzene | 39701 | 5000U | | |
| 41. 4-bromophenyl phenyl ether | 34639 | 5000U | | |
| 81. phenanthrene 4/ | 34464 | | | |
| 78. anthracene 5/ | 34223 | 5000U | | |
| 68. di-n-butyl phthalate | 39117 | 5000U | | |
| 39. fluoranthene | 34379 | 5000U | | |
| 84. pyrene | 34472 | 5000U | | |
| 67. butyl benzyl phthalate | 34295 | 5000U | | |
| 5. benzidine | 39121 | 10000U | | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 5000U | | |
| 76. chrysene 2/ | 34323 | | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 5000U | | |
| 28. 3,3'-dichlorobenzidine | 34634 | 5000U | | |
| 69. di-n-octyl phthalate | 34599 | 5000U | | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | | |
| 75. 11,12-benzofluoranthene 6/ | 34265 | 5000U | | |
| 73. 3,4-benzopyrene | 34250 | 5000U | | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 5000U | | |
| 82. 1,2,3,6-dibenzanthracene | 34559 | 5000U | | |
| 79. 1,12-benzoperylene | 34526 | 5000U | | |
| 24. 2-chlorophenol | 34589 | 2100U | | |
| 57. 2-nitrophenol | 34594 | 2100U | | |
| 65a. phenol (GC/MS) | 34695 | 2100U | | |
| 34. 2,4-dimethylphenol | 34609 | 2100U | | |
| 31. 2,4-dichlorophenol | 34604 | 2100U | | |
| 21. 2,4,6-trichlorophenol | 34624 | 2100U | | |
| 22. parachlorometa cresol | 34455 | 2100U | | |
| 59. 2,4-dinitrophenol | 34619 | 17000U | | |
| 60. 4,6-dinitro-o-cresol | 34660 | 2100U | | |
| 64. pentachlorophenol | 39061 | 2100U | | |
| 58. 4-nitrophenol | 34649 | 4200U | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine.

4/ - Phenanthrene and/or anthracene.

5/ - Chrysene and/or 1,2-benzant
6/ - 3,4-benzofluoranthene and/o
11,12-benzofluoranthene.

(OVER)

EPA, SAG, RCM. 1
Athens, CA 4

RESULTS ON DRY WEIGHT BASIS

THE CHROMATOGRAM INDICATES THE PRESENCE OF
A PETROLEUM TYPE PRODUCT.

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

ATKENS, CA
4/80

REC'D. 10-20-80 COMPLET'D. 12-19-80

Memphis, TN

BASED ON WET WEIGHT BASIS

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit
NA - Not analyzed.

NA - Not analyzed.

1/- Tentative identification.

2/- On NRDC List of Priority Pollutants.

SEDIMENT
DATA REPORTING SHEET
PURGEABLE ORGANIC ANALYSIS

KENTON, NORTON
ATHENS, GA
4/80

PROJECT International Harvester CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPLET'D 11-19-80
Memphis, TN

BASED ON WET WEIGHT BASIS

| SAD NO. | 81C 0103 | 81C 0104 | 81C 0105 |
|---|--|---|--------------------------------|
| SOURCE & STATION | IH-2 Depositional area below dump. | IH-3 Below dump ditch western side. | IH-5 composite of 4 top. |
| DATE/TIME | 10-20-80 @ 1045 | 10-20-80 @ 1100 | 10-20-80 @ 1100-1 |
| Compound | ug/kg | ug/kg | ug/kg |
| dichlorodifluoromethane ^{2/} | 34334 | 5U | 5U |
| methyl chloride ^{2/} | 34423 | 5U | 5U |
| methyl bromide ^{2/} | 34416 | 5U | 5U |
| vinyl chloride ^{2/} | 34495 | 5U | 5U |
| chloroethane ^{2/} | 34314 | 5U | 5U |
| methylen chloride ^{2/} | 34426 | 5U | 5U |
| trichlorofluoromethane ^{2/} | 34491 | 5U | 5U |
| 1,1-dichloroethylene ^{2/} | 34504 | 5U | 5U |
| 1,1-dichloroethane ^{2/} | 34499 | 5U | 5U |
| 1,2-trans-dichloroethylene ^{2/} | 34549 | 5U | 5U |
| chloroform ^{2/} | 34318 | 5U | 5U |
| 1,2-dichloroethane ^{2/} | 34534 | 5U | 5U |
| 1,1,1-trichloroethane ^{2/} | 34509 | 5U | 5U |
| carbon tetrachloride ^{2/} | 34299 | 5U | 5U |
| dichlorobromomethane ^{2/} | 34330 | 5U | 5U |
| 1,2-dichloropropane ^{2/} | 34544 | 5U | 5U |
| 1,3-dichloropropylene ^{2/} | 34564 | 5U | 5U |
| trichloroethylene ^{2/} | 34487 | 5U | 5U |
| benzene ^{2/} | 34237 | 5U | 5U |
| chlorodibromomethane ^{2/} | 34309 | 5U | 5U |
| 1,1,2-trichloroethane ^{2/} | 34514 | 5U | 5U |
| 2-chloroethyl vinyl ether (mixed) ^{2/} | 34579 | 5U | 5U |
| bromoform ^{2/} | 34290 | 5U | 5U |
| 1,1,2,2-tetrachloroethane ^{2/} | 34519 | 5U | 5U |
| tetrachloroethylene ^{2/} | 34478 | 5U | 5U |
| toluene ^{2/} | 34483 | 5U | 5U |
| chlorobenzene ^{2/} | 34304 | 5U | 5U |
| ethylbenzene ^{2/} | 34374 | 5U | 5U |
| acrolein ^{2/} | 34213 | 100U | 100U |
| acrylonitrile ^{2/} | 34218 | 100U | 100U |
| Bihydrothiophene 1/ | 5U | 5U | 8.1 |

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

NA - Not analyzed.

1/ - Tentative identification.

2/ - On NRDC List of Priority Pollutants.

ADDITIONAL
DATA REPORTING SHEET
PURGEABLE ORGANIC ANALYSIS

ATHENS, GA
4/80

PROJECT: International Harvester CHEMIST: E. W. Lov, Jr. REC'D: 10-20-80 COMPLET'D: 12-12-80
Memphis, TN

BASED ON NET WEIGHT BASIS

| SKD NO. | BIC | U106 | BIC | C107 |
|---|--------------------------------|-------|---------------------------------|-------|
| SOURCE & STATION | IH-4 Below dump northern part. | | IH-7 Effluent ditch at Culvert. | |
| DATE/TIME | 10-20-80 1120-1145 | | 10-20-80 1125-1145 | |
| Compound | ug/kg | ug/kg | ug/kg | ug/kg |
| dichlorodifluoroethane ^{2/} | 34374 | 5U | 5U | |
| methyl chloride ^{2/} | 34421 | 5U | 5U | |
| ethyl bromide ^{2/} | 34416 | 5U | 5U | |
| vinyl chloride ^{2/} | 34495 | 5U | 5U | |
| chloroethane ^{2/} | 34314 | 5U | 5U | |
| methylene chloride ^{2/} | 34426 | 5U | 5U | |
| trichlorofluoromethane ^{2/} | 34491 | 5U | 5U | |
| 1,1-dichloroethene ^{2/} | 34504 | 5U | 5U | |
| 1,1-dichloroethane ^{2/} | 34499 | 5U | 5U | |
| 1,2-trans-dichloroethene ^{2/} | 34549 | 5U | 5U | |
| chloroform ^{2/} | 34318 | 5U | 5U | |
| 1,2-dichloroethane ^{2/} | 34534 | 5U | 5U | |
| 1,1,1-trichloroethane ^{2/} | 34509 | 5U | 5U | |
| carbon tetrachloride ^{2/} | 34299 | 5U | 5U | |
| dichlorobromomethane ^{2/} | 34330 | 5U | 5U | |
| 1,2-dichlorobromomethane ^{2/} | 34544 | 5U | 5U | |
| 1,3-dichloropropene ^{2/} | 34564 | 5U | 5U | |
| trichloroethene ^{2/} | 34487 | 5U | 5U | |
| benzene ^{2/} | 34237 | 5U | 5U | |
| chlorodibromomethane ^{2/} | 34309 | 5U | 5U | |
| 1,1,2-trichloroethane ^{2/} | 34514 | 5U | 5U | |
| 2-chloroethyl vinyl ether (mixed) ^{2/} | 34578 | 5U | 5U | |
| bromoform ^{2/} | 34290 | 5U | 5U | |
| 1,1,2,2-tetrachloroethane ^{2/} | 34519 | 5U | 5U | |
| tetrachloroethene ^{2/} | 34478 | 5U | 5U | |
| toluene ^{2/} | 34493 | 5U | 5U | |
| chlorobenzene ^{2/} | 34304 | 5U | 5U | |
| ethylbenzene ^{2/} | 34374 | 5U | 5U | |
| acrolein ^{2/} | 34213 | 100U | 100U | |
| acrylonitrile ^{2/} | 34218 | 100U | 100U | |

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

NA - Not analyzed.

1/ - Tentative identification.

2/ - On NRDC List of Priority Pollutants.

EPA-SAD-LSE-4-10-EC
6

CO'PL'D : 2-17-59

RESULTS ON DRY WEIGHT BASIS

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

PROJECT International Harvester
Memphis, TNCHEMIST B. McDanielREC'D 10-20-80COMPL'D 12-17-80PROJECT NUMBER 81-6

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 610 | 0107 | | | |
|------------------|-------|--|--|--|--|
| SOURCE & STATION | | IN-7 Eff. ditch at Culvert at field Rd. below pipe. | | | |
| DATE/TIME | | 10-20-80 1425-1445 | | | |
| ELEMENT (mg/kg) | | | | | |
| Silver* | 01078 | 3K | | | |
| Arsenic* | 01003 | 14K | | | |
| Boron | 01023 | | | | |
| Barium | 01008 | 221 | | | |
| Beryllium* | 01013 | 4K | | | |
| Cadmium* | 01028 | 4 | | | |
| Cobalt | 01038 | 8K | | | |
| Chromium* | 01029 | 278 | | | |
| Copper* | 01043 | 37 | | | |
| Molybdenum | 01063 | 8K | | | |
| Nickel* | 01068 | 33 | | | |
| Lead* | 01052 | 210 | | | |
| Antimony* | 01098 | 10K | | | |
| Selenium* | 01148 | 16K | | | |
| Tin | 01103 | 24K | | | |
| Strontium | 01083 | 41 | | | |
| Tellurium | 45513 | 16K | | | |
| Titanium | 01153 | 224 | | | |
| Thallium* | 74480 | 40K | | | |
| Vanadium | 01088 | 55 | | | |
| Yttrium | 45514 | 14 | | | |
| Zinc* | 01093 | 174 | | | |
| Zirconium | 01163 | 4K | | | |
| Mercury* | 71921 | 0.1 | | | |
| Calcium | 00917 | 6050 | | | |
| Manganese | 00924 | 5350 | | | |

- CONTINUED ON BACK -

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

* - Priority Pollutant.

WATER
DATA REPORTING SHEET

SAD NO. RIC 0108 CONTRACT LAB NO. D0212 CONTRACT LAB Ward Technology
PROJECT International Harvester SOURCE & STATION IR-6 EFF. DRAIN AT Culvert at
Memphis, TN Field Road below pipe
DATE/TIME SAMPLED 10-20-80 @ 1429 SAMPLE RECEIVED 10-20-80 DATA RECEIVED 11-12-80

| VOLATILE COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | | ug/L | TENTATIVELY-IDENTIFIED COMPOUNDS | ug/L |
|--|----------------------------|-------|------|--|------|
| 2V | Acrolein | 34210 | 100U | The chromatogram indicates the presence of a petroleum-type product. | |
| 3V | Acrylonitrile | 34215 | 100U | | |
| 4V | Benzene | 34030 | 10U | | |
| 6V | Carbon Tetrachloride | 32102 | 10U | | |
| 7V | Chlorobenzene | 34301 | 10U | | |
| 10V | 1,2-Dichloroethane | 32103 | 10U | | |
| 11V | 1,1,1-Trichloroethane | 34506 | 10U | | |
| 13V | 1,1-Dichloroethane | 34496 | 10U | | |
| 14V | 1,1,2-Trichloroethane | 34511 | 10U | | |
| 15V | 1,1,2,2-Tetrachloroethane | 34516 | 10U | | |
| 16V | Chloroethane | 34311 | 10U | | |
| 19V | 2-Chloroethylvinyl Ether | 34576 | 10U | | |
| 23V | Chloroform | 32106 | 10U | | |
| 29V | 1,1-Dichloroethylene | 34501 | 10U | | |
| 30V | 1,2-Trans-Dichloroethylene | 34546 | 10U | | |
| 32V | 1,2-Dichloropropane | 34541 | 10U | | |
| 33V | 1,3-Dichloropropane | 34551 | 10U | | |
| 38V | Ethylbenzene | 34371 | 10U | | |
| 44V | Methylene Chloride | 34423 | 10U | | |
| 45V | Methyl Chloride | 34418 | 10U | | |
| 46V | Methyl Bromide | 34413 | 10U | | |
| 47V | Bromoform | 32104 | 10U | | |
| 48V | Dichlorobromomethane | 32101 | 10U | | |
| 49V | Trichlorofluoromethane | 34458 | 10U | | |
| 50V | Dichlorodifluoromethane | 34658 | 10U | | |
| 51V | Chlorodibromomethane | 34305 | 10U | | |
| 85V | Tetrachloroethylene | 34475 | 10U | | |
| 86V | Toluene | 34010 | 10U | | |
| 87V | Trichloroethylene | 39150 | 10U | | |
| 88V | Vinyl Chloride | 39175 | 10U | | |

| PESTICIDES/PCB'S ON NRDC LIST OF PRIORITY POLLUTANTS | | | ug/L |
|--|--|-------|-------|
| 89P | Aldrin | 39330 | 0.10U |
| 90P | Dieldrin | 39320 | 0.10U |
| 91P | Chlordane (Tech. Mixture & Metabolites) | 39350 | 0.10U |
| 92P | 4,4'-DDT (p,p'-DDT) | 39300 | 0.10U |
| 93P | 4,4'-DDE (p,p'-DDE) | 39320 | 0.10U |
| 94P | 4,4'-DDD (p,p'-TDE) | 39310 | 0.10U |
| 95P | a-Endosulfan-Alpha | 34361 | 0.10U |
| 96P | b-Endosulfan-Beta | 34356 | 0.10U |
| 97P | Endosulfan Sulfate | 34351 | 0.10U |
| 98P | Endrin | 39390 | 0.10U |
| 99P | Endrin Aldehyde | 34356 | 0.10U |
| 100P | Heptachlor | 39410 | 0.10U |
| 101P | Heptachlor Epoxide | 39420 | 0.10U |
| 102P | a-BHC-Alpha | 39337 | 0.10U |
| 103P | b-BHC-Beta | 39338 | 0.10U |
| 104P | gamma-BHC-(Lindane)-Gamma | 39340 | 0.10U |
| 105P | delta-BHC-Delta | 34359 | 0.10U |
| 106P | PCB-1242 (Aroclor 1242) | 39496 | 0.10U |
| 107P | PCB-1254 (Aroclor 1254) | 39504 | 0.10U |
| 108P | PCB-1221 (Aroclor 1221) | 39493 | 0.10U |
| 109P | PCB-1232 (Aroclor 1232) | 39491 | 0.10U |
| 110P | PCB-1248 (Aroclor 1248) | 39500 | 0.10U |
| 111P | PCB-1260 (Aroclor 1260) | 39508 | 0.15U |
| 112P | PCB-1016 (Aroclor 1016) | 34471 | 0.10U |
| 113P | Toxaphene | 39400 | 0.40U |
| 129P | 2,3,7,8-Tetrachlorodibenzo-p-dioxin (TCDD) | 34675 | NA |

NA - Not analyzed.
J - Estimated value.
K - Actual value is known to be less than value given.

5/22/80

WATER
DATA REPORTING SHEET

SAD NO. 81C010R CONTRACT LAB NO. D0212 CONTRACT LAB Head Technology
 PROJECT International Harvester SOURCE & STATION IH-6 EFF. Ditch at Culvert at
 Memphis, TN Field Road below mine.
 DATE/TIME SAMPLED 10-20-80 @ 1420 SAMPLE RECEIVED 10-20-80 DATA RECEIVED 10-17-80

| PAH/NEUTRAL COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | ug/L |
|--|-------|------|
| 19 Acenaphthene | 34205 | 10U |
| 5B Benzidine | 39120 | 10U |
| 9A 1,2,4-Trichlorobenzene | 34551 | 10U |
| 9B Hexachlorobenzene | 39700 | 10U |
| 12A Hexachlorocyclopentadiene | 34396 | 10U |
| 17A Bis(Chloromethyl) Ether | 34269 | NA |
| 18B Bis(2-Chloroethyl) Ether | 34273 | 10U |
| 20A 2-Chloronaphthalene | 34581 | 10U |
| 25B 1,2-Dichlorobenzene | 34536 | 10U |
| 26A 1,3-Dichlorobenzene | 34566 | 10U |
| 27B 1,4-Dichlorobenzene | 34571 | 10U |
| 28B 3,3'-Dichlorobenzidine | 34631 | 10U |
| 35B 2,4-Dinitrotoluene | 34611 | 10U |
| 36B 2,6-Dinitrotoluene | 34626 | 10U |
| 37B 1,2-Diphenylhydrazine | 34346 | 10U |
| 39B Fluoranthene | 34375 | 10U |
| 40B 4-Chlorophenyl Phenyl Ether | 34641 | 10U |
| 41B 4-Bromophenyl Phenyl Ether | 34636 | 10U |
| 42B Bis(2-Chloroisopropyl) Ether | 34283 | 10U |
| 43B Bis(2-Chloroethoxy) Methane | 34278 | 10U |
| 52B Hexachlorobutadiene | 39702 | 10U |
| 53B Hexachlorocyclopentadiene | 34386 | 10U |
| 54B Isophorone | 34408 | 10U |
| 55B Naphthalene | 34696 | 10U |
| 56B Nitrobenzene | 34447 | 10U |
| 61B N-Nitrosodimethylamine | 34438 | NA |
| 62B N-Nitrosodiphenylamine | 34433 | 10U |
| 63B N-Nitrosodi-N-Propylamine | 34428 | 10U |
| 66B Bis(2-Ethylhexyl) Phthalate | 39100 | 50U |
| 67B Butyl Benzyl Phthalate | 34292 | 10U |
| 68B Di-N-Butylphthalate | 39110 | 10U |
| 69B Di-N-Octylphthalate | 34596 | 10U |
| 70B Diethylphthalate | 34336 | 10U |
| 71B Dimethylphthalate | 34341 | 10U |
| 72B Benzo (A) Anthracene | 34526 | 10U |
| 73B Benzo(A) Pyrene | 34247 | 10U |
| 74B 3,4-Benzofluoranthene | 34230 | 10U |
| 75B Benzo(K) Fluoranthene | 34242 | 10U |
| 76B Chrysene | 34320 | 10U |
| 77B Acenaphthylene | 34200 | 10U |
| 78B Anthracene | 34220 | 10U |
| 79B Benzo(GHI) Perylene | 34521 | 25U |
| 80B Fluorene | 34381 | 10U |
| 81B Phenanthrene | 34461 | 10U |
| 82B Dibenzo(A, H) Anthracene | 34556 | 25U |
| 83B Indeno (1,2,3-CD) Pyrene | 34403 | 25U |
| 84B Pyrene | 34469 | 25U |

| ACID COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | ug/L |
|---|-------|------|
| 21A 2,4,6-Trichlorophenol | 34621 | 25U |
| 22A p-Chloro-m-Cresol | 34452 | 25U |
| 24A 2-Chlorophenol | 34586 | 25U |
| 31A 2,4-Dichlorophenol | 34601 | 25U |
| 34A 2,4-Dimethylphenol | 34606 | 25U |
| 37A 2-Nitrophenol | 34591 | 25U |
| 38A 4-Nitrophenol | 34646 | 25U |
| 59A 2,4-Dinitrophenol | 34616 | 250U |
| 60A 4,6-Dinitro-o-Cresol | 34657 | 250U |
| 64A Pentachlorophenol | 39032 | 25U |
| 65A Phenol (GC/MS) | 34694 | 25U |

X - Actual value is known to be less than value given.
 U - Material was analyzed for but not detected. The number is the minimum detection limit.
 1/ - And/or Azobenzene.
 2/ - And/or Diphenylamine.
 3/ - 813 Phenanthrene and/or 783 Anthracene.

DATA REPORTING SHEET
WATER

EPA-SAD-108 4-10-80

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-20-80 COMPL'D 11-20-80
Memphis, TN

PROJECT No. 81-6

| SAD NO. | 81-C | 0103 | | |
|-------------------|--|------|--|--|
| SOURCE & STATION | IH-6 EFF Ditch at Culvert and Field Rd. Below Pipe. | | | |
| DATE/TIME | 10-20-80 @ 1420-1145 | | | |
| ELEMENT (ug/l.) | | | | |
| Silver * 01077 | 10K | | | |
| Arsenic * 01002 | 45K | | | |
| Boron 01022 | --- | | | |
| Barium 01007 | 41 | | | |
| Beryllium * 01012 | 10K | | | |
| Cadmium * 01027 | 10K | | | |
| Cobalt 01037 | 20K | | | |
| Chromium * 01034 | 104 | | | |
| Copper * 01042 | 14 | | | |
| Molybdenum 01062 | 215 | | | |
| Nickel * 01067 | 35K | | | |
| Lead * 01051 | 40K | | | |
| Antimony * 01097 | 25K | | | |
| Selenium * 01147 | 40K | | | |
| Tin 01102 | 60K | | | |
| Strontium 01082 | 44 | | | |
| Tellurium 01064 | 40K | | | |
| Titanium 01152 | 10K | | | |
| Thallium * 01059 | 100K | | | |
| Vanadium 01087 | 10K | | | |
| Yttrium * 01203 | 10K | | | |
| Zinc * 01092 | --- | | | |
| Zirconium 01162 | 10K | | | |
| Mercury * 71200 | 0.2K | | | |
| Aluminum 01105 | 300 | | | |
| Manganese 01055 | 50K | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

* - Priority Pollutant.

(Continued on Encl)

001-000-000-000-000

COMPL'D 11-20

X - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

DATA REPORTING SHEET
WATER

10-21-80 11-20-80

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-21-80 COPIED 11-20-80
Memphis, TN
PROJECT No. 81-6

| SAD NO. | SIC | 0150 | | | |
|------------------|-------|---|--|--|--|
| SOURCE & STATION | | 1H-001 NPDES Outfall in ditch downstream. | | | |
| DATE/TIME | | 10-21-80 @ 0935 | | | |
| ELEMENT (ug/L) | | | | | |
| Silver * | 01077 | 10K | | | |
| Arsenic * | 01002 | 45K | | | |
| Boron | 01022 | --- | | | |
| Barium | 01007 | 38 | | | |
| Beryllium * | 01012 | 10K | | | |
| Cadmium * | 01027 | 10K | | | |
| Cobalt | 01037 | 20K | | | |
| Chromium * | 01034 | 58 | | | |
| Copper * | 01042 | 11 | | | |
| Molybdenum | 01062 | 68 | | | |
| Nickel * | 01067 | 35K | | | |
| Lead * | 01051 | 40K | | | |
| Antimony * | 01097 | 25K | | | |
| Selenium * | 01147 | 40K | | | |
| Tin | 01102 | 60K | | | |
| Strontium | 01082 | 38 | | | |
| Tellurium | 01064 | 40K | | | |
| Titanium | 01152 | 10K | | | |
| Thallium * | 01059 | 100K | | | |
| Vanadium | 01087 | 10K | | | |
| Yttrium | 01203 | 10K | | | |
| Zinc * | 01092 | --- | | | |
| Zirconium | 01162 | 10K | | | |
| Mercury * | 71900 | 0.2K | | | |
| Aluminum | 01105 | 154 | | | |
| Manganese | 01055 | 50K | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

11-11-1964

CONFIDENTIAL-20

Memphis, TN

81-6

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

* - Priority Pollutant.

CO2K: 15, 11, 6, 4 : 25.0

ATTACHMENT 2

U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>TH-001</u> |
| ADDRESS <u>Memphis TN</u> | SAMPLING LOCATION <u>UPPER outlet</u> |
| CONTACT <u></u> | <u>exl in ditch downstream</u> |
| | <u>open sampling for 1 month</u> |
| | <u>collecting 4 1/2 liter samples weekly</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☒ IND. ☐ INF. ☒ EFF. ☐ 24 HR. COMP. AT 30 MIN. INTERVALS ☐ FLOW PRO
 SAMPLER ☒ EPA ☐ DISCHARGER ☐ MAN. ☒ AUTO. ☐ TYPE 1510 1680 H 163022 (1:30)
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ EQUIP.
 COMPUTED FROM

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------------------|------------------------|-----------------|------------------|
| DATE | <u>10/21/50</u> | <u>10/21/50</u> | 0 BACTERIAL |
| TIME | <u>1000 1045</u> | <u>0935</u> | 1 BOD COD TOC |
| FLOW (cfs) L | <u>1.44</u> | | 2 CYANIDE |
| TEMPERATURE °C | | <u>25</u> | 3 METALS |
| pH | | <u>7.3</u> | 4 N.P. |
| TOT. Cl ₂ RES. mg/l | | | 5 ORG. OBG. PEST |
| | | | 6 PHENOLS |
| | | | 7 SOLIDS |
| SAMPLE CODE | <u>2c water</u> | | 8 |
| SAMPLED BY (Sig) | <u>EST. / 10/21/50</u> | | 9 |
| SEALED BY (Sig) | <u>EST.</u> | | A |
| DATE AND TIME | <u>10/21/50 7:30</u> | | B |
| | | | P PRESERVED |

11 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>B. G. ...</u> | <u>10/21/50</u> | <u>11:30</u> | <u>1</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

Q-1 - 1 pt glass metals

pH Buffer 1

4 4.2

7 6.8

10 7.4

1,440,000 gal / 24 hr peak

pH meter sufficient

7.0, 7.0, 7.0 on 4

on 10

**U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION**

REGION IV

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>I H-2</u> |
| ADDRESS <u>Memphis, TN</u> | SAMPLING LOCATION <u>area behind Smith's market park of dump</u> |
| CONTACT <u>Gene Cuthrell</u> | |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT SAMPLE HR. COMP. AT 5 MIN. INTERVALS ☐ FLOW PRO

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | DATE | TIME | FLOW () L | TEMPERATURE °C | pH | TOT. C12 RES. mg/l | SAD NO. | DATE | TIME | FLOW () L | TEMPERATURE °C | pH | TOT. C12 RES. mg/l | SAMPLE CODE 13 |
|---------|-----------|------|------|------------|----------------|----|--------------------|---------|------|------|------------|----------------|----|--------------------|----------------|
| | | | | | | | | | | | | | | | 1 |
| | | | | | | | | | | | | | | | 2 |
| | | | | | | | | | | | | | | | 3 |
| | | | | | | | | | | | | | | | 4 |
| | | | | | | | | | | | | | | | 5 |
| | | | | | | | | | | | | | | | 6 |
| | | | | | | | | | | | | | | | 7 |
| | | | | | | | | | | | | | | | 8 |
| | | | | | | | | | | | | | | | 9 |
| | | | | | | | | | | | | | | | 10 |
| | | | | | | | | | | | | | | | 11 |
| | | | | | | | | | | | | | | | 12 |
| | | | | | | | | | | | | | | | 13 |
| | | | | | | | | | | | | | | | 14 |
| | | | | | | | | | | | | | | | 15 |
| | | | | | | | | | | | | | | | 16 |
| | | | | | | | | | | | | | | | 17 |
| | | | | | | | | | | | | | | | 18 |
| | | | | | | | | | | | | | | | 19 |
| | | | | | | | | | | | | | | | 20 |
| | | | | | | | | | | | | | | | 21 |
| | | | | | | | | | | | | | | | 22 |
| | | | | | | | | | | | | | | | 23 |
| | | | | | | | | | | | | | | | 24 |
| | | | | | | | | | | | | | | | 25 |
| | | | | | | | | | | | | | | | 26 |
| | | | | | | | | | | | | | | | 27 |
| | | | | | | | | | | | | | | | 28 |
| | | | | | | | | | | | | | | | 29 |
| | | | | | | | | | | | | | | | 30 |
| | | | | | | | | | | | | | | | 31 |
| | | | | | | | | | | | | | | | 32 |
| | | | | | | | | | | | | | | | 33 |
| | | | | | | | | | | | | | | | 34 |
| | | | | | | | | | | | | | | | 35 |
| | | | | | | | | | | | | | | | 36 |
| | | | | | | | | | | | | | | | 37 |
| | | | | | | | | | | | | | | | 38 |
| | | | | | | | | | | | | | | | 39 |
| | | | | | | | | | | | | | | | 40 |
| | | | | | | | | | | | | | | | 41 |
| | | | | | | | | | | | | | | | 42 |
| | | | | | | | | | | | | | | | 43 |
| | | | | | | | | | | | | | | | 44 |
| | | | | | | | | | | | | | | | 45 |
| | | | | | | | | | | | | | | | 46 |
| | | | | | | | | | | | | | | | 47 |
| | | | | | | | | | | | | | | | 48 |
| | | | | | | | | | | | | | | | 49 |
| | | | | | | | | | | | | | | | 50 |
| | | | | | | | | | | | | | | | 51 |
| | | | | | | | | | | | | | | | 52 |
| | | | | | | | | | | | | | | | 53 |
| | | | | | | | | | | | | | | | 54 |
| | | | | | | | | | | | | | | | 55 |
| | | | | | | | | | | | | | | | 56 |
| | | | | | | | | | | | | | | | 57 |
| | | | | | | | | | | | | | | | 58 |
| | | | | | | | | | | | | | | | 59 |
| | | | | | | | | | | | | | | | 60 |
| | | | | | | | | | | | | | | | 61 |
| | | | | | | | | | | | | | | | 62 |
| | | | | | | | | | | | | | | | 63 |
| | | | | | | | | | | | | | | | 64 |
| | | | | | | | | | | | | | | | 65 |
| | | | | | | | | | | | | | | | 66 |
| | | | | | | | | | | | | | | | 67 |
| | | | | | | | | | | | | | | | 68 |
| | | | | | | | | | | | | | | | 69 |
| | | | | | | | | | | | | | | | 70 |
| | | | | | | | | | | | | | | | 71 |
| | | | | | | | | | | | | | | | 72 |
| | | | | | | | | | | | | | | | 73 |
| | | | | | | | | | | | | | | | 74 |
| | | | | | | | | | | | | | | | 75 |
| | | | | | | | | | | | | | | | 76 |
| | | | | | | | | | | | | | | | 77 |
| | | | | | | | | | | | | | | | 78 |
| | | | | | | | | | | | | | | | 79 |
| | | | | | | | | | | | | | | | 80 |
| | | | | | | | | | | | | | | | 81 |
| | | | | | | | | | | | | | | | 82 |
| | | | | | | | | | | | | | | | 83 |
| | | | | | | | | | | | | | | | 84 |
| | | | | | | | | | | | | | | | 85 |
| | | | | | | | | | | | | | | | 86 |
| | | | | | | | | | | | | | | | 87 |
| | | | | | | | | | | | | | | | 88 |
| | | | | | | | | | | | | | | | 89 |
| | | | | | | | | | | | | | | | 90 |
| | | | | | | | | | | | | | | | 91 |
| | | | | | | | | | | | | | | | 92 |
| | | | | | | | | | | | | | | | 93 |
| | | | | | | | | | | | | | | | 94 |
| | | | | | | | | | | | | | | | 95 |
| | | | | | | | | | | | | | | | 96 |
| | | | | | | | | | | | | | | | 97 |
| | | | | | | | | | | | | | | | 98 |
| | | | | | | | | | | | | | | | 99 |
| | | | | | | | | | | | | | | | 100 |

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Bob Williams</u> | <u>10/20/80</u> | <u>15:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1-1qt glass - organics ← ext. 2
use R

1-1qt glass - metals ← - dup. metals sample collected
plastic for I H; see signature
sheet

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|--|---|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>11400 Highway 101</u> CONTACT _____ | SAMPLING STATION NO. <u>T-11-3</u> SAMPLING LOCATION <u>Department store</u> <u>below drainage - down A.D. hole on</u> <u>western side of site</u> |
|--|---|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT HR. COMP AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | DATE | TIME | FLOW () L | TEMPERATURE °C | pH | TOT. Cl ₂ RES. mg/l | SAMPLE CODE L ² |
|---------|-----------|-----------------|-------------|------------|----------------|----|--------------------------------|----------------------------|
| | | <u>10/20/80</u> | <u>1100</u> | | | | | 0 BACTERIAL |
| | | | | | | | | 1 BOD, COD, TOC |
| | | | | | | | | 2 CYANIDE |
| | | | | | | | | 3 METALS |
| | | | | | | | | 4 N, P |
| | | | | | | | | 5 ORG, O&G, PEST |
| | | | | | | | | 6 PHENOLS |
| | | | | | | | | 7 SOLIDS |
| | | | | | | | | 8 |
| | | | | | | | | 9 |
| | | | | | | | | A |
| | | | | | | | | B |
| | | | | | | | | P PRESERVED |

L¹ Use Avg. Flow for Composites and Inst. Flow for Grabs L² Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Bob Gorman</u> | <u>10/30/80</u> | <u>13:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1 - 1 qt glass - organics ^{24 hr} _{100 P}
 1 - 1 pt plastic - metals & (metals dupl. collected for TH)

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IX

ATHENS, GEORGIA

| | |
|--|--|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Mountain TN</u> CONTACT <u>Leo Buttrick</u> | SAMPLING STATION NO. <u>IH-4</u> SAMPLING LOCATION <u>Deposition area below dump on northeast end of dump (South of NDDOT ditch) sample area (ditch in woods ditch)</u> |
|--|--|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ HR. COMP AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE ¹³ |
|--------------------------------|-----------------------|--------------|---------------------------|
| DATE | <u>10/25/80</u> | | 0 BACTERIAL |
| TIME | <u>11:00</u> | | 1 BOD, COD, TOC |
| FLOW () L | | | 2 CYANIDE |
| TEMPERATURE °C | | | 3 METALS |
| pH | | | 4 H. P. |
| TOT. Cl ₂ RES. mg/l | | | 5 ORG. ONG. PEST |
| | | | 6 PHENOLS |
| | | | 7 SOLIDS |
| | | | 8 |
| SAMPLE CODE | <u>See below</u> | | 9 |
| SAMPLED BY (Sig) | <u>D. W. C. T. H.</u> | | A |
| SEALED BY (Sig) | <u>PH</u> | | B |
| DATE AND TIME | <u>10/25/80 1:00</u> | | P PRESERVED |

¹¹ Use Avg. Flow for Composites and Inst. Flow for Grabs ¹³ Circle or indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>PH Buttrick</u> | <u>10/26/80</u> | <u>15:30</u> | <u>7</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1 - 1 qt glass - organics ^{ext. p} _{NOT P}
 1 - 1 pt plastic - metals _{ext. p} (dept metals collected for IH)

U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|---------------------------------------|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>I.H.-5</u> |
| ADDRESS <u>Maple Hill TN</u> | SAMPLING LOCATION <u>Gravities of</u> |
| CONTACT <u>Gene Cathers</u> | <u>Sample (4) - procedure on site</u> |
| | <u>from top of dump</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------|----------------------|--------------|--------------------|
| DATE | <u>10/30/80</u> | | 1 BACTERIAL 0 |
| TIME | <u>1130-1145</u> | | 2 BOD, COD, TOC 1 |
| FLOW () L | | | 3 CYANIDE 2 |
| TEMPERATURE °C | | | 4 METALS 3 |
| pH | | | 5 N. P. 4 |
| TOT. C12 RES. mg/l | | | 6 ORG. OGG, PEST 5 |
| | | | 7 PHENOLS 6 |
| | | | 8 SOLIDS 7 |
| SAMPLE CODE | <u>See below</u> | | 9 8 |
| SAMPLED BY (Sig) | <u>SLH B.G. Hill</u> | | 10 A |
| SEALED BY (Sig) | <u>SLH</u> | | 11 B |
| DATE AND TIME | <u>10/12/80 1200</u> | | 12 PRESERVED P |

11 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO CONT. NO CART. | RECEIPT NO. |
|--|-----------------|--------------|-------------------|-------------|
| <u>SLH</u> | <u>11/24/80</u> | <u>15:30</u> | <u>2</u> | |
| | | | | |
| | | | | |

REMARKS AND SKETCHES

1- "lower pile" - 1130
 2- "upper pile" - 1140
 5- " " " 1142
 7- " " " 1145

1- 1qt glass - organic (241 P)
 1- 1pt plastic - metals (VOR R)
 (Dupl. metals collected for I.H.)

U.S. ENVIRONMENTAL PROTECTION
SURVEILLANCE AND ANALYSIS D 0212

REGION IV

ATHENS, GEORGIA

| | |
|---|---|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>TH-6</u> |
| ADDRESS <u>Memphis TN</u> | SAMPLING LOCATION <u>Effluent discharge</u> |
| CONTACT <u>Gene Cardwell</u> | <u>Canvass at 10000 Road - Locust</u> |
| | <u>below discharge (Hilltop) pump</u> |

SAMPLE AND WASTE FLOW INFORMATION

WINTER

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☐ _____ HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | | | | SAMPLE CODE L3 | |
|--------------------------------|-----------|---------------|---|---|---|----------------|---|
| | | 1 | 2 | 3 | 4 | 5 | 6 |
| DATE | | 01/18 | | | | BACTERIAL | Q |
| TIME | | 10/20/80 | | | | BOD, COD, TOC | 1 |
| FLOW () L | | 1420 | | | | CYANIDE | 2 |
| TEMPERATURE °C | | 25.0 | | | | METALS | 3 |
| pH | | 6.4 | | | | N.P. | 4 |
| TOT. Cl ₂ RES. mg/l | | | | | | ORG. OAG, PEST | 5 |
| | | | | | | PHENOLS | 6 |
| | | | | | | SOLIDS | 7 |
| | | | | | | | 8 |
| SAMPLE CODE | | 500-1000 | | | | | 9 |
| SAMPLED BY (Sig) | | 10/20/80 | | | | | A |
| SEALED BY (Sig) | | 10/20/80 | | | | | B |
| DATE AND TIME | | 10/20/80 1500 | | | | PRESERVED | P |

L1 Use Avg. Flow for Composites and Inst. Flow for Grabs

L3 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|------------|-----------|-------------|
| <u>B. L. Green</u> | <u>10/26/80</u> | <u>15:30</u> | <u>2/5</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

D-0212

1- 1-gal glass - organics
 1- 1-pt glass - metals
 1- VIAL - UOA
 1- 1/2 gal plastic - CN
 1- TOC

- metals dupl. collected
 for I H

U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>IH-7</u> |
| ADDRESS <u>Memphis, TN</u> | SAMPLING LOCATION <u>Shiloh Battlefield, Ga.</u> |
| CONTACT <u>Gene C. Huff</u> | <u>Field Book 2100 of 4</u> <u>known NPDES discharge pipe</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE |
|--------------------------------|----------------------|-----------------|------------------|
| DATE | <u>11/13/78</u> | <u>10/22/78</u> | BACTERIAL 0 |
| TIME | <u>11</u> | <u>1425</u> | BOD, COD, TOC 1 |
| FLOW () L | | | CYANIDE 2 |
| TEMPERATURE °C | | | METALS 3 |
| pH | | | N, P 4 |
| TOT. Cl ₂ RES. mg/l | | | ORG, OBG, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| SAMPLE CODE | <u>see below</u> | | |
| SAMPLED BY (Sig) | <u>JSH/CA/TII</u> | | |
| SEALED BY (Sig) | <u>12/1/78</u> | | |
| DATE AND TIME | <u>11/13/78 1500</u> | | |
| | | | PRESERVED P |

Use Avg. Flow for Composites and Inst. Flow for Grabs

13 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>BBG/Quinn</u> | <u>11/20/78</u> | <u>10:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

VSA R

1 - 1 qt glass - organic - env. R

1 - .1 pt plastic - metals R (dupl. metals collected for IH)

SUPPLEMENTAL REPORT
HAZARDOUS WASTE SITE INVESTIGATION
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE
APRIL 29, 1981


A hazardous waste site investigation report for International Harvester Company was issued April 7, 1981, by the U. S. Environmental Protection Agency, Surveillance and Analysis Division (SAD). At the time the report was issued, cyanide data were not available for the soil and sediment samples collected at the International Harvester Company. Cyanide analyses were reported on April 20, 1981, by the Laboratory Services Branch. These data are included in Table 1; general site location and sampling locations are included in Figures 1 and 2.

The cyanide concentration in sediment sample IH-3 (0.68 mg/kg) collected at the southern portion of the landfill appears to be higher than the concentrations in the other soil and sediment samples. The sediment sample (IH-7) taken from the drainage ditch that carries runoff to the Mississippi River contained a concentration of 0.27 mg/kg. The water sample (IH-6) contained a trace concentration (<0.002 mg/l) but was too low to be quantified (see April 7, 1981 report).

TABLE 1
CYANIDE CONCENTRATIONS IN SOIL AND SEDIMENT SAMPLES
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

| <u>Sample Number</u> | <u>Location</u> | <u>Cyanide Concentration mg/kg (dry weight)</u> |
|----------------------|--|---|
| IH-2 | Depositional area below the southern most part of landfill | 0.68 |
| IH-3 | Depositional area below landfill in drainage ditch on western side of landfill | 0.25 |
| IH-4 | Area below landfill on northern part of dump | 0.37 |
| IH-5 | Composite sample collected on top of landfill | 0.21 |
| IH-7 | Effluent and drainage ditch at culvert and field road | 0.27 |

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE






FIGURE 2
SITE MAP & SAMPLING LOCATIONS
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

← DRAINAGE FLOW DIRECTION

● SAMPLING LOCATION
IH-2

Shacklette

Element Concentrations in Soils and Other Surficial Materials of the Conterminous United States

By HANSFORD T. SHACKLETTE and JOSEPHINE G. BOERNGEN

U.S. GEOLOGICAL SURVEY PROFESSIONAL PAPER 1270

*An account of the concentrations of
50 chemical elements in samples of
soils and other regoliths*



1, unlike the geometric means shown in table 2, are estimates of geochemical abundance (Miesch, 1957). Arithmetic means are always larger than corresponding geometric means (Miesch, 1967, p. B1) and are estimates of the fractional part of a single specimen that consists of the element of concern rather than of the typical concentration of the element in a suite of samples.

Concentrations of 46 elements in samples of this study are presented in table 2, which gives the determination ratios, geometric-mean concentrations and deviations, and observed ranges in concentrations. The analytical data for most elements as received from the laboratories were transformed into logarithms because of the tendency for elements in natural materials, particularly the trace elements, to have positively skewed

TABLE 2.—Mean concentrations, deviations, and ranges of elements in samples of soils and other surficial materials in the conterminous United States

(Means and ranges are reported in parts per million (μg/g) and means and deviations are geometric except as indicated. Ratio, number of samples in which the element was found in measurable concentrations to number of samples analysed. <, less than; >, greater than)

| Element | Conterminous United States | | | | Western United States (west of 96th meridian) | | | | Eastern United States (east of 96th meridian) | | | | |
|-------------|----------------------------|-----------|---------------------------|---------|---|-----------|----------------|---------------------------|---|------|-----------|----------------|---------------------------|
| | Mean | Deviation | Estimated arithmetic mean | Ratio | Mean | Deviation | Observed range | Estimated arithmetic mean | Ratio | Mean | Deviation | Observed range | Estimated arithmetic mean |
| Al, percent | 4.7 | 2.48 | 7.2 | 661:770 | 5.8 | 2.00 | 0.5 - >10 | 7.4 | 450:477 | 3.3 | 2.87 | 0.7 - >10 | 5.7 |
| As | 5.2 | 2.23 | 7.2 | 728:730 | 5.5 | 1.98 | <0.10 - 97 | 7.0 | 521:527 | 4.8 | 2.56 | <0.1 - 73 | 7.4 |
| B | 26 | 1.97 | 31 | 506:778 | 23 | 1.99 | <20 - 300 | 29 | 425:541 | 31 | 1.88 | <20 - 150 | 38 |
| Ba | 400 | 2.14 | 580 | 778:778 | 550 | 1.12 | 70 - 5,000 | 670 | 541:541 | 290 | 2.35 | 10 - 1,500 | 420 |
| Be | .63 | 2.38 | .92 | 310:778 | .68 | 2.30 | <1 - 15 | .97 | 169:525 | .55 | 2.53 | <1 - 7 | .85 |
| Bz | .56 | 2.50 | .85 | 113:220 | .52 | 2.74 | <0.5 - 11 | .86 | 78:128 | .62 | 2.18 | <0.5 - 5.3 | .93 |
| C, percent | 1.6 | 1.57 | 2.5 | 150:150 | 1.7 | 2.37 | 0.16 - 10 | 2.5 | 162:162 | 1.5 | 2.88 | 0.06 - 37 | 2.6 |
| Ca, percent | .92 | 4.00 | 2.4 | 777:777 | 1.8 | 3.05 | 0.06 - 32 | 3.3 | 514:514 | .34 | 3.08 | 0.01 - 28 | .43 |
| Ce | 63 | 1.78 | 75 | 81:683 | 65 | 1.71 | <1 - 300 | 75 | 70:489 | 63 | 1.85 | <150 - 300 | 76 |
| Co | 6.7 | 2.19 | 9.1 | 698:778 | 7.1 | 1.97 | <3 - 50 | 9.0 | 403:533 | 5.9 | 2.57 | <0.3 - 70 | 9.2 |
| Cr | 37 | 2.37 | 54 | 778:778 | 41 | 2.10 | 3 - 2,000 | 56 | 541:541 | 33 | 2.60 | 1 - 1,000 | 52 |
| Cu | 17 | 2.44 | 25 | 778:778 | 21 | 2.07 | 2 - 300 | 27 | 523:533 | 13 | 2.80 | <1 - 700 | 22 |
| F | 210 | 3.34 | 430 | 598:610 | 250 | 2.52 | <10 - 1,900 | 440 | 390:435 | 130 | 4.19 | <10 - 3,700 | 360 |
| Fe, percent | 1.8 | 2.38 | 2.6 | 776:777 | 2.1 | 1.95 | 0.1 - >10 | 2.6 | 539:540 | 1.4 | 2.87 | 0.01 - >10 | 2.5 |
| Ga | 13 | 2.03 | 17 | 767:776 | 16 | 1.68 | <5 - 70 | 19 | 431:540 | 9.3 | 2.38 | <5 - 70 | 14 |
| Ce | 1.2 | 1.37 | 1.2 | 224:224 | 1.2 | 1.32 | 0.58 - 2.5 | 1.2 | 120:131 | 1.1 | 1.45 | <0.1 - 2.0 | 1.2 |
| Hg | .054 | 2.52 | .089 | 729:733 | .046 | 2.33 | <0.01 - 4.6 | .065 | 534:534 | .081 | 2.52 | 0.01 - 5.4 | .12 |
| I | .75 | 2.63 | 1.2 | 169:246 | .79 | 2.55 | <0.5 - 9.6 | 1.2 | 90:153 | .68 | 2.81 | <0.5 - 7.0 | 1.2 |
| K, percent | 1.5 | .79 | None | 777:777 | 1.8 | .71 | 0.19 - 6.3 | None | 537:537 | 1.2 | .75 | 0.005 - 3.7 | — |
| La | 30 | 1.92 | 37 | 462:777 | 30 | 1.89 | <30 - 200 | 37 | 294:516 | 29 | 1.98 | <30 - 200 | 37 |
| Li | 20 | 1.85 | 24 | 731:731 | 21 | 1.58 | 5 - 130 | 25 | 479:527 | 17 | 2.16 | <5 - 140 | 22 |
| Mg, percent | .44 | 3.28 | .90 | 777:778 | .74 | 2.21 | 0.03 - >10 | 1.0 | 528:528 | .21 | 3.55 | 0.005 - 5 | .46 |
| Mn | 330 | 2.77 | 550 | 777:777 | 320 | 1.98 | 30 - 5,000 | 490 | 537:540 | 260 | 3.82 | <2 - 7,000 | 640 |
| Mo | .59 | 2.72 | .97 | 57:774 | .95 | 2.17 | <1 - 7 | 1.1 | 32:524 | .52 | 3.93 | <3 - 13 | .79 |
| Nb, percent | .59 | 3.27 | 1.2 | 744:744 | .97 | 1.95 | 0.05 - 10 | 1.2 | 361:449 | .25 | 4.55 | <0.05 - 5 | .78 |
| Nb | 9.3 | 1.75 | 11 | 418:771 | 6.7 | 1.82 | <10 - 100 | 10 | 322:498 | 10 | 1.65 | <10 - 50 | 12 |
| Nd | 40 | 1.65 | 46 | 120:538 | 36 | 1.76 | <70 - 300 | 43 | 109:332 | 46 | 1.58 | <70 - 300 | 51 |
| NI | 13 | 2.31 | 19 | 747:778 | 15 | 2.10 | <5 - 700 | 19 | 463:540 | 11 | 2.64 | <5 - 700 | 18 |
| P | 260 | 2.67 | 430 | 524:524 | 320 | 2.33 | 40 - 4,500 | 460 | 380:382 | 200 | 2.95 | <20 - 6,800 | 360 |
| Pb | 16 | 1.86 | 19 | 712:778 | 17 | 1.80 | <10 - 700 | 20 | 422:541 | 14 | 1.95 | <10 - 300 | 17 |
| Rb | 58 | 1.72 | 67 | 221:224 | 69 | 1.50 | <20 - 210 | 74 | 107:131 | 43 | 1.94 | <20 - 160 | 53 |
| S, percent | .12 | 2.04 | .16 | 34:224 | .13 | 2.37 | <0.08 - 4.8 | .19 | 20:131 | .10 | 1.34 | <0.08 - 0.31 | .11 |
| Sb | .48 | 2.27 | .67 | 35:223 | .47 | 2.15 | <1 - 2.6 | .62 | 31:131 | .52 | 2.38 | <1 - 8.8 | .76 |
| Sc | 7.5 | 1.82 | 8.9 | 685:778 | 8.2 | 1.74 | <5 - 50 | 9.6 | 389:528 | 6.5 | 1.90 | <5 - 30 | 8.0 |
| Se | .26 | 2.46 | .39 | 590:733 | .23 | 2.43 | <0.1 - 4.3 | .34 | 449:534 | .30 | 2.44 | <0.1 - 3.9 | .43 |
| Si, percent | 31 | 6.48 | None | 250:250 | 30 | 5.70 | 15 - 44 | None | 156:156 | 34 | 6.64 | 1.7 - 45 | — |
| Sn | .89 | 2.36 | 1.3 | 218:224 | .90 | 2.11 | <0.1 - 7.4 | 1.2 | 123:131 | .86 | 2.81 | <0.1 - 10 | 1.5 |
| Str | 120 | 3.30 | 240 | 778:778 | 200 | 2.16 | 10 - 3,000 | 270 | 501:540 | 53 | 3.61 | <5 - 700 | 170 |
| Ti, percent | .24 | 1.89 | .29 | 777:777 | .22 | 1.78 | 0.05 - 2.0 | .26 | 540:540 | .28 | 2.00 | 0.007 - 1.5 | .35 |
| Th | 8.6 | 1.53 | 9.4 | 195:195 | 9.1 | 1.49 | 2.4 - 31 | 9.8 | 102:102 | 7.7 | 1.58 | 2.2 - 23 | 8.6 |
| U | 2.3 | 1.73 | 2.7 | 224:224 | 2.5 | 1.45 | 0.68 - 7.9 | 2.7 | 130:130 | 2.1 | 2.12 | 0.29 - 11 | 2.7 |
| V | 58 | 2.25 | 80 | 778:778 | 70 | 1.95 | 7 - 500 | 98 | 316:541 | 43 | 2.51 | <7 - 300 | 88 |
| T | 21 | 1.78 | 25 | 739:778 | 22 | 1.86 | <10 - 150 | 25 | 477:541 | 20 | 1.97 | <10 - 200 | 25 |
| Tb | 2.6 | 1.79 | 3.1 | 734:764 | 2.6 | 1.65 | <1 - 20 | 3.0 | 452:486 | 2.6 | 2.06 | <1 - 50 | 3.3 |
| Zn | 48 | 1.95 | 60 | 766:766 | 55 | 1.79 | 10 - 2,100 | 65 | 473:482 | 40 | 2.11 | <5 - 2,900 | 57 |
| Zr | 120 | 1.91 | 220 | 777:778 | 160 | 1.77 | <20 - 1,500 | 190 | 539:541 | 220 | 2.01 | <20 - 2,000 | 290 |

¹Means are arithmetic, deviations are standard.



PICKERING
WOOTEN
SMITH
WEISS, INC.

ENGINEERING AND PLANNING

Reference 14

JUL 27 1984

July 18, 1984

Mr. Danny Brewer
Environmental Engineer, Superfund
Division of Solid Waste Management
Department of Health and Environment
295 Summar Avenue
Jackson, Tennessee 38301

Dear Mr. Brewer:

Enclosed with this letter is a copy of the laboratory analyses of water and soil samples collected at the International Harvester landfill near Harvester Lane in North Memphis. These samples were collected on June 15, 1984 under my personal supervision.

The sampling locations and methods of collection and analyses were in accordance with our letter to you dated June 11, 1984.

In addition, we analyzed the two water samples "A" and "B" for phenol.

As stated in the June 11, 1984 letter, the sampling locations were as follows:

| <u>Sample</u> | <u>1980 EPA Investigation Sample Number</u> | <u>Description</u> |
|---------------|---|--|
| A | 1 | Water from NPDES outfall. |
| B | 6 | Water 1000 ft. below NPDES outfall. |
| C | 2 3 4 | Sediment samples below landfill. To be composited into one sample. |
| D | 5 | Composite of 4 soil samples from top of landfill. |
| E | 7 | Sediment from same location as water sample B. |
| F | - | Sediment from 3 new sites in the cultivated area below the landfill. To be composited into one sample. |

Mr. Danny Brewer
Environmental Engineer, Superfund
Division of Solid Waste Management
July 18, 1984
Page 2

| <u>Sample</u> | <u>1980 EPA Investigation Sample Number</u> | <u>Description</u> |
|---------------|---|--|
| G | - | Soil from 3 new sites in adjacent property proposed as cover material. To be composited into one sample. |
| H | 5 | Duplicated of sample D for quality assurance. |

It appears that the test results from sites A thru E and H are similar to the EPA results. The new sites F and G were quite "clean". Based on these results, we propose to move forward with our proposal to reshape and close the landfill.

Please review these results and schedule a meeting so we can proceed with plans for closing the landfill.

Very truly yours,

PICKERING-WOOTEN-SMITH-WEISS, INC.

Sheldon Kelman

Sheldon Kelman, Ph.D., P.E.

SK:mt

Enclosure

cc: Mr. Gene Cutrell, International Harvester

SAMPLE IDENTIFIER: Pickering, Wooten, Smit
& Weiss, Inc.

AWARE SAMPLE NO.: 9020

DATE RECEIVED: June 18, 1984

EP TOXICITY EXTRACTS

Report #02381

| ANALYSIS | "A" | "B" | "C" | "D" | "E" | "F" | "G" | "H" duplicate |
|----------|--------|--------|--------|--------|--------|--------|--------|---------------|
| Al | <0.2 | <0.2 | 2.6 | 0.9 | 0.6 | 0.4 | 0.4 | 1.5 |
| Ba | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | <0.2 | 0.5 |
| Cd | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 |
| Cr | <0.02 | <0.02 | <0.02 | <0.02 | <0.02 | <0.02 | <0.02 | <0.02 |
| Cu | <0.02 | <0.02 | 1.37 | <0.02 | <0.02 | <0.02 | <0.02 | 0.03 |
| Fe | <0.05 | <0.05 | 0.20 | 0.05 | <0.05 | 0.08 | 0.08 | 0.10 |
| Pb | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Hg | <0.002 | <0.002 | <0.002 | <0.002 | <0.002 | <0.002 | <0.002 | <0.002 |
| Ni | <0.03 | <0.03 | 11.3 | <0.03 | 0.07 | 0.05 | <0.03 | 0.05 |
| Zn | 0.05 | <0.02 | 0.19 | 0.04 | 0.27 | 0.06 | 0.58 | 0.06 |

EXTRACTABLE ORGANICS

| ANALYSIS | "A" | "B" | "C" | "D" | "E" | "F" | "G" | "H" dup. |
|---------------------|-------|-------|------|------|------|------|------|----------|
| Phenol | <0.05 | <0.05 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | 1.4 |
| Pesticide Scan(BHC) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| (DDT) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| (DDE) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| (Endrin) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| (Aldrin) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| (Heptachlor) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |
| PCB Scan (1254) | <0.01 | <0.01 | 1.4 | 1.2 | 2.8 | <0.5 | <0.5 | 4.1 |
| PCB Scan (1248) | <0.01 | <0.01 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 | <0.5 |

POLYNUCLEAR AROMATIC HYDROCARBON SCAN

| | | | | | | | | |
|----------------------|-------|-------|----|----|----|----|----|----|
| (Naphthalene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |
| (Phenanthrene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |
| (Anthracene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |
| (Fluoranthene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |
| (Pyrene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |
| (3,4-benzopyrene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |
| (1,2-benzanthracene) | <0.05 | <0.05 | <1 | <1 | <1 | <1 | <1 | <1 |

Results are expressed in ppm.



Pickering
Environmental
Consultants, Inc.

Asbestos Management
Building Site Evaluation

1750 Madison Avenue
Memphis, TN 38104

Phone: (901) 521-1100
Fax: (901) 521-1101

September 20, 1989

Mr. Jordan English
Geologist, TDSF
Department of Health and Environment
295 Summar Avenue
Memphis, Tennessee 38301-3984

Re: Harvester Landfill - Memphis

Dear Mr. English:

I have surveyed the four monitoring wells at the Harvester Landfill per your request of September 7, 1989. The attached table shows dates of monitoring, well casing elevations and groundwater levels. As can be seen, Well Numbers 1, 2 and 3 have descending water elevations. This can be accounted for by the ditch which is closest to Well Number 3. Well Number 4 apparently has a different drainage pattern and has a higher groundwater elevation.

In any event, Well Number 1 is higher than Numbers 2 and 3 and can be considered a background well.

We do not know the source of the chromium in Well Number 1. It did not show up in the early monitoring tests and may be a transient that will decrease with time. In any event, it is on the City's property, not Navistar's. It does not appear to be Navistar's problem. In addition, this level of chromium is within the proposed state limits for fishing and recreational water.

Please let me know if you have any questions regarding this letter.

Very truly yours,

PICKERING ENVIRONMENTAL CONSULTANTS, INC.

Sheldon Kelman, Ph.D., P.E.
Director/Environmental Engineering

SK:mt

cc: Edith Ardiente - Navistar

FILE:WELLS

COMPARISON OF HARVESTER WELL READINGS

| DATE | WELL NO.1 | | | | WELL NO.2 | | | | WELL NO.3 | | | | WELL NO.4 | | | |
|----------|--------------|----------------------|--------------|----------------------|--------------|----------------------|--------------|----------------------|--------------|----------------------|--------------|----------------------|--------------|----------------------|--------------|----------------------|
| | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER | TOP ELEV. | DIST. TO WATER |
| 10/28/86 | 235.47 | 31.9 | 203.57 | 221.65 | 18.4 | 203.25 | 219.85 | 16.1 | 203.75 | 222.17 | 16.9 | 205.27 | | | | |
| 04/09/87 | 235.47 | 26.5 | 208.97 | 221.65 | 14.7 | 206.95 | 219.85 | 13.7 | 206.15 | 222.17 | 13.2 | 208.97 | | | | |
| 09/03/87 | 235.47 | 32.7 | 202.77 | 221.65 | 21.6 | 200.05 | 219.85 | 22.3 | 197.55 | 222.17 | 25.0 | 197.17 | | | | |
| 12/03/87 | 235.47 | 34.5 | 200.97 | 221.65 | 24.1 | 197.55 | 219.85 | - | NA | 222.17 | 16.5 | 205.67 | | | | |
| 10/06/88 | 235.47 | 35.1 | 200.37 | 221.65 | - | NA | 219.85 | - | NA | 222.17 | - | NA | | | | |
| 05/11/89 | 235.47 | 25.4 | 210.07 | 221.65 | 11.7 | 209.95 | 219.85 | 11.9 | 207.95 | 222.17 | 12.4 | 209.77 | | | | |

- INDICATES DRY WELL
NA INDICATES NOT APPLICABLE




Figure 1

TENN. DEPT. OF HEALTH & ENVIRONMENT

BILLING CODE: 0000

SOURCE INTERNATIONAL HARVESTER

IDENTIFICATION Well #4, Down's Gradient

FIELD # COLLECTED BY BUAN PRIMARY STATION # DATE COLLECTED 04 DEC 87

TIME COLLECTED 1530 SAMPLE DEPTH (IN FEET) JBL LAB NUMBER J5F-275 *

| | | | |
|---|--------|---|-------------|
| 10-Temperature °C | | 21340-C.O.D. mg/L (High Level) | 1 |
| 300-D.O. mg/L | | 31335-C.O.D. mg/L (Low Level) | 1 |
| 310-5-day B.O.D. 20°C mg/L | | 4170508-Acidity Total - Hot mg/L | 1 |
| 403-pH, Lab. | | 51412-Alkalinity (Net) mg/L | 1 |
| 400-pH, Field | | 6138260-MEAS mg/L | 1 |
| 81-App. Color Pt - Co units | | 7195-Conductivity Micromho 25°C | 1 |
| 80-True Color Pt - Co units | | 81105-Aluminum as Al ug/L | ✓ 116,240 1 |
| 70-Turbidity NTU | | 911007-Barium as Ba ug/L | ✓ 2129 1 |
| 410-Total Alk. as CaCO ₃ mg/L | | 1011032-Chromium-Hex. as Cr. ug/L | 1 |
| 415-Phth. Alk. as CaCO ₃ mg/L | | 1111033-Chromium-Tri. as Cr. ug/L | 1 |
| 437-Acidity as CaCO ₃ mg/L | | 1211034-Chromium-total as Cr. ug/L | ✓ 169 1 |
| 500-Total Hardness as CaCO ₃ mg/L | | 1311037-Cobalt as Co ug/L | 1 |
| 510-Calcium as CaCO ₃ mg/L | | 1411147-Selenium-total as Se ug/L | ✓ 169 4/12 |
| 527-Magnesium as Mg mg/L | | 1511145-Selenium (Diss.) as Se ug/L | 1 |
| 529-Sodium as Na mg/L | | 1611077-Silver as Ag ug/L | ✓ 210 1 |
| 537-Potassium as K mg/L | | 17132730-Phenols ug/L | 1 |
| 500-Total Residue mg/L | | 1811022-Boron-Total as B ug/L | 1 |
| 530-Sus. Residue mg/L | | 191615-Nitrite Nitrogen as N mg/L | 1 |
| 703M-Diss. Residue mg/L | | 201620-Nitrate Nitrogen as N mg/L | 1 |
| 31501-Coliform No./100 ml. | | 211405-Free CO ₂ mg/L | 1 |
| 31616-Fecal Coliform No./100 ml. | | 221505-Total Vol. Residue mg/L | 1 |
| 31679-Fecal Strep. No. 100 ml. | | 231535-Vol. Sus. Residue mg/L | 1 |
| 535-Total Kil. Nitrogen as N mg/L | | 241545-Settleable Residue ml/L | 1 |
| 530-NO ₃ & NO ₂ as N mg/L | | 251666-Diss. Phosphate as P mg/L | 1 |
| 1097-Antimony as Sb ug/L | | 261745-Sulfide, total as S mg/L | 1 |
| 1045-Iron as Fe ug/L | | 271746-Sulfide, Dissolved as S mg/L | 1 |
| 1055-Manganese as Mn ug/L | | 281369-Cl ₂ Demand, 30 min. mg/L | 1 |
| 240-Chloride as Cl mg/L | | 29150064-Cl ₂ , Free Res. mg/l | 1 |
| 250-Fluoride as F mg/L | | 30150060-Cl ₂ , Combined Res. mg/L | 1 |
| 265-Total Phosphate as P mg/L | | 1690-Total Carbon mg/L | 1 |
| 245-Sulfate as SO ₄ mg/L | | 21550-Oil and Grease mg/L | 1 |
| 280-Total Organic Carbon mg/L | | 31720-Cyanide as CN mg/L | 1 |
| 1067-Nickel as Ni ug/L | ✓ 264 | 4132240-Tannin and Lignin mg/L | 1 |
| 21900-Mercury-Total as Hg ug/L | ✓ 0.5 | 51610-Ammonia Nitrogen as N mg/L | 1 |
| 1051-Lead as Pb ug/L | ✓ 141 | 61605-Organic Nitrogen as N mg/L | 1 |
| 1042-Copper as Cu ug/L | ✓ 207 | 7158-Flow Rate CFM | 1 |
| 1002-Arsenic as As ug/L | ✓ 41.0 | 8161-Flow Rate CFS, Instantaneous | 1 |
| 1027-Cadmium as Cd ug/L | ✓ 13 | 9160-Flow Rate CFS, Mean Daily | 1 |
| 1092-Zinc as Zn ug/L | ✓ 656 | 10 | |
| 535-Silica as SiO ₂ mg/L | | 11 | |

* REMARKS: THIS SAMPLE IS UNFILTERED

DIVISION SFF PROGRAM CODE

PRIORITY C

W

PH-0549, WQC-6/79

WW

repeated 04 Jan 88
(WWS)

CL

1-4-88

LEGAL

TENN. DEPT. OF HEALTH & ENVIRONMENT

BILLING CODE: SOURCE INTERNATIONAL MARQUETERIDENTIFICATION WEL #4, DOWN GRADIENTFIELD # COLLECTED BY BURR PRIMARY STATION # DATE COLLECTED 04 DEC 87TIME COLLECTED 1530 SAMPLE DEPTH (IN FEET) JEL LAB NUMBER J6F-275F*

| | | | |
|--|--------|--|-------------|
| 10-Temperature °C | | 21340-C.O.D. mg/L (High Level) | 11 |
| 20-D.O. mg/L | | 31335-C.O.D. mg/L (Low Level) | 12 |
| 10-5-Sav B.O.D. 20°C mg/L | | 4170508-Acidity Total - Hot mg/L | 11 |
| 23-pH, Lab. | | 51412-Alkalinity (Net) mg/L | 12 |
| 20-pH, Field | | 6138260-WEAS mg/L | 12 |
| 31-App. Color Pt - Co units | | 7195-Conductivity Micromho 25°C | 17 |
| 30-True Color Pt - Co units | | 81105-Aluminum as Al ug/L | ✓ 24,310 12 |
| 70-Turbidity NTU | | 912007-Barium as Ba ug/L | ✓ 1267 12 |
| 10-Total Alk. as CaCO ₃ mg/L | | 101032-Chromium-Hex. as Cr. ug/L | 120 |
| 15-Phth. Alk. as CaCO ₃ mg/L | | 111033-Chromium-Tri. as Cr. ug/L | 12 |
| 37-Acidity as CaCO ₃ mg/L | | 121034-Chromium-total as Cr. ug/L | ✓ 39 12 |
| 20-Total Hardness as CaCO ₃ mg/L | | 131037-Cobalt as Co ug/L | 12 |
| 10-Calcium as CaCO ₃ mg/L | | 141147-Selenium-total as Se ug/L | ✓ 1.6 12 |
| 27-Magnesium as Mg mg/L | | 151145-Selenium (Diss.) as Se ug/L | 12 |
| 29-Sodium as Na mg/L | | 161077-Silver as Ag ug/L | ✓ 410 12 |
| 37-Potassium as K mg/L | | 1732730-Phenols ug/L | 12 |
| 20-Total Residue mg/L | | 181022-Boron-Total as B ug/L | 12 |
| 30-Sus. Residue mg/L | | 19615-Nitrite Nitrogen as N mg/L | 12 |
| 03M-Diss. Residue mg/L | | 20620-Nitrate Nitrogen as N mg/L | 30 |
| 1501-Coliform No./100 ml. | | 21405-Free CO ₂ mg/L | |
| 1616-Fecal Coliform No./100 ml. | | 22305-Total Vol. Residue mg/L | |
| 1679-Fecal Strep. No. 100 ml. | | 23535-Vol. Sus. Residue mg/L | |
| 35-Total Kil. Nitrogen as N mg/L | | 24545-Settleable Residue ml/L | |
| 30-NO ₃ & NO ₂ as N mg/L | | 25666-Diss. Phosphate as P mg/L | |
| 097-Antimony as Sb ug/L | | 26745-Sulfide, total as S mg/L | |
| 045-Iron as Fe ug/L | | 27746-Sulfide, Dissolved as S mg/L | |
| 035-Manganese as Mn ug/L | | 28369-Cl ₂ Demand, 30 min. mg/L | |
| 40-Chloride as Cl mg/L | | 2950064-Cl ₂ , Free Res. mg/l | |
| 950-Fluoride as F mg/L | | 3050060-Cl ₂ , Combined Res. mg/L | 11 |
| 65-Total Phosphate as P mg/L | | 1690-Total Carbon mg/L | 11 |
| 45-Sulfate as SO ₄ mg/L | | 2350-Oil and Grease mg/L | 11 |
| 80-Total Organic Carbon mg/L | | 3720-Cyanide as CN mg/L | 11 |
| 067-Nickel as Ni ug/L | ✓ 127 | 4132240-Tannin and Lignin mg/L | 11 |
| 1900-Mercury-Total as Hg ug/L | ✓ 0.2 | 51610-Ammonia Nitrogen as N mg/L | 11 |
| 051-Lead as Pb ug/L | ✓ 78 | 61605-Organic Nitrogen as N mg/L | 11 |
| 042-Copper as Cu ug/L | ✓ 121 | 758-Flow Rate CFM | 11 |
| 002-Arsenic as As ug/L | ✓ 5.13 | 861-Flow Rate CFS, Instantaneous | 11 |
| 027-Cadmium as Cd ug/L | ✓ 13 | 960-Flow Rate CFS, Mean Daily | 11 |
| 092-Zinc as Zn ug/L | ✓ 346 | 10 | |
| 35-Silica as SiO ₂ mg/L | | 11 | |

REMARKS: * THIS SAMPLE HAS BEEN FILTERED THRU WHAT #31 PREDIGEST.DIVISION PROGRAM CODE PRIORITY W

PH-0549, WQC-6/79

WW reported 09 JAN 88
msCL

P

LEGAL

11-88

TENN. DEPT. OF HEALTH & ENVIRONMENT

BILLING CODE: 55FSOURCE INTERNATIONAL HARVESTORIDENTIFICATION Well #1 BACKGROUNDFIELD # 1 COLLECTED BY BNAW PRIMARY STATION # _____ DATE COLLECTED 041 DEC 87TIME COLLECTED 1042 SAMPLE DEPTH (IN FEET) _____ JBL LAB NUMBER SSF-274

| | | | | |
|---|--------|---|----------|----|
| 10-Temperature °C | | 2340-C.O.D. mg/L (High Level) | | 1 |
| 100-D.O. mg/L | | 3335-C.O.D. mg/L (Low Level) | | 1 |
| 110-5-day B.O.D. 20°C mg/L | | 470308-Acidity Total - Hot mg/L | | 1 |
| 103-pH, Lab. | | 51412-Alkalinity (Net) mg/L | | 1 |
| 100-pH, Field | | 6132260-MEAS mg/L | | 1 |
| 81-App. Color Pt - Co units | | 7195-Conductivity Micromho 25°C | | 1 |
| 80-True Color Pt - Co units | | 811105-Aluminum as Al ug/L | ✓ 9502 | 1 |
| 70-Turbidity NTU | | 911007-Barium as Ba ug/L | ✓ 516/15 | 1 |
| 110-Total Alk. as CaCO ₃ mg/L | | 1011032-Chromium-Hex. as Cr. ug/L | | 12 |
| 115-Phth. Alk. as CaCO ₃ mg/L | | 1111033-Chromium-Tri. as Cr. ug/L | | 12 |
| 137-Acidity as CaCO ₃ mg/L | | 1211034-Chromium-total as Cr. ug/L | ✓ 800 | 12 |
| 100-Total Hardness as CaCO ₃ mg/L | | 1311037-Cobalt as Co ug/L | | 12 |
| 110-Calcium as CaCO ₃ mg/L | | 1411147-Selenium-total as Se ug/L | ✓ 21 | 12 |
| 127-Magnesium as Mg mg/L | | 1511145-Selenium (Diss.) as Se ug/L | | 12 |
| 129-Sodium as Na mg/L | | 1611077-Silver as Ag ug/L | ✓ 1 | 12 |
| 137-Potassium as K mg/L | | 17132730-Phenols ug/L | | 12 |
| 100-Total Residue mg/L | | 1811022-Boron-Total as B ug/L | | 12 |
| 130-Sus. Residue mg/L | | 191615-Nitrite Nitrogen as N mg/L | | 12 |
| 10300-Diss. Residue mg/L | | 201620-Nitrate Nitrogen as N mg/L | | 13 |
| 11501-Coliform No./100 ml. | | 211403-Free CO ₂ mg/L | | |
| 11616-Fecal Coliform No./100 ml. | | 221505-Total Vol. Residue mg/L | | |
| 11679-Fecal Strep. No. 100 ml. | | 231535-Vol. Sus. Residue mg/L | | |
| 135-Total Kil. Nitrogen as N mg/L | | 241545-Settleable Residue ml/L | | |
| 130-NO ₃ & NO ₂ as N mg/L | | 251666-Diss. Phosphate as P mg/L | | |
| 1097-Antimony as Sb ug/L | | 261745-Sulfide, total as S mg/L | | |
| 1045-Iron as Fe ug/L | | 271746-Sulfide, Dissolved as S mg/L | | |
| 1035-Manganese as Mn ug/L | | 281369-Cl ₂ Demand, 30 min. mg/L | | |
| 140-Chloride as Cl mg/L | | 29150064-Cl ₂ , Free Res. mg/L | | |
| 150-Fluoride as F mg/L | | 30150060-Cl ₂ , Combined Res. mg/L | | 1 |
| 165-Total Phosphate as P mg/L | | 1690-Total Carbon mg/L | | 1 |
| 145-Sulfate as SO ₄ mg/L | | 2550-Oil and Grease mg/L | | 1 |
| 180-Total Organic Carbon mg/L | | 3720-Cyanide as CN mg/L | | 1 |
| 1067-Nickel as Ni ug/L | ✓ 21 | 432240-Tannin and Lignin mg/L | | 1 |
| 11900-Mercury-Total as Hg ug/L | ✓ <0.2 | 5610-Ammonia Nitrogen as N mg/L | | 1 |
| 1051-Lead as Pb ug/L | ✓ 31 | 6005-Organic Nitrogen as N mg/L | | 1 |
| 1042-Copper as Cu ug/L | ✓ 9 | 58-Flow Rate CFM | | 1 |
| 1002-Arsenic as As ug/L | ✓ 3.00 | 61-Flow Rate CFS, Instantaneous | | 1 |
| 1027-Cadmium as Cd ug/L | ✓ 1 | 60-Flow Rate CFS, Mean Daily | | 1 |
| 1092-Zinc as Zn ug/L | ✓ 20 | | | |
| 135-Silica as SiO ₂ mg/L | | | | |

REMARKS: _____

DIVISION SSF

PROGRAM CODE _____

PRIORITY C

W _____

PH-0549, WQC-6/79

WW _____

checked & reported
04 JAN 88

CL _____

R _____

1-4-88

LEGAL



ENVIRONMENTAL TESTING & CONSULTING INC.

2924 WALNUT GROVE RD. • MEMPHIS, TENN. 38111 • PHONE (901) 327-2750

May 23, 1988

RECEIVED JUN - 2 1988

Ms. Connie Hess, President
Hess Environmental Services, Inc.
6890 Hillshire Drive, Suite 13
Memphis, Tenn. 38134


REF: ANALYTICAL TESTING - SIH SAMPLES - SEDIMENT & COMPOSITE SOIL
SAMPLE(S) DATE: 5/5/88

Dear Ms. Hess:

The above referenced samples have been analyzed per your instructions. The tests were performed in our laboratory (#00210) in accordance with SW-846, Method 8080 & 3550. The results are shown on the attached Organic Analysis Data Sheet.

If you have any questions please feel free to contact me.

Very truly yours,


Michael J. Cimballo
President

MJC/mg

Attachment



ENVIRONMENTAL TESTING & CONSULTING INC.

2924 WALNUT GROVE RD. • MEMPHIS, TENN. 38111 • PHONE (901) 327-2750

June 1, 1988

Ms. Connie Hess, President
Hess Environmental Services, Inc.
6890 Hillshire Drive, Suite 13
Memphis, Tenn. 38134

RECEIVED JUN - 2 1988

REF: ANALYTICAL TESTING

SAMPLE(S) DATE: 5/5/88

SAMPLE I.D.: SIH SAMPLES - SURFACE & GROUND WATER,
SEDIMENT & COMPOSITE SOILS

Dear Ms. Hess:

The above referenced samples have been analyzed per your instructions. The tests were performed in our laboratory (#00210) in accordance with Standard Methods, 16th Edition, and the results are shown below.

| Tests | SIH Samples - Results (mg/l) | | | | | Standard Methods Page # | By | Date |
|----------|------------------------------|--------------|-------|-------|-------|-------------------------------|----|------|
| | Surface | Ground Water | | | | | | |
| | Water #1 | #1 | #2 | #3 | #4 | | | |
| Chromium | <0.02 | 0.63 | 0.04 | 0.06 | 0.11 | 157 | JF | 5/6 |
| Lead | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | 157 | JF | 5/6 |

| Tests | Sediment #1 (as rec. ppm) | Composite Soils | | Standard Methods Page # | By | Date |
|------------|------------------------------|------------------|------------------|-------------------------------|----|------|
| | | South #1 | North #2 | | | |
| | | (Dry Weight ppm) | (Dry Weight ppm) | | | |
| Chromium | 10.3 | 16.2 | 16.4 | 157 | JF | 5/6 |
| Lead | 12.2 | 25.3 | 24.2 | 157 | JF | 5/6 |
| % Moisture | - | 4.74 | 5.50 | | | |

If you have any questions please feel free to contact me.

Very truly yours,

Michael J. Cimbalò
President

MJC/mg

ENVIRONMENTAL TESTING AND CONSULTING, INC.

ORGANIC ANALYSIS DATA SHEET PCBs

SAMPLE NAME : _HESS ENVIRONMENTAL_
SAMPLE ID(S) : _SEE RESULTS_____
SAMPLE DATE : _05/05/88_____
DATE ARRIVED : _05/06/88_____
MATRIX : _SEDIMENT/SOIL____

PROJECT # : _SIH_____
INSTRUMENT ID : _V3700_____
ANALYST : _LB_____
FILE NAME : _0506-002.DOC

DATE EXTRACTED/PREPARED : _05/18/88_
DATE ANALYZED : _05/19/88_

METHOD(SW-846) : _8080_____
3550

| COMPOUND | SAMPLE RESULTS UNITS: (mg/kg) | METHOD DETECTION LIMIT: (mg/kg) |
|-----------|------------------------------------|--------------------------------------|
| | SEDIMENT #1 | |
| TOTAL PCB | : ____0.04j____ | ____0.05____ |
| | COMPOSITE SOIL #1 | |
| TOTAL PCB | : ____0.04j____ | ____0.05____ |
| | COMPOSITE SOIL #2 | |
| TOTAL PCB | : ____BDL____ | ____0.05____ |

RECEIVED JUN - 2 1988

Vi = Volume of extract injected (ul) : _3.0_____
Ws = Weight of sample extracted (g) : _30_____
Vt = Volume of final extract (ml) : _10_____

BDL - BELOW DETECTION LIMIT
j - ESTIMATED VALUE

Reference 17

RECEIVED

JUN 22 1988

REPORT OF GROUND WATER MONITORING,
WELL DEVELOPMENT AND POST
CLOSURE MONITORING AT THE
INTERNATIONAL HARVESTER LANDFILL SITE
MEMPHIS, TENNESSEE
-SECOND QUARTER, SECOND YEAR-

PREPARED BY:
HESS ENVIRONMENTAL SERVICES, INC.
MEMPHIS, TENNESSEE

JUNE 17, 1988

TABLE OF CONTENTS

| | Page No. |
|--|----------|
| Summary | |
| I. Introduction | 1 |
| II. Well Development | 2 |
| III. Sample Collection | 4 |
| IV. Discussion of Data | 13 |
| V. Conclusions | 16 |
| Tables | |
| I. Monitoring Well Measurements | 6 |
| II. Analytical Methods | 8 |
| III. Location of Soil Composites Collected | 12 |
| IV. Summary of Data | 14 |
| Figure | |
| International Harvester Site | 5 |
| Appendix | |
| Laboratory Report | A-1 |

SUMMARY

Second quarter, second year ground water, surface water, sediment and soil samples were collected and analyzed in compliance with post closure monitoring requirements set forth in the International Harvester Closure Plan, enforced by the State of Tennessee.

All water samples were analyzed for chromium and lead content. All sediment and soil samples were analyzed for chromium, lead and Polychlorinated Biphenyls (PCBs) content.

Ground water samples were collected from upgradient well no. 1 and downgradient wells no. 2, 3, and 4.

Second quarter, second year data is somewhat different from previous data in that metals levels increased in downgradient ground water and decreased in the sediment and north landfill composite.

All levels of chromium in downgradient ground water were low and were well below that found in upgradient ground water and therefore should not be of concern. No lead was detected in any of the ground water sampled. Based on this data, the landfill can not be said to have impacted the ground water in its vicinity. (?at this time)

No metals were detected in the surface water composite, this is consistent with data from previous quarters.

Sediment and soil from the composite collected north of the NPDES discharge point contained reduced levels of metals as compared with first year data. These decreases probably reflect a combination of the ranges of chromium and lead present at the site and normal variations in laboratory data.

Where is the upgradient well (the town) and vertically relative to plume? ... relative to other contaminants present?

Maybe not - but this is not sufficient material for "no concern"

or further leaching

No other remarkable data was noted.

A summary of all second quarter, second year data is displayed in Table IV of this report.

I. INTRODUCTION

Prior to initiating second quarter, second year post closure monitoring, Hess Environmental Services, Inc. (HES) developed the four (4) ground water monitoring wells surrounding the International Harvester Landfill. These wells were first developed in November of 1986. Since then, ground water recharge rates have become slower in these wells necessitating this redevelopment effort.

To comply with post closure monitoring requirements set forth in the International Harvester (IH) Closure Plan enforced by the State of Tennessee, Department of Health and Environment, Division of Superfund (the State), HES collected ground water samples from four (4) ground water monitoring wells, water and sediment samples from the National Pollutant Discharge Elimination System (NPDES) discharge point and soil samples from two (2) areas at the base of the landfill.

All samples were analyzed for chromium and lead content. The soil samples collected below the landfill and the sediment sample collected from the NPDES discharge point were also analyzed for PCB content.

This report addresses well development, sampling, testing and chain-of-custody protocols followed to fulfill second quarter, second year, post closure monitoring requirements.

II. WELL DEVELOPMENT

On April 26, 1988, HES provided personnel to develop the four (4) ground water monitoring wells at the International Harvester Landfill Site, Memphis, Tennessee.

HES team members participating in this effort were:

Marolyn Howe - Chemical Engineer

Jeff Bennett - Environmental Scientist

The well development process is used to restore the natural hydraulic conductivity of the subsurface formation and remove foreign materials which may have been introduced during well construction. This process should speed up recent sluggish recharge rates.

The well development protocol used by HES employed reversals of flow surges to avoid particle bridging, a phenomenon which frequently occurs when flow is continuously in one direction. The surges also served to flush the sand pack around the well screens removing drilling and/or soil fines that may have been present in the monitoring wells.

At each monitoring well developed, the depth to ground water was measured, using the YSI Model 3000 T-L-C meter, to the nearest hundredth (0.01) of a foot. The volume of ground water in each well was calculated as follows:

$(T. \text{ Depth of Well}^*) - (\text{Depth to water}^*) = \text{ht. of water col.}^*$

$(\text{Ht. water col.}^*) \times (\text{gal. water/ft. pipe}) = \text{vol. of std. water}^{**}$

*Feet.

**Gallons.

The two (2) inch ID well casings have 0.16 gallons of water per linear foot of well casing.

During well development, two (2) volumes of standing water were removed from well no. 1 using a Teflon bailer, wells no. 2, 3, and 4 (slow recharge wells) were bailed to dryness. As soon as bailing was complete and the wells recharged, the depth to water was measured using the T-L-C meter. A recovery rate was established by measuring the depth to water at regular time intervals until a consistent recovery rate was attained.

Once the recovery rate for each well was determined, the air compressor holding tank was filled to approximately 100 psi. Air pressure was applied through the center of the casing (with a hand cover top seal) in short vigorous blasts, using a bent air hose to control air burst. Surging blasts of air were applied until the air compressor had too little air remaining to continue. This constituted the "blow down" of a well.

Immediately after blow down was completed, the water level in the well was measured and recorded. Two (2) volumes of standing water were then removed (bailed), the depth to water measured and water level recovery in the well recorded with respect to time, as previously outlined.

The bailing, timed recovery and air pressure blow down steps were repeated until it was determined that either an improved recovery rate had been established and the recovery rate was not further improved by additional bailing and blow down or that the initial recovery rate was the maximum rate achievable because it was not improved by the bailing and blow down process.

III. SAMPLE COLLECTION

On May 5, 1988, HES provided personnel to collect: ground water samples from three (3) downgradient wells no. 2, 3, and 4, and one (1) upgradient well no. 1; one (1) sediment composite and one (1) surface water composite from the NPDES discharge point ditch; and two (2) soil composites, the first from below the landfill on the south side, and the second from below the landfill on the north side. All sampling locations at the International Harvester Landfill Site are shown in Figure 1.

Present on site during sample collection were:

| | | |
|---------------|---|---|
| Marolyn Howe | - | Chemical Engineer with HES |
| Jeff Bennett | - | Environmental Scientist with HES |
| Bobby G. King | - | Environmental Specialist, State of Tennessee |

Weather conditions were clear, sunny and 16°C (61°F).

A - Ground Water Monitoring Wells

Each of the four (4) two (2) inch ID ground water monitoring wells had a protective, metal, outer well casing with a pad-locked lid. HES found all lids locked. Before sampling, the well depth and the depth to the surface of the ground water was measured in each well and the volume of the standing water calculated. A record of these measurements is shown in Table I.

A Well Wizard stainless steel portable positive gas displacement bladder pump, Model ST110P, with a Teflon bladder, Teflon tubing and a stainless steel intake screen was used to evacuate one (1) volume of standing water and three (3) volumes of recharge water from upgradient well.

TABLE I
MONITORING WELL
MEASUREMENTS

| | 1 | 2 | 3 | 4 |
|--|------|------|------|------|
| Total Depth of Well (Ft.) | 41.8 | 24.7 | 24.7 | 24.8 |
| Depth from MP* to Top of Water Column (Ft.) | 28.0 | 16.4 | 16.3 | 14.1 |
| Height of Water Column (Ft.) | 13.8 | 8.3 | 8.4 | 10.7 |

*MP = Measuring Point, an area (point) at the top of each PVC well casing used as a reference point for measurements.

Breathing grade air was used to inflate the pump bladder facilitating sample collection.

Ground water was filtered using a 0.45 micron filter attached to the discharge tube of the ST1100P pump and pumped into precleaned glass sample containers with Teflon lined lids.

A Teflon bailer was used to evacuate one (1) volume of standing water and three (3) volumes of recharge water from the downgradient wells no. 2, 3, and 4. The bailer was used instead of the pump because these wells had a slower recharge rate. Ground water from wells no. 2, 3, and 4 were filtered through a 0.45 microfilter at the laboratory.

All ground water samples were stored on ice ($<4^{\circ}\text{C}$) immediately after collection (in the field). Ground water from well no. 1 to be analyzed for metals was pH adjusted with nitric acid to a pH of <2 . Ground water from wells no. 2, 3 and 4 was filtered then preserved, with nitric acid to a pH of less <2 , at the laboratory.

why filter? or at least why filter down gradient? & up gradient?

why?

All sample container cleaning, preservation and analytical procedures were performed in accordance with "Methods for Chemical Analysis of Water and Wastes," EPA-600/4-79-020, March, 1979, as referenced in the "Rules Governing Hazardous Waste Management in Tennessee." See Table II for the specific analytical method references for each parameter.

Established chain-of-custody sample handling protocols were followed. A "Field Log Book" was kept, as required in the chain-of-custody protocol. Pertinent data concerning the site in general, weather conditions and data collected during the sampling event were recorded. This log is updated during each quarter's sampling event.

TABLE II
ANALYTICAL METHODS

| <u>PARAMETER</u> | <u>WATER SAMPLES METHOD REFERENCE</u> | <u>SOIL/SEDIMENT SAMPLES METHOD REFERENCES</u> |
|------------------|---|--|
| Chromium | 302D*, 303A* | 302D*, 303A* |
| Lead | 302D*, 303A* | 302D*, 303A |
| PCB | - | 3550, 8080** |

*Standard Methods for the Examination of Water and Wastewater, 16th Edition, American Public Health Association, Inc., New York, New York, 1985.

**Test Methods for Evaluating Solid Waste: Physical/Chemical Methods, (SW-846), Third Edition, U. S. Environmental Protection Agency, 1986.

Environmental Testing and Consulting, Inc. (ETC), received samples from all four (4) wells. ETC is a laboratory certified by the State of Tennessee (Certificate No. 00210). Samples were delivered to ETC via courier on May 6, 1988.

All samples arrived at the laboratory with seals intact.

*certified for
what?
? drinking water
2 boy water*

B - NPDES Discharge Point

Samples were collected at the NPDES discharge sampling point, below the discharge of storm water, located in the northwest area of Parcel 4 (see Figure 1). A water and then a sediment composite were collected from this discharge point.

HES personnel collected grab samples of water from two (2) locations along the south bank in the vicinity of the NPDES discharge point. Water was scooped from each location via a clean glass sampling jar then added to a second jar to form the composite. Equal portions of water from each grab sample were poured into the composite accumulation jar; when all grabs were deposited into the accumulation jar the sample was pH adjusted to pH <2 with nitric acid, then covered with a Teflon lined lid.

Four (4) sediment grab samples were collected in the same general area as the water grabs. Sediment grabs were scooped from the rocky stream bed by raking a sampler, comprised of a small stainless steel beaker attached to a stainless steel pole, across each area then pouring each scoop raked into a glass sampling jar. The sediment accumulated in the jar was then stirred with a stainless steel spatula to form a uniform composite. The jar was then covered with a Teflon lined lid.

Both composite samples were sealed by placing a chain-of-custody seal across each jar lid and down the sides of the jar. The samples were then stored on ice (<4°C) along with the ground water samples. Both samples were delivered along with the monitoring well samples, to ETC, via courier, on May 6, 1988.

*Any
composites
two sites
along
same bank
Are there
two separate
prints for
two separate
samples*

C - Soil Composites

Two (2) soil composite samples were collected at the landfill site, one (1) north and the second south of the NPDES (and storm water) discharge point, below the west face of the landfill.

All areas sampled are shown in Figure I. A description of the soil areas sampled is provided in Table III.

The north and south soil composites were each formed by mixing grabs collected with a stainless steel core sampler. Two (2) 6" x 1" solid cores were collected from each of the two (2) areas north of the NPDES discharge point and deposited into a Pyrex glass tray. All soil was then mixed with a stainless steel spoon to form as uniform a composite as possible. A sample jar was filled with soil from this composite, covered with a Teflon lined lid then sealed with a chain-of-custody seal by HES personnel. The south soil composite was formed in the same manner from cores collected in two (2) areas south of the NPDES discharge point.

Both soil composites were stored on ice ($<4^{\circ}\text{C}$) along with the water and sediment samples and delivered to ETC, via courier on May 6, 1988.

TABLE III
LOCATION OF SOIL COMPOSITES COLLECTED

| <u>COMPOSITES</u> | <u>LOCATIONS SAMPLED</u> |
|-------------------|------------------------------|
| South Composite: | |
| Grab S1 | 20 feet due west of well #2 |
| Grab S2 | 20 feet due west of well #3 |
| North Composite: | |
| Grab N1 | 3 feet due west of well #4 |
| Grab N2 | 60 feet due south of well #4 |

IV. DISCUSSION OF DATA

As stipulated in the International Harvester Closure Plan, all water, soil and sediment samples were analyzed for chromium and lead content. The soil and sediment samples were also analyzed for PCB content.

A summary of all second quarter, second year laboratory data is presented in Table IV, the actual laboratory report is included in the Appendix of this report. A discussion of current data follows:

GROUND WATER

- * Chromium levels in downgradient ground water from wells 2-4 are slightly higher than the levels measured in ground water from the same wells during the first year.
- * The chromium level in upgradient ground water is above downgradient levels; it is comparable with historical data.
- * Lead was not found in any of the ground water samples collected at the site; this is also comparable with historical data.

would
difference
in filtering
account for this
22 field
filtering now
an accepted
sampling
procedure

SURFACE WATER

- * Chromium and lead were not detected in the surface water composite collected this quarter; this is consistent with past data.

why composite
from 2 points
if concern is
only from
"NADP's (and storm
water)" outfall

TABLE IV
SUMMARY OF DATA

| GROUND WATER MONITORING WELLS | UNITS | CHROMIUM | LEAD | PCB |
|--|-------|--------------------|----------------------|-------------------|
| #1 | mg/l | 0.63 | <0.05 | - |
| #2 | mg/l | 0.04 | <0.05 | - |
| #3 | mg/l | 0.06 | <0.05 | - |
| #4 | mg/l | 0.11 | <0.05 | - |
| <u>NPDES DISCHARGE POINTS</u> | | | | |
| Surface Water Comp. | mg/l | <0.02 | <0.05 | - |
| Sediment Comp. | mg/Kg | 10.3 | 12.2 | <0.25 |
| <u>SOILS</u> | | | | |
| North Landfill Comp.* | mg/Kg | 16.4 | 24.2 | <0.25 |
| South Landfill Comp.* | mg/Kg | 16.2 | 25.3 | <0.25 |
| <u>BACKGROUND COMP. 4/9/87</u> | mg/Kg | 6.9 | 44.7 | <0.25 |
| <u>PUBLISHED AVERAGE BACKGROUND LEVELS</u> | mg/Kg | 100 ⁽¹⁾ | 302 ^{(2)**} | <1 ⁽³⁾ |

REFERENCES:

- (1) Allaway, W.H., 1968. Agronomic controls over the environmental cycling of trace elements. Adv. Agron. 20: 235-274.
- (2) Final Report of Soil Sampling and Analysis for the North Hollywood Dump Health Effects Study, Hess Environmental Services, Inc., May 30, 1986.
- (3) Richardson, B.J. and Waid, J.S. (1982). Polychlorinated Biphenyls (PCB): An Australian viewpoint on a global problem. Search 13, 17.

*Dry Weight Basis.

**Range 40.7 to 2002 mg/Kg.

SEDIMENT

- * Current chromium and lead levels are lower than levels previously observed in site sediment. No PCBs were found in the sediment; historical data ranges from 5.1 mg/kg (ppm) to none detected (<0.25 mg/kg).

SOIL

- * Current soil chromium, lead and PCB data from the landfill composite collected south of the NPDES discharge point is generally comparable with data from previous quarters.
- * Current soil chromium, lead and PCB data from the landfill collected north of the NPDES discharge point composite is generally lower than data from previous quarters.

V. CONCLUSIONS AND RECOMMENDATIONS

The following conclusions can be drawn from data obtained during the second quarter, second year, post closure, monitoring at the International Harvester landfill site:

- * Because metals found in downgradient ground water are at or below levels found in upgradient ground water and no metals have been found in surface water, the landfill can not be said to have impacted ground water or surface water in its vicinity.
- * Second quarter, second year data is somewhat different from previous data.
- * Downgradient ground water contained low levels of chromium. No chromium had been detected in these wells during the first year of monitoring. This should not be of concern however, because downgradient levels are very low and are well below the chromium level found in upgradient ground water.
- * Metals in the sediment composite and soil from the north landfill composite were below first year levels. These data variations probably reflect a combination of the ranges present in soil and sediments at the site and normal variations in laboratory data.
- * All other current data is comparable with first year data.

I don't necessarily agree w/ this conclusion as it is not strictly supported by the previous data herein.

define low

this is not a valid reason for no concern potential?

what about leaching? Why report all this? saying it twice doesn't make it any more valid.

No action beyond reporting the data contained in this report to the Tennessee Department of Health and Environment,

Division of Superfund, should be required until the fourth quarter, 1988, when monitoring will again be required.

- Oh yes there is ^{the} question
herein need answers which can
be corroborated by expertise
employed by TDHE.
- ② I want to see the site.
 - ③ I want to accompany
the next monitoring run.

APPENDIX
LABORATORY REPORT

Reference 18

RECEIVED

JUL 14 1989

REPORT OF POST CLOSURE MONITORING
AT THE
INTERNATIONAL HARVESTER LANDFILL SITE
MEMPHIS, TENNESSEE
- SECOND QUARTER, THIRD YEAR -

PREPARED FOR:
DR. SHELMAN KELMAN
PICKERING FIRM
MEMPHIS, TENNESSEE

PREPARED BY:
HESS ENVIRONMENTAL SERVICES, INC.
MEMPHIS, TENNESSEE

JUNE 26, 1989

TABLE OF CONTENTS

| | PAGE |
|----------------------------------|------|
| EXECUTIVE SUMMARY | |
| I. INTRODUCTION | 1 |
| II. SAMPLE COLLECTION | 2 |
| A. Ground Water Monitoring Wells | 2 |
| B. NPDES Discharge Point | 7 |
| C. Soil Composites | 8 |
| D. All Samples | 10 |
| III. DISCUSSION OF DATA | 11 |
| IV. CONCLUSIONS | 13 |

Figure

| | |
|---|---|
| I. International Harvester Landfill Site | 4 |
|---|---|

Tables

| | |
|------------------------------------|----|
| I. Monitoring Well Measurements | 5 |
| II. Analytical Methods | 6 |
| III. Soil Composite Sampling Sites | 9 |
| IV. Summary of Data | 12 |

Appendix

Laboratory Report

EXECUTIVE SUMMARY

Second quarter, third year ground water, surface water, sediment and soil samples were collected and analyzed in compliance with post closure monitoring requirements delineated in International Harvester's Landfill Closure Plan, as enforced by the State of Tennessee.

Ground water samples were collected from the four (4) monitoring wells on site, which include one (1) upgradient well (No. 1) and three (3) downgradient wells (Nos. 2, 3 and 4). All ground water samples were analyzed for chromium and lead content.

Chromium was detected in the ground water sample collected from upgradient Well No. 1, southwest of the landfill. No metals were found in ground water samples collected from the downgradient wells. It would probably be advisable to survey the Measuring Point (MP) on the casing of each well with respect to Mean Sea Level (MSL) to varify that well No. 1 is currently an upgradient well.

Surface water and sediment composite samples were collected from the National Pollutant Discharge Elimination System (NPDES) discharge point. No metals were detected in the surface water composite, which is consistent with data from previous sampling events; sediment data is addressed below.

Soil composite samples were collected from two (2) areas at the base of the landfill. All sediment and soil samples were analyzed for chromium, lead and Polychlorinated Biphenyls (PCBs) content.

Metals and PCBs were found in all soil and sediment composites, but the levels of these constituents were comparable with those previously found at this site, and were below published background levels for soils.

A summary of all analytical data is presented in Table IV.

A copy of this report should be submitted to the State. No further action is required until fourth quarter, when monitoring will again be required.

I. INTRODUCTION

The State of Tennessee, Department of Health and Environment, Division of Superfund (the State), enforces the International Harvester (IH) Landfill Closure Plan. To comply with post closure monitoring requirements delineated in that plan (and modified as noted below), Hess Environmental Services, Inc. (HES) collected ground water samples from Monitoring Wells Nos. 1 -4, water and sediment samples from the NPDES discharge point and soil samples from two (2) areas at the base of the landfill.

The Closure Plan, referenced above, has been modified, monitoring is now required on a semi-annual basis, a reduction from the quarterly monitoring originally required.

All samples were analyzed for chromium and lead content. The soil samples collected below the landfill and the sediment samples collected from the NPDES discharge point were also analyzed for PCB content.

This report addresses sampling, testing and chain-of-custody protocols followed to fulfill the first semi-annual, third year, post closure monitoring requirements.

II. SAMPLE COLLECTION

On May 11, 1989, Hess provided a team to collect:

- * Ground water samples from three (3) downgradient wells (Nos. 2, 3 and 4) and one (1) upgradient well (No. 1),
- * One (1) surface water composite and one (1) sediment composite from the NPDES discharge point ditch, and
- * Two (2) soil composites: the first from below the landfill on the north side of the NPDES discharge point, and the second from below the landfill on the south side of the NPDES discharge point.

All sampling locations at the IH Landfill Site, Parcel 4, are shown in Figure I.

Present at the IH site during sample collection were: Mr. Jeff Bennett, a HES Environmental Scientist, Mr. John Stedman Jr., a HES Environmental Engineer, and Mr. Jordan English, a representative from the State of Tennessee, Division of Superfund.

During this sampling event the weather was mild and sunny; the temperature was 65 degrees F.

A. Ground Water Monitoring Wells

Each of the four (4), two (2) inch ID ground water monitoring wells had a protective, metal, outer well casing with a pad-locked lid. HES personnel found all the lids locked. Before sampling, the well depth and the depth to the surface of the ground water was measured in each well and the volume of standing water calculated. These measurements are shown in Table 1. A Teflon bailer was used to evacuate one (1) volume of standing water and three (3) volumes of recharge water from well Nos. 1 - 4. This is in accordance with the protocol described in the Environmental Protection Agency's (EPA), Resource Conservation and Recovery Act (RCRA), Ground Water Monitoring Technical Enforcement Guidance Document.

The ground water samples were stored in jars, on ice ($<4^{\circ}\text{C}$) for preservation, immediately after collection. Ground water samples collected for chromium and lead analyses were filtered at the laboratory. After filtering, the samples were preserved with nitric acid to a pH of less than ($<$) 2.

All sample container cleaning, sample preservation and analyses were performed in accordance with "Methods for Chemical Analysis of Water and Wastes," EPA-600/4-79-020, March, 1979, as referenced in the "Rules Governing Hazardous Waste Management in Tennessee". See Table II for the specific analytical method employed for each parameter.

Established chain-of-custody sample handling protocols were followed. A "Field Log Book" was kept, as required in the chain-of-custody protocol, to record general site and weather data, as well as data collected during each sampling event. This log will be updated during each future sampling event.

All of the samples were shipped, via reliable courier on May 12, 1989, to Environmental Testing and Consulting, Inc. (ETC), a laboratory certified by the State (Certification 00210). ETC received all of the sample jars with their seals intact.

TABLE I
MONITORING WELL MEASUREMENTS

| PARAMETER | WELL NUMBER | | | |
|--------------------------------------|-------------|-------|-------|-------|
| | 1 | 2 | 3 | 4 |
| Total Depth of Well | 41.80 | 24.75 | 24.75 | 25.55 |
| Depth from MP to top of water column | 25.40 | 11.70 | 11.93 | 12.40 |
| Height of water column | 16.40 | 13.05 | 12.82 | 13.15 |

Notes: MP = Measuring Point, an area (point) at the top of each PVC well casing used as a reference point for measurements.

All measurements are in feet.

TABLE II
ANALYTICAL METHODS

| <u>PARAMETER</u> | <u>WATER SAMPLES METHOD REFERENCE</u> | <u>SOIL/ SEDIMENT SAMPLES METHOD REFERENCE</u> |
|------------------|---|--|
| Chromium | 302D*, 303A* | 302D*, 303A* |
| Lead | 302D*, 303A* | 302D*, 303A* |
| PCBs | - | 3540**, 8080** |

*Standard Methods for the Examination of Water and Wastewater, 16th Edition, American Public Health Association, Inc., New York, New York, 1985.

**Test Methods for Evaluating Solid Waste, Physical Chemistry Methods, SW-846, Second Edition, Revised, 1985, U.S. Environmental Protection Agency.

B. NPDES Discharge Point

Samples were collected at the NPDES discharge sampling point, located at the foot of the landfill, an earthen ditch which channels storm water runoff. This ditch is located in the northwest area of Parcel 4 (see Figure I). Water and sediment composites were collected in the vicinity of this discharge point.

HES personnel collected grab samples of water from two (2) locations along the south bank of the ditch, near the NPDES discharge point. Water was scooped from each location via a clean glass sampling jar, then added to a second jar to form the composite. Equal portions of water from each grab sample were poured into the composite accumulation jar. When all grabs were deposited into the accumulation jar, the sample was gently mixed; the sample pH was then adjusted to less than 2 with nitric acid. Each sample jar was covered with a Teflon-lined lid.

Eight (8) sediment grabs were collected in the same areas as the water grabs. Sediment grabs were scooped from the rocky earthen stream bed by raking a sampler, comprised of a small stainless steel beaker attached to a stainless steel pole, across each area. The grab sediment samples were then deposited in a clean stainless steel tray and stirred with a stainless steel spatula to form as uniform a composite as possible. The composite was placed in a clean glass jar covered with a Teflon-lined lid.

Both composite samples were handled via chain-of-custody handling protocols.

C. Soil Composites

Two (2) soil composites were collected at the landfill site, one (1) north and one (1) south of the NPDES discharge point; below the west face of the landfill.

The north soil composite was formed by collecting two (2) soil cores from each of five (5) locations and depositing them in a pre-cleaned Pyrex glass mixing tray. The soil was then mixed in the tray with a stainless steel spatula to form as uniform as possible a composite and placed in a sample jar. The jar housing the composite was then covered with a Teflon-lined lid and handled via chain-of-custody protocols. The south soil composite was formed and handled in the same manner as the north composite (as described above).

TABLE III
SOIL COMPOSITE SAMPLING SITES

| <u>COMPOSITE</u> | <u>SAMPLING SITE</u> |
|-------------------------|---|
| South Composite: | |
| Grab S1 | 15 feet due west and 30 feet due north of Well No. 2 |
| Grab S2 | 15 feet due west and 15 feet due north of Well No. 2 |
| Grab S3 | 15 feet due west of Well No. 2 |
| Grab S4 | 15 feet due west and 30 feet due south of Well No. 2 |
| Grab S5 | 15 feet due west and 15 feet due south of Well No. 2 |
| North Composite: | |
| Grab N1 | 15 feet due west and 30 feet due north of Well No. 3 |
| Grab N2 | 15 feet due west and 15 feet due north of Well No. 3 |
| Grab N3 | 15 feet due west of Well No. 3 |
| Grab N4 | 15 feet due west and 15 feet due south of Well No. 3 |
| Grab N5 | 15 feet due west and 30 feet due south of Well No. 3 |

D. All Samples

The four (4) ground water, one (1) surface water, one (1) sediment and two (2) soil samples were each sealed by placing a chain-of-custody seal across the jar lid and down the sides of the jar. The samples were then promptly stored on ice ($<4^{\circ}\text{C}$). All eight (8) samples were delivered to ETC, via reliable courier, on May 12, 1989.

III. DISCUSSION OF DATA

As stipulated in the International Harvester Closure Plan, all water, sediment and soil samples were analyzed for chromium and lead content. The sediment and soil samples were also analyzed for PCB content.

All soil sample data is reported on a dry weight basis, in milligrams per kilogram ((mg/kg) or parts per million (ppm)).

A summary of all semi-annual (second quarter), third year, laboratory data is presented in Table IV; the actual laboratory report is in the Appendix of this report.

Chromium was detected in ground water from Well No. 1, the upgradient well. Ground water samples obtained from down-gradient well Nos. 2 - 4 contained no detectable levels of chromium. The 2.60 ppm chromium found in ground water collected from the upgradient well was slightly lower than the 3.24 ppm level detected in ground water that location during the previous sampling event. No lead was detected in ground water from any of the wells sampled.

No metals were detected in the surface water composite, which is comparable with data from previous sampling events conducted at this site.

Lead, Chromium, and PCBs were detected in the soil and sediment composites, but were below the average background level found in soils. These background levels can be found in Table IV.

TABLE IV
SUMMARY OF DATA

| <u>GROUND WATER MONITORING WELLS</u> | <u>UNITS</u> | <u>CHROMIUM</u> | <u>LEAD</u> | <u>PCBs</u> |
|--|--------------|-----------------|-------------|-------------|
| No. 1 | mg/l | 2.60 | <0.05 | - |
| No. 2 | mg/l | <0.02 | <0.05 | - |
| No. 3 | mg/l | <0.02 | <0.05 | - |
| No. 4 | mg/l | <0.02 | <0.05 | - |
| NPDES Discharge Pt. | | | | |
| Surface Water Comp. | mg/l | <0.02 | <0.05 | - |
| Sediment Comp. | mg/Kg* | 31.4 | 169 | 0.49 |
| Soils | | | | |
| N. Landfill Comp. | mg/Kg | 14.8 | 17.8 | 0.12 |
| S. Landfill Comp. | mg/Kg | 20.9 | 20.7 | 0.13 |
| Average Background Levels | | | | |
| Soil | mg/Kg | 100(1) | 313(2)** | <1(3) |

*Millograms per kilogram = mg/kg (Dry Weight Basis).

References

- (1) Allaway, W.H. 1968. Agronomic controls over the environmental cycling of trace elements. Adv. Agron. 20: 235-274.
- (2) Final Report of Soil Sampling and Analysis for the North Hollywood Dump Health Effects Study, Hess Environmental Services, Inc., May 30, 1986.
Range 40.7 to 2002 mg/Kg.
- (3) Richardson, B.J. and Waid, J.S. (1982). Polychlorinated biphenyls (PCBs): An Australian Viewpoint on a Global Problem. Search 13, 17.

IV. CONCLUSIONS

- * Ground water samples collected from downgradient wells contained no significant levels of metals.
- * Significant levels of chromium (consistent with previous results) were found in ground water collected from the upgradient well (Monitoring Well No. 1).
- * Site surface water does not contain detectable levels of chromium or lead.
- * Site soil and sediment composites do not contain contaminants of interest above published background levels.

Although the chromium concentration has decreased since the last sampling event, careful attention should continue to be given to the chromium levels detected in Monitoring Well No. 1 during future sampling events. If the level of chromium continues to remain relatively high it may be necessary to conduct a study of ground water near the upgradient well to determine the source of chromium in this area.

It would probably be advisable to survey the Measuring Point (MP) marked on the casing of each well with respect to Mean Sea Level (MSL), to verify that ground water monitoring well No. 1 is currently an upgradient well.

Aside from reporting the data contained in this report, no further action is required until the second semi-annual, third year monitoring is required.

**APPENDIX
LABORATORY REPORT**



ENVIRONMENTAL TESTING & CONSULTING INC.

2924 WALNUT GROVE RD. • MEMPHIS, TENN 38111 • PHONE (901) 327-2750

RECEIVED MAY 25 1989

May 24, 1989

Ms. Connie Hess, President
Hess Environmental Services
6890 Hillshire Dr., Suite 13
Memphis, Tenn. 38133

REF: ANALYTICAL TESTING
SAMPLE(S) DATE: 5/11/89
SITE 181
WATER, SOIL, SEDIMENT

Dear Ms. Hess:

The above referenced sample has been analyzed per your instructions. The tests were performed in our laboratory (#00210) in accordance with Standard Methods, 16th Edition, and the results are shown below. Testing results using SW-846, Method 8080, 3550 (PCB) are shown on the attached Organic Analysis Data Sheet.

| <u>Standard Methods Page #</u> | <u>Lead</u> | <u>Chromium</u> |
|--------------------------------|-------------|-----------------|
| <u>By</u> | 157 | 157 |
| <u>Date</u> | JF | JF |
| | 5/16 | 5/16 |

Sample ID: Water Results mg/l

| | | |
|---------|-------|-------|
| 181MW1 | <0.05 | 2.60 |
| 181MW2 | <0.05 | <0.02 |
| 181MW3 | <0.05 | <0.02 |
| 181MW4 | <0.05 | <0.02 |
| 181MW5 | <0.05 | <0.02 |
| 181SW-1 | <0.05 | <0.02 |

| <u>Soil Results ppm</u> | | <u>PCB</u> |
|-------------------------|------|------------|
| 181SW-2 | 169 | 31.4 |
| 181SS-1C | 17.8 | 14.8 |
| 181SS-2C | 20.7 | 20.9 |

See Attached Results

If you have any questions please call me.

Very truly yours,

Michael J. Cimbalò
President

MIC/mc

ORGANIC ANALYSIS DATA SHEET
PCBs

RECEIVED MAY 25 1989

SAMPLE NAME : HESS
SAMPLE ID(S) : SITE 181
SAMPLE DATE : 05/11/89
DATE ARRIVED : 05/12/89
MATRIX : SOIL/SEDIMENT

PROJECT # :
INSTRUMENT ID : V3700
ANALYST : LB


FILE NAME : 0512-001.DCC
SAMPLE # : 0512-001

DATE EXTRACTED/PREPARED : 05/15/89
DATE ANALYZED : 05/18/89

METHOD (SW-846) : 8080
3550

| SAMPLE ID | SAMPLE RESULTS UNITS:(mg/kg) | METHOD DETECTION LIMIT:(mg/kg) |
|-----------|-----------------------------------|-------------------------------------|
| 1 SW-2 | <u>0.49</u> | <u>0.05</u> |
| 2 SS-1C | <u>0.12</u> | <u>0.05</u> |
| 3 SS-2C | <u>0.13</u> | <u>0.05</u> |

BDL - BELOW DETECTION LIMIT



ANNUAL REPORT OF POST CLOSURE MONITORING
AT THE
INTERNATIONAL HARVESTER LANDFILL SITE
MEMPHIS, TENNESSEE
SECOND QUARTER, SIXTH YEAR
PECI PROJECT #5222.01

PREPARED BY:
PICKERING ENVIRONMENTAL CONSULTANTS, INC.
MEMPHIS, TENNESSEE

DECEMBER 1992

TABLE OF CONTENTS

| | Page |
|----------------------------------|------|
| EXECUTIVE SUMMARY | 1 |
| I. INTRODUCTION | 2 |
| II. SAMPLE COLLECTION | 3 |
| A. Ground Water Monitoring Wells | 3 |
| B. NPDES Discharge Point | 4 |
| C. Soil Composites | 5 |
| D. Sample Handling | 5 |
| III. DISCUSSION OF DATA | 6 |
| IV. CONCLUSIONS | 7 |

FIGURES

- I. INTERNATIONAL HARVESTER LANDFILL SITE

TABLES

- I. GROUND WATER SURFACE ELEVATION MEASUREMENTS
- II. ANALYTICAL METHODS
- III. SOIL COMPOSITE SAMPLING SITES
 - A-NORTH COMPOSITE
 - B-SOUTH COMPOSITE
- IV. SUMMARY OF SECOND QUARTER, Sixth year DATA
- V. SUMMARY OF HISTORICAL SITE DATA

SUPPLEMENTARY INFORMATION

LABORATORY REPORT

EXECUTIVE SUMMARY

Second quarter, sixth year ground water, surface water, sediment and soil samples were collected and analyzed in compliance with post closure monitoring requirements delineated in International Harvester's Landfill Closure Plan, as enforced by the State of Tennessee.

Ground water surface elevations were measured and samples were collected from the four (4) monitoring wells on site. All ground water samples were analyzed for chromium and lead content.

Chromium was detected in the ground water sample collected from Monitoring Well No. 1, southeast of the landfill. No lead was found in ground water from monitoring Well No. 1 and no chromium or lead were found in ground water samples collected from Monitoring well Nos. 2 through 4. All current ground water data is consistent with historical data for this site.

Surface water and sediment composite samples were collected from the National Pollutant Discharge Elimination System (NPDES) discharge point on-site. No metals were detected in the surface water composite, which is consistent with data from previous sampling events; sediment data is addressed below.

Soil composite samples were collected from two (2) areas at the base of the landfill; one (1) north of the NPDES discharge point and west of the landfill and the second south of the NPDES discharge point and west of the landfill.

All sediment and soil samples were analyzed for chromium, lead and Polychlorinated Biphenyls (PCBs) content.

Lead and chromium (metals) were found in all soil and sediment composites. PCB's were found in the southern composite and the sediment composite but were not detected in the northern composite.

The levels of PCB's, lead and chromium in all soil composites were consistent with historical data.

A copy of current data is summarized in Table IV of this report.

A copy of this report should be submitted to the State. No further action should be required until second quarter, seventh year, when monitoring will again be required.

I. INTRODUCTION

The State of Tennessee, Department of Health and Environment, Division of Superfund (the State), enforces the International Harvester (IH) Landfill Closure Plan. To comply with post closure monitoring requirements delineated in that plan (and modified as noted below), Pickering Environmental Consultants, Inc. collected ground water samples from Monitoring Well Nos. 1 through 4, water and sediment samples from the NPDES discharge point and soil samples from two (2) areas at the base of the landfill.

September 12, 1989, the Pickering Firm surveyed the measuring points on each monitoring well with respect to Mean Sea Level (MSL). Ground water surface elevations were calculated based on this data.

The Closure Plan, referenced above, has been modified so that monitoring is now required on an annual basis, a reduction from the quarterly and then semi-annual monitoring required previously.

All samples were analyzed for chromium and lead content. The soil samples collected below the landfill and the sediment samples collected from the NPDES discharge point were also analyzed for PCB content.

this report addresses sampling, testing and Chain-of-Custody protocols followed to fulfill post closure monitoring requirements.

II. SAMPLE COLLECTION

On November 19, 1992, Pickering Environmental representatives collected:

- * Ground water samples from Monitoring Well Nos. 1, 2, 3, and 4;
- * One (1) surface water composite and one (1) sediment composite from the NPDES discharge point ditch; and,
- * Two (2) soil composites; the first from below the landfill on the north side of the NPDES discharge point; and the second from below the landfill on the south side of the NPDES discharge point.

All sampling locations at the IH Landfill Site, Parcel 4, are shown in Figure I.

During this sampling event the weather was sunny and mild; the temperature was about 70 degrees F.

A. Ground Water Monitoring Wells

Each of the four (4), 2-inch ID ground water monitoring wells had a protective, metal, outer well casing with a pad-locked lid. PECO personnel found all the lids locked. Before sampling, the well depth and the depth to the surface of ground water was measured with respect to the Measuring Point (MP), in each well and the volume of standing water calculated (see Table I for these measurements).

A new disposable Teflon bailer was used to evacuate one (1) volume of standing water and three (3) volumes of recharge water from each of the Monitoring Well Nos. 1 - 4. This is in accordance with the protocol described in the Environmental Protection Agency's (EPA), Resource Conservation and Recovery Act (RCRA), Ground Water Monitoring Technical Enforcement Guideline Document.

The ground water samples were placed in precleaned, glass jars, and stored on ice (<4C) for preservation, immediately after collection. Ground water samples were preserved with nitric acid to a pH of less than (<) 2.

All sample container cleaning, sample preservation and analyses were performed in accordance with "Methods for Chemical Analysis of Water and Wastes," EPA-600/4-79-020, March, 1979, as referenced in the "Rules Governing Hazardous Waste Management in Tennessee" (see Table II

for the specific analytical method employed for each parameter).

Established Chain-of-Custody sample handling protocols were followed. A "Field Log Book" was kept, as required in the Chain-of-Custody protocol, to record general site and weather data, as well as data collected during each sampling event. This log will be updated during each future sampling event.

All of the samples were delivered by PECI personnel on November 19, 1992, to Environmental Testing and Consulting, Inc. (ETC), a laboratory certified by the State (Certification No. 02027). ETC received all of the sample jars with the seals intact.

B. NPDES Discharge Point

Samples were collected at the NPDES discharge sampling point, located at the foot of the landfill, an earthen, rock laden, ditch which channels storm water runoff. This ditch is located in the northwest area of Parcel 4 (see Figure I). Water and sediment composites were collected in the vicinity of this discharge point.

PECI personnel collected grab samples of water from two (2) locations along the south bank of the ditch, near the NPDES discharge point. Water was scooped from each location via a clean glass sampling jar, then added to a second jar to form the composite. Equal portions of water from each grab sample were poured into the composite accumulation jar. When all grabs were deposited into the accumulation jar, the sample was gently mixed. The sample jar was covered with a Teflon-lined lid and handled via the same protocols for ground water.

Eight (8) sediment grabs were collected in the same general area as the water grabs. Sediment grabs were scooped from the rocky earthen stream bed by a stainless steel spoon. The grab sediment samples were then deposited in a clean Pyrex glass tray and stirred with a stainless steel spoon to form as uniform a composite as possible. The composite was placed in a clean glass jar covered with a Teflon-lined lid.

Both composite samples were handled via Chain-of-Custody handling protocols.

*not necessary
sterilizing
only
for
SRI
not
SRI*

C. Soil Composites

Two (2) soil composites were collected at the landfill site, one (1) north and one (1) south of the NPDES discharge point; below the west face of the landfill.

The north soil composite was formed by collecting one (1) soil core from each of nine (9) locations and depositing them in a precleaned Pyrex glass mixing tray. The soil was then mixed in the tray with a stainless steel spoon to form as uniform as possible a composite and placed in a sample jar. The jar housing the composite was then covered with a Teflon-lined lid and handled via Chain-of-Custody protocols. The south soil composite was formed by collecting one (1) soil core from each of ten (10) locations; the cores were handled in the same manner as the north composite, (described above); see Tables III-A and III-B for the locations sampled.

D. Sample Handling

The four (4) ground water, one (1) surface water, one (1) sediment and two (2) soil samples were each sealed by placing a Chain-of-Custody seal across the jar lid and down the sides of the jar. The samples were then promptly stored on ice (<4C). All eight (8) samples were delivered to ETC, via PECI personnel, on November 19, 1992, for analysis.

III. DISCUSSION OF DATA

As stipulated in the International Harvester Closure Plan, all water, sediment and soil samples were analyzed for chromium and lead content. The sediment and soil samples were also analyzed for PCB content.

All soil sample data is reported on a dry weight basis, in milligrams per kilogram ((mg/kg) or parts per million (ppm)).

A summary of all second quarter, sixth year, analytical data is presented in Table IV; a copy of the actual laboratory report is in the Appendix of this report.

Chromium was detected in ground water from Monitoring Well No. 1. The 0.19 ppm chromium level currently present in ground water from this well is consistent with recent sampling events (see Table V for a summary of historical data). Ground water samples obtained from Monitoring Well Nos. 2 through 4 contained no detectable levels of chromium. No lead was detected in ground water from any of the wells sampled. Current ground water data is comparable with historical data.

No metals were detected in the surface water composite, which is comparable with data from previous sampling events conducted at this site.

Lead and chromium were detected in all sediment and soil composites. PCB's were detected in the sediment composite and the southern soil composite.


Lead, chromium, and PCB's found in the sediment and both the north and south soil composites were all consistent with historical data. (See Table V for a summary of historical data.)


IV. CONCLUSIONS

- * Ground water samples collected from Monitoring Well Nos. 2 through 4 contained no significant levels of metals.
- * Chromium was found in ground water collected from Monitoring Well No. 1, however this level is consistent with historical data.
- * Site surface water does not contain detectable levels of chromium or lead, which is consistent with historical data.
- * Site soil and sediment composites do not contain contaminants of interest above published background levels and are comparable with historical levels.

Aside from reporting the data contained in this report, no further action should be required until the second quarter, seventh year monitoring is required.

FIGURES





Pickering Environmental
 Consultants, Inc.
 Asbestos Management
 Building/Site Evaluation

Title: Figure I
Subject: International Harvester
Landfill Site
Memphis, Tennessee

TABLES

TABLE I
GROUND WATER SURFACE ELEVATION MEASUREMENTS

| PARAMETER | WELL NUMBER | | | |
|---|-------------|--------|--------|--------|
| | 1 | 2 | 3 | 4 |
| Total Depth of Well | 41.75 | 24.69 | 24.72 | 25.50 |
| Depth from MP to top of Water column | 31.48 | 21.66 | 21.26 | 21.77 |
| Height of water column | 10.27 | 3.03 | 3.46 | 3.73 |
| Measuring Point Elevations* | 210.29 | 207.95 | 207.82 | 207.77 |

*Surveyed on September 12, 1989, by the Pickering Firm.

Notes: MP = Measuring Point, an area (point) at the top of each PVC well casing used as a reference point for measurements.

All measurements are in feet.

All elevations are in relation to Mean Sea Level.

TABLE II
ANALYTICAL METHODS

| <u>PARAMETERS</u> | <u>WATER SAMPLES METHOD REFERENCE</u> | <u>SOIL/ SEDIMENT SAMPLES METHOD REFERENCE</u> |
|---|---|--|
| Chromium | 3111 - B* | 7190* |
| Lead | 3111 - B* | 7420* |
| PCBs | - | 3550**, 8080** |
| * <u>Standard Methods for the Examination of Water and Wastewater</u> , 17th Edition, American Public Health Association, Inc., New York, New York. | | |
| ** <u>Test Methods for Evaluating Solid Waste, Physical Chemistry Methods</u> , SW-846, Second Edition, Revised, 1985, U.S. Environmental Protection Agency. | | |

TABLE III-A
NORTH SOIL COMPOSITE SAMPLING SITES

| <u>COMPOSITE</u> | <u>SAMPLING SITE</u> |
|------------------|--|
| North Composite: | |
| Grab N1 | 15 feet west and 30 feet north of Well No. 4 |
| Grab N2 | 15 feet west and 15 feet north of Well No. 4 |
| Grab N3 | 15 feet west of Well No. 4 |
| Grab N4 | 15 feet west and 30 feet south of Well No. 4 |
| Grab N5 | 15 feet west and 15 feet south of Well No. 4 |
| Grab N6 | Above the drainage pipe, along the rocks surrounding the pipe, 15 feet west of the drainage pipe inlet |
| Grab N7 | Adjacent to the drainage pipe, along the rocks surrounding the pipe, 15 feet NW of Grab N6 |
| Grab N8 | Adjacent to the drainage pipe, along the rocks surrounding the pipe, 15 feet NW of Grab N7 |
| Grab N9 | Adjacent to the drainage pipe, along the rocks surrounding the pipe, 15 feet NW of Grab N8 |

TABLE III-B
SOUTH SOIL COMPOSITE SAMPLING SITES

| <u>COMPOSITE</u> | <u>SAMPLING SITE</u> |
|-------------------------|--|
| South Composite: | |
| Grab S1 | 15 feet west and 30 feet north of Well No. 2 |
| Grab S2 | 15 feet west and 15 feet north of Well No. 2 |
| Grab S3 | 15 feet west of Well No. 2 |
| Grab S4 | 15 feet west and 30 feet south of Well No. 2 |
| Grab S5 | 15 feet west and 15 feet south of Well No. 2 |
| Grab S6 | 15 feet west and 30 feet north of Well No. 3 |
| Grab S7 | 15 feet west and 15 feet north of Well No. 3 |
| Grab S8 | 15 feet west of Well No. 3 |
| Grab S9 | 15 feet west and 15 feet south of Well No. 3 |
| Grab S10 | 15 feet west and 30 feet south of Well No. 3 |

TABLE IV
SUMMARY OF SECOND QUARTER, SIXTH YEAR DATA

| <u>GROUND WATER MONITORING WELLS</u> | <u>UNITS</u> | <u>CHROMIUM</u> | <u>LEAD</u> | <u>PCB'S</u> |
|--|--------------|--------------------|-----------------------|-------------------|
| No. 1 | *mg/L | 0.19 | <0.05 | - |
| No. 2 | mg/L | <0.02 | <0.05 | - |
| No. 3 | mg/L | <0.02 | <0.05 | - |
| No. 4 | mg/L | <0.02 | <0.05 | - |
| NPDES Discharge Pt. | | | | |
| Surface Water Comp. | mg/L | <0.02 | <0.05 | - |
| Sediment Comp. | **mg/kg | 17.3 | 30.3 | 0.08 |
| Soils | | | | |
| N. Landfill Comp. | mg/kg | 13.2 | 18.5 | 0.02 |
| S. Landfill Comp. | mg/kg | 11.6 | 20.8 | 0.10 |
| Average Background Levels | | | | |
| Soil | mg/kg | 100 ⁽¹⁾ | ***313 ⁽²⁾ | <1 ⁽³⁾ |

*mg/L = milligrams per Liter

**mg/kg = milligrams per kilogram (Dry Weight Basis)

***Range 40.7 to 2002 mg/kg

References

- (1) Allaway, W.H. 1968. Agronomic controls over the environmental cycling of trace elements. Adv. Agron. 20: 235-274.
- (2) Final Report of Soil Sampling and Analysis for the North Hollywood Dump Health Effects Study, Hess Environmental Services, Inc., May 30, 1986.
- (3) Richardson, B.J. and Waid, J.S. (1982). Polychlorinated biphenyls (PCBs): An Australian Viewpoint on a Global Problem. Search 13, 17.

TABLE V
SUMMARY OF DATA

| GROUND WATER MONITORING WELLS | UNITS | CHROMIUM | | | | LEAD | | | | PCBS | | | | | |
|-------------------------------------|-------|-----------|-------|---------|-------|--------|-------|---------|-------|--------|-------|---------|-------|------|-------|
| | | YEAR I | | YEAR II | | YEAR I | | YEAR II | | YEAR I | | YEAR II | | | |
| | | I* | II | III | IV | I | II | III | IV | I | II | III | IV | | |
| 1 | mg/l | 0.24 | 0.58 | 0.02 | 0.68 | 0.63 | 3.24 | <0.05 | <0.05 | <0.05 | <0.05 | - | - | - | - |
| 2 | mg/l | <0.02 | <0.02 | <0.02 | NS | 0.04 | NS | <0.05 | <0.05 | <0.05 | NS | - | - | - | - |
| 3 | mg/l | <0.02 | <0.02 | <0.02 | NS | 0.06 | NS | <0.05 | <0.05 | <0.05 | NS | - | - | - | - |
| 4 | mg/l | <0.02 | <0.02 | NS | <0.02 | 0.11 | NS | <0.05 | <0.05 | NS | <0.05 | <0.05 | NS | - | - |
| NPDES | | | | | | | | | | | | | | | |
| DISCHARGE | | | | | | | | | | | | | | | |
| POINT | | | | | | | | | | | | | | | |
| Surface | | | | | | | | | | | | | | | |
| Water Comp. | mg/l | <0.02 | <0.02 | <0.02 | <0.02 | <0.02 | <0.02 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | - | - |
| Sediment Comp. | mg/Kg | 70.2 | 110 | 144 | 64.6 | 10.3 | 112.5 | 646 | 191 | 144 | 161 | 12.2 | 204.5 | 2.97 | 5.1 |
| SOILS | | | | | | | | | | | | | | | |
| N. Landfill | | | | | | | | | | | | | | | |
| Comp. | mg/Kg | 26.4 | 21.1 | 21.7 | 27.9 | 16.4 | 29.0 | 46.5 | 36.9 | 38.4 | 40.6 | 24.2 | 42.6 | 0.39 | <0.25 |
| S. Landfill | mg/Kg | 15.4 | 12.9 | 11.9 | 10.8 | 16.2 | 11.9 | 26.4 | 29.6 | 15.9 | <2.5 | 25.3 | 15.8 | 0.41 | <0.25 |
| Comp. | mg/Kg | NS*** | 6.9 | NS | NS | NS | NS | NS | NS | NS | NS | NS | NS | NS | NS |
| Site Back-ground | mg/Kg | NS*** | 6.9 | NS | NS | NS | NS | NS | 44.7 | NS | NS | NS | NS | NS | NS |
| Average | mg/Kg | 100 (1) | | | | | | | | | | | | | |
| Background | mg/Kg | 302 (2)** | | | | | | | | | | | | | |
| <1 (3) | | | | | | | | | | | | | | | |

Soils
Revised
Pb 200/500
Cr 100/500

*Quarter.

**Range 40.7 to 2002 mg/Kg.

***NS = No Sample.

TABLE V
SUMMARY OF DATA
(continued)

| GROUND WATER MONITORING WELLS | UNITS | CHROMIUM | | | | LEAD | | | | PCB | | | |
|-------------------------------------|-------|----------|-------|---------|-------|----------|-------|----------|-------|----------|-------|---------|-------|
| | | YEAR III | | YEAR IV | | YEAR III | | YEAR IV | | YEAR III | | YEAR IV | |
| | | II | IV | II | IV | II | IV | II | IV | II | IV | II | IV |
| 1 | mg/l | 2.60 | 3.58 | 1.52 | 2.99 | <0.05 | <0.05 | <0.05 | <0.05 | - | - | - | - |
| 2 | mg/l | <0.02 | <0.02 | <0.02 | <0.02 | <0.05 | <0.05 | <0.05 | <0.05 | - | - | - | - |
| 3 | mg/l | <0.02 | <0.02 | <0.02 | <0.02 | <0.05 | <0.05 | <0.05 | <0.05 | - | - | - | - |
| 4 | mg/l | <0.02 | <0.02 | <0.02 | <0.02 | <0.05 | <0.05 | <0.05 | <0.05 | - | - | - | - |
| NPDES | | | | | | | | | | | | | |
| DISCHARGE | | | | | | | | | | | | | |
| POINT | | | | | | | | | | | | | |
| Surface Water | mg/l | <0.02 | <0.02 | <0.02 | <0.02 | <0.05 | <0.05 | <0.05 | <0.05 | - | - | - | - |
| Comp. | | | | | | | | | | | | | |
| Sediment | mg/l | 31.4 | 17.6 | 30.7 | 83.0 | 169 | 63.5 | 337 | 194 | 0.49 | <0.05 | 12.8 | <0.05 |
| Comp. | | | | | | | | | | | | | |
| SOILS | | | | | | | | | | | | | |
| N. Landfill | mg/Kg | 14.8 | 35.0 | 22.4 | 42.9 | 17.8 | 33.7 | 38.3 | 41.1 | 0.12 | <0.05 | <0.05 | <0.05 |
| Comp. | | | | | | | | | | | | | |
| S. Landfill | mg/Kg | 20.9 | 11.3 | 9.10 | 18.9 | 20.7 | 16.5 | 18.0 | 19.4 | 0.13 | <0.05 | <0.05 | <0.05 |
| Comp. | | | | | | | | | | | | | |
| Site | mg/Kg | NS*** | 6.9 | NS | NS | NS | NS | NS | 44.7 | NS | NS | NS | NS |
| Background | | | | | | | | | | | | | |
| Average | mg/Kg | | | 100(1) | | | | 302(2)** | | | | <1(3) | |
| Background | | | | | | | | | | | | | |

REFERENCES:

- (1) Allaway, W. H. 1968. "Agronomic Controls Over the Environmental Cycling of Trace Element," Adv. Agron. 20: 235-274.
- (2) "Final Report Of Soil Sampling And Analysis For the North Hollywood Dump Health Effects Study," Hess Environmental Services, Inc., May 30, 1986.
- (3) Richardson, B. J. and Wajid, J. S. (1982). "Polychlorinated Biphenyls (PCB): An Australian Viewpoint On A Global Problem." Search 13, 17.

*Quarter.

**Range 40.7 to 2002 mg/Kg.

***NS = No Sample.

TABLE V

SUMMARY OF DATA
(continued)

| GROUND WATER MONITORING WELLS | UNITS | CHROMIUM | | LEAD | | PCB | |
|-------------------------------------|-------|----------|---------|--------|--|--------|--|
| | | YEAR V | | YEAR V | | YEAR V | |
| | | | | | | | |
| 1 | mg/l | 2.49 | <0.05 | | | | |
| 2 | mg/l | <0.02 | <0.05 | | | | |
| 3 | mg/l | <0.02 | <0.05 | | | | |
| 4 | mg/l | <0.02 | <0.05 | | | | |
| NPDES | | | | | | | |
| DISCHARGE | | | | | | | |
| POINT | | | | | | | |
| Surface Water | | | | | | | |
| Comp. | mg/l | <0.02 | <0.05 | | | | |
| Sediment | | | | | | | |
| Comp. | mg/l | 59.8 | 30.3 | | | 0.81 | |
| SOILS | | | | | | | |
| N. Landfill | | | | | | | |
| Comp. | mg/Kg | 24.0 | 49.0 | | | 0.14 | |
| S. Landfill | | | | | | | |
| Comp. | mg/Kg | 13.0 | 14.5 | | | 0.05 | |
| Site | | | | | | | |
| Background | mg/Kg | NS** | NS | | | NS | |
| Average | | | | | | | |
| Background | mg/Kg | 100(1) | 302(2)* | | | <1(3) | |

REFERENCES:

- (1) Allaway, W. R. 1968. "Agronomic Controls Over the Environmental Cycling of Trace Element," Adv. Agron. 20: 235-274.
- (2) "Final Report of Soil Sampling And Analysis For the North Hollywood Dump Health Effects Study," Hesp Environmental Services, Inc., May 30, 1986.
- (3) Richardson, B. J. and Wald, J. S. (1982). "Polychlorinated Biphenyls (PCB): An Australian Viewpoint On A Global Problem." Search 10, 17.

*Range 40.7 to 2002 mg/Kg.

**NS = No Sample.

SUPPLEMENTARY INFORMATION



ENVIRONMENTAL TESTING & CONSULTING, INC.

2921 Walnut Grove Road • Memphis, TN 38111 • (901) 327-2750 • FAX (901) 327-0331

Founded 1972

December 1, 1992

Mr. Ed Powell
Pickering Environmental Consultants, Inc.
1750 Madison Avenue, Suite 500
Memphis, TN 38104

REF: ANALYTICAL TESTING
SAMPLE DATE: 11/19/92
SITE ID: 5222
SAMPLE ID: SEE BELOW (AQUEOUS/SOIL)


Dear Mr. Powell:

The above referenced samples have been analyzed according to your instructions. The tests were performed in our laboratory (#02027) in accordance with Standard Methods, 17th Edition and The Solid Waste Manual, SW-846. The results are shown below and on the attached Organic Analysis Data Sheet.

| Test | Results (ppm) | | | | | Method Number | Date Analyzed | By |
|---------------------------|--------------------|-------|------------------|-------|-----------------|---------------|---------------|----|
| | MW1 | MW2 | MW3 | MW4 | SW1 | | | |
| Chromium | 0.19 | <0.02 | <0.02 | <0.02 | <0.02 | 3111-B | 11/30/92 | BB |
| Lead | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | 3111-B | 12/01/92 | BB |
| <u>Soil Results (ppm)</u> | | | | | | | | |
| | North | | South | | | | | |
| | <u>Composite</u> | | <u>Composite</u> | | <u>Sediment</u> | | | |
| Chromium | 13.2 | | 11.6 | | 17.3 | 7190 | 11/30/92 | BB |
| Lead | 18.5 | | 20.8 | | 30.3 | 7420 | 12/01/92 | BB |
| PCBs | See Attached Sheet | | | | | | | |

Please call our office if you have any questions.

Sincerely,


Randall H. Thomas
Vice President

jw

Attachment

1119-048

ENVIRONMENTAL TESTING AND CONSULTING, INC.
MEMPHIS, TN
ORGANIC ANALYSIS DATA SHEET
PCBs

CLIENT NAME : PICKERING ENVIRONMENTAL PROJECT # :
CONSULTANTS, INC. ANALYST : CC
SITE ID : 5222
SAMPLE DATE : 11/19/92
DATE ARRIVED : 11/19/92
MATRIX : SOIL
FILE NAME : 1119-048.DOC
SAMPLE # : 1119-048
DATE EXTRACTED/PREPARED : 11/20/92
DATE ANALYZED : 11/20/92
METHOD (SW-846) : 8080
3580

| ETC # | SAMPLE ID | SAMPLE RESULTS UNITS: (ppm) | PCB IDENTITY | PQL (ppm) |
|-------|------------|--------------------------------|-----------------|--------------|
| #6 | NORTH COMP | ND | NA | 0.02 |
| #7 | SOUTH COMP | 0.10 | 1248 | 0.02 |
| #8 | SEDIMENT | 0.08 | 1248 | 0.02 |

PQL - PRACTICAL QUANTITATION LIMIT
ND - NONE DETECTED


LABORATORY MANAGER

HYDROGEOLOGY AND PRELIMINARY ASSESSMENT OF THE POTENTIAL FOR CONTAMINATION OF THE MEMPHIS AQUIFER IN THE MEMPHIS AREA, TENNESSEE

By William S. Parks

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations Report 90-4092

Prepared in cooperation with the
CITY OF MEMPHIS,
MEMPHIS LIGHT, GAS AND WATER DIVISION



Memphis, Tennessee
1990

DEPARTMENT OF THE INTERIOR

MANUEL LUJAN, JR., Secretary

U.S. GEOLOGICAL SURVEY

Dallas L. Peck, Director

For additional information write to:

District Chief
U.S. Geological Survey
A-413 Federal Building
U.S. Courthouse
Nashville, Tennessee 37203

Copies of this report can be purchased from:

U.S. Geological Survey
Books and Open-File Reports Section
Federal Center, Building 810
Box 25425
Denver, Colorado 80225

CONTENTS

| | |
|---|----|
| Abstract | 1 |
| Introduction | 1 |
| Purpose and scope | 2 |
| Previous investigations | 2 |
| Acknowledgments | 5 |
| Physiographic setting | 5 |
| Hydrogeology | 6 |
| Thickness of the confining unit overlying the Memphis aquifer | 9 |
| Water table in the alluvium and fluvial deposits | 18 |
| Potentiometric surface of the Memphis aquifer | 24 |
| Potential sources of contamination of the Memphis aquifer | 28 |
| Indications of downward leakage to the Memphis aquifer | 32 |
| Potential for contamination of the Memphis aquifer | 34 |
| Summary and conclusions | 36 |
| References | 38 |

PLATES (in pocket)

- Plate 1. Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area, Tennessee
2. Altitude of the water table in the alluvium and fluvial deposits in the Memphis area, Tennessee, fall 1988
3. Altitude of the potentiometric surface of the Memphis aquifer in the Memphis area, Tennessee, late summer-fall 1988
4. Sites where contaminants have been detected in the water-table and Memphis aquifers and areas where the confining unit is thin or absent in the Memphis area, Tennessee

ILLUSTRATIONS

- Figure 1. Map showing major physiographic subdivisions in the Memphis area and locations of Memphis Light, Gas and Water Division well fields 3
2. Hydrogeologic sections showing the principal aquifers and confining units in the Memphis area 8

TABLES

- Table 1. Post-Wilcox Group geologic units underlying the Memphis area and their hydrologic significance 6
2. Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area 10
 3. Water levels measured in wells screened in the water-table aquifers in the Memphis area, fall 1988 19
 4. Water levels from records of wells screened in the water-table aquifers in the Memphis area, 1944-1987 21
 5. Water levels measured in wells screened in the Memphis aquifer in the Memphis area, late summer and fall 1988 25
 6. Sites where synthetic organic compounds or relatively high concentrations of inorganic trace constituents have been detected in the water-table aquifers in the Memphis area 29

CONVERSION FACTORS AND DEFINITIONS

Factors for converting inch-pound units to metric units are shown to four significant digits:

| Multiply inch-pound units | By | To obtain metric units |
|----------------------------------|---------|--|
| inch (in.) | 2.540 | centimeter (cm) |
| foot (ft) | 0.3048 | meter (m) |
| mile (mi) | 1.609 | kilometer (km) |
| square mile (mi ²) | 2.590 | square kilometer (km ²) |
| million gallons per day (Mgal/d) | 0.04381 | cubic meter per second (m ³ /s) |

Sea level: In this report "sea level" refers to the National Geodetic Vertical Datum of 1929 (NGVD of 1929)—a geodetic datum derived from a general adjustment of the first-order level nets of both the United States and Canada, formerly called Sea Level Datum of 1929.

Well-Numbering System: Wells are identified according to the numbering system used by the U.S. Geological Survey (USGS) throughout Tennessee. The well number consists of three parts: (1) an abbreviation of the name of the county in which the well is located; (2) a letter designating the USGS 7 1/2-minute topographic quadrangle on which the well is plotted; and (3) a number generally indicating the numerical order in which the well was inventoried. The well number Sh:K-141, for example, indicates that the well is located in Shelby County on the "K" quadrangle and is identified as well 141 in the numerical sequence. Quadrangles are lettered from left to right, beginning in the southwest corner of the county. In this report, wells in Crittenden County, Ark., and DeSoto County, Miss., are numbered using the prefixes "Ar:" and "Ms:" for the preparation of illustrations. The suffixes (for example, "A-7") for the wells in DeSoto County are the same as the well designations assigned by the USGS in Mississippi.

HYDROGEOLOGY AND PRELIMINARY ASSESSMENT OF THE POTENTIAL FOR CONTAMINATION OF THE MEMPHIS AQUIFER IN THE MEMPHIS AREA, TENNESSEE

By William S. Parks

ABSTRACT

Detailed maps of the thickness of the Jackson-upper Claiborne confining unit and the altitude of the water table in the alluvium and fluvial deposits provide much new information concerning areas where downward leakage is or may be occurring from the water-table aquifers to the Memphis aquifer in the Memphis area. A detailed map of the altitude of the potentiometric surface of the Memphis aquifer and the locations of 44 sites where contaminants have been detected in the water-table aquifers indicate that many of these sites are located in areas where the direction of ground-water flow in the Memphis aquifer is toward municipal well fields. Consequently, if contaminants enter the Memphis aquifer, a hydraulic potential exists for their transport to those well fields.

Recently (1986-88), volatile organic compounds were detected in water from five municipal wells screened in the Memphis aquifer—three in the Allen well field of the Memphis Light, Gas and Water Division at Memphis and two in the west well field at Collierville. Concentrations of seven volatile organic compounds totaled about 11 micrograms per liter in a sample from one well in the Allen well field at Memphis, and the concentration of one compound was 25 micrograms per liter in a sample from one well at Collierville. These are the first

reported occurrences of synthetic organic compounds in the Memphis aquifer and prove that the principal aquifer in the Memphis area is vulnerable to contamination.

INTRODUCTION

The City of Memphis presently (1989) depends solely on the Memphis aquifer for its water supply. Withdrawals from this aquifer in the Memphis area for municipal, industrial, and commercial uses were about 200 Mgal/d in 1988. Historically, the Memphis aquifer was thought of as an ideal artesian aquifer overlain by a thick, impermeable clay layer that serves as an upper confining unit and protects it from contamination from near-surface sources. Studies made over the past few decades, however, indicate that the confining unit locally is thin or absent or contains sand "windows" that could provide "pathways" for contaminants to reach the Memphis aquifer (Criner and others, 1964; Bell and Nyman, 1968; Parks and Lounsbury, 1976; Graham and Parks, 1986).

Other studies indicate that downward leakage from the water-table aquifers to the Memphis aquifer is widespread in the Memphis area (Graham and Parks, 1986; J.V. Brabana and

R.E. Broshears, USGS, written commun., 1987). Areas particularly susceptible to leakage are places where the confining unit is thin or absent and in the vicinity of the Memphis Light, Gas and Water Division (MLGW) well fields where leakage is accelerated as a result of pumping stress in the Memphis aquifer (Graham and Parks, 1986).

Recently, volatile organic compounds were detected in water from five municipal wells pumping from the Memphis aquifer—three in the MLGW Allen well field at Memphis (J.H. Webb, MLGW, oral commun., 1986-88) and two in the west well field at Collierville (J.L. Ashner, Tennessee Department of Health and Environment (TDHE), oral commun., 1986). These are the first reported occurrences of synthetic organic compounds in the Memphis aquifer and prove that the principal aquifer in the Memphis area is vulnerable to contamination.

The concerns about the effectiveness of the confining unit to protect the Memphis aquifer prompted the City of Memphis, MLGW, and the U.S. Geological Survey (USGS) in 1987 to initiate a cooperative investigation of the potential for contamination of the aquifer. This report summarizes the findings of the investigation.

Purpose and Scope

The objectives of this investigation were to: (1) prepare detailed maps of the thickness of the Jackson-upper Claiborne confining unit, the water table in the alluvium and fluvial deposits, and the potentiometric surface of the Memphis aquifer; (2) identify potential sources of contamination of the Memphis aquifer; (3) update knowledge of indications of downward leakage from the water-table aquifers to the Memphis aquifer; and (4) make a preliminary assessment of the potential for contamination of the Memphis aquifer.

The investigation was limited to the Memphis area, as defined in recent reports (about 1,500 square miles), which includes all of Shelby County and parts of Fayette and Tipton Counties, Tenn., DeSoto and Marshall Counties, Miss., and Crittenden and Mississippi Counties, Ark. (fig. 1). Emphasis was placed on Shelby County, Tenn., where most of the municipal well fields are located (fig. 1).

Tasks included in the investigation were to: (1) interpret and correlate geophysical logs selected from a USGS file of more than 500 logs, (2) measure water levels in about 140 wells in the water-table and Memphis aquifers, (3) search for historic water levels in the USGS and State files to supplement data for the water-table aquifers, (4) collect information from various regulatory agencies relative to the location and type of potential sources of contamination of the Memphis aquifer, and (5) prepare interpretive maps and the final report.

Previous Investigations

Many previous reports include information concerning the local and regional aspects of the aquifer systems in the Memphis area, and many others contain water-level and water-quality data. Consequently, this discussion of previous investigations is limited to primary sources of information concerning the hydrology, geology, water levels, and water quality of the principal aquifers and associated environmental concerns. This report and primary previous reports contain lists of references that provide additional information sources. Extensive lists of selected references (although not all inclusive) are given in reports by Graham and Parks (1986) and Brahana and others (1987).

The hydrology and general geology of the principal aquifers are described in reports by Safford (1890), Glenn (1906), Wells (1931, 1933), Kazmann (1944), Schneider and Cushing




Figure 1.—Major physiographic subdivisions in the Memphis area and

(1948), Criner and Armstrong (1958), Plebuch (1961), Criner and others (1964), Nyman (1965), Bell and Nyman (1968), and Dalsin and Bettendorff (1976). Parks (1973, 1975, 1977, 1978, 1979a, 1979b, 1987a) mapped and described the surface and shallow subsurface geology of the Memphis urban area.

A series of potentiometric-surface maps and graphs showing historic water-level changes and pumpage (1886-1975) from the Memphis and Fort Pillow aquifers are included in a report by Criner and Parks (1976). The potentiometric surface of the Memphis aquifer in August 1978 was given by Graham (1979). Graham (1982) updated pumpage and water-level information for the Memphis and Fort Pillow aquifers through 1980 and included a map of the potentiometric surface of the Memphis aquifer for September 1980. The altitude of the water table in the alluvium and fluvial deposits and the potentiometric surfaces of the Memphis and Fort Pillow aquifers in the Memphis urban area for the fall 1984 are included in a report by Graham and Parks (1986).

A two-dimensional digital computer flow model of the Memphis aquifer was described by Brahana (1982). The application of this model as a predictive tool to estimate aquifer response to various hypothetical pumpage projections was described by Brahana and included in the U.S. Army Corps of Engineers, Memphis Metropolitan Urban Water Resources Study (1981). Brahana and Brosbears (USGS, written commun., 1987) described the hydrologic framework of the Memphis area and documented the development of an integrated conceptual model of the ground-water flow and testing of this conceptual model through application of a multilayer finite-difference flow model.

Information concerning quality of water in the principal aquifers in the Memphis area is in reports by Wells (1933), Schneider and Cushing (1948), Lanphere (1955), Criner and Armstrong

(1958), Plebuch (1961), Criner and others (1964), Bell and Nyman (1968), and Dalsin and Bettendorff (1976). Graham (1982) summarized the quality of water in the principal aquifers and discussed the potential for contamination of the aquifers. A report by Parks and others (1982) describes the installation and sampling of observation wells at six abandoned or inactive dumps in the Memphis area and provides data on the quality of water in the water-table aquifers at these sites. Graham (1985) described the installation and sampling of additional wells at the North Hollywood Dump and gave a summary of the quality of water in the water-table aquifers in the area of the dump.

Brahana and others (1987) provided background information concerning the quality of natural, uncontaminated water from the principal aquifers in the Memphis area, including tables summarizing the minimum, median, and maximum concentrations of selected major and trace inorganic constituents. This report also summarizes water-quality data for the MLGW well fields. McMaster and Parks (1988) provided background information concerning concentrations of selected trace inorganic constituents and synthetic organic compounds in the water-table aquifers. This report summarizes the results of previous investigations that give information concerning quality of water in the water-table aquifers.

A summary of some current and possible future environmental problems related to geology and hydrology in the Memphis area is given in a report by Parks and Lounsbury (1976). Rima (1979) discussed the susceptibility of the Memphis ground-water supply to contamination from a pesticide waste-disposal site in northeastern Hardeman County, Tenn. Graham and Parks (1986) described the potential for leakage among the principal aquifers in the Memphis area and provided information to support the fact that downward leakage from the water-table aquifers to the Memphis aquifer is widespread.

They also summarize information from previous investigations documenting downward leakage. Parks (1987b) summarized indications of downward leakage from the water-table aquifers to the principal artesian aquifer (Memphis aquifer) at Memphis.

Acknowledgments

Acknowledgments are due many individuals who contributed information or provided assistance during this investigation, particularly in regard to the identification of potential sources of contamination and the measurement of water levels. Early in the investigation, Ms. Jennifer L. Ashner, formerly with the TDHE, Division of Solid Waste Management (DSWM), provided information about sites under investigation in Shelby County, Tenn. Later, Mr. John Fox, Jr., with the TDHE, Division of Ground Water Protection (DGWP), provided lists of 1,679 underground storage tanks in Shelby County, Tenn. Before water-level measurements were made, Mr. James C. Ozment, then with the DGWP, provided information concerning investigations of underground storage tanks in Shelby County where wells installed in the water-table aquifers were available for measurement. Ms. Gwynne A. Woodward of the DSWM provided information on wells in the water-table aquifers at landfills and other sites under investigation and assisted in measuring water levels at many sites. Messrs. Fred P. Von Hofe and William J. Cole, MLGW, arranged to turn off many wells in the Memphis aquifer in the MLGW well fields during a high water-demand period and provided personnel to make airline measurements in the wells. Mr. Ozment, with the TDHE Underground Storage Tank Program, also reviewed the files of underground-storage-tank investigations and identified sites where the water-table aquifers are contaminated. Mr. J. Paul Patterson and Ms. Woodward of the DSWM provided information about contamination of the water-table

aquifers at several sites under investigation. Ms. Betty J. Maness and Mr. W. Jordan English of the TDHE, Division of Superfund, reviewed a list and identified sites where contaminants have been detected in the water-table aquifers and provided water-quality analyses for these sites and the two contaminated wells screened in the Memphis aquifer at Collierville. Mr. R.R. Franklin of the U.S. Environmental Protection Agency (U.S. EPA) provided information concerning the Gallaway pits. Mr. James H. Webb, MLGW, provided information concerning contaminants that have been detected in water from wells screened in the Memphis aquifer in the Allen well field.

PHYSIOGRAPHIC SETTING

The Memphis area is situated in two major physiographic subdivisions (fig. 1). The eastern three-quarters of the area is in the Gulf Coastal Plain section and the western one-quarter is in the Mississippi Alluvial Plain section of the Coastal Plain physiographic province (Fenneman, 1938). The principal river in the area is the Mississippi River; the major tributaries are the Wolf River, the Loosahatchie River, and Nonconnah Creek.

The Gulf Coastal Plain is characterized by gently rolling to steep topography formed as a result of erosion of geologic formations of Quaternary and Tertiary age. During the later stages of Pleistocene glaciation, this topography was covered by a relatively thick blanket of loess that makes up the present land surface. The gently rolling to steep topography is broken in many places by the flat-lying alluvial plains of streams crossing the area. Perhaps the most distinctive feature of the Gulf Coastal Plain is the loess covered bluffs that rise abruptly above the Mississippi Alluvial Plain at its eastern boundary. Land-surface altitudes in the Gulf Coastal Plain are as low as 190 feet above sea level at the mouth of Nonconnah Creek in southwestern

Shelby County, Tenn., and are as high as 470 feet above sea level in southwestern Fayette County, Tenn. Maximum local relief between the Gulf Coastal Plain and the Mississippi Alluvial Plain is about 200 feet along the bluffs in northwestern Shelby County.

The Mississippi Alluvial Plain is flat lying and is characterized by features of fluvial deposition such as point bars, abandoned channels, and natural levees. Land-surface altitudes are as low as 180 feet above sea level on the banks of the Mississippi River in extreme northwestern DeSoto County, Miss., and as high as 230 feet above sea level adjacent to the bluffs in southwestern Tipton County, Tenn. Maximum local relief commonly is not more than 10 or 20 feet, except where the Mississippi Alluvial Plain is built up above flood levels by man-placed fill.

HYDROGEOLOGY

The Memphis area is located in the north-central part of the Mississippi embayment, a broad structural trough or syncline that plunges southward along an axis that approximates the Mississippi River (Cushing and others, 1964). This syncline is filled with a few thousand feet of unconsolidated to semiconsolidated sediments that make up formations of Cretaceous and Tertiary age. These formations dip gently westward into the embayment and southward down the axis. Overlying the Cretaceous and Tertiary formations in many areas are the fluvial deposits (terrace deposits), loess, and alluvium of Tertiary(?) and Quaternary age. Descriptions of the post-Wilcox Group geologic units and their hydrologic significance in the Memphis area are given in table 1.

Table 1.—Post-Wilcox Group geologic units underlying the Memphis area and their hydrologic significance

[Modified from Graham and Parks, 1986]

| System | Series | Group | Stratigraphic unit | Thickness, in feet | Lithology and hydrologic significance |
|----------------------------|-----------------------------|-----------|---|--------------------|---|
| Quaternary | Miocene and Pliocene | | Alluvium | 0-175 | Sand, gravel, silt, and clay. Underlies the Mississippi Alluvial Plain and alluvial plains of streams in the Gulf Coastal Plain. Thickest beneath the Alluvial Plain, where commonly between 100 and 150 feet thick; generally less than 50 feet thick elsewhere. Provides water to domestic, farm, industrial, and irrigation wells in the Mississippi Alluvial Plain. |
| | Pleistocene | | Loess | 0-65 | Silt, silty clay, and minor sand. Principal unit at the surface in upland areas of the Gulf Coastal Plain. Thickest on the bluffs that border the Mississippi Alluvial Plain, thinner eastward from the bluffs. Tends to retard downward movement of water providing recharge to the fluvial deposits. |
| Quaternary and Tertiary(?) | Pleistocene and Pliocene(?) | | Fluvial deposits (terrace deposits) | 0-100 | Sand, gravel, minor clay and ferruginous sandstones. Generally underlies the loess in upland areas, but are locally absent. Thickness varies greatly because of erosional surfaces at top and base. Provides water to many domestic and farm wells in rural areas. |
| Tertiary | Eocene | ? | Jackson Formation and upper part of Claiborne Group, includes Coatsfield and Coats Mountain Formations (capping clay) | 0-375 | Clay, silt, sand, and lignite. Because of similarities in lithology, the Jackson Formation and upper part of the Claiborne Group cannot be reliably subdivided easily based on present work. Most of the preserved sequence consists of the Coatsfield and Coats Mountain Formations, but the Jackson Formation occurs beneath the higher hills and ridges in the northern part of the Memphis area. Serves as the upper confining unit for the Memphis aquifer. |
| | | Claiborne | Memphis Sand (200-foot sand) | 200-600 | Sand, clay, and minor lignite. Thick body of sand with lenses of clay at some stratigraphic horizons and minor lignite. Thickest in the southwestern part of the Memphis area, thinnest in the northeastern part. Principal aquifer providing water for municipal and industrial supplies east of the Mississippi River, sole source of water for the City of Memphis. Underlain by the Flour Island Formation of the Wilcox Group, which serves as the lower confining unit for the Memphis aquifer. |

Hydrogeologic units considered in this report (discussed in descending order of age) are: (1) the alluvium and fluvial deposits that comprise the shallow water-table aquifers, (2) the Jackson Formation and the Cockfield and Cook Mountain Formations in the upper part of the Claiborne Group that comprise the Jackson-upper Claiborne confining unit, and (3) the Memphis Sand that comprises the Memphis aquifer. Hydrogeologic sections showing the principal aquifers and confining units in the Memphis area are given in figure 2.

The alluvium occurs beneath the Mississippi Alluvial Plain and alluvial plains of streams draining the Gulf Coastal Plain (fig. 1) and consists primarily of sand, gravel, silt, and clay. The unit generally consists of fine sand, silt, and clay in the upper part, and sand and gravel in the lower part. The alluvium ranges from 0 to 175 feet in thickness. It commonly is about 100 to 150 feet thick beneath the Mississippi Alluvial Plain and less than 50 feet thick beneath the alluvial plains of major streams draining the Gulf Coastal Plain. The alluvium supplies water to many domestic, farm, industrial, and irrigation wells in the Mississippi Alluvial Plain.

The fluvial deposits occur beneath the uplands and valley slopes of the Gulf Coastal Plain (fig. 1) and consist primarily of sand, gravel, and minor clay lenses. Locally, the sand and gravel is cemented with iron oxide to form thin layers of ferruginous sandstone or conglomerate in the lower or basal parts. The fluvial deposits range from 0 to 100 feet in thickness. Thickness varies because of erosional surfaces at both the top and base of the unit. The fluvial deposits provide water to many domestic and farm wells in rural areas of the Gulf Coastal Plain.

Because of the lithologic similarities of the Jackson, Cockfield, and Cook Mountain Formations and upper part of the Memphis Sand, a detailed study of the stratigraphy and geologic

structure would be needed to correlate the units on the many geophysical logs available for wells and test holes drilled in the Memphis area. Such a study is beyond the scope of the present investigation. For the Gulf Coast Regional Aquifer-System Analysis (GC RASA) investigation (Grubb, 1984), however, the Jackson, Cockfield, and Cook Mountain Formations were correlated and mapped regionally in the subsurface of western Tennessee and the occurrence of these units was extended into the Memphis area (Parks and Carmichael, 1990a,b). From the GC-RASA work and additional observations made during the present investigation, some generalizations can be made concerning the occurrence of these units.

The Jackson Formation, which was once thought to comprise most of the thickness of the confining unit separating the water-table aquifers from the Memphis aquifer, occurs only beneath the higher hills and ridges in the northern part of the Memphis area. Based on geophysical-log correlations, this unit consists generally of fine sand or sandy clay and ranges from 0 to about 50 feet in thickness. The Jackson Formation (Tennessee, Kentucky, and Missouri) and the Jackson Group (Mississippi, Arkansas, Louisiana, and Texas) overlies the Cockfield Formation (Yegua Formation in Texas) and is part of a thick regional confining unit for the Cockfield aquifer (Hosman, 1988). In the Memphis area, the Jackson Formation is included in the upper part of the Jackson-upper Claiborne confining unit.

The Cockfield Formation occurs in the subsurface in most of the Memphis area, extending eastward at places nearly to the approximate eastern limits of the Jackson-upper Claiborne confining unit (plate 1). The Cockfield Formation consists of interfingering fine sand, silt, clay, and local lenses of lignite. The unit ranges from 0 to about 250 feet in thickness. In most of the Memphis area, the formation is an erosional remnant, and the original thickness is preserved





Figure 2.—Hydrogeologic sections showing the principal aquifers and confining units in the Memphis area (Modified from Graham and Parks, 1986.)

only beneath the higher hills and ridges in the northern part. The discontinuous and interconnected sands of the Cockfield Formation constitute a regional aquifer in some parts of the area of occurrence in Tennessee, Kentucky, Missouri, Arkansas, Louisiana, Texas (Yegua Formation), and Mississippi (Hosman, 1988). In the Memphis area, the Cockfield Formation consists predominantly of fine sediments and lacks the thicker, coarser sands present in other areas. Consequently, the formation is included in the Jackson-upper Claiborne confining unit. A few domestic wells in the Memphis area are screened in sands in the Cockfield Formation.

The Cook Mountain Formation occurs in the subsurface of most of the Memphis area, extending eastward to the approximate eastern limits of the Jackson-upper Claiborne confining unit (plate 1). The Cook Mountain Formation consists primarily of clay, but it locally contains varying amounts of fine sand. The formation ranges from about 30 to 150 feet in thickness, but it is commonly about 60 to 70 feet thick. The Cook Mountain Formation is a regional confining unit overlying the Memphis Sand in Tennessee, Missouri, and northeastern Arkansas and the Sparta Sand in Kentucky, southern Arkansas, Louisiana, and Mississippi (Hosman, 1988). In the Memphis area, the formation is the most persistent clay layer in the Jackson-upper Claiborne confining unit.

The Memphis Sand occurs in the subsurface of all of the Memphis area. Eastward from the approximate eastern limits of the Jackson-upper Claiborne confining unit (plate 1), the eroded upper part of the Memphis Sand directly underlies the alluvium and fluvial deposits. The Memphis Sand consists primarily of a thick body of sand that includes subordinate lenses of clay and silt at various horizons and ranges from about 500 to 900 feet in thickness. The Memphis Sand (and its equivalents) is a regional aquifer in Tennessee, Missouri, Kentucky (Tallahatta Formation and Sparta Sand), and northeastern

Arkansas. The Memphis Sand is equivalent to (in ascending order) the Tallahatta Formation, Winona Sand, Zilpha Clay, and Sparta Sand of northern Mississippi and the Carrizo Sand, Cane River Formation, and Sparta Sand of southern Arkansas (Hosman, 1988). In the Memphis area, the Memphis aquifer provides water for most municipal, industrial, and commercial supplies.

Thickness of the Confining Unit Overlying the Memphis Aquifer

The thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet are shown in plate 1. This map was prepared by interpretation and correlation of 236 geophysical logs made primarily in test holes for water wells or through the casings of observation wells and abandoned water wells. These logs were selected from a file of more than 500 electric and gamma-ray logs made by the USGS in the Memphis area from the early 1950's to 1989. Most of the logs in the file were examined during this investigation. Because many of the geophysical logs were made in test holes drilled at MLGW and industrial well fields, the logs used for making the map were selected on the basis of well spacing and, when a choice could be made, on the basis of the quality of the log. Through the years, wells were drilled on some MLGW well field lots to both the Memphis and Fort Pillow aquifers or to replace wells in the Memphis aquifer to about the same or greater depths. Thus, the file may contain as many as three logs for wells on the same well lots. In addition, lots in MLGW well fields are commonly about 1,000 feet apart, necessitating a further selection of logs based on well spacing for the scale of the map. Interpretive information from the geophysical logs used to prepare the map showing the thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet (plate 1) are given in table 2.

Table 2.--Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area--Continued

| Well No. | Lat. tude | Long. tude | Alt. tude | Base of water-table aquifer | Base of Cook Mountain Formation | Thickness of confining unit | Clay bed top | Clay bed bot. | Clay bed thickness | Clay bed top | Clay bed bot. | Clay bed thickness | Aggregate thicknesses of clay beds |
|----------|-----------|------------|-----------|-----------------------------|---------------------------------|-----------------------------|--------------|---------------|--------------------|--------------|---------------|--------------------|------------------------------------|
| Sh:J-36 | 350711 | 0900187 | 315 | 97 | 238 | 141 | 109 | 238 | 129 | -- | -- | -- | 129 |
| Sh:J-41 | 350723 | 0900213 | 275 | 49 | 248 | 199 | 82 | 116 | 34 | 185 | 248 | 63 | 97 |
| Sh:J-47 | 350508 | 0900489 | 230 | 94 | 228 | 132 | 94 | 108 | 14 | 154 | 228 | 72 | 86 |
| Sh:J-49 | 350611 | 0900344 | 280 | 75 | 277 | 202 | 112 | 141 | 29 | 149 | 189 | 40 | |
| Sh:J-50 | 350411 | 0900418 | 241 | 54 | 187 | 133 | 220 | 243 | 23 | 260 | 277 | 17 | 109 |
| Sh:J-58 | 350402 | 0900513 | 241 | 104 | 189 | 85 | 104 | 187 | 83 | -- | -- | -- | 83 |
| Sh:J-62 | 350459 | 0900330 | 223 | 45 | 183 | 138 | 45 | 76 | 31 | 89 | 183 | -- | 85 |
| Sh:J-65 | 350232 | 0900249 | 303 | 94 | 205 | 111 | 94 | 132 | 38 | 146 | 205 | 60 | 125 |
| Sh:J-71 | 350206 | 0900212 | 295 | 97 | 165 | 68 | 97 | 108 | 11 | 115 | 165 | 80 | 98 |
| Sh:J-74 | 350022 | 0900117 | 303 | 65 | 140 | 75 | 72 | 140 | 68 | -- | -- | -- | 61 |
| Sh:J-83 | 350319 | 0900144 | 280 | 45 | 167 | 122 | 45 | 95 | 60 | 112 | 144 | 32 | 68 |
| Sh:J-84 | 350536 | 0900627 | 243 | 168 | 197 | 29 | 168 | 186 | 18 | -- | -- | -- | 82 |
| Sh:J-104 | 350537 | 0900145 | 248 | 82 | 202 | 120 | 117 | 202 | 85 | -- | -- | -- | 16 |
| Sh:J-111 | 350503 | 0900132 | 280 | 114 | 240 | 126 | 114 | 128 | 14 | 140 | 240 | 100 | 85 |
| Sh:J-113 | 350449 | 0900138 | 272 | 85 | 174 | 89 | 85 | 174 | 88 | -- | -- | -- | 114 |
| Sh:J-115 | 350553 | 0900223 | 295 | 101 | 262 | 161 | 101 | 119 | 18 | 131 | 262 | 131 | 89 |
| Sh:J-118 | 350521 | 0900204 | 280 | 98 | 180 | 82 | 112 | 180 | 68 | -- | -- | -- | 149 |
| Sh:J-127 | 350436 | 0900136 | 245 | 40 | 166 | 128 | 40 | 57 | 17 | 85 | 79 | 14 | 68 |
| Sh:J-129 | 350353 | 0900640 | 280 | 103 | 249 | 146 | 88 | 168 | 80 | -- | -- | -- | 111 |
| Sh:J-133 | 350633 | 0900119 | 300 | 88 | 310 | 222 | 103 | 180 | 67 | 180 | 249 | 89 | 126 |
| Sh:J-138 | 350148 | 0900702 | 300 | 84 | 242 | 158 | 68 | 164 | 76 | 230 | 310 | 80 | 156 |
| Sh:J-144 | 350053 | 0900708 | 280 | 96 | 204 | 108 | 182 | 242 | 80 | -- | -- | -- | 80 |
| Sh:J-166 | 350611 | 0900205 | 278 | 100 | 210 | 108 | 136 | 204 | 88 | -- | -- | -- | 68 |
| Sh:K-13 | 350341 | 0905902 | 295 | 80 | 224 | 144 | 130 | 210 | 80 | -- | -- | -- | 68 |
| Sh:K-16 | 350323 | 0905801 | 293 | 55 | 208 | 151 | 117 | 224 | 107 | -- | -- | -- | 80 |
| Sh:K-23 | 350647 | 0905420 | 320 | 112 | 220 | 108 | 55 | 110 | 55 | 132 | 208 | 74 | 107 |
| Sh:K-26 | 350111 | 0905905 | 320 | 36 | 150 | 114 | 112 | 136 | 24 | 181 | 198 | 37 | 129 |
| Sh:K-29 | 350258 | 0905928 | 271 | 58 | 84 | 36 | 204 | 220 | 18 | -- | -- | -- | 77 |
| Sh:K-31 | 350143 | 0905357 | 317 | 27 | 82 | 25 | 66 | 117 | 28 | 123 | 150 | 27 | 56 |
| Sh:K-33 | 350345 | 0905928 | 275 | 85 | 210 | 145 | 27 | 94 | 36 | -- | -- | -- | 36 |
| Sh:K-72 | 350309 | 0905553 | 252 | 44 | 150 | 108 | 65 | 102 | 37 | 110 | 210 | 100 | 137 |
| Sh:K-79 | 350024 | 0905827 | 350 | 38 | 172 | 136 | 44 | 180 | 108 | -- | -- | -- | 106 |
| Sh:K-81 | 350103 | 0905719 | 380 | 44 | 184 | 140 | 36 | 86 | 30 | 85 | 172 | 67 | 117 |
| Sh:K-86 | 350633 | 0905438 | 313 | 83 | 178 | 93 | 44 | 88 | 42 | 89 | 184 | 85 | 127 |
| Sh:K-89 | 350627 | 0905533 | 285 | 92 | 116 | 26 | 128 | 178 | 48 | -- | -- | -- | 48 |
| Sh:K-104 | 350151 | 0905340 | 300 | 32 | 37 | 5 | 105 | 118 | 13 | -- | -- | -- | 13 |
| Sh:K-108 | 350153 | 0905259 | 295 | 24 | 74 | 50 | 32 | 37 | 5 | -- | -- | -- | 5 |
| Sh:K-109 | 350532 | 0905553 | 258 | 88 | 194 | 128 | 24 | 74 | 50 | -- | -- | -- | 50 |
| Sh:K-114 | 350205 | 0905341 | 302 | 21 | 47 | 28 | 68 | 84 | 18 | 119 | 194 | 75 | 93 |
| Sh:K-115 | 350360 | 0905347 | 273 | 92 | 170 | 78 | 21 | 47 | 28 | -- | -- | -- | 26 |
| | | | | | | | 92 | 102 | 10 | 132 | 170 | 38 | 46 |

(Latitude and longitude are in degrees, minutes, and seconds; altitude is in feet above sea level; base of water-table aquifer, base of Cook Mountain Formation, and tops and bottoms of clay beds are depths in feet below land surface; thicknesses are in feet; dashes (--) indicate no data given for any clay beds below base of the Cook Mountain Formation)

| Well No. | Lat. tude | Long. tude | Alt. tude | Base of water. table aquifer | Base of Cook Mountain Formation | Thickness of confining unit | Clay bed top | Clay bed bot. tem | Clay bed thick. ness | Clay bed top | Clay bed bot. tem | Clay bed thick. ness | Aggregate thicknesses of clay beds |
|-----------|-----------|------------|-----------|------------------------------|---------------------------------|-----------------------------|--------------|-------------------|----------------------|--------------|-------------------|----------------------|------------------------------------|
| Ar: C-1 | 350938 | 0901738 | 209 | 148 | 288 | 140 | 172 | 204 | 32 | 220 | 288 | 88 | 100 |
| Ar: E-2 | 350518 | 0901810 | 207 | 102 | 313 | 211 | 102 | 142 | 40 | 258 | 313 | 57 | 97 |
| Ar: M-2 | 350344 | 0901300 | 211 | 90 | 286 | 176 | 90 | 120 | 30 | 162 | 268 | 104 | 134 |
| Ar: N-4 | 350724 | 0901347 | 214 | 164 | 272 | 118 | 190 | 272 | 82 | -- | -- | -- | 82 |
| Ar: N-1 | 350849 | 0900928 | 211 | 84 | 182 | 98 | 84 | 98 | 15 | 110 | 182 | 72 | 87 |
| Ar: O-1 | 351349 | 0900428 | 217 | 105 | 302 | 197 | 105 | 120 | 18 | 128 | 187 | 41 | 135 |
| Ar: O-2 | 350748 | 0900553 | 227 | 99 | 227 | 128 | 99 | 131 | 32 | 180 | 227 | 77 | 109 |
| Ar: A-7 | 345918 | 0900828 | 220 | 57 | 150 | 93 | 74 | 150 | 76 | -- | -- | -- | 76 |
| Ar: A-8 | 345731 | 0900911 | 211 | 127 | 204 | 77 | 134 | 204 | 70 | -- | -- | -- | 70 |
| Ar: A-12 | 345712 | 0900918 | 210 | 117 | 198 | 81 | 117 | 196 | 81 | -- | -- | -- | 81 |
| Ar: A-28 | 348748 | 0900438 | 202 | 78 | 318 | 240 | 130 | 140 | 10 | 178 | 204 | 26 | 112 |
| Ar: A-103 | 345737 | 0901028 | 211 | 124 | 226 | 102 | 242 | 318 | 76 | -- | -- | -- | 102 |
| Ar: B-3 | 345839 | 0900054 | 325 | 80 | 177 | 117 | 90 | 177 | 87 | -- | -- | -- | 87 |
| Ar: B-8 | 345740 | 0905945 | 335 | 48 | 181 | 112 | 104 | 181 | 57 | -- | -- | -- | 57 |
| Ar: B-7 | 345917 | 0900100 | 305 | 28 | 123 | 95 | 40 | 84 | 14 | 77 | 113 | 36 | 50 |
| Ar: B-63 | 345937 | 0900311 | 289 | 86 | 172 | 86 | 86 | 172 | 86 | -- | -- | -- | 86 |
| Ar: C-4 | 345817 | 0905712 | 373 | 60 | 147 | 87 | 118 | 147 | 28 | -- | -- | -- | 28 |
| Ar: C-15 | 345812 | 0905851 | 345 | 40 | 198 | 158 | 98 | 198 | 100 | -- | -- | -- | 100 |
| Ar: C-17 | 345805 | 0905400 | 402 | 58 | 88 | 10 | 58 | 88 | 10 | -- | -- | -- | 10 |
| Ar: D-3 | 345747 | 0904943 | 391 | 63 | 124 | 71 | 53 | 124 | 71 | -- | -- | -- | 71 |
| Ar: D-28 | 345903 | 0904741 | 402 | 61 | 82 | 21 | 61 | 82 | 21 | -- | -- | -- | 21 |
| Ar: D-48 | 345708 | 0905014 | 412 | 51 | 174 | 123 | 51 | 84 | 33 | 98 | 174 | 76 | 109 |
| Ar: D-57 | 345820 | 0905142 | 390 | 36 | 101 | 65 | 36 | 101 | 65 | -- | -- | -- | 65 |
| Ar: R-1 | 352226 | 0903301 | 318 | 40 | 122 | 82 | 40 | 122 | 82 | -- | -- | -- | 82 |
| Ar: E-3 | 345842 | 0905221 | 335 | 24 | 65 | 41 | 24 | 65 | 41 | -- | -- | -- | 41 |
| Ar: E-4 | 345943 | 0904902 | 403 | 78 | 153 | 77 | 76 | 87 | 11 | 101 | 163 | 52 | 63 |
| Ar: M-1 | 350331 | 0900729 | 312 | 110 | 270 | 180 | 134 | 270 | 156 | -- | -- | -- | 156 |
| Ar: M-2 | 350405 | 0900736 | 215 | 94 | 201 | 107 | 84 | 201 | 107 | -- | -- | -- | 107 |
| Ar: M-8 | 350157 | 0900742 | 305 | 84 | 246 | 162 | 136 | 164 | 26 | 181 | 246 | 85 | 91 |
| Ar: H-11 | 350115 | 0900740 | 274 | 50 | 191 | 141 | 50 | 85 | 15 | 88 | 102 | 18 | 83 |
| | | | | | | | 139 | 191 | 52 | -- | -- | -- | 83 |
| Ar: H-13 | 350452 | 0900789 | 238 | 114 | 196 | 84 | 123 | 175 | 52 | 185 | 198 | 13 | 65 |
| Ar: J-1 | 350004 | 0900546 | 240 | 50 | 162 | 112 | 50 | 68 | 16 | 76 | 162 | 86 | 102 |
| Ar: J-10 | 350501 | 0900239 | 270 | 104 | 214 | 110 | 104 | 214 | 110 | -- | -- | -- | 110 |
| Ar: J-27 | 350718 | 0900330 | 268 | 60 | 265 | 205 | 60 | 107 | 47 | 202 | 265 | 63 | 110 |
| Ar: J-32 | 350857 | 0900428 | 280 | 122 | 262 | 140 | 122 | 139 | 17 | 197 | 262 | 65 | 82 |

Table 2.--Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area--Continued

| Well No. | Lat. tude | Long. tude | Alt. tude | Base of water-table aquifer | Base of Cook Mountain Formation | Thickness of confining unit | Clay bed top | Clay bed bot. | Clay bed thickness | Clay bed top | Clay bed bot. | Clay bed thickness | Aggregate thickness of clay beds |
|----------|-----------|------------|-----------|-----------------------------|---------------------------------|-----------------------------|--------------|---------------|--------------------|--------------|---------------|--------------------|----------------------------------|
| Sh:K-120 | 350008 | 0895450 | 362 | 29 | 133 | 104 | 46 | 63 | 17 | 83 | 133 | 50 | 67 |
| Sh:K-122 | 350434 | 0895739 | 240 | 33 | 155 | 122 | 33 | 155 | 122 | -- | -- | -- | 122 |
| Sh:K-125 | 350114 | 0895822 | 311 | 28 | 138 | 112 | 54 | 72 | 18 | 104 | 138 | 34 | 52 |
| Sh:K-127 | 350024 | 0895838 | 320 | 36 | 178 | 142 | 60 | 81 | 21 | 107 | 178 | 71 | 92 |
| Sh:K-139 | 350810 | 0895528 | 295 | 96 | 120 | 24 | 102 | 120 | 18 | -- | -- | -- | 18 |
| Sh:K-141 | 350724 | 0895553 | 311 | 108 | 176 | 70 | 121 | 176 | 85 | -- | -- | -- | 55 |
| Sh:K-142 | 350642 | 0895550 | 278 | 99 | 105 | 8 | 99 | 105 | 8 | -- | -- | -- | 6 |
| Sh:K-143 | 350233 | 0895838 | 281 | 89 | 112 | 53 | 80 | 112 | 32 | -- | -- | -- | 32 |
| Sh:K-148 | 350228 | 0895232 | 300 | 35 | 51 | 16 | 35 | 51 | 16 | -- | -- | -- | 16 |
| Sh:L-9 | 350504 | 0894828 | 370 | 45 | 127 | 82 | 45 | 73 | 28 | 100 | 127 | 27 | 55 |
| Sh:L-15 | 350412 | 0894530 | 341 | 28 | 74 | 48 | 28 | 74 | 48 | -- | -- | -- | 48 |
| Sh:L-17 | 350721 | 0895130 | 310 | 20 | 108 | 88 | 20 | 45 | 25 | 80 | 76 | 16 | 58 |
| Sh:L-18 | 350516 | 0894940 | 320 | 17 | 93 | 78 | 17 | 93 | 78 | -- | -- | -- | 76 |
| Sh:L-21 | 350540 | 0895211 | 330 | 51 | 151 | 100 | 99 | 151 | 82 | -- | -- | -- | 52 |
| Sh:L-23 | 350519 | 0895212 | 330 | 78 | 155 | 70 | 94 | 155 | 81 | -- | -- | -- | 61 |
| Sh:L-25 | 350435 | 0895034 | 288 | 24 | 128 | 104 | 38 | 128 | 90 | -- | -- | -- | 90 |
| Sh:L-28 | 350248 | 0895123 | 352 | 43 | 91 | 48 | 43 | 91 | 48 | -- | -- | -- | 48 |
| Sh:L-27 | 350457 | 0895044 | 317 | 45 | 154 | 109 | 70 | 154 | 84 | -- | -- | -- | 84 |
| Sh:L-29 | 350440 | 0894947 | 325 | 27 | 135 | 108 | 27 | 135 | 108 | -- | -- | -- | 108 |
| Sh:L-32 | 350146 | 0895200 | 332 | 23 | 86 | 83 | 23 | 86 | 83 | -- | -- | -- | 83 |
| Sh:L-38 | 350232 | 0895158 | 315 | 18 | 72 | 56 | 16 | 72 | 56 | -- | -- | -- | 56 |
| Sh:L-46 | 350658 | 0894920 | 280 | 42 | 113 | 71 | 42 | 113 | 71 | -- | -- | -- | 71 |
| Sh:L-52 | 350024 | 0894722 | 390 | 52 | 120 | 88 | 52 | 120 | 88 | -- | -- | -- | 88 |
| Sh:L-57 | 350534 | 0895121 | 320 | 44 | 157 | 113 | 48 | 157 | 109 | -- | -- | -- | 109 |
| Sh:L-61 | 350354 | 0895638 | 272 | 26 | 75 | 46 | 26 | 75 | 46 | -- | -- | -- | 49 |
| Sh:L-64 | 350639 | 0895225 | 305 | 53 | 165 | 112 | 86 | 165 | 77 | -- | -- | -- | 77 |
| Sh:L-67 | 350447 | 0894828 | 360 | 38 | 136 | 100 | 75 | 85 | 10 | 98 | 136 | 40 | 50 |
| Sh:L-68 | 350259 | 0895213 | 329 | 33 | 78 | 45 | 33 | 78 | 45 | -- | -- | -- | 45 |
| Sh:L-70 | 350207 | 0895224 | 307 | 21 | 71 | 50 | 20 | 71 | 50 | -- | -- | -- | 50 |
| Sh:L-81 | 350450 | 0894807 | 360 | 52 | 158 | 104 | 52 | 82 | 30 | 94 | 158 | 62 | 92 |
| Sh:L-86 | 350730 | 0894900 | 257 | 42 | 42 | 0 | -- | -- | -- | -- | -- | -- | 0 |
| Sh:L-95 | 350349 | 0894501 | 369 | 58 | 114 | 56 | 58 | 114 | 56 | -- | -- | -- | 56 |
| Sh:L-96 | 350323 | 0895156 | 331 | 38 | 90 | 52 | 38 | 90 | 52 | -- | -- | -- | 52 |
| Sh:L-97 | 350207 | 0895110 | 353 | 26 | 82 | 56 | 26 | 82 | 56 | -- | -- | -- | 56 |
| Sh:L-99 | 350441 | 0894809 | 368 | 32 | 142 | 110 | 32 | 42 | 10 | 44 | 85 | 41 | 94 |
| Sh:L-102 | 350199 | 0895137 | 342 | 90 | 105 | 15 | 90 | 105 | 15 | -- | -- | -- | 15 |
| Sh:M-11 | 350223 | 0894458 | 338 | 60 | 71 | 11 | 60 | 71 | 11 | -- | -- | -- | 11 |
| Sh:M-17 | 350017 | 0894417 | 336 | 41 | 336 | 0 | -- | -- | -- | -- | -- | -- | 0 |
| Sh:M-24 | 350853 | 0894215 | 340 | 33 | 87 | 54 | 33 | 87 | 54 | -- | -- | -- | 54 |
| Sh:M-26 | 350404 | 0894356 | 332 | 49 | 68 | 17 | 49 | 68 | 17 | -- | -- | -- | 17 |

Table 2.--Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area--Continued

| Well No. | Lat. tude | Long. tude | Alt. tude | Base of water-table aquifer | Base of Cook Mountain Formation | Thickness of confining unit | Clay bed top | Clay bed bot. | Clay bed thickness | Clay bed top | Clay bed bot. | Clay bed thickness | Aggregate thicknesses of clay beds |
|----------|-----------|------------|-----------|-----------------------------|---------------------------------|-----------------------------|--------------|---------------|--------------------|--------------|---------------|--------------------|------------------------------------|
| Sh:M-27 | 350334 | 0894335 | 355 | 64 | 75 | 21 | 62 | 75 | 13 | -- | -- | -- | 13 |
| Sh:M-37 | 350842 | 0894360 | 355 | 42 | 72 | 30 | 42 | 72 | 30 | -- | -- | -- | 30 |
| Sh:M-38 | 350344 | 0894448 | 363 | 62 | 86 | 38 | 62 | 98 | 36 | -- | -- | -- | 36 |
| Sh:M-40 | 350480 | 0894444 | 342 | 34 | 97 | 63 | 34 | 97 | 63 | -- | -- | -- | 63 |
| Sh:M-41 | 350407 | 0894437 | 355 | 64 | 128 | 62 | 64 | 128 | 62 | -- | -- | -- | 62 |
| Sh:M-43 | 350413 | 0894133 | 320 | 64 | 84 | 0 | -- | -- | -- | -- | -- | -- | 0 |
| Sh:O-1 | 351437 | 0900046 | 228 | 57 | 280 | 233 | 150 | 290 | 140 | -- | -- | -- | 140 |
| Sh:O-18 | 351034 | 0900243 | 235 | 76 | 240 | 164 | 76 | 98 | 22 | 118 | 240 | 122 | 144 |
| Sh:O-54 | 351119 | 0900223 | 238 | 77 | 306 | 229 | 77 | 185 | 108 | 203 | 306 | 103 | 211 |
| Sh:O-87 | 350828 | 0900214 | 286 | 91 | 264 | 173 | 91 | 128 | 35 | 150 | 284 | 114 | 149 |
| Sh:O-82 | 350833 | 0900147 | 288 | 87 | 258 | 171 | 87 | 102 | 15 | 164 | 196 | 32 | -- |
| Sh:O-93 | 350839 | 0900239 | 236 | 46 | 242 | 196 | 220 | 258 | 38 | -- | -- | -- | 85 |
| Sh:O-118 | 351219 | 0900232 | 272 | 80 | 328 | 268 | 123 | 114 | 68 | 129 | 242 | 113 | 181 |
| Sh:O-120 | 351030 | 0900035 | 230 | 72 | 158 | 88 | 89 | 113 | 24 | -- | -- | -- | 205 |
| Sh:O-184 | 350958 | 0900138 | 251 | 78 | 333 | 255 | 78 | 184 | 106 | 193 | 333 | 140 | 58 |
| Sh:O-191 | 350818 | 0900335 | 278 | 99 | 292 | 193 | 100 | 148 | 48 | 158 | 292 | 134 | 248 |
| Sh:O-194 | 350817 | 0900043 | 285 | 84 | 278 | 214 | 184 | 278 | 94 | -- | -- | -- | 162 |
| Sh:O-199 | 350848 | 0900311 | 285 | 85 | 289 | 224 | 102 | 184 | 82 | 179 | 289 | 110 | 94 |
| Sh:O-202 | 351032 | 0900143 | 242 | 71 | 258 | 185 | 71 | 258 | 185 | -- | -- | -- | 172 |
| Sh:O-204 | 350922 | 0900154 | 257 | 78 | 301 | 223 | 78 | 140 | 62 | 176 | 301 | 125 | 185 |
| Sh:O-208 | 350805 | 0900204 | 272 | 82 | 284 | 182 | 82 | 110 | 28 | 186 | 284 | 98 | 187 |
| Sh:O-207 | 350913 | 0900109 | 255 | 81 | 236 | 155 | 130 | 236 | 106 | -- | -- | -- | 126 |
| Sh:O-213 | 350918 | 0900030 | 250 | 78 | 246 | 168 | 180 | 246 | 86 | -- | -- | -- | 108 |
| Sh:O-243 | 350808 | 0900022 | 280 | 70 | 254 | 184 | 70 | 90 | 20 | 188 | 254 | 88 | 86 |
| Sh:P-1 | 351320 | 0895401 | 300 | 41 | 239 | 198 | 103 | 120 | 17 | 149 | 239 | 90 | 108 |
| Sh:P-11 | 351028 | 0893050 | 244 | 62 | 182 | 120 | 62 | 88 | 26 | 101 | 182 | 81 | 107 |
| Sh:P-14 | 350843 | 0893787 | 262 | 62 | 194 | 132 | 62 | 94 | 32 | 107 | 194 | 87 | 107 |
| Sh:P-34 | 350807 | 0895825 | 283 | 104 | 186 | 84 | 125 | 188 | 63 | -- | -- | -- | 119 |
| Sh:P-38 | 350850 | 0895833 | 243 | 80 | 217 | 137 | 120 | 217 | 97 | -- | -- | -- | 83 |
| Sh:P-39 | 351045 | 0895855 | 251 | 62 | 270 | 208 | 62 | 75 | 13 | 83 | 85 | 12 | 97 |
| Sh:P-54 | 350904 | 0895805 | 255 | 80 | 234 | 154 | 186 | 270 | 77 | -- | -- | -- | 102 |
| Sh:P-62 | 350735 | 0895733 | 280 | 94 | 170 | 76 | 94 | 108 | 60 | -- | -- | -- | 68 |
| Sh:P-68 | 351220 | 0895525 | 300 | 64 | 200 | 136 | 80 | 104 | 24 | 127 | 170 | 43 | 55 |
| Sh:P-71 | 351323 | 0895764 | 290 | 65 | 289 | 224 | 132 | 200 | 68 | -- | -- | -- | 104 |
| Sh:P-73 | 350901 | 0895248 | 250 | 52 | 102 | 80 | 52 | 102 | 50 | 144 | 289 | 145 | 180 |
| Sh:P-75 | 351248 | 0895525 | 300 | 41 | 276 | 235 | 139 | 276 | 137 | -- | -- | -- | 50 |
| Sh:P-78 | 350735 | 0895932 | 287 | 84 | 176 | 92 | 84 | 124 | 40 | -- | -- | -- | 137 |
| Sh:P-79 | 350738 | 0895835 | 311 | 109 | 131 | 82 | 109 | 124 | 40 | 132 | 176 | 44 | 137 |
| Sh:P-85 | 351101 | 0895240 | 293 | 76 | 220 | 144 | 76 | 117 | 41 | -- | -- | -- | 22 |
| Sh:P-86 | 351131 | 0895312 | 275 | 30 | 226 | 198 | 123 | 226 | 103 | 188 | 220 | 52 | 93 |
| | | | | | | | | | | | | | 103 |

Table 2.—Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area—Continued

| Well No. | Lat. tude | Long. tude | Alt. tude | Base of water-table aquifer | Base of Cook Mountain Formation | Thickness of confining unit | Clay bed top | Clay bed bottom | Clay bed thickness | Clay bed top | Clay bed bottom | Clay bed thickness | Aggregate thicknesses of clay beds |
|----------|-----------|------------|-----------|-----------------------------|---------------------------------|-----------------------------|--------------|-----------------|--------------------|--------------|-----------------|--------------------|------------------------------------|
| Sh:R-23 | 350848 | 0884355 | 340 | 48 | 114 | 68 | 48 | 114 | 68 | .. | .. | .. | 66 |
| Sh:R-24 | 350811 | 0884244 | 330 | 45 | 110 | 65 | 45 | 110 | 65 | .. | .. | .. | 65 |
| Sh:R-25 | 350737 | 0884342 | 278 | 31 | 78 | 47 | 31 | 78 | 47 | .. | .. | .. | 47 |
| Sh:R-26 | 351402 | 0883935 | 285 | 31 | 92 | 61 | 31 | 92 | 61 | .. | .. | .. | 61 |
| Sh:R-28 | 350848 | 0884318 | 360 | 34 | 87 | 63 | 34 | 84 | 53 | .. | .. | .. | 53 |
| Sh:R-29 | 350835 | 0884341 | 318 | 48 | 107 | 59 | 48 | 107 | 59 | .. | .. | .. | 59 |
| Sh:R-30 | 350811 | 0884309 | 325 | 40 | 120 | 80 | 60 | 120 | 40 | .. | .. | .. | 40 |
| Sh:T-6 | 351805 | 0880322 | 280 | 185 | 326 | 181 | 286 | 326 | 30 | .. | .. | .. | 30 |
| Sh:T-7 | 352040 | 0880184 | 400 | 98 | 420 | 321 | 208 | 219 | 10 | 136 | 206 | 70 | 203 |
| | | | | | | | 328 | 420 | 92 | .. | 286 | 10 | |
| | | | | | | | 123 | 166 | 43 | 228 | 282 | 34 | 164 |
| | | | | | | | 367 | 454 | 87 | .. | .. | .. | |
| Sh:T-13 | 352213 | 0880058 | 400 | 90 | 454 | 364 | 112 | 150 | 38 | 321 | 337 | 16 | 108 |
| | | | | 102 | 398 | 296 | 344 | 398 | 64 | .. | .. | .. | |
| Sh:T-16 | 352044 | 0880249 | 359 | | | | 110 | 159 | 48 | 182 | 243 | 61 | 191 |
| Sh:T-17 | 351747 | 0880329 | 330 | 92 | 448 | 356 | 305 | 323 | 18 | 385 | 448 | 63 | 112 |
| Sh:T-18 | 352127 | 0880167 | 391 | 75 | 450 | 378 | 120 | 148 | 28 | 388 | 450 | 84 | 62 |
| Sh:U-1 | 352113 | 0885706 | 264 | 66 | 216 | 148 | 154 | 216 | 62 | .. | .. | .. | 60 |
| Sh:U-8 | 352037 | 0885727 | 288 | 79 | 232 | 183 | 172 | 232 | 60 | .. | .. | .. | 88 |
| Sh:U-12 | 351705 | 0885320 | 238 | 82 | 180 | 88 | 92 | 180 | 88 | .. | .. | .. | 90 |
| Sh:U-18 | 351803 | 0885840 | 242 | 73 | 207 | 134 | 105 | 118 | 13 | 130 | 207 | 42 | 108 |
| Sh:U-22 | 351737 | 0885748 | 300 | 60 | 228 | 186 | 98 | 109 | 11 | 124 | 186 | .. | 85 |
| | | | | | | | 171 | 226 | 55 | .. | .. | .. | 72 |
| Sh:U-29 | 351586 | 0885859 | 242 | 71 | 194 | 123 | 109 | 194 | 85 | .. | .. | .. | 73 |
| Sh:U-48 | 352114 | 0885727 | 267 | 74 | 152 | 78 | 80 | 152 | 72 | .. | .. | .. | 70 |
| Sh:U-49 | 352023 | 0885627 | 251 | 80 | 155 | 105 | 82 | 155 | 73 | .. | .. | .. | 54 |
| Sh:U-52 | 352038 | 0885708 | 257 | 54 | 198 | 144 | 102 | 114 | 12 | 124 | 158 | 14 | 41 |
| Sh:U-54 | 352834 | 0885345 | 265 | 74 | 212 | 138 | 74 | 94 | 20 | 182 | 188 | .. | 52 |
| Sh:U-55 | 352038 | 0885334 | 285 | 98 | 216 | 120 | 192 | 212 | 20 | .. | .. | .. | 108 |
| | | | | | | | 137 | 150 | 13 | 168 | 182 | 16 | 67 |
| | | | | | | | 204 | 216 | 12 | .. | .. | .. | 56 |
| Sh:U-58 | 351907 | 0885709 | 282 | 80 | 230 | 170 | 178 | 230 | 52 | .. | .. | .. | 77 |
| Sh:U-59 | 352024 | 0885257 | 285 | 66 | 174 | 108 | 68 | 174 | 108 | .. | .. | .. | 98 |
| Sh:U-60 | 352009 | 0885253 | 285 | 97 | 184 | 87 | 87 | 184 | 87 | .. | .. | .. | 67 |
| Sh:V-4 | 352027 | 0885232 | 292 | 88 | 204 | 116 | 148 | 204 | 58 | .. | .. | .. | 58 |
| Sh:V-7 | 352044 | 0885218 | 283 | 78 | 205 | 127 | 78 | 110 | 32 | 160 | 205 | 45 | 77 |
| | | | | | | | 27 | 72 | 45 | 124 | 177 | 63 | 98 |
| Sh:V-8 | 352012 | 0885038 | 273 | 60 | 222 | 162 | 150 | 222 | 72 | .. | .. | .. | 72 |
| Sh:V-10 | 352010 | 0885038 | 271 | 63 | 185 | 122 | 118 | 144 | 28 | 150 | 185 | 35 | 63 |
| Sh:V-16 | 351804 | 0884800 | 283 | 81 | 164 | 103 | 94 | 134 | 40 | .. | .. | .. | 40 |
| Sh:V-17 | 351850 | 0884935 | 282 | 83 | 180 | 117 | 120 | 180 | 60 | .. | .. | .. | 60 |
| Sh:V-24 | 352227 | 0885043 | 375 | 88 | 362 | 293 | 255 | 362 | 107 | .. | .. | .. | 107 |

Table 2.--Thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet in the Memphis area--Concluded

| Well No. | Lat. tude | Long. tude | Alt. tude | Base of water-table aquifer | Base of Cook Mountain Formation | Thickness of confining unit | Clay bed top | Clay bed bot. | Clay bed thick. nose | Clay bed top | Clay bed bot. | Clay bed thick. nose | Aggregate thicknesses of clay beds |
|----------|-----------|------------|-----------|-----------------------------|---------------------------------|-----------------------------|--------------|---------------|----------------------|--------------|---------------|----------------------|------------------------------------|
| Sh:W-3 | 351750 | 0893843 | 278 | 49 | 66 | 17 | 49 | 68 | 17 | -- | -- | -- | 17 |
| Sh:W-7 | 352026 | 0884408 | 322 | 31 | 202 | 171 | 31 | 44 | 13 | 49 | 80 | 11 | |
| Sh:W-13 | 351938 | 0894130 | 320 | 42 | 147 | 105 | 102 | 202 | 100 | -- | -- | -- | 124 |
| Sh:W-16 | 351923 | 0884228 | 304 | 44 | 218 | 172 | 84 | 147 | 93 | -- | -- | -- | 83 |
| Tp:E-3 | 352841 | 0884721 | 441 | 102 | 411 | 308 | 44 | 113 | 68 | 124 | 216 | 92 | 161 |
| Tp:F-3 | 352817 | 0884124 | 405 | 55 | 296 | 241 | 180 | 184 | 34 | 338 | 411 | 73 | 107 |
| | | | | | | | 210 | 296 | 86 | -- | -- | -- | 80 |

Geophysical logs were chosen as the primary source of information about the confining unit. The logs can be interpreted and correlated based on recorded measurements of the electrical characteristics (electric logs) of the sediments and contained water, and the natural radioactivity (gamma-ray logs) of the sediments. Descriptive driller's and geologist's logs, when available, were used to supplement the geophysical logs. These logs were particularly useful in determining the base of the water-table aquifers in wells where geophysical logs were not made in the upper parts of the bore holes that included the contact with the underlying Jackson-upper Claiborne confining unit. During the drilling of some wells, the near surface formations were cased off to prevent caving before drilling was continued to total depth.

Driller's and geologist's logs of test holes for water wells drilled by hydraulic rotary methods, when used alone, generally were not considered to be satisfactory for determining the thickness of the confining unit or estimating the thickness of clay beds within the confining unit. The sand and gravel of the water-table aquifers commonly cave into the bore hole and obscure recognition of the top of the Jackson-upper Claiborne confining unit. Because of caving, some driller's and geologist's logs indicate the occurrence of gravel to unreasonable depths. In addition, sand in the upper part of the confining unit commonly is included with the sand and gravel of the alluvium and fluvial deposits. This gives an exaggerated impression of the thickness of these units. The local occurrence of clay and interbedded clay and fine sand in the upper part of the Memphis Sand obscures determination of the base of the confining unit. In addition, very fine or silty fine sand in the upper part of the Memphis Sand commonly is logged as "clay" or "sandy clay."

Sediments encountered in a bore hole and described in driller's logs often are identified by drill penetration rate, drill action, and sample

material recovered from the drilling mud returns. This precludes any further interpretation or correlation of the logs based on visual inspection, as is possible using geophysical logs. In the Memphis area, driller's logs of test holes drilled for water wells are made primarily to record thickness and grain size of the sands that have potential for installing water wells. The logs also record the thickness of sediments that may cause caving or penetration problems while drilling a water well, such as thick intervals of sand and gravel or clay. Consequently, intervals of fine sand, silt, and clay are logged in general terms, such as "sand and clay mixed," "clay with streaks of sand," or "clay." Very fine sand and silt commonly pass through in the drilling mud unnoticed and are difficult to collect and examine unless a special effort is made.

Geophysical logs also have some limitations. The more than 500 geophysical logs in the USGS files were made during a period of about 35 years. Modifications in the instrumentation were made several times, and the geophysical logs were made by many individuals with varying degrees of experience. As a result of problems with the logging equipment and bore-hole conditions, the logs vary greatly in quality. One problem that affects the quality of electric logs are local "stray" electrical currents near high-voltage lines or utility power substations. Factors affecting gamma-ray logs, not easily recognizable, are possible shielding of the logger tool by cement grout and casing in large diameter wells. This may result in clay being recorded with a log trace that might be interpreted as sand. Also, the possible presence of radioactive mineral grains (for example, monazite) may result in some sands being recorded with a log trace that might be interpreted as clay.

The map in this report (plate 1) showing the thickness of the Jackson-upper Claiborne confining unit and aggregate thicknesses of clay beds in the confining unit thicker than 10 feet differs significantly from the small-scale maps in

a previous report by Graham and Parks (1986, fig. 3 and 4). The thickness of the confining unit on plate 1 is shown as much as 150 feet thinner in some areas, and consequently, not as much clay is included in the confining unit in these areas. This difference is the result of new data from many additional geophysical logs made since the previous investigation, a refinement in the definition of the lower boundary of the Jackson-upper Claiborne confining unit, and a re-correlation of the geophysical logs in the USGS files.

For the previous investigation by Graham and Parks (1986), the Jackson-upper Claiborne confining unit was considered to be that interval of sediments between the base of the water-table aquifers and the top of the first prominent sand in the Memphis aquifer. This definition of the lower boundary of the confining unit included thick local intervals of clay or interbedded clay and fine sand in the upper part of the Memphis Sand. These thick intervals of clay or interbedded clay and fine sand are highly variable and may interfinger with sand in the main body of the Memphis aquifer within short lateral distances.

For the present investigation, the Jackson-upper Claiborne confining unit was redefined to be that interval of sediments between the base of the water-table aquifers and the base of the Cook Mountain Formation (top of the Memphis Sand). The base of the Cook Mountain Formation commonly is very difficult to recognize, particularly where it overlies a thick interval of clay or interbedded clay and fine sand in the upper part of the Memphis Sand. However, a determined effort was made to identify this contact. Possible positions of this contact on the geophysical logs were compared as related to an altitude where this contact locally would be expected assuming a relatively low, "normal" (as opposed to extreme) dip of the base of the formation toward the axis of the Mississippi embayment (approximately the Mississippi River). In addition, consideration was given to the expected

local thickness of the underlying Memphis Sand (where geophysical logs are available to provide information to this depth), a range in thickness to be expected for the Cook Mountain Formation, and tentative identification of the overlying Cockfield Formation.

The GC-RASA work indicated that many faults exist in the Memphis area that displace the bases of the Cockfield Formation, Memphis Sand, and the Fort Pillow Sand (Parks and Carmichael, 1989; 1990a,b). During the present investigation, while comparing the expected altitude of the base of the Cook Mountain Formation between individual wells and among groups of wells, displacements in this contact between some areas indicated that many other faults may exist. Vertically, these displacements seemed to be less than 50 to 100 feet, which is comparable to the displacements of the faults identified during the GC-RASA investigation.

Water Table in the Alluvium and Fluvial Deposits

The altitude of the water table in the alluvium and fluvial deposits in the Memphis area is shown in plate 2. This map was prepared using: (1) water levels measured in 60 wells in the fall 1988; (2) water levels from historic records (1944-87) of 39 wells in the USGS files; (3) a composite reduction of 15-minute topographic quadrangles to overlay for topographic control; and (4) altitudes of water levels in the larger perennial streams based on USGS 7 1/2-minute topographic quadrangles published during 1965-71 (only 20-foot-contour-interval data was used). Most water-level data are from wells screened in the alluvium or fluvial deposits. However, several wells were screened in sand in the Cockfield Formation just below the fluvial deposits where the Cockfield and fluvial deposits are in direct hydraulic connection. Water-level data from wells used to prepare the water-table map are given in tables 3 and 4.

Table 4.--Water levels from records of wells screened in the water-table aquifers in the Memphis area, 1944-87

[Latitude and longitude are in degrees, minutes and seconds; USGS local aquifer designations are 111ALVM for the alluvium, 112TRRC for the fluvial deposits (terrace deposits), and 12ACCKF for the Cockfield Formation; less than (<) indicates that in wells that were dry the altitude of the water level is below the altitude of the bottom of the well]

| Well No. | Latitude | Longitude | Altitude of land-surface datum, in feet above sea level | Well depth, in feet | Aquifer | Water level below land-surface datum | | Water-level altitude, in feet above sea level |
|----------|----------|-----------|---|---------------------|---------|--------------------------------------|---------------------|---|
| | | | | | | Depth, in feet | Date of measurement | |
| AP:O-4 | 350744 | 0900556 | 227 | 130 | 111ALVM | 44 | 1976 | 183 |
| AP:O-5 | 351349 | 0900826 | 217 | 61 | 111ALVM | 19 | 1964 | 198 |
| Ms:A-8 | 345741 | 0900717 | 290 | 100 | 12ACCKF | 52 | 1971 | 238 |
| Ms:A-14 | 345930 | 0901331 | 209 | 115 | 111ALVM | 17 | 1971 | 192 |
| Ms:A-55 | 345710 | 0900940 | 209 | 32 | 111ALVM | 14 | 1980 | 195 |
| Ms:A-58 | 345753 | 0901152 | 213 | 112 | 111ALVM | 23 | 1981 | 190 |
| Ms:A-104 | 345827 | 0900844 | 213 | 116 | 111ALVM | 16 | 1970 | 195 |
| Ms:B-54 | 345840 | 0900131 | 275 | 63 | 112TRRC | 16 | 1973 | 259 |
| Ms:B-59 | 345810 | 0900527 | 305 | 105 | 12ACCKF | 46 | 1972 | 259 |
| Sh:H-12 | 350152 | 0901046 | 213 | 56 | 111ALVM | 13 | 1964 | 200 |
| Sh:J-7 | 350053 | 0900133 | 309 | 61 | 112TRRC | 43 | 1958 | 266 |
| Sh:J-149 | 350512 | 0900710 | 245 | 111 | 111ALVM | 50 | 1969 | 185 |
| Sh:J-150 | 350029 | 0900345 | 300 | 61 | 112TRRC | 48 | 1969 | 252 |
| Sh:J-155 | 350203 | 0900349 | 285 | 52 | 112TRRC | 28 | 1966 | 257 |
| Sh:J-182 | 350310 | 0900341 | 280 | 90 | 112TRRC | 30 | 1964 | 250 |
| Sh:J-182 | 350022 | 0900112 | 285 | 70 | 112TRRC | 35 | 1969 | 260 |
| Sh:K-65 | 350617 | 0895526 | 310 | 94 | 112TRRC | dry | 1965 | <216 |
| Sh:K-100 | 350023 | 0895840 | 325 | 43 | 112CKKF | 10 | 1967 | 316 |
| Sh:K-134 | 350023 | 0895738 | 375 | 80 | 112TRRC | 39 | 1964 | 336 |
| Sh:L-94 | 350226 | 0895122 | 352 | 67 | 112TRRC | dry | 1966 | <285 |
| Sh:O-192 | 351246 | 0900390 | 221 | 80 | 111ALVM | 30 | 1964 | 191 |
| Sh:O-215 | 351040 | 0900255 | 248 | 100 | 111ALVM | 55 | 1971 | 193 |
| Sh:O-236 | 351417 | 0900327 | 283 | 107 | 112TRRC | 23 | 1964 | 260 |
| Sh:P-33 | 350807 | 0895924 | 295 | 97 | 112TRRC | 47 | 1944 | 248 |
| Sh:P-105 | 351310 | 0895753 | 300 | 62 | 112TRRC | 35 | 1966 | 265 |
| Sh:Q-94 | 351221 | 0895221 | 295 | 82 | 112TRRC | 43 | 1964 | 252 |
| Sh:Q-79 | 351124 | 0895200 | 291 | 70 | 112TRRC | 50 | 1968 | 241 |
| Sh:Q-85 | 351130 | 0894734 | 320 | 60 | 112TRRC | 36 | 1964 | 264 |
| Sh:Q-93 | 351454 | 0895146 | 290 | 82 | 112TRRC | 17 | 1966 | 273 |
| Sh:Q-126 | 350817 | 0895035 | 250 | 39 | 111ALVM | 34 | 1967 | 216 |

Table 4.--Water levels from records of wells screened in the water-table aquifers
in the Memphis area, 1944-87--Concluded

| Well No. | Latitude | Longitude | Altitude of land-surface datum, in feet above sea level | Well depth, in feet | Aquifer | Water level below land- surface datum | | Water-level altitude, in feet above sea level |
|-------------|----------|-----------|---|---------------------------|---------|---|------------------------|---|
| | | | | | | Depth, in feet | Date of measurement | |
| SH:R-17 | 351340 | 0894334 | 380 | 50 | 112TRC | 40 | 1987 | 340 |
| SH:R-27 | 350834 | 0894320 | 330 | 39 | 112TRC | dry | 1987 | <291 |
| SH:U-33 | 352050 | 0895453 | 275 | 80 | 112TRC | 45 | 1970 | 230 |
| SH:U-34 | 351758 | 0895803 | 300 | 85 | 112TRC | 35 | 1970 | 265 |
| SH:U-40 | 352006 | 0895707 | 245 | 60 | 111ALM | 28 | 1981 | 217 |
| SH:U-43 | 361856 | 0895932 | 301 | 83 | 112TRC | 43 | 1984 | 258 |
| SH:V-13 | 351737 | 0894930 | 305 | 70 | 112TRC | 30 | 1970 | 275 |
| SH:V-14 | 352124 | 0894848 | 320 | 88 | 112TRC | 20 | 1970 | 300 |
| SH:V-18 | 351845 | 0894534 | 318 | 72 | 112TRC | 30 | 1970 | 288 |

Table 3.--Water levels measured in wells screened in the water-table aquifers
in the Memphis area, fall 1988

[Latitude and longitude are in degrees, minutes, and seconds; USGS local aquifer designations are 111ALVM for the alluvium, 112TRRC for the fluvial deposits (terrace deposits), and 124CCKF for the Cockfield Formation]

| Well No. | Latitude | Longitude | Altitude of land-surface datum, in feet above sea level | Well depth, in feet | Aquifer | Water level below land-surface datum | | Water-level altitude, in feet above sea level |
|----------|----------|-----------|---|---------------------|---------|--------------------------------------|---------------------|---|
| | | | | | | Depth, in feet | Date of measurement | |
| Ar:H-3 | 350344 | 0901300 | 211 | 63 | 111ALVM | 25.07 | 11-08-88 | 185 |
| Pa:R-10 | 352130 | 0893614 | 395 | 39 | 112TRRC | 31.30 | 10-18-88 | 364 |
| Sh:J-182 | 350302 | 0900412 | 216 | 29 | 111ALVM | 16.08 | 10-17-88 | 200 |
| Sh:J-183 | 350255 | 0900411 | 280 | 89 | 112TRRC | 33.76 | 10-17-88 | 246 |
| Sh:J-184 | 350107 | 0900838 | 270 | 68 | 112TRRC | 32.01 | 10-17-88 | 238 |
| Sh:J-171 | 350508 | 0900150 | 232 | 71 | 112TRRC | 24.77 | 10-25-88 | 207 |
| Sh:J-172 | 350124 | 0900722 | 292 | 110 | 112TRRC | 53.05 | 10-26-88 | 239 |
| Sh:J-173 | 350554 | 0900222 | 295 | 112 | 112TRRC | 59.30 | 10-20-88 | 236 |
| Sh:J-174 | 350510 | 0900200 | 247 | 44 | 112TRRC | 40.80 | 10-20-88 | 206 |
| Sh:J-175 | 350359 | 0900148 | 226 | 28 | 111ALVM | 13.48 | 10-18-88 | 213 |
| Sh:J-176 | 350343 | 0900123 | 238 | 38 | 111ALVM | 23.10 | 10-21-88 | 215 |
| Sh:J-177 | 350512 | 0900454 | 241 | 53 | 112TRRC | 28.15 | 10-18-88 | 212 |
| Sh:J-178 | 350503 | 0900523 | 223 | 40 | 111ALVM | 36.18 | 10-18-88 | 184 |
| Sh:J-179 | 350728 | 0900317 | 274 | 43 | 112TRRC | 15.57 | 10-21-88 | 258 |
| Sh:K-75 | 350514 | 0895537 | 257 | 91 | 124CCKF | 51.05 | 10-25-88 | 206 |
| Sh:K-123 | 350107 | 0895747 | 342 | 38 | 124CCKF | 23.97 | 10-17-88 | 319 |
| Sh:K-129 | 350024 | 0895715 | 380 | 94 | 124CCKF | 63.77 | 10-17-88 | 316 |
| Sh:K-137 | 350704 | 0895555 | 293 | 86 | 112TRRC | 81.60 | 10-25-88 | 211 |
| Sh:K-144 | 350308 | 0895811 | 266 | 53 | 112TRRC | 49.10 | 10-18-88 | 218 |
| Sh:K-145 | 350416 | 0895847 | 280 | 38 | 112TRRC | 31.35 | 10-18-88 | 229 |
| Sh:K-146 | 350628 | 0895807 | 385 | 88 | 112TRRC | 47.71 | 10-17-88 | 317 |
| Sh:K-147 | 350427 | 0895241 | 273 | 30 | 112TRRC | 20.42 | 10-20-88 | 253 |
| Sh:L-66 | 350621 | 0895051 | 349 | 20 | 112TRRC | 13.28 | 10-17-88 | 336 |
| Sh:O-236 | 351058 | 0900050 | 217 | 31 | 111ALVM | 14.55 | 10-17-88 | 202 |
| Sh:O-244 | 350818 | 0900148 | 252 | 93 | 112TRRC | 18.72 | 10-26-88 | 233 |
| Sh:O-245 | 350915 | 0900052 | 242 | 80 | 112TRRC | 8.30 | 10-26-88 | 234 |
| Sh:O-246 | 350817 | 0900229 | 258 | 56 | 112TRRC | 13.50 | 10-18-88 | 244 |
| Sh:O-247 | 351225 | 0900159 | 271 | 39 | 112TRRC | 36.00 | 10-19-88 | 233 |
| Sh:O-248 | 351240 | 0900308 | 235 | 57 | 112TRRC | 37.41 | 10-19-88 | 198 |
| Sh:P-88 | 350658 | 0895814 | 271 | 59 | 112TRRC | 38.30 | 10-26-88 | 233 |

Table 3.—Water levels measured in wells screened in the water-table aquifers in the Memphis area, fall 1988—Concluded

| Well No. | Latitude | Longitude | Altitude of land-surface datum, in feet above sea level | Well depth, in feet | Aquifer | Water level below land-surface datum | | Water-level altitude, in feet above sea level |
|----------|----------|-----------|---|---------------------|---------|--------------------------------------|---------------------|---|
| | | | | | | Depth, in feet | Date of measurement | |
| Sh:P-107 | 351437 | 0895551 | 295 | 82 | 112TRAC | 30.78 | 10-20-88 | 264 |
| Sh:P-123 | 351115 | 0895833 | 220 | 29 | 111ALVN | 13.78 | 10-19-88 | 206 |
| Sh:P-144 | 351040 | 0895028 | 245 | 74 | 112TRAC | 25.82 | 10-19-88 | 219 |
| Sh:P-148 | 351318 | 0895258 | 321 | 58 | 112TRAC | 21.25 | 10-20-88 | 300 |
| Sh:P-197 | 351430 | 0895732 | 301 | 80 | 112TRAC | 57.54 | 10-25-88 | 243 |
| Sh:O-198 | 350945 | 0895847 | 283 | 40 | 112TRAC | 29.20 | 10-20-88 | 234 |
| Sh:P-199 | 351317 | 0895434 | 320 | 40 | 112TRAC | 31.11 | 10-20-88 | 289 |
| Sh:P-200 | 350916 | 0895808 | 260 | 45 | 112TRAC | 29.85 | 10-18-88 | 230 |
| Sh:O-57 | 350812 | 0894700 | 330 | 80 | 112TRAC | 23.85 | 10-19-88 | 308 |
| Sh:O-86 | 351120 | 0895057 | 299 | 70 | 112TRAC | 59.74 | 10-20-88 | 239 |
| Sh:O-94 | 351111 | 0895125 | 310 | 90 | 112TRAC | 70.72 | 10-26-88 | 239 |
| Sh:O-95 | 350749 | 0895058 | 247 | 36 | 111ALVN | 15.23 | 10-24-88 | 232 |
| Sh:O-98 | 350739 | 0895017 | 254 | 52 | 111ALVN | 35.83 | 10-24-88 | 218 |
| Sh:O-101 | 350741 | 0894909 | 258 | 38 | 111ALVN | 35.84 | 10-24-88 | 222 |
| Sh:O-107 | 350844 | 0895032 | 264 | 44 | 111ALVN | 28.28 | 10-25-88 | 236 |
| Sh:O-114 | 350753 | 0894933 | 260 | 45 | 111ALVN | 44.86 | 10-25-88 | 215 |
| Sh:O-116 | 350833 | 0895140 | 248 | 28 | 111ALVN | 17.08 | 10-26-88 | 229 |
| Sh:O-131 | 351408 | 0895187 | 328 | 59 | 112TRAC | 23.85 | 10-20-88 | 304 |
| Sh:T-21 | 351828 | 0900136 | 362 | 85 | 112TRAC | 60.71 | 10-20-88 | 311 |
| Sh:T-22 | 352132 | 0900112 | 401 | 120 | 112TRAC | 87.86 | 10-20-88 | 313 |
| Sh:U-39 | 352018 | 0895852 | 245 | 53 | 111ALVN | 27.28 | 10-20-88 | 218 |
| Sh:U-61 | 351658 | 0895507 | 300 | 68 | 112TRAC | 27.40 | 10-19-88 | 273 |
| Sh:U-62 | 352045 | 0895713 | 261 | 22 | 112TRAC | 14.25 | 10-19-88 | 247 |
| Sh:U-63 | 351907 | 0895831 | 257 | 38 | 112TRAC | 9.45 | 10-19-88 | 246 |
| Sh:U-64 | 351905 | 0895707 | 280 | 51 | 112TRAC | 32.40 | 10-19-88 | 248 |
| Sh:W-20 | 351702 | 0894033 | 281 | 30 | 112TRAC | 7.45 | 10-19-88 | 274 |
| Sh:W-21 | 351657 | 0893858 | 379 | 38 | 112TRAC | 37.20 | 10-19-88 | 342 |
| Sh:W-22 | 351715 | 0893857 | 318 | 20 | 112TRAC | 10.95 | 10-19-88 | 307 |
| Tp:D-3 | 352524 | 0895848 | 430 | 102 | 112TRAC | 72.12 | 10-21-88 | 358 |
| Tp:F-10 | 352539 | 0894018 | 335 | 20 | 112TRAC | 15.72 | 10-21-88 | 319 |

For the fall 1988, when much of the data were collected, the map (plate 2) probably is accurate to one-half a contour interval (10 feet) where control is abundant and the land surface is not too irregular. In other areas where control is sparse and the land surface is irregular, the map may be accurate to one contour interval (20 feet), depending on the degree of local irregularity and relief. In areas of sparse control, as yet unidentified areas may exist where the water table is depressed because of downward leakage from the water-table aquifers to the Memphis aquifer. In any such areas, of course, the above estimates of map accuracy do not apply. Water levels in the water-table aquifers generally are high in the winter and spring and low in the summer and fall. Therefore, the water-table map (plate 2) is considered to represent low water-level conditions during 1988. Water levels in water-table aquifers fluctuate seasonally at varying rates from place to place.

Long-term records are available for only a few observation wells in the water-table aquifers. Well Sh:P-99 (plate 2), located in a wooded area of Overton Park about 1 mile east of the Mallory well field, is screened in the fluvial deposits. Water levels in this well do not seem to be affected by downward leakage from the water-table aquifers to the Memphis aquifer as indicated by a correlation of changes in water levels with variations in annual precipitation (Graham, 1982). Water-levels in Sh:P-99 fluctuate from about 1 to 8 feet each year. Well Sh:K-75 (plate 2), located in the southern part of the Sheahan well field, is screened in sand in the upper part of the Cockfield Formation just below the base of the fluvial deposits. The water level in this well is affected by leakage from the water-table aquifers to the Memphis aquifer and has declined about 22 feet in 34 years (1951-85) (Graham and Parks, 1986). The early part of the record for this well (1948-50), before pumping was begun from the Memphis aquifer in this area, shows seasonal fluctuations of about 5 feet each year. Later record (1977-85) shows that seasonal

fluctuations are less than "normal" at about 1 to 3 feet each year.

During 1986 and 1987, nine wells were installed in the fluvial deposits in the MLGW well fields (McMaster and Parks, 1988). Monthly water-level measurements in seven of these wells (two were dry) indicate seasonal fluctuations ranging from less than 0.5 foot in well Sh:Q-94 at the McCord well field to about 5 feet in well Sh:J-172 in the Davis well field (plate 2). Well Sh:Q-94 is in or on the margin of a depression in the water table associated with downward leakage in the McCord well field area. Fluctuations in the water table greater than 10 feet within a year probably occur in the alluvium adjacent to the Mississippi River and major tributaries in the Memphis area where water levels are affected by variations in the stages of these rivers.

The mapped area of the water table is not extended into the southeastern and eastern parts of the Memphis area where the Jackson-upper Claiborne confining unit is absent because of a general lack of control. In this area, the water table is in the alluvium beneath the alluvial plains and in the fluvial deposits or the Memphis aquifer beneath the hills, ridges, and valley slopes.

West of the approximate eastern limits of the Jackson-upper Claiborne confining unit occurs a belt of disconnected areas designated "NSST" on the water-table map (plate 2). The phrase "no significant saturated thickness" (NSST), as used in this report, implies that the fluvial deposits are dry or are saturated for only a few inches or feet in the basal part. Mapping of the "NSST" areas is based on (1) a lack of historic records of shallow wells in these areas in the files of the USGS and the TDHE, (2) unsuccessful searches for shallow wells in which to measure water levels or to collect samples for water-quality analyses for this and previous investigations (Graham and Parks, 1986;

McMaster and Parks, 1988), and (3) a few wells installed in the fluvial deposits that were essentially dry (McMaster and Parks, 1988). Upon consideration of the large extent of some of these areas, it is evident that significant refinements can be made to the boundaries.

Because the water-table aquifers generally are unconfined, the configuration of the water table is complex (plate 2). The water table is lower than the land surface (except at springs and seeps), but it generally conforms to the topography. Beneath the hills and ridges, the water table is at higher altitudes and greater depths; whereas beneath the valleys and alluvial plains, it is at lower altitudes and lesser depths. In areas of moderate to high relief, local perched water tables above clay or silt beds in the loess or fluvial deposits add to the complexity of determining the configuration of the principal water-table surface. These perched water tables are higher than the principal water-table surface, commonly occur as only a few feet of saturated material, and probably occur in "pockets" that are not very extensive.

Along and for a few miles east of the bluffs, water in the fluvial deposits locally is confined beneath the loess, and water levels in tightly cased wells rise above the top of the fluvial deposits. During the winter and spring when the Mississippi River is at high or flood stages, water in the alluvium locally is confined beneath fine sediments in the upper part, and water levels in tightly cased wells rise above the top of the lower sand and gravel to near or above land surface.

Recharge to the water-table aquifers is primarily from downward infiltration of precipitation that falls on the land surface and is greatest in the winter and spring months when precipitation is greatest. In the summer and fall months, water levels decline in the water-table aquifers because water discharges to perennial streams and maintains base flows. Under natural conditions, the water table is not lower in altitude than

low stages or base flows in adjacent streams. However, where leakage is taking place from the water-table aquifers to the Memphis aquifer depressions in the water table can be as much as 14 feet below the stage of base flow of adjacent streams, such as in an area adjacent to the Wolf River just north of the Shelby County landfill (M.W. Bradley, USGS, written commun., 1989).

Horizontal flow directions in the water-table aquifers at any particular place can be approximated by drawing flow lines perpendicular to the contours on the water-table map (plate 2). Horizontal flow in the water-table aquifers is from the higher water-table altitudes toward the lower altitudes along these lines.

Potentiometric Surface of the Memphis Aquifer

The altitude of the potentiometric surface of the Memphis aquifer is shown in plate 3. This map was prepared using water-level measurements made in 81 observation and production wells screened in the upper or middle parts of the Memphis aquifer. Methods of measurement included steel-tape measurements in observation wells and nonpumping municipal and industrial wells and airline measurements in MLGW wells that were turned off over night to allow for recovery from pumping levels. Data used to prepare the map of potentiometric surface of the Memphis aquifer are given in table 5.

For the late summer and fall 1988, when the data were collected, the map (plate 3) of the potentiometric surface of the Memphis aquifer probably is accurate to one-half a contour interval (5 feet). However, water levels in the Memphis aquifer fluctuate seasonally. In most of the Memphis area, these seasonal fluctuations are more the result of increases or decreases in pumping from the aquifer rather than to the direct effects of recharge. In general, pumping from the Memphis aquifer is less in the winter

Table 5.--Water levels measured in wells screened in the Memphis aquifer in the Memphis area, late summer and fall 1988

[Latitude and longitude are in degrees, minutes, and seconds; USGS local aquifer designation is 124MMPS for the Memphis Sand]

| Well No. | Latitude | Longitude | Altitude of land-surface datum, in feet above sea level | Well depth, in feet | Water level below land-surface datum | | Water-level altitude, in feet above sea level |
|----------|----------|-----------|---|---------------------|--------------------------------------|---------------------|---|
| | | | | | Depth, in feet | Date of measurement | |
| Ar:C-1 | 350958 | 0901738 | 209 | 622 | 25.24 | 09-16-88 | 184 |
| Ar:H-2 | 350344 | 0901300 | 211 | 800 | 31.70 | 09-16-88 | 179 |
| Ar:O-1 | 351349 | 0900628 | 217 | 497 | 41.63 | 09-16-88 | 175 |
| Ms:B-9 | 345709 | 0900205 | 301 | 392 | 99.98 | 11-16-88 | 201 |
| Ms:D-58 | 345820 | 0895142 | 390 | 220 | 150.35 | 11-16-88 | 240 |
| Fa:A-2 | 352226 | 0893301 | 317 | 365 | 41.75 | 10-04-88 | 275 |
| Sh:H-1 | 350331 | 0900729 | 312 | 348 | 143.73 | 09-13-88 | 168 |
| Sh:H-8 | 350157 | 0900742 | 305 | 822 | 137.10 | 09-13-88 | 168 |
| Sh:J-1 | 350004 | 0900546 | 240 | 334 | 63.66 | 09-16-88 | 176 |
| Sh:J-4 | 350524 | 0900458 | 285 | 302 | 132.40 | 09-13-88 | 153 |
| Sh:J-28 | 350639 | 0900436 | 288 | 306 | 137.13 | 09-13-88 | 151 |
| Sh:J-37 | 350707 | 0900122 | 305 | 810 | 179.82 | 09-13-88 | 125 |
| Sh:J-52 | 350408 | 0900415 | 241 | 498 | 82.66 | 09-13-88 | 148 |
| Sh:J-70 | 350201 | 0900212 | 298 | 681 | 127.72 | 11-08-88 | 170 |
| Sh:J-74 | 350022 | 0900117 | 303 | 398 | 116.26 | 11-08-88 | 185 |
| Sh:J-97 | 350602 | 0900210 | 271 | 378 | 147.90 | 09-13-88 | 123 |
| Sh:J-110 | 350507 | 0900110 | 253 | 390 | 117.90 | 09-13-88 | 135 |
| Sh:J-120 | 350511 | 0900200 | 247 | 452 | 123.30 | 09-13-88 | 124 |
| Sh:J-126 | 350433 | 0900151 | 234 | 285 | 98.40 | 09-13-88 | 136 |
| Sh:J-139 | 350100 | 0900703 | 291 | 486 | 123.20 | 09-13-88 | 168 |
| Sh:J-140 | 350124 | 0900722 | 293 | 853 | 127.72 | 10-05-88 | 165 |
| Sh:J-165 | 350538 | 0900631 | 245 | 400 | 85.61 | 11-08-88 | 159 |
| Sh:K-14 | 350539 | 0895855 | 292 | 440 | 145.22 | 09-12-88 | 147 |
| Sh:K-20 | 350618 | 0895822 | 295 | 220 | 139.53 | 09-12-88 | 155 |
| Sh:K-31 | 350143 | 0895357 | 317 | 178 | 113.84 | 09-12-88 | 203 |
| Sh:K-66 | 350724 | 0895552 | 303 | 499 | 165.70 | 09-15-88 | 137 |
| Sh:K-72 | 350509 | 0895553 | 252 | 292 | 81.22 | 09-12-88 | 171 |
| Sh:K-79 | 350024 | 0895827 | 350 | 370 | 155.91 | 09-12-88 | 194 |
| Sh:K-122 | 350434 | 0895739 | 240 | 210 | 80.94 | 09-12-88 | 159 |
| Sh:K-133 | 350113 | 0895543 | 338 | 210 | 135.53 | 09-12-88 | 202 |
| Sh:K-138 | 350625 | 0895549 | 280 | 898 | 128.60 | 09-15-88 | 151 |
| Sh:K-140 | 350653 | 0895517 | 297 | 824 | 141.50 | 09-13-88 | 156 |
| Sh:L-8 | 350506 | 0894832 | 375 | 305 | 162.05 | 09-15-88 | 213 |
| Sh:L-13 | 350354 | 0895218 | 302 | 275 | 109.97 | 09-12-88 | 192 |
| Sh:L-16 | 350412 | 0894530 | 341 | 220 | 82.24 | 09-12-88 | 249 |
| Sh:L-24 | 350243 | 0895213 | 345 | 427 | 168.30 | 09-13-88 | 177 |
| Sh:L-26 | 350248 | 0895123 | 352 | 432 | 166.70 | 09-13-88 | 185 |
| Sh:L-39 | 350206 | 0895109 | 346 | 349 | 151.95 | 09-15-88 | 194 |
| Sh:L-43 | 350115 | 0895049 | 365 | 185 | 154.54 | 09-12-88 | 210 |
| Sh:L-84 | 350252 | 0894503 | 352 | 135 | 82.68 | 09-12-88 | 259 |

Table 5.--Water levels measured in wells screened in the Memphis aquifer in the Memphis area, late summer and fall 1988--Concluded

| Well No. | Latitude | Longitude | Altitude of land-surface datum, in feet above sea level | Well depth, in feet | Water level below land-surface datum | | Water-level altitude, in feet above sea level |
|----------|----------|-----------|---|---------------------|--------------------------------------|---------------------|---|
| | | | | | Depth, in feet | Date of measurement | |
| Sh:L-64 | 350639 | 0895225 | 305 | 261 | 108.60 | 09-12-88 | 196 |
| Sh:O-1 | 351437 | 0900046 | 229 | 434 | 66.75 | 10-04-88 | 162 |
| Sh:O-29 | 350853 | 0900307 | 265 | 442 | 132.05 | 09-14-88 | 133 |
| Sh:O-48 | 351029 | 0900149 | 240 | 471 | 107.08 | 09-13-88 | 133 |
| Sh:O-115 | 351219 | 0900232 | 272 | 563 | 125.56 | 09-13-88 | 146 |
| Sh:O-204 | 350922 | 0900154 | 257 | 471 | 138.20 | 09-14-88 | 119 |
| Sh:O-238 | 350913 | 0900104 | 251 | 517 | 134.70 | 09-14-88 | 116 |
| Sh:P-1 | 351320 | 0895401 | 300 | 342 | 129.12 | 09-14-88 | 171 |
| Sh:P-8 | 351029 | 0895750 | 244 | 428 | 106.88 | 09-13-88 | 137 |
| Sh:P-22 | 350931 | 0895758 | 245 | 315 | 106.25 | 09-14-88 | 139 |
| Sh:P-37 | 351025 | 0895654 | 252 | 335 | 100.98 | 09-13-88 | 151 |
| Sh:P-61 | 350735 | 0895734 | 288 | 361 | 132.91 | 09-14-88 | 155 |
| Sh:P-76 | 350735 | 0895932 | 287 | 488 | 144.05 | 09-14-88 | 143 |
| Sh:P-85 | 351101 | 0895240 | 293 | 319 | 121.82 | 10-04-88 | 171 |
| Sh:P-96 | 351435 | 0895300 | 312 | 456 | 125.62 | 09-19-88 | 186 |
| Sh:P-131 | 351420 | 0895706 | 247 | 404 | 106.20 | 09-14-88 | 141 |
| Sh:P-134 | 351440 | 0895723 | 301 | 411 | 155.60 | 09-14-88 | 145 |
| Sh:P-143 | 351058 | 0895739 | 228 | 442 | 90.39 | 09-13-88 | 139 |
| Sh:P-146 | 350926 | 0895949 | 255 | 512 | 130.50 | 09-14-88 | 125 |
| Sh:Q-1 | 350900 | 0894822 | 330 | 384 | 108.24 | 09-16-88 | 222 |
| Sh:Q-60 | 351224 | 0895215 | 285 | 491 | 126.73 | 09-14-88 | 158 |
| Sh:Q-63 | 351124 | 0895143 | 309 | 506 | 140.45 | 09-14-88 | 169 |
| Sh:Q-69 | 351203 | 0895129 | 281 | 477 | 104.45 | 09-14-88 | 177 |
| Sh:Q-71 | 351045 | 0895151 | 302 | 406 | 131.40 | 09-14-88 | 171 |
| Sh:Q-76 | 351359 | 0894829 | 310 | 430 | 86.50 | 09-14-88 | 224 |
| Sh:Q-81 | 351325 | 0895049 | 317 | 509 | 125.16 | 09-14-88 | 192 |
| Sh:Q-84 | 351347 | 0894952 | 325 | 200 | 121.80 | 09-14-88 | 203 |
| Sh:Q-125 | 350817 | 0895035 | 250 | 100 | 41.73 | 09-19-88 | 208 |
| Sh:R-5 | 351350 | 0894425 | 395 | 330 | 160.89 | 09-15-88 | 234 |
| Sh:R-15 | 351239 | 0893943 | 342 | 150 | 78.20 | 09-15-88 | 264 |
| Sh:R-29 | 350835 | 0894341 | 318 | 585 | 72.20 | 09-13-88 | 243 |
| Sh:U-2 | 352113 | 0895709 | 269 | 440 | 63.41 | 10-04-88 | 206 |
| Sh:U-7 | 352032 | 0895344 | 265 | 411 | 55.85 | 09-15-88 | 209 |
| Sh:U-15 | 351602 | 0895829 | 240 | 431 | 96.19 | 09-19-88 | 144 |
| Sh:U-22 | 351737 | 0895749 | 300 | 387 | 127.97 | 09-15-88 | 172 |
| Sh:U-25 | 351641 | 0895713 | 248 | 430 | 79.16 | 09-15-88 | 169 |
| Sh:V-7 | 351544 | 0894616 | 278 | 300 | 43.67 | 09-15-88 | 234 |
| Sh:V-9 | 352012 | 0895038 | 273 | 445 | 58.45 | 09-15-88 | 215 |
| Sh:W-3 | 351750 | 0893943 | 279 | 221 | 21.83 | 09-15-88 | 257 |
| Sh:W-18 | 351923 | 0894228 | 364 | 499 | 118.20 | 09-15-88 | 248 |
| Tp:E-12 | 352445 | 0894944 | 337 | 470 | 106.83 | 11-17-88 | 230 |

and spring, and water levels rise. Beginning in early summer, the demand for water increases and pumping increases. Pumping continues to increase through the summer, and water levels continue to decline. Low water levels are reached in the late summer or fall. Therefore, the map of the potentiometric surface of the Memphis aquifer (plate 3) is considered to represent low water-level conditions during 1988.

Because of variations in amounts of water pumped in different areas and changes in pumping patterns in and among MLGW well fields, the effect of pumping on water levels varies spatially. The amount of local seasonal fluctuation can only be determined from the records of observation wells at particular places. An indication of the magnitude of water-level fluctuations in the Memphis aquifer is provided by the long-term record of a few principal observation wells in areas away from MLGW well fields. In well Fa:R-2 (plate 3), located in northwestern Fayette County, Tenn., water levels fluctuate about 1 to 1.5 feet each year. In well Sh:Q-1 (plate 3), located in southeastern Shelby County, Tenn., water levels fluctuate about 2 to 3 feet each year. In well Sh:P-76 (plate 3), located in midtown Memphis, water levels fluctuate about 7 to 17 feet each year. In contrast, water levels in Sh:O-179, an observation well located on a MLGW well lot with production well Sh:O-204 (plate 3), fluctuate as much as 45 feet each year. Near the Mississippi River, water levels in wells screened in the Memphis aquifer may rise as a result of loading effects from sustained high stages of the Mississippi River, particularly during winter and spring flood events (Parks and others, 1985).

Outside of the Memphis area where the Memphis aquifer is confined, the potentiometric surface slopes gently westward toward the axis of the Mississippi embayment, and the water moves slowly in that direction (Parks and Carmichael, 1990c). In the Memphis area, a major depression has developed in the potentiometric surface as a

result of the long-term (1886-present) pumping at municipal and industrial well fields. Superimposed on this major depression are localized cones of depression centered at municipal and industrial well fields (plate 3). The velocity of water moving into the major depression is relatively slow but increases considerably in the proximity of pumping centers (Bell and Nymann, 1968).

In addition to seasonal fluctuations, water levels in the Memphis aquifer are also affected by long-term changes. A few principal observation wells in areas away from MLGW well fields also give an indication of the magnitude of these changes. Well Fa:R-2 (plate 3) is the farthest of these wells from the center of the major depression in the potentiometric surface at Memphis. The water level in Fa:R-2 has declined about 3 feet in 39 years (1949-88), an average rate of less than 0.1 foot per year. Well Sh:Q-1 (plate 3) is at an intermediate distance between Fa:R-2 and the center of the major depression. The water level in Sh:Q-1 has declined about 34 feet in 48 years (1940-88), an average rate of about 0.7 foot per year. Well Sh:P-76 (plate 3) is near the center of the major depression. The water level in Sh:P-76 has declined about 78 feet in 58 years (1928-88), an average rate of about 1.3 feet per year.

Recharge to the Memphis aquifer from precipitation generally occurs along the broad outcrop or subcrop belt where it is at or near the surface across western Tennessee (Grabbe, 1982). This outcrop or subcrop belt extends from the Memphis area east and southeast of the proximate eastern limits of the Jackson-upper Claiborne confining unit (plate 3). In this area the Memphis aquifer generally is unconfined and is covered by the alluvium and fluvial deposits. Therefore, recharge is by downward infiltration of water from precipitation through the alluvium and fluvial deposits into the Memphis aquifer.

Where that aquifer is confined and head differences are favorable, a component of recharge locally enters the Memphis aquifer by downward leakage from the water-table aquifers or the Jackson-upper Claiborne confining unit. Conditions for downward leakage are particularly favorable where the confining unit is thin or absent or where leakage is induced by intense pumping from the Memphis aquifer, as in the vicinity of MLGW well fields (Graham and Parks, 1986). Conditions for downward leakage also may be favorable where the Cook Mountain Formation has been displaced vertically by faults, leaving sands in the Cockfield Formation and the Memphis aquifer in direct hydraulic connection (Parks and others, 1985).

Horizontal flow direction in the Memphis aquifer at any particular place can be approximated by drawing flow lines perpendicular to the potentiometric contours on plate 3. In general, horizontal flow is toward the center of the major depression, which is deepest in the area of the Mallory and Allen well fields. Locally, ground water also flows towards smaller cones of depression at other MLGW and industrial well fields.

POTENTIAL SOURCES OF CONTAMINATION OF THE MEMPHIS AQUIFER

Forty-four sites where contaminants have been detected in the water-table aquifers, five municipal wells where contaminants have been detected in the Memphis aquifer, and areas where the Jackson-upper Claiborne confining unit is thin or absent are shown in plate 4. Included in the 44 sites on plate 4 are the locations of several abandoned or inactive waste-disposal dumps or landfills where contaminants were detected in the water-table aquifers during previous investigations of the USGS (Parks and others, 1982; Graham, 1985; M.W. Bradley, USGS, written commun., 1989). Included also are two private wells (Sh:J-155 and Sh:Q-93) and

an industrial well (Sh:O-215) where contaminants have been detected in the water-table aquifers during another previous investigation of the USGS (McMaster and Parks, 1988).

Information concerning the 44 sites where contaminants have been detected in the water-table aquifers are given in table 6. Most of the information concerning 33 of these sites was obtained from records supplied by the offices of the appropriate Federal and State regulatory agencies, as follows:

U.S. Environmental Protection Agency
Waste Management Division
Site Investigation and Support Branch
345 Courtland Street N.E.
Atlanta, GA 30365

Tennessee Department of Health
and Environment
Division of Groundwater Protection
T.E.R.R.A. Building - 5th floor
150 Ninth Avenue N.
Nashville, TN 37219-5404

Tennessee Department of Health
and Environment
Division of Solid Waste Management
Room 1101, State Office Building
170 Mid America Mall N.
Memphis, TN 38103

Tennessee Department of Health
and Environment
Division of Superfund
Southwest Tennessee Regional Office
295 Summar Avenue
Jackson, TN 38301-3984

Tennessee Department of Health
and Environment
Division of Underground Storage Tanks
200 Doctors Building
706 Church Street
Nashville, TN 37247-4101

Table 6.--Sites where synthetic organic compounds or relatively high concentrations of inorganic trace constituents have been detected in the water-table aquifers in the Memphis area

[Sources: U.S. Environmental Protection Agency (EPA); Tennessee Department of Health and Environment, Division of Superfund (DSF), Division of Solid Waste Management (DSWM), and Underground Storage Tank Program (UGST); map numbers refer to plate 4 of this report]

| Map Number | Latitude | Longitude | Type of site | Contaminants detected | Source of information |
|------------|----------|-----------|---------------------------|---|---------------------------|
| 1 | 352006 | 0895707 | Millington Dump/Landfill | PCB's; cadmium | Parks and others (1982) |
| 2 | 352018 | 0895854 | Old Ordnance Dump | chlordane, endrin, mirex, toxaphene | Do. |
| 3 | 352027 | 0895244 | underground storage tank | benzene, toluene, xylenes | UGST |
| 4 | 352130 | 0893614 | industrial waste burial | 2-methylphenol, phenol; chromium | EPA |
| 5 | 351758 | 0898334 | industrial spill | pesticides | DSWM |
| 6 | 351848 | 0893858 | underground storage tank | product (gasoline) | UGST |
| 7 | 351755 | 0893750 | underground storage tank | benzene, trans-1,2-dichloroethene, tetrachloroethene, toluene, | Do. |
| 8 | 351847 | 0893753 | industrial spill | trichloroethene, vinyl chloride, xylenes acetone, benzene, BHC, 2-butanone, carbon disulfide, chloroform, 4,4-DDE, 4,4-DDT, 1,1-dichloroethylene, 1,2-dichloroethylene, trans-1,2-dichloroethylene, endosulfan, heptachlor, tetrachloroethylene, toluene, trichloroethylene, vinyl chloride | DSF |
| 9 | 351454 | 0895148 | private well Sh:0-93 | aldrin, DDT, endosulfan, perthane | McMaster and Parks (1988) |
| 10 | 351230 | 0800245 | industrial spill | chromium | DSF |
| 11 | 351228 | 0800158 | underground storage tank | gasoline "floating" on ground water | UGST |
| 12 | 351300 | 0895810 | underground storage tank | benzene, toluene, xylenes | Do. |
| 13 | 351317 | 0895435 | underground storage tank | benzene, toluene, ethylbenzene/xylenes | Do. |
| 14 | 351215 | 0895131 | underground storage tank | benzene, toluene, xylenes | Do. |
| 15 | 351181 | 0895831 | underground storage tank | benzene, toluene, xylenes | Do. |
| 16 | 351133 | 0895342 | underground storage tank | benzene, toluene, xylenes | Do. |
| 17 | 351050 | 0900040 | Selleue Dump | chlordane, dieldrin, endrin, heptachlor epoxide, PCB's, phenol; arsenic, barium | Parks and others (1982) |
| 18 | 351110 | 0895832 | North Hellywood Dump area | chlordane, chlordane, cyanide, DDT, dieldrin, dieldrin, diethyl phthalate, dimethyl phthalate, di-n-octyl phthalate, endrin, heptachlor, heptachlor epoxide, mirex, PCB's, phenol, 2,4,5-T; arsenic, barium, cadmium | Do. |
| 19 | 351005 | 0895150 | underground storage tanks | benzene, toluene, xylenes | Graham (1985) |
| 20 | 351040 | 0900255 | industrial well Sh:0-215 | barium | Do. |
| 21 | 350943 | 0895847 | underground storage tank | acrolein, benzene, 1,2-dichloroethane, ethylbenzene, toluene | UGST |
| 22 | 350915 | 0895808 | industrial spill | 1,1,1-trichloroethane | DSWM |
| 23 | 350858 | 0895755 | underground storage tank | benzene, ethylbenzene, toluene, xylenes | UGST |
| 24 | 350850 | 0895626 | underground storage tank | benzene, ethylbenzene, toluene, xylenes | Do. |
| 25 | 350852 | 0900238 | underground storage tank | benzene, toluene, xylenes | Do. |
| 26 | 350852 | 0900238 | underground storage tank | benzene, toluene, xylenes | Do. |

Table 6.--Sites where synthetic organic compounds or relatively high concentrations of inorganic trace constituents have been detected in the water-table aquifers in the Memphis area--Concluded

| Map Number | Latitude | Longitude | Type of site | Contaminants detected | Source of information |
|------------|----------|-----------|--|---|--------------------------------|
| 26 | 350817 | 0900229 | underground storage tank | benzene, toluene, xylenes | UGST |
| 27 | 350729 | 0900310 | underground storage tank | benzene, ethylbenzene, toluene, xylenes | Do. |
| 28 | 350755 | 0905050 | Shelby County Landfill | benzene, chlorobenzene, 1,4-dichlorobenzene, 1,1-dichloroethane, cis-1,2-dichloroethane, trans-1,2-dichloroethane, ethylbenzene, methylene chloride, tetrachloroethylene, trichloroethane, vinyl chloride, xylenes; arsenic, barium, chromium, lead | UGOS DSM |
| 29 | 350821 | 0905327 | underground storage tank | ethylbenzene, xylenes; other unidentified volatile organic compounds | UGST |
| 30 | 350828 | 0905302 | underground storage tank | benzene, ethylbenzene, toluene, xylenes | Do. |
| 31 | 350852 | 0900017 | military and industrial waste disposal | purgeable organic compounds | DSM |
| 32 | 350800 | 0900703 | industrial waste disposal | benzene, ethylbenzene, tetrachloroethylene, 1,1,1 trichloroethane, trichloroethylene, toluene, vinyl chloride, xylenes | Do. |
| 33 | 350507 | 0900458 | industrial spill | petroleum products | UGST |
| 34 | 350504 | 0900202 | industrial spill | benzene, chlorobenzene, chloroform, 1,1-dichloroethane, 1,2-dichloroethane, ethylbenzene, methylene chloride, toluene, xylenes | DSM |
| 35 | 350416 | 0905847 | underground storage tank | benzene, toluene, xylenes | UGST |
| 36 | 350442 | 0905307 | underground storage tank | petroleum hydrocarbons | Do. |
| 37 | 350405 | 0900255 | Brooks Road Dump | chloridene, cyanide, DDT, diazinon, dieldrin, endrin, heptachlor, heptachlor epoxide, phenol | Parks and others (1982) |
| 38 | 350359 | 0900148 | underground storage tank | petroleum hydrocarbons, including diesel fuel | UGST |
| 39 | 350343 | 0900123 | underground storage tank | gasoline "floating" on ground water | Do. |
| 40 | 350308 | 0905811 | underground storage tank | benzene, ethylbenzene, toluene, xylenes | Do. |
| 41 | 350203 | 0900349 | private well Sh:J-155 | aldrin, DDT, endosulfan, perthane, 1,1,1-trichloroethane | McMaster and Parks (1988) |
| 42 | 350116 | 0900028 | underground storage tank | benzene, toluene, xylenes (as total BTX) | UGST |
| 43 | 350100 | 0905745 | Jackson Pit Dump | chloridene, chlorobenzene, chloroethane, chloroform, diazinon, 1,4-dichlorobenzene, 1,1-dichloroethane, cis-1,2-dichloroethane, heptachlor, methyl parathion, methylene chloride, PCB's, phenol, tetrachloroethane, trichloroethane, toluene; arsenic, lead | Parks and others (1982) DSF |
| 44 | 350230 | 0904125 | industrial spill | chlorinated hydrocarbons | DSF |

Because of the voluminous records in the files of these agencies that concern both the regulatory and investigative aspects of the sites, personnel with investigative responsibility were asked to assist by identifying those sites where contaminants have been detected in the ground water and to provide an analysis (or analyses) showing the contaminants detected. Many of the sites are still under investigation, so the information provided was from the data available at the time (1987-89).

In the selection of sites, consideration generally was not given to the degree and extent of contamination or the regulatory aspects of the definition of the word "contamination." If synthetic organic compounds have been detected in the water-table aquifers (or perched water tables), then the ground water was considered to be contaminated. Maximum contaminant levels (MCL) in drinking water have been established for some synthetic organic compounds by the U.S. EPA, but only recommended maximum contaminant levels exist for others (U.S. Environmental Protection Agency, 1986). Consequently, the presence of synthetic organic compounds in the water-table aquifers was considered an indication of contamination inasmuch as man-made organic compounds do not occur naturally in ground water. Because trace inorganic constituents occur naturally in the ground water of the Memphis area in small concentrations (Brahana and others, 1987; McMaster and Parks, 1988), these constituents are included in table 6 only if they exceeded the MCL's established by the U.S. EPA. For the trace inorganic constituents included in table 6, the MCL's are arsenic (50 micrograms per liter ($\mu\text{g/L}$)), barium (1,000 $\mu\text{g/L}$), cadmium (10 $\mu\text{g/L}$), chromium (50 $\mu\text{g/L}$), and lead (50 $\mu\text{g/L}$).

Some of the 41 sites (excluding wells Sh:J-155, Sh:O-215, and Sh:Q-93) have only one monitoring well, but others have many. Most of these monitoring wells generally are shallow (commonly less than 50 feet deep) and are

screened in the upper part of the water-table aquifer, although some may be screened in perched water-table zones. Some wells have been sampled only once, but others have been sampled several times. The analyses, which were made by various commercial or government laboratories, generally are limited to reporting the synthetic organic compounds or trace inorganic constituents that are specifically important to assessing contamination based on the type of site under investigation. For example--benzene, toluene, and xylene generally are analyzed for assessing ground-water contamination at leaky underground storage tanks (table 6). These volatile organic compounds are common components of gasoline. Reported concentrations of contaminants range from trace amounts of pesticides just above the detection limits (in micrograms per liter) at some abandoned dumps to several feet of "product" floating on the ground-water surface at some industrial or underground-storage-tank sites.

Thousands of potential point and nonpoint sources of contamination of the water-table aquifers exist in the Memphis area. These sources include abandoned dumps, active and inactive landfills, underground storage tanks industries and commercial establishments that process or use hazardous chemicals, demolition disposal sites, sewers, septic tanks, and local spills. Locations of abandoned dumps and active landfills in Shelby County, Tenn., that were known in 1975 are given in a report by Parks and Lounsbury (1976). Early in the present investigation, a list of 1,679 underground storage tanks in Shelby County was obtained from the TDHE, Division of Ground Water Protection. Personnel with that agency estimated that the list included about 70 percent of the underground storage tanks in the county, which were still being inventoried (John Fox, Jr., TDHE oral commun., 1987). In addition, many other sites where contamination of the soils or surface waters has been detected are included in the list of the U.S. EPA and TDHE. However,

contamination of the ground water presently is known at these sites, or investigations of the sites have not progressed to the stage where ground-water contamination has been determined.

All of the above sources have potential for contaminating the water-table aquifers. Work in determining the degree and extent of contamination of the water-table aquifers is still in the beginning stage, although much progress has been made in recent years. The Memphis aquifer is a step removed from these potential sources of contamination inasmuch as under "natural" conditions contaminants must enter the water-table aquifers before they enter the Memphis aquifer.

INDICATIONS OF DOWNWARD LEAKAGE TO THE MEMPHIS AQUIFER

Indications that downward leakage from the water-table aquifers to the Memphis aquifer is widespread were provided by Graham and Parks (1986). This previous investigation used a multi-aspect approach that included studies of: (1) areal variations in the thickness of the Jackson-upper Claiborne confining unit that indicated areas where the confining unit is thin or absent, (2) the configuration of the water table that indicated an anomaly in this surface where the water table is depressed because of downward leakage, (3) differences in hydraulic head between the water-table and Memphis aquifers that indicated a general downward gradient, (4) areal and local variations in carbon-14 and tritium concentrations in water from the upper part of the Memphis aquifer that indicated relatively recent water has entered the Memphis aquifer, and (5) deviations from the normal geothermal gradient that indicated the coolest temperatures in areas of intense pumping are at greater depths (as a result of leakage) than in areas away from this pumping. The present investigation, which includes detailed studies of

the thickness of the confining unit and the configuration of the water table, has resulted in much refinement of the previous work and identification of several additional areas where leakage is or may be occurring.

Graham and Parks (1986) indicated four general areas in the Memphis urban area (as defined in that report) where the Jackson-upper Claiborne confining unit is thin or absent and a high potential for downward leakage exists. These areas are: (1) in the eastern part along and north of the Wolf River, (2) in the southeastern part along Nonconnah Creek, (3) in the south-central part along Nonconnah and Johns Creeks in the vicinity of the southern part of Sheahan well field, and (4) in the western part in a belt along the Mississippi River. The areas in the eastern and southeastern parts along the Wolf River and Nonconnah Creek are extensions of the outcrop or subcrop belt of the Memphis aquifer into the Memphis urban area. The boundaries of these areas are refined on the maps prepared for the present investigation as the eastern limits of the Jackson-upper Claiborne confining unit (plates 1-4).

The area in a belt along the Mississippi River where the confining bed is shown to be thin or absent by Graham and Parks (1986, figs. 3 and 21) was significantly modified during the present investigation. The extension of the belt north of Memphis where the confining bed was thought to be thin or absent was removed from the present map showing the thickness of the Jackson-upper Claiborne confining unit (plate 1). This modification of the northern extension of the belt is based on a re-correlation of geophysical logs partly as a result of a new geophysical log made in well Sh:O-115 (plate 1). No new information from geophysical logs is available for the southern part of the belt. However, a study by Richardson (1989) indicates that water-quality changes in several wells in the Davis well field are the result of leakage of water from the Mississippi River alluvium to the Memphis aquifer.

Richardson concluded that the confining unit is thin or absent beneath the alluvium west of the Davis well field or that a "window" exists in the confining unit.

The area in the south-central part of the Memphis urban area along Nonconnah and Johns Creeks in the vicinity of the southern part of the Sheahan well field has the most information to indicate that downward leakage from the water-table aquifers to the Memphis aquifer is occurring. Indications given by Parks and Graham (1986) include: (1) a loss of water along the stretch of Nonconnah Creek south and southeast of the southern part of Sheahan well field, (2) an adjacent area to the southeast where the confining unit is thin or absent, (3) a depression in the water-table surface, (4) long-term water-level declines in shallow observation well Sh:K-75, (5) carbon-14 and tritium concentrations indicating the presence of relatively recent water in the Memphis aquifer, (6) a distorted geothermal gradient with the coolest temperature at a depth of 230 feet below land surface, and (7) head differences between the water-table and Memphis aquifers favoring downward movement of water. The area where the confining unit is thin or absent is shown on plate 1 as the large area southeast of the southern part of Sheahan well field and west of Lichterman well field. This area is enlarged from the area shown by Graham and Parks (1986, fig. 3), based partly on a new geophysical log of the test hole for well Sh:K-148 in the western part of Lichterman well field (plate 1). The depression in the water-table aquifer, shown on plate 2 as the area extending from the southern part to the northern part of Sheahan well field, also is enlarged from the area shown by Graham and Parks (1986, fig. 7), based partly on the water level in new observation well Sh:K-137.

New information from test holes for wells drilled in the northern part of Sheahan well field since the Graham and Parks report (1986) indicates an area west of that part of the well field

with a high potential for leakage. The Jackson-upper Claiborne confining unit in this area is shown by Graham and Parks (1986, fig. 3) to be about 150 feet thick. The stratigraphy of the Sheahan well field is complex and faults may exist. The tops of at least two sand beds in the geologic sequence can be interpreted on geophysical logs as being the top of the Memphis Sand and two clay beds can be interpreted as being the Cook Mountain Formation. The top of the shallower clay bed underlies the fluvial deposits and varies in thickness, but it commonly is thin. The deeper clay bed is thick and seems to be persistent throughout the area. Consequently, during the Graham and Parks investigation, the lower clay was interpreted to be the Cook Mountain Formation and the underlying (deeper) sand to be at the top of the Memphis Sand. During 1986 and 1987, test holes for several new MLGW production wells were drilled in the northern part of Sheahan well field. The geophysical and driller's logs for the test hole for well Sh:K-142 (plate 1) indicate that the confining unit, if present, consisted of only about 6 feet of sandy clay (or clayey sand) overlying a thick interval of sand in the Memphis Sand. In addition, the geophysical log of well Sh:K-141 (plate 1), drilled at the Tennessee Earthquake Information Center for installation of a seismic instrument, indicated that the Cook Mountain Formation may be the shallower clay and that the top of the Memphis Sand may be at the top of the shallower sand. Based on this new information, a re-correlation of the geophysical logs available for the northern part of the Sheahan well field and surrounding areas indicates that the confining unit is thin or absent in an area west of the northern part of the well field (plate 1). This area of high potential for leakage is consistent with a depression in the water table as indicated by a deeper than expected water level in observation well Sh:K-137 (plate 2) installed at the Sheahan pumping station in 1986. In addition, in an area between the Sheahan and Allen well fields (defined by the 160-foot contour on plate 3), the potentiometric surface of the

Memphis aquifer is higher than would be expected when considering the intense pumping at these well fields. This "high" in the potentiometric surface may be the result of leakage from the water-table aquifers in the area where the confining unit is thin or absent (plate 1).

A new area of leakage from the water-table aquifers to the Memphis aquifer identified since the Graham and Parks (1986) report is just north and northeast of the Shelby County landfill (plate 4). During an investigation of the area to satisfy requirements of the TDHE, Division of Solid Waste Management, for expansion of the landfill, water levels in auger holes and observation wells drilled in the vicinity of the landfill indicated that the water table is depressed to levels below low-flow stages of the nearby Wolf River (J.L. Ashner, TDHE, oral commun., 1986). Subsequently, the USGS investigated the geohydrology of the area with emphasis on determining the effects of vertical leakage and leachate migration on the ground-water quality. The results of the investigation indicate that (1) the depression in the water table is centered just north or northeast of the landfill and is as much as 14 feet below the low-flow stages of the Wolf River, (2) a downstream loss of water from the Wolf River occurs along the stretch that flows past the landfill, (3) leachate from the landfill has entered the Wolf River alluvium and is moving northward toward the depression in the water table, and (4) uncontaminated water from the alluvium has entered the Memphis aquifer (M.W. Bradley, USGS, written commun., 1989). The map of the thickness of the Jackson-upper Claiborne confining unit indicates an area in the vicinity and east of the landfill where the confining unit is thin or absent. This is based partly on the geophysical log of well Sh:Q-90 drilled for the landfill investigation (plate 1). A depression in the water table is defined by the 220-foot contour on the map of the altitude of the water table in the alluvium and fluvial deposits. The center of this depression is near well Sh:Q-128 installed for the landfill investigation (plate 2).

New areas identified during the present investigation where the Jackson-upper Claiborne confining unit is thin or absent or where depressions are in the water table include: (1) in the southeastern part of Lichterman well field based on the geophysical log for well Sh:L-102 (plate 1), (2) in the vicinity of McCord well field based on an area east of the well field along Fletcher Creek where the confining bed is interpreted to be thin or absent (plate 1) and the lower than expected water levels in wells Sh:Q-86 and Sh:Q-94 (plate 2), (3) south of Nonconnah Creek and between Interstate 55 and U.S. Highway 78 based on the geophysical log of well Sh:K-143 (plate 1) and the lower than expected water levels in wells Sh:K-144 and Sh:K-145 (plate 2), and (4) west of Olive Branch based on the geophysical log of well Ms:C-17 (plate 1). These newly identified areas have a high potential for downward leakage from the water-table aquifers to the Memphis aquifer.

POTENTIAL FOR CONTAMINATION OF THE MEMPHIS AQUIFER

A sequence of events that would result in contamination of the Memphis aquifer under "natural" conditions is: (1) contaminants enter the water-table aquifers; (2) contaminants are transported downward through the Jackson-upper Claiborne confining unit or enter the Memphis aquifer directly in areas where the confining unit is absent; and (3) contaminants persist despite the effects of various physical, chemical, and biological processes, including dilution and adsorption. Other events that would result in contamination of the Memphis aquifer include: (1) contaminated water in the water-table aquifers leaks downward through faulty well seals (cement grout or backfill material) outside the casings of wells screened in the Memphis aquifer and (2) contaminants from spills, vandalism, or illegal waste disposal enter the casings of wells screened in the Memphis aquifer. ---

Based on "natural" conditions, the potential for contamination of the Memphis aquifer generally is least in the northern and west-central parts of the Memphis area where the confining bed is thickest and contains much clay, and is greatest in the southern and eastern parts where the confining bed is thin or absent (plate 1). The Jackson-upper Claiborne confining unit is as much as 375 feet thick in the northwestern part of the Memphis area in well Sh:T-18 (plate 1). In this area, the confining unit consists of fine sand, silt, clay, and lignite in the Jackson, Cockfield, and Cook Mountain Formations. The confining unit is absent in the southeastern part of the Memphis area in wells Sh:M-17, Sh:M-43, and Sh:R-10 (plate 1). Aggregate thickness of clay beds within the confining unit thicker than 10 feet is greatest in the west-central part of the Memphis area. In the Mallory well field, an aggregate thickness of clay beds thicker than 10 feet makes up 246 feet of the total thickness of 255 feet for the confining unit in well Sh:O-184 (plate 1).

Sites where the water-table and Memphis aquifers are reported to contain contaminants and areas where the Jackson-upper Claiborne confining bed is thin or absent are shown on plate 4. Thus far, 44 sites have been identified where contaminants have been detected in the water-table aquifers (table 6). Many of these sites, which are potential sources of contamination of the Memphis aquifer, are located in areas where the direction of ground-water flow in the Memphis aquifer is toward cones of depression at MLGW well fields (plate 3). Based on present (1989) information, the Allen well field has the most sites in close proximity. Some sites also are located in areas where the confining unit is thin or absent or in areas where the direction of flow in the water-table aquifers is toward these areas (plate 2). It is likely that additional sites where the water-table aquifers are contaminated will be found as monitoring and investigations continue.

Thus far, only two sites have been found where volatile organic compounds have been detected in the Memphis aquifer—wells Sh:J-119 (398 feet deep), Sh:J-120 (452 feet) and Sh:J-121 (436 feet) in the Allen well field at Memphis and wells Sh:M-31 (324 feet) and Sh:M-35 (287 feet) in the west well field at Collierville (plate 4). Volatile organic compounds detected in wells Sh:J-119 and Sh:J-120 are: 1,1-dichloroethane, 1,1-dichloroethylene, cis-1,2-dichloroethylene, 1,2-dichloropropane, 1,2-dichloroethane, trichloroethylene, and vinyl chloride. Concentrations of these compounds ranged from 0.02 to 5.52 $\mu\text{g/L}$ in these two wells—the highest concentration was for 1,2-dichloroethane detected in a sample collected from well Sh:J-120. The concentrations of the seven compounds in a sample from this well totaled about 11 $\mu\text{g/L}$ (J.H. Webb, MLGW, written commun., 1988). Well Sh:J-120 is about 650 feet and well Sh:J-119 is about 2,000 feet from the nearest known potential source of contamination in the water-table aquifers (site 34, plate 4; table 6). The wells in the Allen well field are in an area where the confining unit is as thin as 82 feet and contains as little as 68 feet of aggregate thickness of clay beds thicker than 10 feet, based on the geophysical log of well Sh:J-119 (plate 1). Driller's logs for wells Sh:J-120 and Sh:J-121 provide no indication that a sand "window" exists in this area, although it is possible.

The volatile organic compound detected in water from wells Sh:M-31 and Sh:M-35 at Collierville is trichloroethylene. Since August 1988, these two municipal wells have been sampled periodically to determine concentrations of trichloroethylene. Concentrations detected have ranged from 1.6 to 25.0 $\mu\text{g/L}$ with the highest concentration in a sample collected from well Sh:M-35 (B.J. Maness, TDHE, written commun., 1989). These wells are about 2,000 feet from the nearest known potential source of contamination (site 44, plate 4; table 6). The wells at Collierville are east of the eastern limits of the Jackson-upper Claiborne confining unit.

(plate 4). However, the driller's logs for wells Sb:M-31 and Sb:M-35 indicate at least 60 feet of clay in the Memphis aquifer separating the water-table aquifers from sand in the Memphis aquifer.

The facts that these volatile organic compounds (1) have been transported through the Jackson-upper Claiborne confining unit or through (or around) relatively thick intervals of clay in the Memphis aquifer, (2) have persisted despite the effects of various physical, chemical, and biological processes, and (3) have been detected in wells ranging from 287 to 452 feet in depth at distances as far as 2,000 feet from the nearest known potential sources of contamination in the water-table aquifers, emphasize the vulnerability of the Memphis aquifer to contamination.

Recently (1987-88), MLGW began a yearly routine sampling of all of their production wells in the Memphis aquifer and analytical "scans" of the water to determine the presence of organic compounds. If unidentified organic compounds are detected, a follow-up analysis is conducted to identify specific compounds. The results of the first sampling of all production wells indicated that only the water from the three wells in the Allen well field contained contaminants (J.H. Webb, MLGW, oral commun., 1989).

SUMMARY AND CONCLUSIONS

The City of Memphis presently (1989) depends solely on the Memphis aquifer for its water supply. Withdrawals from the Memphis aquifer in the Memphis area for municipal, industrial, and commercial uses totaled about 200 Mgal/d in 1988. Historically, the Memphis aquifer was thought of as an ideal aquifer overlain by a thick, impermeable clay layer that serves as a confining unit and protects the aquifer from contamination from near-surface sources. Studies in recent decades (1964-86), however,

indicate that the confining unit locally may be thin or absent and may contain sand "windows" that could provide "pathways" for contaminants to reach the Memphis aquifer. Studies also indicate that downward leakage from the water-table aquifers (alluvium and fluvial deposits) to the Memphis aquifer is widespread in the Memphis area.

Indications of areas where downward leakage from the water-table aquifers to the Memphis aquifer is or may be occurring that were recognized during the previous and present investigations are as follows:

- areas where the confining unit is thin or absent and downward leakage can occur directly from the water-table aquifers to the Memphis aquifer;
- differences in hydraulic head between the water-table aquifers and the Memphis aquifer indicate a general downward gradient in most of the Memphis area;
- local depressions in the water-table surface indicate that leakage from the water-table aquifers to the Memphis aquifer is occurring;
- long-term declines and reduced seasonal fluctuations in observation wells in the water-table aquifers indicate that leakage is occurring;
- downstream losses of water along a stretch of a major stream based on a series of discharge measurements made during low-flow conditions indicate that leakage is occurring;
- areal and local variations in carbon-14 and tritium concentrations in water from the Memphis aquifer show the presence of relatively recent water, indicating leakage;

- local deviations in geothermal gradient in areas of intense pumping indicate that shallow subsurface temperatures in the water-table aquifers, confining unit, and Memphis aquifer are warmer than expected as a result of leakage;
- water-quality anomalies and changes in water quality in the Memphis aquifer indicate downward leakage from the water-table aquifers to the Memphis aquifer; and
- volatile organic compounds detected in water from the Memphis aquifer indicate that contaminants in water from the water-table aquifers has reached the Memphis aquifer.

Detailed maps of the thickness of the confining unit and the altitude of the water table in the alluvium and fluvial deposits prepared during the present investigation have provided much refinement of previously identified areas of downward leakage. Several new areas where downward leakage is or may be occurring also have been identified. Maps showing the altitude of the potentiometric surface of the Memphis aquifer and the locations of 44 sites where contaminants have been detected in the water-table aquifers indicate that many potential sources of contamination are located in areas where the direction of ground-water flow in the Memphis

aquifer is toward cones of depression at MLGW well fields. Based on present information, the MLGW Allen well field has the most sites in close proximity. The water-table map also indicates that some of the sites where contaminants have been detected are in areas where the confining unit is thin or absent or in areas where the direction of flow in the water-table aquifer is toward these areas.

Recently, (1986-88) volatile organic compounds were detected in water from five municipal wells in the Memphis area—three in the MLGW Allen well field at Memphis and two in the west well field at Collierville. Concentrations totaled about 11.0 $\mu\text{g/L}$ for seven compounds in a sample from one of the wells at the Allen well field and 25.0 $\mu\text{g/L}$ for one compound in a sample from one of the wells at Collierville.

The facts that volatile organic compounds (1) have been transported downward through the confining unit or through (or around) relatively thick intervals of clay in the Memphis aquifer; (2) have persisted despite the effects of various physical, chemical, and biological processes; and (3) have been detected in wells ranging from 257 to 452 feet in depth at distances as far as 2,000 feet away from the nearest known potential source of contamination in the water-table aquifers, emphasize the vulnerability of the Memphis aquifer to contamination.

REFERENCES

- Bell, E.A., and Nyman, D.J., 1968, Flow pattern and related chemical quality of ground water in the "500-foot" sand in the Memphis area, Tennessee: U.S. Geological Survey Water-Supply Paper 1853, 27 p.
- Brabana, J.V., 1982, Two-dimensional digital ground-water model of the Memphis Sand and equivalent units, Tennessee, Arkansas, Mississippi: U.S. Geological Survey Open-File Report 82-99, 55 p.
- Brabana, J.V., Parks, W.S., and Gaydos, M.W., 1987, Quality of water from freshwater aquifers and principal well fields in the Memphis area, Tennessee: U.S. Geological Survey Water-Resources Investigations Report 87-4052, 22 p.
- Criner, J.H., and Armstrong, C.A., 1958, Ground-water supply of the Memphis area: U.S. Geological Survey Circular 408, 20 p.
- Criner, J.H., and Parks, W.S., 1976, Historic water-level changes and pumpage from the principal aquifers of the Memphis area, Tennessee: 1886-1975: U.S. Geological Survey Water-Resources Investigations Report 76-67, 45 p.
- Criner, J.H., Sun, P.-C.P., and Nyman, D.J., 1964, Hydrology of the aquifer systems in the Memphis area, Tennessee: U.S. Geological Survey Water-Supply Paper 1779-O, 54 p.
- Cushing, E.M., Borwell, E.H., and Hosman, R.L., 1964, General geology of the Mississippi embayment: U.S. Geological Survey Professional Paper 448-B, 28 p.
- Dalsin, G.J., and Bettendorff, J.M., 1976, Water for industrial and agricultural development in Coahoma, DeSoto, Panola, Quitman, Tate, and Tunica Counties, Mississippi: Mississippi Research and Development Center, 87 p.
- Fenneman, N.M., 1938, Physiography of eastern United States: New York, McGraw-Hill, 714 p.
- Glenn, L.C., 1906, Underground waters of Tennessee and Kentucky west of Tennessee River and of an adjacent area in Illinois: U.S. Geological Survey Water-Supply Paper 164, 173 p.
- Graham, D.D., 1979, Potentiometric map of the Memphis Sand in the Memphis area, Tennessee, August 1978: U.S. Geological Survey Water-Resources Investigations Report 79-80, scale 1:125,000, 1 sheet.
- 1982, Effects of urban development on the aquifers in the Memphis area Tennessee: U.S. Geological Survey Water-Resources Investigations Report 82-4024, 20 p.
- 1985, Test well installation and water quality, Hollywood Dump area, Memphis, Tennessee: U.S. Geological Survey Water-Resources Investigations Report 84-4212, 35 p.
- Graham, D.D., and Parks, W.S., 1986, Potential for leakage among principal aquifers in the Memphis area, Tennessee: U.S. Geological Survey Water-Resources Investigations Report 85-4295, 46 p.
- Grubb, H.F., 1984, Planning report for the Gulf Coast Regional Aquifer-System Analysis in the Gulf of Mexico Coastal Plain, United States: U.S. Geological Survey Water-Resources Investigations Report 84-4219, 30 p.
- Hosman, R.L., 1988, Geohydrologic framework of the Gulf Coastal Plain: U.S. Hydrologic Atlas HA-695, 2 sheets.
- Kazmann, R.G., 1944, The water supply of the Memphis area, A progress report: U.S. Geological Survey, 66 p.
- Lanphere, C.R., 1955, Geologic source and chemical quality of public ground-water supplies in western Tennessee: Tennessee Division of Geology Report of Investigations no. 1, 69 p.
- McMaster, B.W., and Parks, W.S., 1988, Concentrations of selected trace inorganic constituents and synthetic organic compounds in the water-table aquifers in the Memphis area, Tennessee: U.S. Geological Survey Open-File Report 88-485, 23 p.
- Nyman, D.J., 1965, Predicted hydrologic effects of pumping from the Lichterman well field in the Memphis area, Tennessee: U.S. Geological Survey Water-Supply Paper 1819-B, 26 p.
- Parks, W.S., 1973, Geologic map of the Southwest Memphis quadrangle, Tennessee: U.S. Geological Survey open-file report, scale 1:24,000.
- 1975, Geologic map of the Germantown quadrangle, Tennessee: U.S. Geological Survey open-file report, scale 1:24,000.
- 1977, Geologic map of the Ellendale quadrangle, Tennessee: U.S. Geological Open-File Report 77-752, scale 1:24,000.
- 1978, Geologic map of the Tennessee portion of the Fletcher Lake quadrangle, Tennessee (including portions of adjacent quadrangles to the north, west,

- and south): Tennessee Division of Geology GM 404-SW, scale 1:24,000.
- 1979a, Geologic map of the Northeast Memphis quadrangle, Tennessee: U.S. Geological Survey Open-File Report 79-1268, scale 1:24,000.
- 1979b, Geologic map of the Tennessee portion of the Northwest Memphis quadrangle, Tennessee: U.S. Geological Survey Open-File Report 79-1269, scale 1:24,000.
- 1987a, Geologic map of the Southeast Memphis quadrangle, Tennessee (including the Tennessee part of the Pleasant Hill quadrangle, Tennessee-Mississippi): Tennessee Division of Geology GM 409-SW, scale 1:24,000.
- 1987b, Indications of downward leakage from the water-table aquifers to the principal artesian aquifer at Memphis, Tennessee: Proceedings of the Mississippi Water Resources Conference, Jackson, Mississippi, March 25-26, 1987, p. 95-97.
- Parks, W.S., and Carmichael, J.K., 1989, Geology and ground-water resources of the Fort Pillow Sand in western Tennessee: U.S. Geological Survey Water-Resources Investigations Report 89-4120, 20 p.
- 1990a, Geology and ground-water resources of the Memphis Sand in western Tennessee: U.S. Geological Survey Water-Resources Investigations Report 88-4182, 30 p.
- 1990b, Geology and ground-water resources of the Cockfield Formation in western Tennessee: U.S. Geological Survey Water-Resources Investigations Report 88-4181, 17 p.
- 1990c, Potentiometric surface, fall 1985, and water-level changes in the Memphis aquifer in western Tennessee: U.S. Geological Water-Resources Investigations Report 88-4180, 8 p.
- Parks, W.S., Carmichael, J.K., and Graham, D.D., 1985, Preliminary assessment of ground-water resources of Lauderdale County, Tennessee: U.S. Geological Survey Water-Resources Investigations Report 84-4104, 35 p.
- Parks, W.S., Graham, D.D., and Lowery, J.F., 1982, Installation and sampling of observation wells and analyses of water from the shallow aquifer at selected waste-disposal sites in the Memphis area, Tennessee: U.S. Geological Survey Open-File Report 82-266, 32 p.
- Parks, W.S., and Lounsbury, R.W., 1976, Summary of some current and possible future environmental problems related to geology and hydrology at Memphis, Tennessee: U.S. Geological Survey Water-Resources Investigations Report 4-76, 34 p.
- Plebuch, R.O., 1961, Fresh-water aquifers of Crittenden County, Arkansas: Arkansas Geology and Conservation Commission Water Resources Circular no. 8, 65 p.
- Richardson, G.J., 1989, A study of potential sources of leakage into the Memphis Sand aquifer beneath the Davis well field in Memphis, Tennessee: Memphis, Tennessee, Memphis State University, unpublished thesis, 82 p.
- Rima, D.R., 1979, Susceptibility of the Memphis water supply to contamination from the pesticide waste disposal site in northeastern Hardeman County, Tennessee: U.S. Geological Survey Open-File Report 79-750, 5 p.
- Safford, J.M., 1890, The water supply of Memphis: Tennessee Board of Health Bulletin v. 5, 93 p.
- Schneider, Robert, and Cushing, E.M., 1948, Geology and water-bearing properties of the "1,400-foot" sand in the Memphis area: U.S. Geological Survey Circular 33, 13 p.
- U.S. Army Corps of Engineers, Memphis District, 1981, Memphis metropolitan urban area water resources study: Memphis, Tennessee, U.S. Army Corps of Engineers, 127 p.
- U.S. Environmental Protection Agency, 1986, Maximum contaminant levels (subpart B of part 141, National interim primary drinking-water regulations): U.S. Code of Federal Regulations, Title 40, Parts 140 to 149, revised July 1, 1986, p. 524-528.
- Wells, F.G., 1931, A preliminary report on the artesian water supply of Memphis, Tennessee: U.S. Geological Survey Water-Supply Paper 638-A, 34 p.
- 1933, Ground-water resources of western Tennessee, with a discussion of Chemical character of the water by F.G. Wells and M.D. Foster: U. S. Geological Survey Water-Supply Paper 656, 319 p.

DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

PLATE I

EXPLANATION

DAVIS



MEMPHIS LIGHT, GAS AND WATER
DIVISION WELL FIELD

— 200 —

LINE OF EQUAL THICKNESS OF THE
JACKSON-UPPER CLAIBORNE
CONFINING UNIT--Dashed where
approximately located. Interval
50 feet

161

30



WELL FOR WHICH GEOPHYSICAL LOG
WAS USED AS CONTROL--Upper
number is thickness of confining
unit in feet. Lower number is
aggregate thickness of clay beds
in the confining unit thicker than
10 feet


Sh:0-115

268

205





WELL REFERRED TO IN TEXT



35°15'

90°15'





DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

Plate 2

EXPLANATION

DAVIS



MEMPHIS LIGHT, GAS AND WATER
DIVISION WELL FIELD



AREA OF NO SIGNIFICANT SATURATED
THICKNESS

— 200 —

WATER-TABLE CONTOUR--Shows
altitude of water table. Dashed
where approximately located.
Hachures indicate depression.
Contour interval 20 feet.
Datum is sea level

• 313

WELL FOR WHICH WATER-LEVEL
MEASUREMENT MADE IN THE
FALL 1988 WAS USED AS
CONTROL--Number is altitude
of water level, in feet above
sea level

○ 198

WELL FOR WHICH HISTORIC (1944-87)
WATER-LEVEL MEASUREMENT WAS
USED AS SUPPLEMENTAL
CONTROL--Number shown as less
than (<) indicates altitude of
water level is below bottom of
well

Sh:P-99
• 233



WELL REFERRED TO IN THE TEXT

△ 240

POINT WHERE 20-FOOT INTERVAL
CONTOUR ON 7 1/2-MINUTE
TOPOGRAPHIC QUADRANGLE
CROSSES PERENNIAL STREAM

35°15'

90°15'



EXPLANATION

DAVIS



MEMPHIS LIGHT, GAS AND WATER
DIVISION WELL FIELD

POTENTIOMETRIC CONTOUR--Shows
altitude at which water level would
have stood in tightly cased wells.
Dashed where approximately located.
Hachures indicate depression.
Contour Interval 10 feet.
Datum is sea level


175

WELL FOR WHICH WATER LEVEL
MEASUREMENT MADE IN THE
LATE SUMMER-FALL 1988 WAS
USED AS CONTROL--Number is
altitude of water level, in feet
above sea level

Sh:O-179

119


WELL REFERRED TO IN THE TEXT




35°15'

90°15'

1-40



⊕ Altitude of the potentiometric surface of the Memphis aquifer in the N



DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

PLATE 4

EXPLANATION

DAVIS



MEMPHIS LIGHT, GAS AND WATER
DIVISION WELL FIELD



AREA WHERE THE CONFINING UNIT
IS THIN OR ABSENT

10 ●

INDUSTRIAL SPILL OR WASTE BURIAL--
Number refers to sites listed in
table 6



LEAKY UNDERGROUND STORAGE TANK



ABANDONED OR INACTIVE WASTE DUMP
OR LANDFILL



WELL IN THE WATER-TABLE AQUIFER




WELL IN THE MEMPHIS AQUIFER

Sh:J-119



WELL REFERRED TO IN THE TEXT




1" = 2 mi

35°15'

90°15'



1-5



Loosahatchie

MORTON

Mississippi

E-240

MALLORY

SITE

ALLEN

SHEAHAN

LICHTERMAN

VIS

Nonco


I-55



13



Wolf



Jackson Pit Dump

Brooks Road Dump

Sh:J-119

Sh:J-120

Sh:J-121

Sh:J-155

North Hollywood Dump

Sh:Q-93

Ogi

an

U

Allec

1971

Site for

McC

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215


Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215

Sh:O-215



R. Allan Freeze

Department of Geological Sciences
University of British Columbia
Vancouver, British Columbia

John A. Cherry

Department of Earth Sciences
University of Waterloo
Waterloo, Ontario

GROUNDWATER

Prentice Hall, Inc.
Englewood Cliffs, New Jersey 07632

Table 2.2 Range of Values of Hydraulic Conductivity and Permeability

| | Rocks | Unconsolidated deposits | K (darcy) | K (cm ²) | K (cm/s) | K (m/s) | K (gal/day/ft ²) |
|--|-------|-------------------------|----------------|---------------------------|---------------|--------------|-----------------------------------|
| | | | 10^5 | 10^{-3} | 10^{-2} | 1 | 10^6 |
| | | | 10^4 | 10^{-4} | 10 | 10^{-1} | 10^5 |
| | | | 10^3 | 10^{-5} | 1 | 10^{-2} | 10^4 |
| | | | 10^2 | 10^{-6} | 10^{-1} | 10^{-3} | 10^3 |
| | | | 10^1 | 10^{-7} | 10^{-2} | 10^{-4} | 10^2 |
| | | | | 10^{-8} | 10^{-3} | 10^{-5} | 10 |
| | | | 10^{-1} | 10^{-9} | 10^{-4} | 10^{-6} | 1 |
| | | | 10^{-2} | 10^{-10} | 10^{-5} | 10^{-7} | 10^{-1} |
| | | | 10^{-3} | 10^{-11} | 10^{-6} | 10^{-8} | 10^{-2} |
| | | | 10^{-4} | 10^{-12} | 10^{-7} | 10^{-9} | 10^{-3} |
| | | | 10^{-5} | 10^{-13} | 10^{-8} | 10^{-10} | 10^{-4} |
| | | | 10^{-6} | 10^{-14} | 10^{-9} | 10^{-11} | 10^{-5} |
| | | | 10^{-7} | 10^{-15} | 10^{-10} | 10^{-12} | 10^{-6} |
| | | | 10^{-8} | 10^{-16} | 10^{-11} | 10^{-13} | 10^{-7} |

Table 2.3 Conversion Factors for Permeability and Hydraulic Conductivity Units

| | Permeability, K^* | | | Hydraulic conductivity, K | | |
|------------------------------|------------------------|------------------------|-----------------------|-----------------------------|-----------------------|------------------------------|
| | cm ² | ft ² | darcy | m/s | ft/s | U.S. gal/day/ft ² |
| cm ² | 1 | 1.08×10^{-3} | 1.01×10^9 | 9.80×10^{-12} | 3.22×10^{-3} | 1.85×10^9 |
| ft ² | 9.29×10^2 | 1 | 9.42×10^{10} | 9.11×10^{-3} | 2.99×10^{-6} | 1.71×10^{12} |
| darcy | 9.87×10^{-9} | 1.06×10^{-11} | 1 | 9.66×10^{-16} | 3.17×10^{-5} | 1.82×10^3 |
| m/s | 1.02×10^{-3} | 1.10×10^{-6} | 1.04×10^3 | 1 | 3.28 | 2.12×10^6 |
| ft/s | 3.11×10^{-4} | 3.35×10^{-7} | 3.15×10^4 | 3.05×10^{-3} | 1 | 6.46×10^5 |
| U.S. gal/day/ft ² | 5.42×10^{-10} | 5.83×10^{-13} | 5.49×10^{-7} | 4.72×10^{-7} | 1.55×10^{-6} | 1 |

*To obtain K in ft², multiply K in cm² by 1.08×10^{-3} .

Reference 22

B&V WASTE SCIENCE AND TECHNOLOGY CORP.

TELEPHONE MEMORANDUM

BVWST Project 52012.001

March 3, 1992

11:00 a.m.

Subject: Site-Specific geology & confining layer information

To: Dr. William S. Parks
Company: USGS Water Investigations
Phone No.: (901) 766-2977

Recorded by: Carter Helm

Since there exists no mention of hydraulic conductivity values for aquitards in the Memphis area in Dr. Parks' publication Hydrogeology and Preliminary Assessment of the Potential for Contamination of the Memphis /Aquifer in the Memphis Area, TN, I asked Dr. Parks if the range 1.0×10^{-7} to 1.0×10^{-5} cm/sec is acceptable for the Jackson-Upper Claiborne clay confining unit. He said it is highly variable but the estimation I extracted from Freeze and Cherry appears to somewhat accurately describe the aquitard.

Hydrology of Aquifer Systems in the Memphis Area, Tennessee

By J. H. CRINER, P.C. P. SUN, and D. J. NYMAN

CONTRIBUTIONS TO THE HYDROLOGY OF THE


GEOLOGICAL SURVEY WATER-SUPPLY

*Prepared in cooperation with the city of
Memphis, Memphis Light, Gas, and
Water Division*

*A hydrogeologic delineation, analysis, and
evaluation of the principal water-bearing
formations in the Memphis area, Tennessee*

Reference 23

U. S. Geological Survey



Nashville, Tennessee

UNITED STATES DEPARTMENT OF THE INTERIOR

STEWART L. UDALL, *Secretary*

GEOLOGICAL SURVEY

Thomas B. Nolan, *Director*

CONTENTS

| | |
|---|------------|
| Abstract..... | Page 01 |
| Introduction..... | 2 |
| Purpose and scope of investigation..... | 2 |
| Location and general features of the area..... | 3 |
| Previous investigations..... | 6 |
| Acknowledgments..... | 6 |
| Well-numbering system..... | 6 |
| General geology of the aquifer systems..... | 8 |
| Description of the geologic units..... | 9 |
| Wilcox Group..... | 9 |
| Cibola Group..... | 11 |
| Jackson(?) Formation..... | 12 |
| Terrace deposits and alluvium..... | 12 |
| Geologic structure..... | 13 |
| Hydrology of the aquifer systems..... | 13 |
| Geologic control of ground water in the Memphis area..... | 13 |
| Texture of aquifer materials..... | 14 |
| Effects of ground-water withdrawal..... | 15 |
| The "500-foot" sand and aquifer..... | 16 |
| Delineation..... | 16 |
| Water levels..... | 18 |
| Decline caused by pumping..... | 18 |
| Fluctuation..... | 27 |
| Hydraulic characteristics..... | 28 |
| Recharge and movement..... | 30 |
| Pumping..... | 31 |
| The "1,400-foot" sand aquifer..... | 32 |
| Delineation..... | 32 |
| Water levels..... | 33 |
| Decline caused by pumping..... | 33 |
| Fluctuation..... | 36 |
| Hydraulic characteristics..... | 37 |
| Recharge and movement..... | 38 |
| Pumping..... | 39 |
| Other aquifers..... | 39 |
| Quality of water..... | 40 |
| Water in the "500-foot" sand..... | 40 |
| Water in the "1,400-foot" sand..... | 42 |
| Water in other aquifers..... | 43 |
| Factors affecting future use and development..... | 44 |
| Adequacy of the aquifer analysis..... | 46 |
| Conclusions..... | 46 |
| References..... | 51 |
| Index..... | 63 |

ILLUSTRATIONS

(Plates are in pocket)

| PLATE | | PAGE |
|-------|---|------|
| 1. | Geologic sections of the Memphis area, Tennessee. | 010 |
| 2. | Structure map showing configuration of the top of the "500-foot" sand, Memphis area, Tennessee. | 42 |
| 3. | Structure map showing configuration of the bottom of the "500-foot" sand, Memphis area, Tennessee. | 43 |
| 4. | Map showing configuration of the piezometric surface of the "500-foot" sand in August, 1960, Memphis area, Tennessee. | |
| 5. | Map showing decline of water level in the "500-foot" sand 1950-1960, Memphis area, Tennessee. | |
| 6. | Structure map showing configuration of the top of the "1,400-foot" sand, Memphis area, Tennessee. | |
| 7. | Structure map showing configuration of the bottom of the "1,400-foot" sand, Memphis area, Tennessee. | |

FIGURE

| FIGURE | | PAGE |
|--------|--|------|
| 1. | Map of Mississippi embayment showing projection area. | 03 |
| 2. | Graph showing annual precipitation at Memphis, Tenn. | 4 |
| 3. | Map showing topographic quadrangles in the Memphis area and showing the well-numbering system used in Tennessee. | 6 |
| 4. | Graphs of particle-size distribution. | 15 |
| 5. | Memphis municipal pumpage. | 17 |
| 6. | Relation between pumpage and water level. | 18 |
| 7. | Relation between "500-foot" sand and water-level in center of pumping. | 20 |
| 8. | Decline of water level in "500-foot" sand, 8 and 10 miles from center of pumping. | 21 |
| 9. | Decline of water level in "500-foot" sand, 15 and 30 miles from the center of pumping. | 22 |
| 10-13. | Relation between pumping and water level in "500-foot" sand at: | |
| 10. | McCord well field. | 23 |
| 11. | Allen well field. | 24 |
| 12. | Shelham well field. | 25 |
| 13. | Parkway well field. | 26 |
| 14. | Sample computations of T and S, "500-foot" sand. | 29 |
| 15. | Relation between pumping and water level ("1,400-foot" sand) at Parkway well field. | 34 |
| 16. | Relation between pumping and water level ("1,400-foot" sand) at Sheahan well field. | 35 |
| 17. | Relation between total pumpage and water level ("1,400-foot" sand), 15 and 30 miles from center of pumping. | 36 |
| 18. | Sample computations of T and S, "1,400-foot" sand. | 37 |
| 19. | Iron concentration, hardness, and total dissolved solids of water from principal aquifers. | 41 |

CONTENTS

TABLES

| TABLE | | PAGE |
|-------|--|------|
| 1. | Geologic units underlying the Memphis area. | 010 |
| 2. | Typical chemical analysis of water from the "500-foot" sand. | 42 |
| 3. | Typical chemical analysis of water from the "1,400-foot" sand. | 43 |

CONTRIBUTIONS TO THE HYDROLOGY OF THE UNITED STATES

HYDROLOGY OF AQUIFER SYSTEMS IN THE
MEMPHIS AREA, TENNESSEE

By J. H. CAINE, P-C. P. SUN, and D. J. NYMAN

ABSTRACT

The Memphis area as described in this report comprises about 1,500 square miles of the Mississippi embayment part of the Gulf Coastal Plains. The area is underlain by as much as 8,000 feet of sediments ranging in age from Cretaceous through Quaternary.

In 1960, 150 mgd (million gallons per day) of water was pumped from the principal aquifers. Municipal pumpage accounted for almost half of this amount, and industrial pumpage a little more than half. About 90 percent of the water used in the area is derived from the "500-foot" sand, and most of the remainder is from the "1,400-foot" sand; both sands are of Eocene age. A small amount of water for domestic use is pumped from the terrace deposits of Pliocene and Pleistocene age.

Both the "500-foot" and the "1,400-foot" sands are artesian aquifers except in the southeastern part of the area; there the water level in wells in the "500-foot" sand is now below the overlying confining clay. Water levels in both aquifers have declined almost continuously since pumping began, but the rate of decline has increased rapidly since 1940. Water-level decline in the "1,400-foot" sand has been less pronounced since 1900.

The cones of depression in both aquifers have expanded and deepened as a result of the annual increases in pumping, and an increase in hydraulic gradients has induced a greater flow of water into the area. Approximately 135 mgd entered the Memphis area through the "500-foot" sand aquifer in 1960, and, of this amount, 60 mgd originated as inflow from the east and about 75 mgd was derived from leakage from the terrace deposits, from the north, south, and west and from other sources. Of the water entering the "1,400-foot" sand, about 5 mgd was inflow from the east, and about half that amount was from each of the north, south, and west directions. The average rate of movement of water outside the area of heavy withdrawals is about 70 feet per year in the "500-foot" sand and about 40 feet per year in the "1,400-foot" sand. The average rate of depletion of storage in each aquifer since pumping began is about 1 mgd.

Most of the recharge to the "500-foot" and "1,400-foot" sands occurs in outcrop areas about 30-80 miles east of Memphis. Also, water leaks from the terrace deposits to the "500-foot" sand in some places, and there may be some leakage from streams where the confining clay is thin or is breached by faults or streams.

The quality of water from both the principal aquifers is very good. Iron, carbon dioxide, and hydrogen sulfide are the only constituents found in undrinkable quantities. Water from the terrace deposits is hard but generally contains less iron and carbon dioxide than water from either of the principal aquifers.

The hydraulic characteristics of both aquifers were determined by pumping tests and by applying the knowledge of the geology of the area; these characteristics indicate that the aquifers are capable of producing more water than is currently being pumped from them. The "500-foot" sand will produce more water per unit decline of water level than will the "1,400-foot" sand. There appears to be no reason why the development of water supplies from both aquifers should not continue, but well spacing will remain a factor which could affect future development. Greater well spacing will tend to prolong the useful life of a well and the aquifers.

INTRODUCTION

In 1900, industrial and municipal supply wells in the Memphis area pumped about 160 million gallons of water a day. Pumping has increased continuously since 1898, the earliest date for which records are available, and the rate of this increase has accelerated greatly since 1940. Decline of water levels has accompanied increases in the pumping, and in 1928 the city of Memphis began a program of periodic water-level measurements to determine ways to reduce the rate of decline. The U.S. Geological Survey was requested to assist in this study, and a continuing cooperative program of investigations was begun in 1940. Early investigations showed the need for proper spacing of wells, which has been practiced to the present time.

PURPOSE AND SCOPE OF INVESTIGATION

The present investigation was started in 1958 as a quantitative study of the two principal aquifers that supply water to the Memphis area. The objectives were to delineate these aquifers, evaluate their hydraulic characteristics, show the relation between pumping and water-level change, and determine the factors affecting the economical development and use of ground water. The study was based partly on the premise that the questions posed by Kazmann (1944, p. 17-18) must be answered as completely as possible to provide for orderly development and management of the ground-water resources. These questions were repeated and discussed in the concluding section of this report.

Work consisted of (1) delineation of the "500-foot" and "1,400-foot" sands by a series of subsurface contour maps based on drillers' logs and geophysical logs of wells, (2) collection of water-level records from a network of about 150 observation wells, 53 of which were equipped with automatic recorders, (3) preparation of contour maps showing water levels and the amount of water-level decline in the "500-foot" sand, (4) analyses of pumping data, and (5) preparation of


area through each aquifer before development began and during 1960, (6) preparation of a ground-water budget for the "500-foot" sand, based on 1960 records, and (7) inventory of ground-water withdrawal and study of its relation to water-level decline.

LOCATION AND GENERAL FEATURES OF THE AREA

The Memphis area (fig. 1), about 1,300 square miles in this report, includes all Shelby County and parts of Fayette and Tipton Counties, Tenn., and contiguous parts of Arkansas and Mississippi. The area is near the center of the upper half of the Mississippi embayment in the Gulf Coastal Plain.

The climate of the Memphis area is warm and humid, having hot summers, mild winters, and a frost-free period of about 230 days between late March and early November. The average annual temperature is 61.9°F; the hottest month is July, which has an average temperature of 81.1°F; and the coldest month is January, which has an average temperature of 41.5°F.

The average annual rainfall Memphis (fig. 2), based on an 89-year period of record (1872-1960), is 48.48 inches. The maximum annual rainfall recorded was 76.85 inches in 1957, and the minimum was 30.54






FIGURE 2.—Graph showing annual precipitation at Memphis, Tenn.

inches in 1941. The wet season usually begins in late November and ends in April. Rainfall at Moscow and Belvoir (fig. 1) in the outcrop or recharge area of the principal aquifers, is slightly greater than that in the Memphis area.

The Memphis area (fig. 1) consists mostly of a gently rolling upland ranging in elevation from about 400 feet in the eastern part of Shelby County to about 200 feet on the alluvial plain of the Mississippi River. The maximum topographic relief is about 200 feet, but the local relief of individual topographic features seldom exceeds 40 feet. The upland area is terminated by a bluff 50 to 150 feet high along the eastern margin of the alluvial plain of the Mississippi River. This is virtually flat plain, which is approximately 210 feet above sea level, is about 3 miles wide along the east side of the Mississippi River except in the vicinity of Memphis; at Memphis the river flows along the base of the bluff.

The principal streams that drain the Memphis area are the Wolf and Loosahatchie Rivers and Nonconah Creek, all of which flow north-northwestward and discharge into the Mississippi River. These streams have wide flood plains that are generally adequate to accommodate flood waters during the rainy season. Some sections of the channels of these and smaller tributaries have been artificially deepened for more effective drainage of the lowland areas. In the past all three major streams have flowed throughout the year; however, in recent years Nonconah Creek was dry in its lower reach for short periods during the dry season from July to October.

Memphis is a large industrial center; the principal industries produce hardwood lumber and cotton and associated products. The Memphis Chamber of Commerce reported 765 industries in Memphis (1938-39), 120 of which have their own water-supply wells. More than half the total ground-water pumpage from the area is from these wells.

The 1960 U.S. Census shows that the population of Memphis and Shelby County has approximately doubled since 1930. The successive census figures are as follows:

| Population of Memphis and Shelby County, Tenn. | | |
|--|----------|---------------|
| Year | Memphis | Shelby County |
| 1930 | 233, 143 | 804, 482 |
| 1940 | 292, 942 | 858, 250 |
| 1950 | 306, 012 | 482, 803 |
| 1960 | 497, 624 | 627, 019 |

PREVIOUS INVESTIGATIONS

The earliest reports describing the geology and the ground-water resources of the Memphis area were by Safford (1869, 1890) and Glenn (1906). Wells (1931) described the artesian water supply of Memphis and, in a subsequent report (1933), the ground-water resources of West Tennessee, including a more detailed discussion of ground-water conditions in the Memphis area. Since the beginning of the cooperative program in 1940, progress reports have been published by Kazmann (1944), Schneider and Cushing (1948), and Criner and Armstrong (1958).

Regional and local studies relating to the geology of the Memphis area were made by Fisk (1944), Caplan (1954), Stearns and Armstrong (1955), and Stearns (1957).

Records of water levels from 1936 through 1955 have been reported by the U.S. Geological Survey (issued annually). Earlier measurements were reported by Wells (1931, 1933).

ACKNOWLEDGMENTS


The assistance and cooperation of many city and county officials, industry representatives, drilling contractors, and well owners were helpful in the collection of data for this report. Mr. J. J. Davis, Director, Water Division, and Messrs. A. J. Runney and Hugh Mills, Memphis Light, Gas, and Water Division, provided essential well and water-use data from the city records and assisted greatly in the investigation. Mr. E. C. Handorf and Mr. W. M. Craddock, of the Memphis and Shelby County Health Department have, through their interest in the Memphis area water supply, contributed substantially to the study. Drilling contractors, industries, and individual well owners also were especially helpful in providing well data, permitting use of wells for geophysical and hydraulic tests, and furnishing information on water use in the area.

06 CONTRIBUTIONS TO THE HYDROLOGY OF THE UNITED STATES

WELL-NUMBERING SYSTEM

Figure 3 illustrates the standard system for numbering wells in this report. Each well number consists of three units: (1) an abbreviation of the name of the county in which the well is located; (2) a letter designating the 7½-minute topographic quadrangle, or 7½-minute quadrant of a 15-minute quadrangle, in which the well is located; and (3) a number generally indicating the numerical order in which the wells were inventoried.

The index map (fig. 3) shows the 15-minute topographic quadrangles of the U.S. Army Corps of Engineers that include Shelby County and adjacent areas described in this report. The example, well Sh: P-76, is in Shelby County, in the northwest quadrant (7½-minute quadrangle designated "P") of the Bartlett 15-minute quadrangle and is identified as well 76 in the numerical sequence.



In this report the county designation "Sh" is omitted in figures. Well numbers in adjoining counties in Tennessee are preceded by the county abbreviation. Wells in adjoining States are not numbered.

At Memphis, the Memphis Light, Gas, and Water Division many years ago established their own well-numbering system. According to this plan, blocks of numbers were assigned for the city's five existing well fields (pl. 1) and other blocks of numbers were reserved for future well fields. The block assignments are as follows:

| | |
|---|-------------------------------------|
| 1-40..... Parkway Field | 200-240..... McCord Field |
| 50-90..... Sheehan Field | 250-290..... (Not assigned) |
| 100-140..... Allen Field | 300-340..... Hickory Hill (Lichter- |
| 150-190..... Miscellaneous wells at scattered locations (abandoned) | man) Field (proposed) |

Listed below are city-owned wells in use as of January 1962 and those that have been withdrawn from use. Well numbers followed by the letters "A," "B," and so on, indicate first, second, and so on, replacement wells for those withdrawn from use. For convenient reference, the wells owned by the Memphis Light, Gas, and Water Division are listed below, together with the corresponding numbers assigned by the U.S. Geological Survey.

| City | Geological Survey | City | Geological Survey |
|------------------|-------------------|----------|-------------------|
| 1..... Sh: O-125 | 15A..... | 100..... | 183..... |
| 1A..... | 15B..... | 101..... | 184..... |
| 2..... | 15C..... | 102..... | 185..... |
| 2A..... | 15D..... | 103..... | 186..... |
| 3..... | 15E..... | 104..... | 187..... |
| 4..... | 15F..... | 105..... | 188..... |
| 4A..... | 15G..... | 106..... | 189..... |
| 5..... | 15H..... | 107..... | 190..... |
| 5A..... | 15I..... | 108..... | 191..... |
| 6..... | 15J..... | 109..... | 192..... |
| 6A..... | 15K..... | 110..... | 193..... |
| 7..... | 15L..... | 111..... | 194..... |
| 7A..... | 15M..... | 112..... | 195..... |
| 8..... | 15N..... | 113..... | 196..... |
| 8A..... | 15O..... | 114..... | 197..... |
| 9..... | 15P..... | 115..... | 198..... |
| 9A..... | 15Q..... | 116..... | 199..... |
| 10..... | 15R..... | 117..... | 200..... |
| 10A..... | 15S..... | 118..... | 201..... |
| 11..... | 15T..... | 119..... | 202..... |
| 11A..... | 15U..... | 120..... | 203..... |
| 12..... | 15V..... | 121..... | 204..... |
| 12A..... | 15W..... | 122..... | 205..... |
| 13..... | 15X..... | 123..... | 206..... |
| 13A..... | 15Y..... | 124..... | 207..... |
| 14..... | 15Z..... | 125..... | 208..... |
| 14A..... | 15AA..... | 126..... | 209..... |
| 15..... | 15AB..... | 127..... | 210..... |
| 15A..... | 15AC..... | 128..... | 211..... |
| 16..... | 15AD..... | 129..... | 212..... |
| 16A..... | 15AE..... | 130..... | 213..... |
| 17..... | 15AF..... | 131..... | 214..... |
| 17A..... | 15AG..... | 132..... | 215..... |
| 18..... | 15AH..... | 133..... | 216..... |
| 18A..... | 15AI..... | 134..... | 217..... |
| 19..... | 15AJ..... | 135..... | 218..... |
| 19A..... | 15AK..... | 136..... | 219..... |
| 20..... | 15AL..... | 137..... | 220..... |
| 20A..... | 15AM..... | 138..... | 221..... |
| 21..... | 15AN..... | 139..... | 222..... |
| 21A..... | 15AO..... | 140..... | 223..... |
| 22..... | 15AP..... | 141..... | 224..... |
| 22A..... | 15AQ..... | 142..... | 225..... |
| 23..... | 15AR..... | 143..... | 226..... |
| 23A..... | 15AS..... | 144..... | 227..... |
| 24..... | 15AT..... | 145..... | 228..... |
| 24A..... | 15AU..... | 146..... | 229..... |
| 25..... | 15AV..... | 147..... | 230..... |
| 25A..... | 15AW..... | 148..... | 231..... |
| 26..... | 15AX..... | 149..... | 232..... |
| 26A..... | 15AY..... | 150..... | 233..... |
| 27..... | 15AZ..... | 151..... | 234..... |
| 27A..... | 15BA..... | 152..... | 235..... |
| 28..... | 15BB..... | 153..... | 236..... |
| 28A..... | 15BC..... | 154..... | 237..... |
| 29..... | 15BD..... | 155..... | 238..... |
| 29A..... | 15BE..... | 156..... | 239..... |
| 30..... | 15BF..... | 157..... | 240..... |
| 30A..... | 15BG..... | 158..... | 241..... |
| 31..... | 15BH..... | 159..... | 242..... |
| 31A..... | 15BI..... | 160..... | 243..... |
| 32..... | 15BJ..... | 161..... | 244..... |
| 32A..... | 15BK..... | 162..... | 245..... |
| 33..... | 15BL..... | 163..... | 246..... |
| 33A..... | 15BM..... | 164..... | 247..... |
| 34..... | 15BN..... | 165..... | 248..... |
| 34A..... | 15BO..... | 166..... | 249..... |
| 35..... | 15BP..... | 167..... | 250..... |
| 35A..... | 15BQ..... | 168..... | 251..... |
| 36..... | 15BR..... | 169..... | 252..... |
| 36A..... | 15BS..... | 170..... | 253..... |
| 37..... | 15BT..... | 171..... | 254..... |
| 37A..... | 15BU..... | 172..... | 255..... |
| 38..... | 15BV..... | 173..... | 256..... |
| 38A..... | 15BW..... | 174..... | 257..... |
| 39..... | 15BX..... | 175..... | 258..... |
| 39A..... | 15BY..... | 176..... | 259..... |
| 40..... | 15BZ..... | 177..... | 260..... |
| 40A..... | 15CA..... | 178..... | 261..... |
| 41..... | 15CC..... | 179..... | 262..... |
| 41A..... | 15CD..... | 180..... | 263..... |
| 42..... | 15CE..... | 181..... | 264..... |
| 42A..... | 15CF..... | 182..... | 265..... |
| 43..... | 15CG..... | 183..... | 266..... |
| 43A..... | 15CH..... | 184..... | 267..... |
| 44..... | 15CI..... | 185..... | 268..... |
| 44A..... | 15CJ..... | 186..... | 269..... |
| 45..... | 15CK..... | 187..... | 270..... |
| 45A..... | 15CL..... | 188..... | 271..... |
| 46..... | 15CM..... | 189..... | 272..... |
| 46A..... | 15CN..... | 190..... | 273..... |
| 47..... | 15CO..... | 191..... | 274..... |
| 47A..... | 15CP..... | 192..... | 275..... |
| 48..... | 15CQ..... | 193..... | 276..... |
| 48A..... | 15CR..... | 194..... | 277..... |
| 49..... | 15CS..... | 195..... | 278..... |
| 49A..... | 15CT..... | 196..... | 279..... |
| 50..... | 15CU..... | 197..... | 280..... |
| 50A..... | 15CV..... | 198..... | 281..... |
| 51..... | 15CW..... | 199..... | 282..... |
| 51A..... | 15CX..... | 200..... | 283..... |
| 52..... | 15CY..... | 201..... | 284..... |
| 52A..... | 15CZ..... | 202..... | 285..... |
| 53..... | 15DA..... | 203..... | 286..... |
| 53A..... | 15DB..... | 204..... | 287..... |
| 54..... | 15DC..... | 205..... | 288..... |
| 54A..... | 15DD..... | 206..... | 289..... |
| 55..... | 15DE..... | 207..... | 290..... |
| 55A..... | 15DF..... | 208..... | 291..... |
| 56..... | 15DG..... | 209..... | 292..... |
| 56A..... | 15DH..... | 210..... | 293..... |
| 57..... | 15DI..... | 211..... | 294..... |
| 57A..... | 15DJ..... | 212..... | 295..... |
| 58..... | 15DK..... | 213..... | 296..... |
| 58A..... | 15DL..... | 214..... | 297..... |
| 59..... | 15DM..... | 215..... | 298..... |
| 59A..... | 15DN..... | 216..... | 299..... |
| 60..... | 15DO..... | 217..... | 300..... |
| 60A..... | 15DP..... | 218..... | 301..... |
| 61..... | 15DQ..... | 219..... | 302..... |
| 61A..... | 15DR..... | 220..... | 303..... |
| 62..... | 15DS..... | 221..... | 304..... |
| 62A..... | 15DT..... | 222..... | 305..... |
| 63..... | 15DU..... | 223..... | 306..... |
| 63A..... | 15DV..... | 224..... | 307..... |
| 64..... | 15DW..... | 225..... | 308..... |
| 64A..... | 15DX..... | 226..... | 309..... |
| 65..... | 15DY..... | 227..... | 310..... |
| 65A..... | 15DZ..... | 228..... | 311..... |
| 66..... | 15EA..... | 229..... | 312..... |
| 66A..... | 15EB..... | 230..... | 313..... |
| 67..... | 15EC..... | 231..... | 314..... |
| 67A..... | 15ED..... | 232..... | 315..... |
| 68..... | 15EE..... | 233..... | 316..... |
| 68A..... | 15EF..... | 234..... | 317..... |
| 69..... | 15EG..... | 235..... | 318..... |
| 69A..... | 15EH..... | 236..... | 319..... |
| 70..... | 15EI..... | 237..... | 320..... |
| 70A..... | 15EJ..... | 238..... | 321..... |
| 71..... | 15EK..... | 239..... | 322..... |
| 71A..... | 15EL..... | 240..... | 323..... |
| 72..... | 15EM..... | 241..... | 324..... |
| 72A..... | 15EN..... | 242..... | 325..... |
| 73..... | 15EO..... | 243..... | 326..... |
| 73A..... | 15EP..... | 244..... | 327..... |
| 74..... | 15EQ..... | 245..... | 328..... |
| 74A..... | 15ER..... | 246..... | 329..... |
| 75..... | 15ES..... | 247..... | 330..... |
| 75A..... | 15ET..... | 248..... | 331..... |
| 76..... | 15EU..... | 249..... | 332..... |
| 76A..... | 15EV..... | 250..... | 333..... |
| 77..... | 15EW..... | 251..... | 334..... |
| 77A..... | 15EX..... | 252..... | 335..... |
| 78..... | 15EY..... | 253..... | 336..... |
| 78A..... | 15EZ..... | 254..... | 337..... |
| 79..... | 15FA..... | 255..... | 338..... |
| 79A..... | 15FB..... | 256..... | 339..... |
| 80..... | 15FC..... | 257..... | 340..... |
| 80A..... | 15FD..... | 258..... | 341..... |
| 81..... | 15FE..... | 259..... | 342..... |
| 81A..... | 15FF..... | 260..... | 343..... |
| 82..... | 15FG..... | 261..... | 344..... |
| 82A..... | 15FH..... | 262..... | 345..... |
| 83..... | 15FI..... | 263..... | 346..... |
| 83A..... | 15FJ..... | 264..... | 347..... |
| 84..... | 15FK..... | 265..... | 348..... |
| 84A..... | 15FL..... | 266..... | 349..... |
| 85..... | 15FM..... | 267..... | 350..... |
| 85A..... | 15FN..... | 268..... | 351..... |
| 86..... | 15FO..... | 269..... | 352..... |
| 86A..... | 15FP..... | 270..... | 353..... |
| 87..... | 15FQ..... | 271..... | 354..... |
| 87A..... | 15FR..... | 272..... | 355..... |
| 88..... | 15FS..... | 273..... | 356..... |
| 88A..... | 15FT..... | 274..... | 357..... |
| 89..... | 15FU..... | 275..... | 358..... |
| 89A..... | 15FV..... | 276..... | 359..... |
| 90..... | 15FW..... | 277..... | 360..... |
| 90A..... | 15FX..... | 278..... | 361..... |
| 91..... | 15FY..... | 279..... | 362..... |
| 91A..... | 15FZ..... | 280..... | 363..... |
| 92..... | 15GA..... | 281..... | 364..... |
| 92A..... | 15GB..... | 282..... | 365..... |
| 93..... | 15GC..... | 283..... | 366..... |
| 93A..... | 15GD..... | 284..... | 367..... |
| 94..... | 15GE..... | 285..... | 368..... |
| 94A..... | 15GF..... | 286..... | 369..... |
| 95..... | 15GG..... | 287..... | 370..... |
| 95A..... | 15GH..... | 288..... | 371..... |
| 96..... | 15GG..... | 289..... | 372..... |
| 96A..... | 15GI..... | 290..... | 373..... |
| 97..... | 15GJ..... | 291..... | 374..... |
| 97A..... | 15GK..... | 292..... | 375..... |
| 98..... | 15GL..... | 293..... | 376..... |
| 98A..... | 15GM..... | 294..... | 377..... |
| 99..... | 15GN..... | 295..... | 378..... |
| 99A..... | 15GO..... | 296..... | 379..... |
| 100..... | 15GP..... | 297..... | 380..... |
| 100A..... | 15GQ..... | 298..... | 381..... |
| 101..... | 15GR..... | 299..... | 382..... |
| 101A..... | 15GS..... | 300..... | 383..... |
| 102..... | 15GT..... | 301..... | 384..... |
| 102A..... | 15GU..... | 302..... | 385..... |
| 103..... | 15GV..... | 303..... | 386..... |
| 103A..... | 15GW..... | 304..... | 387..... |
| 104..... | 15GX..... | 305..... | 388..... |
| 104A..... | 15GY..... | 306..... | 389..... |
| 105..... | 15GZ..... | 307..... | 390..... |
| 105A..... | 15HA..... | 308..... | 391..... |
| 106..... | 15HB..... | 309..... | 392..... |
| 106A..... | 15HC..... | 310..... | 393..... |
| 107..... | 15HD..... | 311..... | 394..... |
| 107A..... | 15HE..... | 312..... | 395..... |
| 108..... | 15HF..... | 313..... | 396..... |
| 108A..... | 15HG..... | 314..... | 397..... |
| 109..... | 15HH..... | 315..... | 398..... |
| 109A..... | 15HI..... | 316..... | 399..... |
| 110..... | 15HJ..... | 317..... | 400..... |
| 110A..... | 15HK..... | 318..... | 401..... |
| 111..... | 15HL..... | 319..... | 402..... |
| 111A..... | 15HM..... | 320..... | 403..... |
| 112..... | 15HN..... | 321..... | 404..... |
| 112A..... | 15HO..... | 322..... | 405..... |
| 113..... | 15HP..... | 323..... | 406..... |
| 113A..... | 15HQ..... | 324..... | 407..... |
| 114..... | 15HR..... | 325..... | 408..... |
| 114A..... | 15HS..... | 326..... | 409..... |
| 115..... | 15HT..... | 327..... | 410..... |
| 115A..... | 15HU..... | 328..... | 411..... |
| 116..... | 15HV..... | 329..... | 412..... |
| 116A..... | 15HW..... | 330..... | 413..... |
| 117..... | 15HX..... | 331..... | 414..... |
| 117A..... | 15HY..... | 332..... | 415..... |
| 118..... | 15HZ..... | 333..... | 416..... |
| 118A..... | 15IA..... | 334..... | 417..... |
| 119..... | 15IB..... | 335..... | 418..... |
| 119A..... | 15IC..... | 336..... | 419..... |
| 120..... | 15ID..... | 337..... | 420..... |
| 120A..... | 15IE..... | 338..... | 421..... |
| 121..... | 15IF..... | 339..... | 422..... |
| 121A..... | 15IG..... | 340..... | 423..... |
| 122..... | 15IH..... | 341..... | 424..... |
| 122A..... | 15II..... | 342..... | 425..... |
| 123..... | 15IJ..... | 343..... | 426..... |
| 123A..... | 15IK..... | 344..... | 427..... |
| 124..... | 15IL..... | 345..... | 428..... |
| 124A..... | 15IN..... | 346..... | 429..... |
| 125..... | 15IO..... | 347..... | 430..... |
| 125A..... | 15IP..... | 348..... | 431..... |
| 126..... | 15IQ..... | 349..... | 432..... |
| 126A..... | 15IR..... | 350..... | 433..... |
| 127..... | 15IS..... | 351..... | 434..... |
| 127A..... | 15IT..... | 352..... | 435..... |
| 128..... | 15IU..... | 353..... | 436..... |
| 128A..... | 15IV..... | 354..... | 437..... |
| 129..... | 15IW..... | 355..... | 438..... |
| 129A..... | 15IX..... | 356..... | 439..... |
| 130..... | 15IY..... | 357..... | 440..... |
| 130A..... | 15IZ..... | 358..... | 441..... |
| 131..... | 15JA..... | 359..... | 442..... |
| 131A..... | 15JB..... | 360..... | 443..... |
| 132..... | 15JC..... | 361..... | 444..... |
| 132A..... | 15JD..... | 362..... | 445..... |
| 133..... | 15JE..... | 363..... | 446..... |
| 133A..... | 15JF..... | 364..... | 447..... |
| 134..... | 15JG..... | 365..... | 448..... |
| 134A..... | 15JH..... | 366..... | 449..... |
| 135..... | 15JI..... | 367..... | 450..... |
| 135A..... | 15JJ..... | 368..... | 451..... |
| 136..... | 15JK..... | 369..... | 452..... |
| 136A..... | 15JL..... | 370..... | 453..... |
| 137..... | 15JM..... | 371..... | 454..... |
| 137A..... | 15JN..... | 372..... | 455..... |
| 138..... | 15JO..... | 373..... | 456..... |
| 138A..... | 15JP..... | 374..... | 457..... |

| Core | Original Series | Core | Original Series | Core | Original Series |
|------|--------------------|------|--------------------|------|--------------------|
| 55A | Sh: K- 44 | 80 | Sh: P- 84 | 123 | Sh: J- 110 |
| 56 | 45 | 81 | K- | 124 | 117 |
| 57 | 46 | 82 | 70 | 125 | 118 |
| 57A | 47 | 83 | 71 | 126 | 119 |
| 57B | 48 | 84 | 72 | 127 | 120 |
| 57C | 49 | 85 | 73 | 128 | 121 |
| 58 | 50 | 86 | 74 | 129 | 122 |
| 59 | 51 | 86S | 75 | 131 | 123 |
| 60 | 52 | 87 | 76 | 133 | 124 |
| 61 | 53 | 88 | 77 | 134 | 125 |
| 61A | 54 | 101 | J- 96 | 135 | 126 |
| 62 | 55 | 102 | 97 | 136 | 127 |
| 63 | 56 | 103 | 98 | 137 | 128 |
| 64 | 57 | 104 | 99 | 193 | P- 76 |
| 65 | 58 | 105 | 100 | 201 | Q- 20 |
| 66 | 59 | 106 | 101 | 202 | 30 |
| 67 | 60 | 107 | 102 | 203 | 31 |
| 68 | 61 | 108 | 103 | 204 | 32 |
| 69 | 62 | 109 | 104 | 205 | 33 |
| 70 | 63 | 110 | 105 | 207 | 34 |
| 71 | 64 | 111 | 106 | 208 | 35 |
| 72 | 65 | 112 | 107 | 209 | 36 |
| 73 | 66 | 113 | 108 | 210 | 37 |
| 74 | 67 | 114 | 109 | 218 | 38 |
| 75 | 68 | 115 | 110 | 219 | 39 |
| 76 | 81 | 116 | 111 | 220 | 40 |
| 77 | 82 | 117 | 112 | 221 | 41 |
| 77A | 83 | 118 | 113 | 222 | 42 |
| 78 | P- 82 | 121 | 114 | 307 | L- 30 |
| 79 | 83 | 122 | 115 | 324 | 40 |

GENERAL GEOLOGY OF THE AQUIFER SYSTEMS

The Memphis area is in the northern part of the East Gulf Coastal Plain, near the axis of the Mississippi embayment structural trough (fig. 1). About 3,000 feet of unconsolidated clay, silt, sand, and gravel has been deposited in this area, and these sediments provide a record of the several invasions and recessions of the sea and the intervening periods of erosion that have occurred since the beginning of Cretaceous time. This wedge-shaped sequence of deposits thickens southward toward the Gulf of Mexico and westward toward the Mississippi River.

Stearns and Armstrong (1955, p. 6-7) and Stearns (1957, p. 1084-1085) described the depositional environmental relations and defined three sedimentary rock types that best illustrate these relations in the northern part of the Mississippi embayment. These types are described briefly as follows:

Back-beach clay and sand. Back-beach beds consist of light-colored clay, lignite, and discontinuous beds of sand. The clay beds, in contrast with those of a more marine environment, are character-

ized by the presence of leaf imprints and the general absence of glauconite. These clay and sand deposits are of limited areal extent and therefore cannot be traced easily in the subsurface, even by means of geophysical logs of closely spaced wells. The irregularly interbedded sediments in the upper part of the Claiborne Group (table 1) are typical of the back-beach deposits.

Shallow-water near-shore sand. Well-sorted sand interbedded with glauconitic and fossiliferous clay is characteristic of the shallow-water near-shore deposits. The sand is areally extensive, in contrast with the back-beach deposits. Where sand beds grade laterally or vertically into back-beach beds, they contain lignite and wood fragments; where they grade into deeper-water clay beds, they contain glauconite. The sandy middle unit ("1,400-foot" sand) of the Wilcox Group (table 1) in the Memphis area is typical of the shallow-water near-shore deposits.

Deeper water clay and shale. The deeper water clay and shale is medium gray to dark gray and contains marine fossils, calcareous beds, and glauconite. These beds are thick and areally extensive and therefore are easily recognized and traced in the subsurface by means of drillers' logs and geophysical logs of wells. In the Memphis area, typical deposits of this category are the marine facies of the Jackson (1) Formation and the upper clay unit of the Wilcox Group.

DESCRIPTION OF THE GEOLOGIC UNITS

The Memphis area is underlain by about 3,000 feet of clay, silt, sand, and gravel ranging in age from Cretaceous through Recent. These sediments were deposited on the limestone rocks of Paleozoic age that form the bedrock floor of the Mississippi embayment syncline. This report deals primarily with the geology related to the two principal aquifers in the Memphis area, and for this reason only the stratigraphic units of Eocene and younger age are discussed in detail. These units (table 1) include the major aquifers, the "1,400-foot" sand of the Wilcox Group, and the "500-foot" sand of the Claiborne Group (Kazmann, 1944, p. 2).

WILCOX GROUP

On the basis of drillers' logs and geophysical logs of wells in the Memphis area, the Wilcox Group is divided into a lower clay unit, a middle sand unit ("1,400-foot" sand), and an upper clay unit (Criner and Armstrong, 1958, p. 3).

The lower unit of the Wilcox Group consists of gray to greenish-gray lignite clay which grades upward into silt and fine-grained sand deposits. The percentage of sand increases upward in this unit, perhaps representing a transitional phase between the marine Porters

Potter Creek Clay and the predominately sandy middle unit of the Wilcox. The clay unit ranges in thickness from 130 feet in test well Pa: W-1 about 30 miles northeast of Memphis near Bruden, Fayette County, to 250 feet in well Sh: U-12, 3.5 miles south of Millington, Shelby County (pl. 1).

The middle sand unit is referred to as the "1,400-foot" sand by Criner and Armstrong (1958, p. 3), consists mostly of unconsolidated well-sorted fine- to medium-grained sand. Logs of a few wells in the Memphis area show thin interbedded lenses of clay, but these beds probably are not areally extensive. The sand ranges in thickness from 150 feet in test well Pa: W-1 near Bruden, Fayette County, to 240 feet in well Sh: U-12, 3.5 miles south of Millington, Shelby County (pl. 1). The thickness increases westward to 300 feet in an oil-test well 7 miles west of West Memphis, Ark.

The upper unit of the Wilcox Group in the Memphis area consists of dark-gray or brown lignitic clay containing local lenses of silty and sandy clay from 1 to 50 feet thick. Thin beds of fine-grained sand cemented with iron oxide form "rock" layers a few inches thick in many parts of the unit. The upper clay of the Wilcox grades upward to a sandy clay; however, the contact with the overlying sand of the Claiborne Group is distinct, as is indicated by geophysical logs (pl. 1) of wells in the area. The thickness of the upper clay section varies greatly, ranging from 200 to 395 feet in the Shenhan well field in the south-central part of Shelby County.

CLAIBORNE GROUP

The Claiborne Group in the Memphis area is represented by the "500-foot" sand, which has been divided into lower and upper parts by Criner and Armstrong (1958, p. 7-8). This subdivision was based on the different lithologies of the two parts and on their separation in much of the area by clay beds as much as 150 feet thick. Electrical logs and drillers' logs of wells show that the lower part of the Claiborne varies greatly in thickness and contains a greater number of clay beds that are thicker and more extensive than those in the upper part. Even the thickest of the clay beds, however, are not continuous, so that no particular bed can be considered as a hydrologic boundary between distinctive lower and upper parts. In this report, therefore, the "500-foot" sand is considered as a single hydrologic unit. Generally the Claiborne Group is characterized by a greater proportion of clay in the lower part and by a gradation in sand particle size from fine to medium grained in the lower part to medium to coarse grained in the upper part. The thickest and most extensive clay bed underlies the central part of the Memphis area and is in the lower part of the Claiborne Group.

TABLE 1.—Geologic units underlying the Memphis area

| Series | Group | Stratigraphic unit | Thickness (feet) | Description and relation to water | |
|------------|------------------|---|------------------|---|------------|
| | | | | Adverse | Beneficial |
| Quaternary | Recent | Adverse | 0-200 | Alluvial sand, clay, and gravel. Few domestic wells. Could be important source of water for some industrial uses. | |
| | Prehistoric | Lens | 0-100 | Water-bearing alluvium. (Topography higher than alluvium.) Low potential. Not a source of ground water. | |
| | (or) Pleistocene | Thinner deposits | 0-200 | Artesian sand and gravel. Several domestic wells. Could be major source of water for industrial and irrigation uses. | |
| | | Section (?) from lens (lower part of section) | 0-200 | Gray, lignitic, sandy clay, and thin beds of lignitic sand. Considered to be upper part of section. | |
| Tertiary | Claiborne | "500-foot" sand (lower part) | 100-400 | Thin to coarse-grained sand; lower portions of fine and tan clay and silty sand clay and lignitic lenses. Thick clay bed locally at base. Center channel of river was in section. | |
| | | Upper clay unit | 200-300 | Gray, greenish-gray, and brown mottled clay. Thin lignitic and fine-grained sand lenses locally. Low permeability unless water in "1,400-foot" sand. | |
| | Wilcox | Middle sand unit ("1,400-foot" sand) | 130-250 | Thin to medium-grained sand; lower portions of lignitic and clay lenses. Fine-grained lignitic sand which supplies about 10 percent of water used in Memphis area. | |
| | | Lower clay unit | 100-250 | Gray, greenish-gray, and brown mottled clay, and lignitic, sandy and silty lenses locally. Probably lower sandstone bed in "1,400-foot" sand. | |

PLATE 1

The thickness of the Claiborne Group ranges from 500 feet in test well Fa: W-1 near Itaden, Fayette County, to 800 feet in well Sh: J-101 in the southern part of the city of Memphis (pl. 1). The top of the "500-foot" sand was indicated in geophysical logs of wells as the level at which the sediments change from predominantly sand to predominantly clay or silt. The contacts were picked to define a hydrologic unit ("500-foot" sand regardless of geologic age. For this reason the upper part of the unit as shown on plate 1 may include some sandy beds belonging to the overlying Jackson (f) Formation.

JACKSON(f) FORMATION

The Jackson(f) Formation overlies and confines the "500-foot" sand. Locally the two units interfinger with one another, and the contact between them represents a hydrologic boundary rather than a precise stratigraphic horizon (pl. 1).

The Jackson(f) Formation is composed of dark-gray to greenish-gray, dark-blue, or dark-brown clay. It is generally carbonaceous and contains very fine quartz sand along bedding planes. The formation is absent in southeastern Shelby County but is as much as 330 feet thick in the Parkway well field.

Fisk (1944, fig. 67, p. 62) distinguished a lower marine and an upper nonmarine facies in the Jackson(f) Formation. The marine facies closely follows the present course of the Mississippi River and extends northward at least 25 miles to Lauderdale County; there an exposure contains glauconite, foraminifera, shark teeth, and bones of sea animals. Fossil plants and leaves are abundant, and seams of lignite as much as 10 feet thick are common in the nonmarine facies.

TERRACE DEPOSITS AND ALLUVIUM

The terrace deposits range from a few feet to about 100 feet in thickness and are composed mostly of coarse-grained quartz sand and fine-grained iron-stained quartz and chert gravel. Thin lenses of silty, ochre-colored clay are common in the lower part. The bottom 3 inches to 1 foot of sand and gravel generally is cemented with limonite. Although the contact with the Jackson(f) Formation represents an erosional surface, thin lenses of reworked Jackson(f) clay and sand form a transitional zone at the base of the terrace deposits in many places; geophysical logs show a gradation from one unit to the other.

The terrace deposits occur as an irregular belt parallel to the Mississippi River and also occur along the larger streams in the area. The deposits thin gradually eastward and are absent in many places as a result of erosion or nondeposition.

Two terraces were recognized by Glenn (1906, p. 41-44), who designated them as Pliocene and the lower as Pleistocene. Fisk

(1944, p. 63) considered them both to be of Pleistocene age. Because geophysical logs show no consistent correlation points, by means of which the terrace deposits can be divided in the subsurface, they are considered as a single unit in this report.

The alluvium ranges from 0 to 200 feet in thickness and is composed of sand, clay, silt, and gravel. It is confined to narrow strips along the principal streams and in most places is subject to flooding and reworking. The coarsest material is generally near the present stream channels, and the finest is near the feathered edges of the deposits.

The alluvium is lithologically similar to the underlying terrace deposits, and the contact cannot be determined from geophysical logs. However, samples of the alluvium locally contain carbonaceous material and decaying vegetation which aid in distinguishing between the two units.

GEOLOGIC STRUCTURE

The Memphis area is near the axis of the Mississippi embayment syncline, which plunges southward at a rate of about 10 feet per mile in the vicinity of Memphis. The syncline began to form in Late Cretaceous time (Fisk, 1944, p. 8, 64; and Caplan, 1954, p. 5) as a result of regional subsidence centered along the present coast of the Gulf of Mexico. The axis of the structural trough approximately follows the present course of the Mississippi River.

As the region subsided, faulting of the unconsolidated sediments and the underlying Paleozoic rocks occurred, forming a rectangular pattern of faults and fractures trending northeast and northwest (Fisk, 1944, p. 64, 66). One of the major faults in this system, the Big Creek fault (Fisk, 1944, p. 66), trends northeast from near West Helena, Ark., along the western edge of the Memphis area to Reelfoot Lake near the Tennessee-Kentucky border; at Reelfoot Lake it appears to be related to the New Madrid (Missouri) fault system. This fault is of particular significance because it apparently restricts the movement of ground water from the west into the Memphis area.

A major fault is suggested by an abrupt bend in the Mississippi River near the mouth of Necessim Creek and by electrical logs of wells that indicate as much as 50 feet of displacement of geologic units in the Hickory Hill well field in the south-central part of the area. If such a fault exists, it has so far had little effect on the movement of water in the "500-foot" sand.

HYDROLOGY OF THE AQUIFER SYSTEMS

GEOLOGIC CONTROL OF GROUND WATER IN THE MEMPHIS AREA

The size, shape, and degree of interconnection of the open spaces

cepted, stored, and eventually discharged to wells or by natural subsurface ground-water movement. In the Memphis area all ground water is obtained from unconsolidated deposits of sand and gravel.

Deposits of rounded well-sorted rock particles are the most permeable water-bearing materials because ground water can move freely through them toward pumping wells and into the aquifer in its recharge area. Mechanical analyses of sand samples from the "500-foot" and "1,400-foot" sands in the Memphis area show the sand particles to be well sorted but angular to subangular in shape. Although compaction and cementation affect the water-bearing properties of sand aquifers, these processes are of minor significance in the Memphis area, where cemented beds are rare and are seldom more than 1 foot thick. Faulting may also affect the ground-water conditions in an area by displacement of strata or by formation of a semi-impermeable barrier along the faulted zone. In the Memphis area the only structural deformation believed to affect ground-water movement is the previously described Big Creek fault, which restricts the inflow of ground water from the west. Relative positions of aquifers and confining clay beds also affect ground-water conditions in the Memphis area. In the outcrop area of the "500-foot" and "1,400-foot" sands east of Shelby County, water-table conditions exist. West of the outcrop, or recharge, area, however, confining beds of clay overlie the aquifers, and the water is under artesian pressure. As the water moves downward in the westward dipping aquifers, the pressure surface becomes progressively higher above the confining clay beds which overlie the aquifers.

TEXTURE OF AQUIFER MATERIALS

More than 400 sand samples collected from many drilled wells in the Memphis area were analyzed to determine the distribution of particle size and the degree of sorting. These analyses give an indication of the hydraulic characteristics of the rocks because the size and sorting of the sand grains determine, to a great degree, the permeability and porosity. Coarse-grained sediments are less porous than fine-grained sediments; but because the pores are larger in the coarse-grained sediments, they are more permeable and will allow water to move through them more readily. Poorly sorted sediments are both less porous and less permeable than well-sorted sediments.

(Comparison of one sample with another can best be made by comparing their respective sorting coefficients. The sorting coefficient is defined as the square root of the 75 percentile divided by the 25 percentile (Trask, 1932, p. 72). A value of 1 (unity) represents the highest possible degree of sorting. A sorting coefficient smaller than 1 indicates a well-sorted sample, a normal sample, and 4 or 5 or


higher, a poorly sorted sample. Sorting coefficients of samples from both the "500-foot" and "1,400-foot" sands (fig. 4) range from 1.1 to 1.3. The steepness of the curves (fig. 4), also shows that the sand is well sorted.

The size-distribution curves also show that the grain size of material from the "1,400-foot" sand is fine to medium and that the grain size of material from the upper part of the "500-foot" sand is medium to coarse. Analyses of samples from the lower part of the "500-foot" sand are not shown in figure 4, but the particle-size distribution in the lower part is known to be similar to that in the "1,400-foot" sand.

In summary, particle-size distribution and sorting coefficient of aquifer materials are a measure of the aquifer's capability to transmit water to wells and therefore are useful in determining the best zone in the aquifer to be screened in a well and the type and opening size of screen to be used.

EFFECTS OF GROUND-WATER WITHDRAWAL

The most conspicuous effect of withdrawal of water from an aquifer is the decline of water level that causes a cone of depression to form in the water surface surrounding the point of withdrawal. The size of



the cone of depression formed by pumping a well or group of wells depends on the rate and amount of withdrawal and the hydraulic characteristics of the aquifer. Near the edge of the cone, the water-level depression or drawdown is small and, in effect, immeasurable because it is less than fluctuations caused by atmospheric-pressure changes and other influences. The theoretical distance to the edge of the cone of depression for a typical well field in the "500-foot" sand in the Memphis area pumping at an average rate of 10 mgd (million gallons per day) is about 5 miles from the center of withdrawal.

Increases in the annual rate of withdrawal have accelerated the lowering of the piezometric surface in the entire Memphis area so that the hydraulic gradient (slope of the water or pressure surface) is continually steepening. Consequently, larger amounts of water are transmitted into the area to supply the increased withdrawal. Figure 5 shows the Memphis municipal and industrial pumpage since 1898, and figure 6 shows the total municipal and industrial pumpage from the "500-foot" and the "1,400-foot" sands and the resulting water-level declines in the Memphis area from 1935 through 1960. As the rate of withdrawal increases, the regional cone of depression is expanded and deepened.

Under natural conditions, water was discharged from the "500-foot" and "1,400-foot" sands by subsurface flow to the west, thence southward along the axis of the embayment. Beginning with the first well drilled into the "500-foot" sand in 1886 (Lundie, 1898, p. 5-6), pumping has constantly increased, causing ground water to move into the enlarging cone of depression, thus eventually causing natural discharge as subsurface flow to stop.

THE "500-FOOT" SAND AQUIFER

DELINEATION

The "500-foot" sand in the Memphis area is delineated as a hydrologic unit although it includes all the deposits of the Claiborne Group. Geophysical logs of wells were used to identify the top and bottom of the aquifer as limited by the overlying and underlying confining clay. Most of the logs show distinct differences between the aquifer and the confining clay beds; however some show gradational changes from predominantly clay to predominantly sand beds. In the absence of a distinct and abrupt sand-clay contact, the boundary is selected arbitrarily at the middle of the transition zone in order to determine the average thickness of the aquifer. Delineated on this basis, the aquifer also may include some sandy beds of the lower part of the Jackson (1) Formation. In some parts of the area the Jackson (1) is not present.




FIGURE 6.—Memphis municipal pumpage, 1898-1960.

period, has formed a major cone of depression under the city of Memphis, where most of the pumping is concentrated, and has formed smaller superimposed cones under the Parkway, Allen, and Sheahan well fields (pl. 4). The regional relation between ground-water withdrawal and water-level decline in the "500-foot" sand is best illustrated by the hydrograph of well Sh: P-76 (fig. 7). This well is in the center of the major or regional cone of depression and is approximately equidistant from the smaller superimposed cones of depression caused by pumping in the Parkway, Allen, and Sheahan well fields. During 1935-40 an average rate of withdrawal of about 100 mgd resulted in a water-level decline of about 50 feet in well Sh: P-76, or about one-half foot decline for each million gallons pumped per day. Figure 8 shows progressively smaller declines in well Sh: O-1, 8 miles north of the center of pumping, and in well Sh: Q-1, 10 miles east of the center of pumping. Figure 9 shows still smaller declines in wells Sh: U-2, 15 miles north, and Fa: W-2 (Fayette County), 30 miles northeast of the center of heavy pumping.

The rate of water-level decline has increased since the early 1950's, at which time the rate of pumping increased to an average of about 120 mgd (1950-60) compared with an average of about 90 mgd for the preceding period (1935-50). The maximum decline for the period 1950-60 is about 47 feet in the Allen well field (pl. 5), which was placed in operation in early 1953. About 75 percent of this decline occurred in the first year of operation of this field. Smaller declines occurred in the Parkway and Sheahan well fields (pl. 5) during this period because these fields have been in operation since 1921 and 1931, respectively (fig. 5), and the rates of decline in each have decreased as their cones of depression have expanded and established a stable hydraulic gradient. The 24-foot decline in the McCord well field occurred after early 1958, when the field began operation. As in the Allen well field, the rate of decline in the early years of operation is greater than that in subsequent years, provided the rate of ground-water withdrawal remains the same.

Prior to 1958, when the McCord well field began operation, water levels in the field declined slowly and steadily (fig. 10) as a result of overall pumping in the Memphis area. In 1958, the water level in an observation well near the McCord well field (fig. 10) declined about 18 feet for an average pumping rate of 12.5 mgd. Thus the relation between the water-level decline in this observation well and the pumping rate of the well field was about 1.5 feet for each 1 mgd pumped. The next pronounced change in the rate of pumping occurred during the summer of 1960 when, between June and August, the pumping rate decreased from about 11.5 to 7.5 mgd. The water level in wells near

018 CONTRIBUTIONS TO THE HYDROLOGY OF THE UNITED STATES




FIGURE 8.—Relation between total pumping from the "500-foot" and "1,000-foot" sands and water-level declines in the Memphis area, 1935-60.



posed of coarse sand and gravel. These deposits are hydrologically connected with the "500-foot" sand in such areas but are not considered a part of the aquifer.

Plates 2 and 3 show the elevation and configuration of the top and bottom, respectively, of the "500-foot" sand in the Memphis area. These maps and the geologic section (pl. 1) show that the "500-foot" sand ranges from 500 to 800 feet in thickness, averaging about 700 feet thick, and dips toward the northwest at a rate of about 13 feet per mile. The volume of the aquifer, calculated from the contour maps, is about 25 trillion (25×10^{12}) cubic feet in the 1,300 square mile area shown in plates 2 and 3.

WATER LEVELS

DECLINE CAUSED BY PUMPING

Ground-water withdrawal from the "500-foot" sand for municipal and industrial use in the Memphis area has increased from about 68 mgd in 1935, the first year for which records are available, to about 135 mgd in 1960. This withdrawal, which averages about 100 mgd during






FIGURE 8.—Decline of water level in the "300-foot" sand, 15 and 30 miles from the center of concentrated pumping in the Memphis area.

the well field rose about 4 feet. Normally during this part of the year, the water level declines about 2 feet. Therefore, the effective recovery resulting from the pumpage reduction was about 6 feet. This again indicates a ratio between water-level rise or decline in the selected observation wells and pumpage of about 1.5 feet for each 1 mgd change in rate of pumping. Similar determinations for the Allen (fig. 11) and Sheahan (fig. 12) well fields indicate ratios of 1.1 to 1 and 1.5 to 1 (feet of decline or rise to each million gallons per day increase or decrease in pumping) for these fields, respectively. The production ratio for the Allen well field is less because pumping has not continued long enough for the piezometric surface to stabilize in this newer well field. The production ratio for all well fields in the area should increase as water levels decline toward more stable pumping levels.

The distribution of production wells in the Parkway well field with respect to observation wells make it impossible to show a consistent relationship between the water level and the pumpage in this well field (fig. 13). The fluctuations resulting from seasonal and intermittent pumping are the only discernible parts of water-level changes. Figure 13 shows that a reduction of pumpage during 1945-49 did not cause a rise of water level in observation well 5h: O-153. This well is in the eastern part of the well field where the pumping rate was increased to offset the reduction in pumping in the western part of the well field. However, records of short-term observation wells indicate that the relation between water level and pumping differs little from that of




FIGURE 10.—The relation between pumping and water level ("500-foot" sand) in the McCord well field, Memphis, Tenn.




FIGURE 11.—The relation between pumping and water level ("500-foot" sand) in the Allen well field, Memphis, Tenn.

The hydrographs from observation wells equipped with recording gages generally show that those wells within or near the area of greatest withdrawal have their lowest water level in August each year, reflecting the highest monthly rate of withdrawal. Figures 7-9 show the declining trend of water level in the "500-foot" sand at various distances from the center of pumping as well as the annual low water level. The lowest annual water level occurs progressively later in observation wells that are farther from the center of pumping. The greater the distance, the greater the lag in the time of arrival of the effect of pumping. The lowest annual water level in observation well Pa: W-2 (fig. 9), which is 30 miles from the theoretical center of pumping, occurs in late December or early January, or about 4 months after the annual low water level in Memphis. The effect of cyclical pumping in the Memphis area, where the pumping is greater in summer than winter, is a wavelike motion of alternate low and high water levels traveling outward at a decreasing rate from the center of pumping.




FIGURE 12.—The relation between pumping and water level ("500-foot" sand) in the Sheehan well field, Memphis, Tenn.

bination of several factors including the degree of confinement, elasticity, and transmissibility of the aquifer. This effect should be considered when proposing locations of future well fields so that advance can be made of the time lag of arrival of low water level. In a practical example, a typical well field about 20 miles from Memphis would be pumping at its lowest seasonal rate at a time when water levels are lowest and pumping most water at the time when water levels are highest.

Hydrographs of observation wells in the "500-foot" sand (figs. 7-9) indicate that the annual decline of the piezometric surface can be reasonably estimated for given rates of pumping. These figures show the fluctuations and general decline of water level in the Memphis area near the center of pumping (fig. 7), about 8 and 10 miles from the center of pumping (fig. 8), and 15 and 30 miles from the center of pumping (fig. 9). The theoretical center of pumping in the area is about the location of observation well Sh: P-76 (pls. 4, 6). Figure 9 shows that the seasonal fluctuation of water level in well Fa: W-2 about 30 miles northeast of Memphis in Fayette County is nearly 1 foot. The overall water-level trend is a declining one, although there are short periods of a rising water level caused by reductions in pumping rate, recharge to the aquifer, or both. This observation-well record reflects the regional water-level fluctuations and is less affected by small changes in pumping in Memphis. The seasonal range of water-level fluctuation in well Sh: U-2 in Memphis (fig. 9) has been about 3.5 feet except in 1957, a year of record-high rainfall. The record of this well also indicates the regional water-level trend, but the effect of changes in pumping in Memphis is more pronounced in this record than in that of well Fa: W-2.

FLUCTUATION

Precipitation causes water-level fluctuations in wells by recharging the aquifer in its outcrop area, by seeping through the overlying clay where they are thin or missing, and, to a minor extent, by leakage. The effect of recharge to the aquifer caused by unusually high precipitation is illustrated in the hydrograph of well Fa: W-2 for 1957 (fig. 9). The water level in this well under normal conditions of rainfall and pumping in the Memphis area would have declined about 0.3 foot in 1957. Instead, the water level rose about 0.8 foot, an effective change of 1.1 feet. Past records indicate that a reduction of pumping of 10-20 mgd in Memphis would have been required to cause a 1.1-foot change in water level in this observation well. The annual average daily pumping in 1957 was only about 1 mgd less than in the previous year. Therefore, the rise of water level in 1957 was largely due to recharge from heavy rainfall in the outcrop area of the "500-foot" sand.




FIGURE 13.—The relation between pumping and water level ("500-foot" sand) in the Parkway well field, Memphis, Tenn.

Loading of an aquifer, as by passing railroad trains and by rainfall, may also cause water-level fluctuations; but for a specific load the net water-level change is zero, and no rising or declining trend results. Generally, the water level rises as a load is applied then decreases rapidly even though the load may remain. Wells (1931, p. 26) believed that the Mississippi River added water to the "500-foot" sand, because a series of water-level measurements in wells along the river were higher when the river was high. Data collected by Kazmann (oral communication, 1964), however, indicated that loading of the aquifer by the weight of rapidly rising water in the river caused the water level also to rise in certain wells. In agreement with Kazmann's conclusion, it is doubtful that the river would have furnished water to the aquifer even if there had been a hydraulic connection between the river and the aquifer, because at that time (1931) the water level in the aquifer was about as high as the level of the river.

Atmospheric-pressure fluctuations may cause as much as a foot of change in water-level, depending partly on the rapidity of the change in pressure. These are basically daily-cycle fluctuations and are considered only during strict aquifer performance tests when water-level measurements are corrected for barometric effect. Within a short time the pressure-influenced water level regains its original level, often with the assistance of a reverse change in atmospheric pressure. The net change in water level resulting from atmospheric pressure change is zero over a period of time, generally 1 day.

HYDRAULIC CHARACTERISTICS

The amount of water that can be pumped from an aquifer perennially depends primarily on the capacity of the aquifer to transmit water from areas of recharge to areas of discharge, the amount of water available for recharge, and the amount of water in storage in the aquifer. To estimate the amount of water that can be pumped perennially with proper accuracy, the hydraulic characteristics of the aquifer must be known. Aquifer performance or pumping tests are the most economical method of determining the hydraulic characteristics. These characteristics are permeability (P), transmissibility (T), and storage (S). These and other terms used to describe the hydrologic properties of rocks were defined by Meinzer (1923), Wenzel (1912), and Ferris and others (1962).

Pumping tests consist of observing the rate of drawdown in observation wells for a given uniform rate of pumping in a nearby well or of observing the rate of water level recovery in a pumped well, or observation wells, after pumping stops. Pumping-test data were analyzed by standard methods, and the results were approximately the

same as the values of the hydraulic characteristics. For this reason the less laborious semilog-plot method is used in this report.

Figure 14 shows a semilog plot and sample analysis of pumping-test




FIGURE 14.—Sample computations of transmissibility and storage coefficients for the "500-foot" sand using plotted pumping test data.

data from wells in the "500-foot" sand. The figure also shows the procedure for computing the hydraulic characteristics of the aquifer.

The numerical values of hydraulic characteristics determined by pumping tests reflect the effects of all material within the zone of influence of pumping in the aquifer. This zone extends horizontally to the perimeter of the cone of depression of the pumping well. Its vertical influence may not extend to the bottom of the aquifer because of the anisotropy of the formation and partial penetration of the wells. As a result, a single pumping test provides hydraulic constants determined by the part of the aquifer affected during the test. These values are adequate for predicting aquifer response for that particular affected area under conditions generally the same as those prevailing during the period of the test. The values of the hydraulic characteristics of the total volume of the aquifer were determined by averaging the results of all tests and adjusting them for partial penetration of wells and other factors.

The wells that were used in all tests of the "500-foot" sand in the Memphis area are less than 500 feet deep and penetrate from 5 to 15 percent of the total thickness of the aquifer. Local clay lenses are

present in above sand (or) below the screens of some wells. The wells range in diameter from 4 to 20 inches; well screens range in diameter from 3 to 12 inches and in length from 10 to 120 feet.

Specific capacity of wells ranges from 10 to 100 gpm per foot of drawdown. The coefficient of transmissibility determined by analyses of data from these tests ranged from 100,000 to 410,000 gpd per ft. and the coefficient of storage from 1×10^{-2} to 3×10^{-1} . The average adjusted coefficients of the "500-foot" sand for the total thickness of the aquifer throughout the entire area are about 400,000 gpd per ft and 3×10^{-2} for T and S , respectively. Average values are used in this report to make quantitative determinations, and these values will be adequate for future determinations where artesian conditions prevail.

RECHARGE AND MOVEMENT

Recharge to the "500-foot" sand aquifer generally occurs in the areas where it lies at or near the land surface. Percolation of rainfall directly through the sandy soil in the outcrop area and seepage from streams recharge the aquifer where it crops out in the rolling hills 30-60 miles east of Memphis. The annual precipitation at Moscow and Bolivar, Tenn., in the recharge area, is slightly greater than at Memphis (fig. 2), and rainfall is fairly well distributed throughout the year.

In addition to recharge in the outcrop area, the "500-foot" sand locally receives some water from the overlying terrace deposits where ever the clay bed that generally underlies the terrace deposits is sand or thin and where streams have cut deeply into the clay bed. Monocah Creek, formerly a perennial stream, now has periods of abnormal low flow in its lower reach during part of the year and has been dry during the latter part of the dry season in recent years. This change in its regimen is attributed to increased seepage to the "500-foot" sand as a result of the decline of water level in the aquifer within the past few years. Recharge to the aquifer probably is increasing as the effect of pumping in the Memphis area is felt in the outcrop area and areas where seepage can occur.

The rate of water movement depends on the transmissibility of the aquifer and the hydraulic gradient. In general, the greater the rate of discharge, the more rapid the movement of water through the aquifer along the flow path. However, limitations on the maximum possible rate of movement are determined by the aquifer characteristics, not by the rate of discharge.

The movement of water in the Memphis area before development of the "500-foot" sand began was probably along the dip of the formation, southward down the

lic gradient between Collierville and Memphis was about 5×10^{-4} in 1886. Using this value for the hydraulic gradient and an average transmissibility of 4×10^5 gpd per ft for the "500-foot" sand aquifer, about 1 million gallons of water moved across each 1-mile section of the aquifer each day in 1886. The eastern boundary of the area is about 30 miles in length; therefore, the average rate of water entering the Memphis area in 1886 was about 30 mgd. If we assume that stable conditions existed at that time, the rate of natural discharge was equal to the recharge rate.

The present direction of movement of ground water in the Memphis area is generally toward central Memphis from all directions as shown on plate 4. Water-level contours (pl. 4) indicate that ~~seepage~~ water is derived from the east-southeast; probably because transmissibility is greater in that part of the area, the dip of the "500-foot" sand is toward the northwest (figs. 5, 6), and the nearest area of recharge lies to the southeast. The amount of water moving across the 260-foot contour on plate 4 is about 60 mgd. Total inflow is tabulated in the section on pumping.

The amount of water moving into the area from the west is small, probably because the Big Creek fault forms a hydraulic boundary restricting inflow. Further increases in pumping in the Memphis area will produce steeper gradients and induce a greater amount of water to flow toward the centers of pumping.

The present rate of movement of ground water in the "500-foot" sand in the southeastern part of the area is estimated to be approximately 70 feet per year toward the west-northwest under a hydraulic gradient of about 5 feet per mile (9×10^{-4}). At the edge of the area of heavy withdrawal, approximately 3 miles from the present city limits (pl. 3), the gradient steepens to about 10 feet per mile and the rate of ground-water movement increases accordingly to about 140 feet per year. In and near the well fields, the velocity of flow is even greater. In the northeastern part of the area, the hydraulic gradient is about 3 feet per mile, and the rate of movement about 40 feet per year.

PUMPING

An average of about 135 mgd was pumped from the "500-foot" sand in 1960. A little less than half this amount was for municipal use, and a little more than half was for industrial use. Pumping records reported monthly to U.S. Geological Survey indicate that industrial pumping is nearly constant and that municipal pumping may vary as much as 100 percent from summer to winter. Figure 6 shows the average daily pumping rate for each year since 1935. The effect of

As previously stated, the natural discharge moving out of the Memphis area toward the west and thence southward along the axis of the embayment was about 30 mgd in 1886. Natural discharge probably ceased when the water level was lowered to about 200 feet above mean sea level in central Memphis. The hydraulic gradient created by pumping in Memphis probably was sufficient to stop the natural discharge from the area by 1940.

The total amount of water pumped from the "500-foot" aquifer between 1886 and 1960 is estimated to be about 1.9×10^{12} trillion gallons (1.9×10^{11}). If it is assumed that $S = 3 \times 10^{-3}$ and that the water level declined 60 feet between 1886 and 1960, then the total amount of water pumped from storage is about 19 billion gallons. This quantity is less than 1 percent of the total pumpage since 1886—that is, an average of about 1 percent of the water pumped each year was derived through depletion of storage in the aquifer.

A water-control budget for the "500-foot" sand and aquifer was computed using the low-water-level contours for 1960 (pl. 4) and checked against the average daily pumping rate for 1960. Inflow into the Memphis area was determined to be generally as follows:

| Index | Million gallons per day |
|--|-------------------------------|
| Across eastern boundary..... | 60 |
| Across northern boundary..... | 20 |
| Across southern boundary..... | 25 |
| Across western boundary..... | 20 |
| Depletion of storage..... | 1 |
| Total..... | 135 |
| Average daily pumping rate for 1960..... | 135 |

* Includes leakage from rock above aquifer and inflow of water from other sources.

THE "1,400-FOOT" SAND AQUIFER

DELINEATION

Delineation of the "1,400-foot" sand in the Memphis area is based on the same hydrologic considerations as is delineation of the "500-foot" sand. The upper and lower boundaries (pls. 6, 7) were determined primarily by interpretation of electric and gamma-ray logs which show distinct contacts (pl. 1) of the sand with its confining clay formations. The confining clay formations are thick and for practical purposes may be considered impermeable. The aquifer is continuous throughout the area and dips toward the west at a rate of about 25 feet per mile. The sand probably crops out 60–80 miles east of Memphis although in some

ship, 1950). The thickness of the aquifer increases from about 150 feet in the eastern part of the Memphis area to about 300 feet in the western part. The volume of the aquifer in the 1,300 square mile area is about 7 trillion cubic feet (7×10^{12}).

WATER LEVELS

DECLINE CAUSED BY PUMPING

The relation between water-level fluctuations and pumping in municipal well fields is shown in figures 15 and 16. The two observation wells represented are in the Parkway and Sheshan well fields and clearly show the effect of changes in pumping rates, although the water-level fluctuations cannot be correlated quantitatively with the pumping from each well field because fluctuations caused by natural phenomena obscure the fluctuations caused by pumping. These two municipal well fields and one industrial plant well field are the only ones in Shelby County having one or more wells screened in the "1,400-foot" sand. Nearly all the observation wells are close to production wells in these fields, and intermittent pumping of the production wells often masks any areal water-level trend that might be noted in an observation well several hundred feet from a well field.



The water-level fluctuations in observation wells at greater distances from the areas of heavy withdrawal (fig. 17) are less pronounced, and the hydrographs of these wells reflect regional trends of water level.

The hydrographs in figure 17 show that, except for during 1957 and 1958, the average seasonal fluctuation in well Fa: W-1, about 30 miles northeast of Memphis, is about 1.9 feet; and in well Sh: U-1, about 15 miles north of Memphis, it is about 3.5 feet, or about three times that in well Fa: W-1. The ratio of the logarithms of the two distances mentioned above is also 3, so that a rule can be inferred as follows, relating distance to seasonal fluctuations:

$$\frac{\log 20}{\log 15} \times \text{seasonal fluctuation at 30 miles} = \text{seasonal fluctuation at 15 miles.}$$

This may be a general rule for predicting water-level fluctuations and decline in the Memphis area and possibly other similar areas where no observation wells exist, but it has not been proven.

In wells in the "1,400-foot" sand, water levels declined at an almost constant rate until 1952 as a result of gradual increases in pumping. In 1952 pumping was decreased (fig. 17). However, the trend of decline continued (fig. 17) until 1957 because drought conditions in the outcrop or recharge area of the aquifer prevented immediate replenishment of the water pumped from the Memphis area. Since 1957 the water level has remained about constant. No significant






FIGURE 17.—The relation between total pumping from the "1,400-foot" sand in the Memphis area and water levels in wells W-1 and W-2, 16 and 30 miles, respectively, from the center of pumping.

FLUCTUATION

Water levels in the "1,400-foot" sand fluctuate in response to the same causes discussed earlier for the "500-foot" sand. Fluctuations resulting from atmospheric-pressure changes are slightly more pronounced because the aquifer is under higher artesian pressure and its barometric efficiency is greater. Water level fluctuations resulting from loading are negligible because of the structural support of the greater thickness of material above the aquifer.

Since 1957, water levels have fluctuated primarily in response to rainfall in the outcrop area of the "1,400-foot" sand and aquifer. Hydrographs (fig. 17) show that water levels rose from 1957 to 1959 during a period of normal to above normal precipitation even though pumping increased slightly over the same period. The regional rise of water level is similar to the rise of water level in the "500-foot" sand (fig. 9) during the same period.

HYDRAULIC CHARACTERISTICS

The numerical values of the hydraulic characteristics of the "1,400-foot" sand determined from seven tests in the three well fields in Memphis cover a rather narrow range.

| | Average | Minimum | Maximum |
|-----|--------------------|----------------------|--------------------|
| T | 3×10^{-4} | 90,000 | 140,000 |
| S | 3×10^{-4} | 1.5×10^{-4} | 4×10^{-4} |

An example of test data is shown in figure 18. The highest values of the coefficients were from tests at the Parkway well field (pl. 6), where the thickness of the "1,400-foot" sand is about 15 percent greater than in the other well fields.

The yields of the wells used in the tests ranged from 400 to 1,000 gpm (gallons per minute). The wells range in diameter from 8 to 24 inches. The well screens are 8-10 inches in diameter, 55-120 feet in length, and penetrate less than 50 percent of the thickness of the aquifer.

The aquifer-test results indicate that the "1,400-foot" sand is almost an ideal artesian aquifer. The changes of water level in observation wells in response to changes in the rate of withdrawal were almost instantaneous, indicating near-perfect vertical confinement between the clay boundaries. The barometric efficiency of the aquifer ranged from 75 to more than 95 percent, also indicating near perfect confinement.




FIGURE 18.—Sample computations of transmissibility and storage coefficients for the

Tests made in the same well fields in 1944 and later show that the hydraulic characteristics of the aquifer have not changed appreciably in about 15 years.

The hydraulic constants determined for the "1,400-foot" sand are more reliable than those for the "500-foot" sand, and the constants may be used more extensively because the "1,400-foot" sand is more uniform in texture and thickness.

RECHARGE AND MOVEMENT

In some part of the outcrop area where the "1,400-foot" sand is in contact with the bottom of the "500-foot" sand, the "500-foot" sand outcrop serves as the recharge area for both aquifers (Schneider and Blankenship, 1950, chart 1). Where the sand is exposed at the surface, it receives recharge from precipitation and from seepage from streams. The rate of recharge is influenced by the rate and amount of precipitation, as indicated by hydrographs of wells in the "1,400-foot" sand (fig. 17) which show that the water levels rose in 1957, a year of unusually high rainfall.

The rate of recharge before the development of wells in the aquifer began, based on available data and the assumption that recharge was equal to the natural discharge at that time was about 5 mgd to the Memphis area. The present rate of recharge is unknown but is less than the pumping rate for the area.

The amount of water moving toward a well is proportional to the hydraulic gradient of the cone of depression. Generally, the hydraulic gradient increases as the rate of pumping increases. If the pumping rate remains constant, the cone of depression expands and the hydraulic gradient tends to flatten, other factors being equal, until an equilibrium slope is established. The 1940 rate of withdrawal from the "1,400-foot" sand was about 13 mgd, and this quantity has not varied more than 20 percent during the past decade. The hydrographs of wells F-1 and Sh: 11-1 (fig. 17) show that the hydraulic gradient established in the "1,400-foot" sand has flattened and remained about constant several miles from the area of heavy withdrawal for the past decade also. The gradient 15-30 miles from central Memphis is about 3 feet per mile (or 5.7×10^{-4}), and the rate of movement of water is about 40-50 feet per year.

Water-level data for 1924 (Schneider and Cushing, 1948, p. 9) show that the hydraulic gradient before development of wells in the "1,400-foot" sand was 2.5×10^{-4} and that the transmissibility was 1.2×10^6 gal per ft. Based on these figures the average amount of water that moved westward across a 1-mile section of the "1,400-foot" sand aquifer was about 0.16 mgd, compared to 1 mgd for the "500-foot" sand aquifer.

This rate of movement is equal to the natural discharge and recharge before the development of wells in the aquifer.

PUMPING

The average daily rate of withdrawal of water from the "1,400-foot" sand in the Memphis area between 1935 and 1940 is shown in figure 6. During the period 1947-49 the annual pumpage ranged from 10 to 14 mgd and averaged about 12 mgd. The slopes of the present hydraulic gradient in the area 15-30 miles from the center of heavy withdrawal has developed in response to this constant rate of withdrawal, and near-equilibrium conditions of discharge, recharge, and water level now exist.

In 1924, before the development of wells in the "1,400-foot" sand, was equal to the amount of recharge, or about 5 mgd. Pumps within the area now intercept all the water that formerly was discharged naturally from the area.

Total discharge, or the amount of water withdrawn from 1924 to 1940, is about 120 billion gallons. If we use a coefficient of storage of 3×10^{-4} and a total water-level decline of 74 feet (in the Parkway well field), the amount of storage depletion in the aquifer is about 12 billion gallons. The average annual rate of depletion of storage in the aquifer is 10 percent of the present average daily rate of pumping, or about 1 mgd.

OTHER AQUIFERS

The Ripley Formation of Cretaceous age may be a major source of water in the future. The top of the Ripley lies about 2,600 feet below land surface at Memphis, and, at present, only one well, in the Parkway well field, is screened in the formation. The piezometric surface of this aquifer is more than 100 feet above land surface, and when this well was allowed to flow, it produced about 35 gpm. The water contains more than 1,000 ppm (parts per million) total dissolved solids and is not fit for most uses without treatment.

Terrace deposits consisting of sand and gravel of Pleistocene and (or) Pliocene age may also be a major future source of water. These deposits lie at or near land surface where they are present and may be as much as 100 feet thick. Several domestic wells screened in this aquifer yield as much as 60 gpm, and it is probable that large capacity wells could be developed in some places in the area. Water from the terrace deposits is hard but generally contains less iron than does the water from either of the principal aquifers. Water from the terrace deposits is suitable for some industrial uses without treatment, though none of the industries in the area use water from this source.

QUALITY OF WATER

Water that moves through underground formations comes into contact with and dissolves soluble material in the rocks, thereby changing the chemical quality of the water. Differences in the quality of ground water reflect differences in the geologic environment in the water-bearing formations. Formations lying at considerable depth below the surface and those which yield water derived from distant sources usually contain water that is more highly mineralized than do those which lie at shallow depth or obtain water from nearby sources. A complete discussion of the significance of the chemical and physical characteristics of water was prepared by Lohr and Love (1954, p. 3-13).

The value of a water supply is largely dependent on the quality of the water required for various uses. Water from the two principal aquifers in the Memphis area is of good chemical quality for municipal use and contains chemical constituents in concentrations well below those recommended by the U.S. Public Health Service for water used on interstate carriers. Iron concentration and hardness of water are usually the most troublesome chemical qualities. Iron concentration, hardness, and total dissolved solids in selected samples from the two principal aquifers are shown in figure 10.

The bacteriological quality of water from the "500-foot" and "1,400-foot" sand aquifers in the Memphis area is excellent because of the great depth to the water and because a local ordinance requires filling of abandoned wells with clay and cement. The only aquifer which could become seriously polluted from the land surface is the terrace deposits, and this aquifer is not used extensively for supply where pollution would be likely.

Industrial wastes and sewage do not currently pose a pollution problem, because these materials are discharged to the Mississippi River and are not allowed to accumulate in large amounts at any place in the area. Discharge of waste water to wells is prohibited by municipal ordinances in Memphis and Shelby County.

WATER IN THE "500-FOOT" SAND

The chemical quality of water in the "500-foot" sand is good. The only dissolved constituents that are troublesome are iron, free carbon dioxide, and, in a few places, hydrogen sulfide. Iron is easily removed by aeration and filtration, and most free carbon dioxide and hydrogen sulfide escape as the water is pumped from the ground or during the aeration for iron removal.




FIGURE 10.

EXPLANATION
 ● Well screened in "1,400-foot" sand
 ⊗ Well screened in "500-foot" sand
 ○ Iron concentration (ppm)
 ⊕ Hardness (ppm)
 ⊘ Dissolved solids (ppm)

FIGURE 10.—Iron concentration, hardness, and total dissolved solids of water from selected wells in the "500-foot" and "1,400-foot" sands.

The water temperature ranges from 61° to 61°F, depending on the depth from which the water is pumped. The temperature of the ground water in the Memphis area increases about 1°F per 100 feet of depth below the ground surface, starting at 61° F at a depth of about 100 feet.

The water is generally soft. The average hardness determined from random sampling is about 40 ppm, having a range from 10 to 170 ppm. The highest values, above 60 ppm, may be a result of harder water leaking from the overlying terrace deposits and mixing with water in the "500-foot" sand. More water will probably be induced from the shallower formation as pumping continues to increase.

Determinations of pH made immediately after samples were collected showed the water to be acid, but a neutral condition was approached within a few minutes after collection as a result of the escape of carbon dioxide. The average pH of the water after it has been standing for a few hours is about 6, indicating a slightly acid condition. A typical chemical analysis of water from the "500-foot" sand is shown in table 2. The sample was analyzed several days after it was collected, and for this reason the pH determination was comparatively high.

TABLE 2.—Typical chemical analysis of water from the "500-foot" sand

Chemical analysis of water from well 48-122 in the "500-foot" sand. Well data: diameter, 10 inches; depth, 127 ft.; drilled, 1922. Water data: color, 6 p.p.m.; temperature, 67° F.; date of collection, 4-3-31; specific conductance (microhms at 25° C.), 186. Analyzed by U.S. Geol. Survey.

| Constituent | Parts per million | Conductance | Parts per million | Specific conductance |
|--------------------------------------|-------------------|-------------------------------------|-------------------|----------------------|
| Aluminum (Al)..... | 0.0 | Sulfate (SO ₄)..... | 3.2 | 0.017 |
| Silica (SiO ₂)..... | 13 | Chloride (Cl)..... | 3.0 | .005 |
| Iron (Fe)..... | 44 | Fluoride (F)..... | .0 | .000 |
| Calcium (Ca)..... | 10 | Nitrate (NO ₃)..... | .4 | .000 |
| Magnesium (Mg)..... | 5.5 | Dissolved solids..... | 81 | |
| Sodium (Na)..... | 4.2 | Hardness as CaCO ₃ | | |
| Potassium (K)..... | 1.3 | Total..... | 48 | |
| Bicarbonate (HCO ₃)..... | 72 | Noncarbonate..... | 0 | |

The water for municipal use in Memphis is treated for iron removal only. This treated water, which includes water from the "1,400-foot" sand, contains about 100 ppm total dissolved solids. A few of the industries requiring water of special chemical quality treat the water for the removal of certain constituents, but most of them use the water untreated. The Memphis Light, Gas, and Water Division is equipped to add chlorine to the water as a protective measure, but chlorine is not routinely added.

WATER IN THE "1,400-FOOT" SAND

The chemical quality of water from the "1,400-foot" sand is good (table 3), but the water is generally more highly mineralized than water from the "500-foot" sand. The hardness (as CaCO₃) is lower, ranging from 5 to 17 ppm. Water from the "1,400-foot" sand is untreated for municipal use, except for iron removal, and is mixed with water from the "500-foot" sand in the municipal system. Treatment for iron removal also removes the small amount of free carbon dioxide and hydrogen sulfide from the water.

Table 3 shows a typical chemical analysis of water from the "1,400-foot" sand. The pH is neither representative of water in the formation nor representative of water immediately after pumping, because the analysis was made several days after collection of the water sample.

During this time the escape of free carbon dioxide from the water caused an increase in the pH. No carbon dioxide or pH determinations have been made immediately after collection of water samples from this formation, but such analyses probably would be similar to those made of water from the "500-foot" sand.

TABLE 3.—Typical chemical analysis of water from the "1,400-foot" sand

Chemical analysis of water from well 48-122 in the "1,400-foot" sand. Well data: diameter, 10 inches; depth, 127 ft.; drilled, 1922. Water data: color, 12; temperature, 70° F.; date of collection, 4-3-31; specific conductance (microhms at 25° C.), 186. Analyzed by U.S. Geol. Survey.

| Conductance | Parts per million | Conductance | Parts per million | Specific conductance |
|--------------------------------------|-------------------|-------------------------------------|-------------------|----------------------|
| Aluminum (Al)..... | 0.7 | Sulfate (SO ₄)..... | 5.1 | 0.104 |
| Silica (SiO ₂)..... | 12 | Chloride (Cl)..... | 2.0 | .050 |
| Iron (Fe)..... | 80 | Fluoride (F)..... | .1 | .005 |
| Calcium (Ca)..... | 2.7 | Nitrate (NO ₃)..... | .5 | .008 |
| Magnesium (Mg)..... | 1.3 | Dissolved solids..... | 112 | |
| Sodium (Na)..... | 35 | Hardness as CaCO ₃ | | |
| Potassium (K)..... | 2.8 | Total..... | 12 | |
| Bicarbonate (HCO ₃)..... | 101 | Noncarbonate..... | 0 | |

Samples collected in 1927 and at infrequent intervals afterward indicate that the quality of water in the "1,400-foot" sand has remained constant. If leakage to the aquifer occurred in substantial amounts from rocks either below or above, it would undoubtedly be noted in the chemical analyses of the water because of the difference in quality of water in adjacent formations. The consistency of quality in the area where the pressure head is lowered considerably is further indication that the clays confining this artesian aquifer have very low permeability.

WATER IN OTHER AQUIFERS

Chemical analyses of the few samples of water obtained from the terrace deposits in the Memphis area show that the water is generally hard but that it contains less iron and carbon dioxide than does the water from the two principal aquifers. The average hardness (as CaCO₃) of water from the "500-foot" sand is about 40 ppm, and the average hardness of water from the terrace deposits, about 200 ppm. If the "500-foot" sand is locally recharged by seepage from the terrace deposits in any part of the area, sampling for chemical quality may be used to indicate the location and amount of such recharge. This is one of the objectives of a continuing investigation.

Analyses of several samples of water from the only well screened in the Ripley Formation (about 2,000 ft deep) in the Memphis area show that the water contains more than 1,000 ppm total dissolved solids and is saline. The chemical quality of the water has not changed appreciably since the first sample was collected in 1927. Samples of water from this aquifer 80-100 miles east of Memphis contain as little

as one tenth of the amount of dissolved solids found in water at Memphis, thus indicating the rate of change in chemical quality as the water moves downward toward Memphis.

FACTORS AFFECTING FUTURE USE AND DEVELOPMENT

The foremost consideration at present is whether or not pumping from the principal aquifers in the Memphis area can continue to increase each year, as it has in the past, without causing the abandonment of many wells or a major change in the chemical quality of the water. The answer is a qualified "yes," although, as the development of new wells in the aquifers continues, pumping costs rise primarily as a result of declining piezometric surface and the higher initial cost of developing new wells at greater depths. Other factors which may affect future development include loss of artesian head, change in chemical quality as a result of induced recharge from adjacent formations or from surface water in certain locations, change in hydraulic characteristics of the aquifer, development of wells in shallower or deeper aquifers, development of surface-water supplies where water-quality tolerances are lower, and discovery of new industrial processes which may reduce or increase water consumption. All these factors are of immediate concern in long-range water management, but none appear to offer reasons for curtailment of development of wells at the current rate in either of the principal aquifers. Some of the factors, such as development of surface-water supplies and development of wells in deeper or shallower aquifers, would tend to conserve water in the "500-foot" and "1,400-foot" sands.

Water wells can be developed in either of the principal aquifers anywhere in the Memphis area, but the amount of water discharged by a well per unit drawdown of water level, defined as specific capacity, cannot be predicted accurately because of the nonhomogeneity of the sands and the sporadic presence of clay beds of varying thicknesses in some parts of the area. The size, capacity, and type of construction of a well, the size and length of the well screen, the kind of gravel envelope around the screen, the pumping rate, and the hydraulic properties of the water-bearing formation in the vicinity of the well affect the specific capacity. Theoretically, transmissibility can be used to predict specific capacity of a proposed well where other factors are known. The specific capacity of wells in the Memphis area ranges from a few to more than 100 gpm per foot of drawdown for wells of all sizes and all types of construction. The specific capacity of an average 10-inch well in the "500-foot" sand is about 30 gpm per foot of drawdown.

In the area east of a southwest-trending line through Collierville,

has declined below the top of the aquifer, and nonartesian conditions now prevail in that area. As pumping continues to increase, the artesian-nonartesian boundary will migrate toward Memphis, and, eventually, when the water level in Memphis has declined 300-400 feet below land surface, nonartesian conditions will encompass the entire area. When the present annual pumping rate is doubled, the boundary will have advanced to the present city limits of Memphis. If the current annual increase in pumping rate continues and if the present areal pumping pattern continues to develop, nonartesian conditions will reach the city limits of Memphis in about 30 years (1960). Variations in the future pumping pattern may hasten or delay the approach of nonartesian conditions in the "500-foot" sand. The present practice of wider well and well-field spacing will tend to preserve the artesian condition.

The impending loss of artesian head in the aquifer is not cause for alarm. On the contrary, water levels should fluctuate less and decline more slowly. Some water may be induced from the overlying terrace deposits and cause a change in the chemical quality of water, although probably not a significant amount. The amount of land subsidence resulting from dewatering of the aquifer will probably be immeasurably small unless the water level declines several hundred feet below the top of the aquifer. Nonartesian conditions will result in a relatively small additional cost of developing deeper wells and a slightly higher cost of pumping.

Development of wells in, and use of water from, the "500-foot" sand probably will continue so long as the quality of the water is satisfactory. The coefficient of transmissibility for the "1,400-foot" sand is about 1.2×10^{-4} gpd per ft, and for the "500-foot" sand about 4×10^{-4} . The ratio is about 1 to 3, indicating that three times as much water may move through the "500-foot" sand. The hydraulic diffusivity, defined as the ratio of the coefficient of transmissibility to the coefficient of storage, for the "1,400-foot" sand is 4×10^{-4} , and the "500-foot" sand it is 1.33×10^{-4} . The ratio is 3 to 1, which indicates that the effect of any change in the rate of discharge travels three times farther in the "1,400-foot" sand. The estimated rate of movement of water under natural conditions, prior to development of the "1,400-foot" sand aquifer, was about 0.36 mgd for each 1-mile-wide section of the aquifer; for the "500-foot" sand, about 1 mgd. These values indicate that the ultimate capacity or economic yield of the "1,400-foot" sand is about 16 percent of that of the "500-foot" sand under similar conditions.

ADEQUACY OF THE AQUIFER ANALYSIS

Determinations of the rate of movement of water, the natural and artificial discharge, the indication and effect of recharge, and the hydraulic characteristics of the two principal aquifers in the Memphis area are results of the application of mathematical formulas to the data collected for these purposes. Geological and geophysical data collected during the investigation contributed to, and tended to verify, these results. The analyses are adequate for the current (1900) rate of pumping and location of well fields. Only the total amount of water involved and its rate of movement is expected to change significantly in the future. The hydraulic characteristics described in this report may be used to predict the results of these changes throughout the area except where the "500-foot" sand is no longer under artesian pressure. Tests will have to be conducted in areas where nonartesian conditions exist to determine the hydraulic characteristics of the aquifer. In such areas, however, pumping is expected to have a less pronounced effect on the water level than it has in the artesian part of the area.

In general the aquifer analysis as presented in this report is sufficiently adequate to predict with reasonable accuracy the future water-level changes for given rates of pumping, either greater or smaller than the present rate. The analysis also indicates that greater amounts of water may be pumped from both aquifers without impairing the water supply or seriously affecting the quality of water.

CONCLUSIONS

The two principal aquifers of the Memphis area are the "500-foot" and "1,400-foot" sands, from which practically all the water used in the area is pumped. The present (1900) rate of withdrawal is about 150 mgd, 135 mgd of which is pumped from the "500-foot" sand. Of the inflow to the area through the "500-foot" sand, excluding leakage from streams and adjacent aquifers, about 45 percent is from the east, about 20 percent is from the south, about 15 percent is from the north, and about 10 percent or less is from the west. The remaining 10 percent of the water derived annually from the "500-foot" sand comes from depletion of storage as a result of declining water level and from leakage from the overlying terrace deposits which, in turn, may be partly recharged by streams and by precipitation. Faults in the area may influence water movement and water levels by retarding the inflow of water from the west.

Pumping tests were made to determine the hydraulic characteristics of that section of the "500-foot" sand nonifer adjacent to the well

17000

is estimated to have a coefficient of transmissibility of about 4×10^{-4} gpd per ft and a coefficient of storage of about 3×10^{-2} . The long-range effect on water levels in the area may be determined by using these coefficients for any given rate of pumping and computing the future drawdown. For example, if the present pumping rate from the "500-foot" sand remains constant, water levels will cease to decline within a few years. However, if the annual pumping rate from the "500-foot" sand continues to increase at the present rate of approximately 5 mgd per year, water levels will decline at about the same rate as at present unless future wells and well fields are located at greater distances from the present centers of pumping.

The water level in the "500-foot" sand in the southeastern part of the Memphis area has declined to a few feet below the top of the aquifer. The line marking the boundary between artesian and non-artesian conditions is slowly advancing toward Memphis, and, in about 30 years, nonartesian conditions may exist over the entire area. No detrimental effect can be forecast, though the quality of the water pumped may change slightly as water is induced from adjacent formations and streams. Water-level fluctuations and the overall decline in water levels probably will be less pronounced than at the present, although transmissibility will decrease as the aquifer is drained.

The "1,400-foot" sand, an almost ideal artesian aquifer, is a secondary aquifer because it is only about one fourth as thick as the "500-foot" sand and, therefore, can furnish only one fourth as much water or less. The coefficient of transmissibility in the "1,400-foot" sand is 1.2×10^{-4} gpd per ft, or about the same as that in the "500-foot" sand per unit of thickness. The storage coefficient is 3×10^{-2} indicating that less water is derived from storage per foot of water-level decline than is derived from the "500-foot" sand. The effect of pumping on the water level in this aquifer is also more pronounced at greater distances from the center of pumping than is the effect on the water level in the "500-foot" sand, primarily because of the greater artesian head in the "1,400-foot" sand.

The present (1900) rate of pumping from the "1,400-foot" sand in the Memphis area is about 13 mgd, and a total of about 120 billion gallons is estimated to have been withdrawn since the first wells were developed in 1924. The aquifer is primarily a standby source of water for the city of Memphis.

Part of this investigation was directed toward answering specific questions relating to water supply that might be asked by those charged with planning for an expanding community. Kazmann (1944, p. 17-18) expressed the problems of the Memphis area water

ADEQUACY OF THE AQUIFER ANALYSIS

Determinations of the rate of movement of water, the natural and artificial discharge, the indication and effect of recharge, and the hydraulic characteristics of the two principal aquifers in the Memphis area are results of the application of mathematical formulas to the data collected for these purposes. Geological and geophysical data collected during the investigation contributed to, and tended to verify, these results. The analyses are adequate for the current (1960) rate of pumping and location of well fields. Only the total amount of water involved and its rate of movement is expected to change significantly in the future. The hydraulic characteristics described in this report may be used to predict the results of these changes throughout the area except where the "500-foot" sand is no longer under artesian pressure. Tests will have to be conducted in areas where nonartesian conditions exist to determine the hydraulic characteristics of the aquifer. In such areas, however, pumping is expected to have a less pronounced effect on the water level than it has in the artesian part of the area.

In general the aquifer analysis as presented in this report is sufficiently adequate to predict with reasonable accuracy the future water-level changes for given rates of pumping, either greater or smaller than the present rate. The analysis also indicates that greater amounts of water may be pumped from both aquifers without impairing the water supply or seriously affecting the quality of water.

CONCLUSIONS

The two principal aquifers of the Memphis area are the "500-foot" and "1,400-foot" sands, from which practically all the water used in the area is pumped. The present (1960) rate of withdrawal is about 150 mgd, 135 mgd of which is pumped from the "500-foot" sand. Of the inflow to the area through the "500-foot" sand, excluding leakage from streams and adjacent aquifers, about 45 percent is from the east, about 20 percent is from the south, about 15 percent is from the north, and about 10 percent or less is from the west. The remaining 10 percent of the water derived annually from the "500-foot" sand comes from depletion of storage as a result of declining water level and from leakage from the overlying terrace deposits which, in turn, may be partly recharged by streams and by precipitation. Faults in the area may influence water movement and water levels by retarding the inflow of water from the west.

Pumping tests were made to determine the hydraulic characteristics of that section of the "500-foot" sand aquifer adjacent to the well

is estimated to have a coefficient of transmissibility of about 4×10^{-5} gpd per ft and a coefficient of storage of about 3×10^{-4} . The long-range effect on water levels in the area may be determined by using these coefficients for any given rate of pumping and computing the future drawdown. For example, if the present pumping rate from the "500-foot" sand remains constant, water levels will cease to decline within a few years. However, if the annual pumping rate from the "500-foot" sand continues to increase at the present rate of approximately 5 mgd per year, water levels will decline at about the same rate as at present unless future wells and well fields are located at greater distances from the present centers of pumping.

The water level in the "500-foot" sand in the southeastern part of the Memphis area has declined to a few feet below the top of the aquifer. The line marking the boundary between artesian and non-artesian conditions is slowly advancing toward Memphis, and, in about 30 years, nonartesian conditions may exist over the entire area. No detrimental effect can be forecast, though the quality of the water pumped may change slightly as water is induced from adjacent formations and streams. Water-level fluctuations and the overall decline in water levels probably will be less pronounced than at the present, although transmissibility will decrease as the aquifer is drained.

The "1,400-foot" sand, an almost ideal artesian aquifer, is a secondary aquifer because it is only about one fourth as thick as the "500-foot" sand and, therefore, can furnish only one fourth as much water or less. The coefficient of transmissibility in the "1,400-foot" sand is 1.2×10^{-4} gpd per ft, or about the same as that in the "500-foot" sand per unit of thickness. The storage coefficient is 3×10^{-4} indicating that less water is derived from storage per foot of water-level decline than is derived from the "500-foot" sand. The effect of pumping on the water level in this aquifer is also more pronounced at greater distances from the center of pumping than is the effect on the water level in the "500-foot" sand, primarily because of the greater artesian head in the "1,400-foot" sand.

The present (1960) rate of pumping from the "1,400-foot" sand in the Memphis area is about 13 mgd, and a total of about 120 billion gallons is estimated to have been withdrawn since the first wells were developed in 1924. The aquifer is primarily a sandy source of water for the city of Memphis.

Part of this investigation was directed toward answering specific questions relating to water supply that might be asked by those charged with planning for an expanding community. Kazmann (1944, p. 17-18) expressed the problems of the Memphis area water

maximum amount of water that can be pumped safely from the aquifers be determined. That limit cannot be determined at present because the change from artesian to nonartesian conditions and the decentralization of pumping tends to increase the maximum safe amount of water that may be obtained in the area. Therefore, the answers to Kazmann's questions are qualified and reflect the status of knowledge of the area for the period ending with this investigation. The questions will continue to be the basis for a logical continuing investigation if supplemented by other pertinent questions which are listed in the final pages of this report.

1. What is the origin of the ground water obtained in the Memphis area?

At present about 90 percent of the water obtained from the "500-foot" sand originates as underground inflow into the area. Less than 1 percent of the water comes from depletion of the storage of the aquifer. The remainder, about 10 percent, is leakage from the overlying terrace deposits or from other sources of recharge in the area.

About 10 percent of the water obtained from the "1,400-foot" sand comes from depletion of the storage of the aquifer. The other 90 percent probably originates as inflow into the area.

2. Is more water being taken from the underground sources than nature puts back each year? If so, what is the excess of average withdrawal over input? If not, what is the ultimate safe yield of the water-bearing formations?

Presently, the answer is yes. More water is being taken from the aquifers than is being replaced each year because of the annual increase in pumping. However, if the annual pumping rate remained constant, equilibrium conditions would be reached within a few years, and the amount of recharge would equal discharge on an annual basis.

If each aquifer is considered as a unit ending at the boundary of the Memphis area and if a comparison is made of what is added to each of these units by inflow and any other processes with what has been taken out, then the difference is the amount of depletion of storage of each aquifer in the area. The average annual rate of depletion of storage of the "500-foot" sand in the area is less than 1 percent of the annual pumping rate, or about 1 mgd. Therefore, 99 percent of the water taken annually from the "500-foot" sand within the area is replaced by recharge.

Similarly, about 90 percent or more of the water that has been taken from the "1,400-foot" sand in the area has been replaced. Rising water levels in this aquifer indicate that recharge has been greater than discharge during the last 1 year.

3. Are the water-bearing formations continuous between the outcrops (if any) and the well fields?

The answer is yes. This continuity is shown by the influence of pumping from both the "500-foot" and the "1,400-foot" sands on the water levels in observation wells 30 miles northeast of Memphis (figs. 9, 17). Recharge to the aquifers

observation wells. These facts indicate that the two aquifers are hydraulically continuous between their outcrop areas and the well fields in the Memphis area. Continuity within the area is proven by geophysical logs.

4. How much water are the formations capable of transmitting each day?

Throughout their total thickness in the Memphis area, the "500-foot" sand has a coefficient of transmissibility of 4×10^{-6} gpd per ft, and the "1,400-foot" sand, about 1.2×10^{-6} gpd per ft. The amount of water the formations are capable of transmitting is indicated by their coefficients and by the hydraulic gradient in each aquifer in the area. The present steepest gradient outside the area of heavy pumping is about 10 feet per mile in the "500-foot" sand, and about 4 mgd is transmitted in each 1-mile-wide section of the aquifer along a north-south line in the vicinity of well Sh: Q-1 (pl. 2). The present steepest gradient is about 8 feet per mile in the "1,400-foot" sand, and about 0.36 mgd is transmitted in each 1-mile-wide section of the aquifer in the vicinity of the Sheehan well field (pl. 2). The extent to which these gradients can be increased is unknown, but it is certain that both aquifers can supply more water than is presently pumped from them.

5. Is the limit on water withdrawals set by the recharge to the formations or the transmissibility of the formations?

The limit on water withdrawal for a well field or for a small part of the Memphis area depends on the transmissibility of the aquifer and the geologic conditions in the vicinity of the well field. For example, the presence of a local clay lens in the aquifer will lower the limit of withdrawal for a well field. Similar clay lenses may be so spaced in or near the outcrop area to prevent maximum recharge that would otherwise take place. The present annual pumping rate in the Memphis area is not great enough to determine which of the two factors limit the rate of withdrawal. If the rate of recharge under ultimate development of the aquifers are assumed to be the same as those prior to development, then the limit on withdrawal would be set by the recharge to the formations. However, perennial streams flowing across the sandy outcrop areas strongly suggests the possibility of large amounts of rejected recharge. The amount and maximum possible rate of recharge may be great enough that withdrawals may be limited by the transmissibilities of the formations. This limitation appears to be the most likely conclusion.

6. Are the chemical quality and temperature of ground water changing or are they constant within certain limits?

The water samples analyzed since 1927 show that the chemical quality of water from both aquifers varies little with time except for the hardness of "500-foot" sand water which appears to be increasing in the north-central part of the area (fig. 19). The temperature of water in the "500-foot" sand ranges from 61° to 64° F depending on the depth of the well; the temperature of water in the "1,400-foot" sand ranges from 70° to 71° F.

7. What directions are the most promising for the establishment of new well fields and what is the most desirable well spacing?

The preferable direction for the establishment of new well fields in the "500-foot" sand is unknown, although the southeastern part of the area is

indicated because the greater rate of inflow is from that direction. The hydraulic characteristics of the aquifer under nonartesian conditions, the hydrologic condition of the outcrop area, and the influence of geologic features in the area could alter the selection of preferable direction as pumping continues. The question of well spacing is primarily a problem of economics relating to water production and transportation. Obviously, the greater distance between production wells causes less interference, but the cost of distributing the water on the land surface is greater. The drawdown in a well pumping 1,000 gpm from the "500-foot" sand is about 50 feet. If the allowable interference of another pumping well is 10 percent of its own drawdown and the wells are smaller in construction and depth to presently used wells in the Memphis area, the well spacing should be 1,000 feet or more. If the wells are constructed using longer screens, a greater thickness of the aquifer would be effective, and closer well spacing would be allowable.

The preferable direction for the development of new well fields in the "1,400-foot" sand is roughly north and south of Memphis or perpendicular to the flow path of water moving downward in the aquifer into the area. Well spacing, under requirements similar to those for the "500-foot" sand should be 1,000 feet or more.

8. What is the relationship between ground-water levels and quantities of water pumped in the area?

Water levels decline in the Memphis area as a result of increases in pumping. The water levels would cease to decline if the total annual pumping rate remained constant for a few years. Generally, for the "500-foot" sand, the decline in Memphis is about 1 foot for each 1-mgd increase in water production in level decline is less than 0.1 foot for each 1-mgd increase in water production in Memphis.

The water-level decline in the "1,400-foot" sand is at present as much as four times greater than that in the "500-foot" sand for each 1-mgd increase in water production.

9. How much water is being obtained from each water-bearing formation?

Approximately 1.0 trillion gallons of water was pumped from the "500-foot" sand from 1960 to 1964. Records of pumping are accurate, and during the last several years more than half the daily pumping in the area was metered and reported monthly to the U.S. Geological Survey. The 1960 rate of pumping was about 135 mgd. All the water pumped from the "1,400-foot" sand is metered also, and more than 65 percent of the daily pumping is reported monthly. The total amount of water pumped from the "1,400-foot" sand from 1924 to 1960 was about 120 billion gallons. The 1960 rate of pumping was about 13 mgd.

Supplemental questions which need to be answered during the continuing investigation in order to promote further efficient management of the water supply in the Memphis area are:

1. What is the amount of recharge perennially available, and can the aquifers accept and transmit the total available recharge?

2. What are the steepest hydraulic gradients that can be established in the aquifers?

HYDROLOGY, AQUIFER SYSTEMS, MEMPHIS AREA, TENN. 051

3. What are the hydraulic characteristics of the aquifers under impounding nonartesian conditions, and will surface-water resources in the area be affected?

4. What are the effects of faults and similar structural controls on water production?

5. What are the interference effects, resulting from different heads or water levels in the aquifers, between aquifers?

6. What is the change in chemical quality of water as production from the aquifers continues? Is it significant, and is there a trend toward greater change?

7. Will streamflow be significantly affected as the effect of pumping in Memphis extends to the outcrop area of the two principal aquifers?

8. Should the shallower terrace deposits or alluvium be considered a major source of water, or are they being drained by leakage to the "500-foot" sand?

9. What are the legal and economic aspects of continued development?


There are no apparent reasons why development of wells in the two principal aquifers of the Memphis area should not continue, although the supply is not unlimited. Any evidence of overdevelopment would probably be noted during the continuing future investigation in sufficient time to prepare solutions to the problem or to recommend that alternate sources of supply be developed. The potential water production from the two aquifers is much greater than the present yield, and the possibility of overdevelopment of either aquifer in the immediate future is remote.

REFERENCES

- Caplan, W. M., 1954, Subsurface geology and related oil and gas possibilities of northeastern Arkansas: Arkansas Resources and Development Comm., Div. Geology Bull. 20.
- Criquer, J. H., and Armstrong, O. A., 1958, Ground-water supply of the Memphis area: U.S. Geol. Survey Circ. 408, 20 p.
- Ferris, J. O., Knowles, D. H., Brown, R. H., and Stallman, R. W., 1962, Theory of aquifer tests: U.S. Geol. Survey Water-Supply Paper 1696-A, 174 p.
- Flak, H. N., 1914, Geological investigation of the alluvial valley of the lower Mississippi River: U.S. Dept. Army, Mississippi River Comm., 78 p.
- Gleason, L. O., 1900, Underground waters of Tennessee and Kentucky west of Tennessee River and of an adjacent area in Illinois: U.S. Geol. Survey Water-Supply Paper 164, 173 p.
- Kazianka, R. O., September 1944, The water supply of the Memphis area: U.S. Geol. Survey open-file report, 60 p.
- Lahr, M. W., and Love, B. K., 1954, The industrial utility of public water supplies in the United States, 1952: Pt. 1 of States east of the Mississippi River: U.S. Geol. Survey Water-Supply Paper 164, 173 p.

INDEX


| Page | Page | Page |
|--------|--------|--------|
| Index | Index | Index |
| 10, 11 | 10, 11 | 10, 11 |
| 12 | 12 | 12 |
| 13 | 13 | 13 |
| 14 | 14 | 14 |
| 15 | 15 | 15 |
| 16 | 16 | 16 |
| 17 | 17 | 17 |
| 18 | 18 | 18 |
| 19 | 19 | 19 |
| 20 | 20 | 20 |
| 21 | 21 | 21 |
| 22 | 22 | 22 |
| 23 | 23 | 23 |
| 24 | 24 | 24 |
| 25 | 25 | 25 |
| 26 | 26 | 26 |
| 27 | 27 | 27 |
| 28 | 28 | 28 |
| 29 | 29 | 29 |
| 30 | 30 | 30 |
| 31 | 31 | 31 |
| 32 | 32 | 32 |
| 33 | 33 | 33 |
| 34 | 34 | 34 |
| 35 | 35 | 35 |
| 36 | 36 | 36 |
| 37 | 37 | 37 |
| 38 | 38 | 38 |
| 39 | 39 | 39 |
| 40 | 40 | 40 |
| 41 | 41 | 41 |
| 42 | 42 | 42 |
| 43 | 43 | 43 |
| 44 | 44 | 44 |
| 45 | 45 | 45 |
| 46 | 46 | 46 |
| 47 | 47 | 47 |
| 48 | 48 | 48 |
| 49 | 49 | 49 |
| 50 | 50 | 50 |
| 51 | 51 | 51 |
| 52 | 52 | 52 |
| 53 | 53 | 53 |
| 54 | 54 | 54 |
| 55 | 55 | 55 |
| 56 | 56 | 56 |
| 57 | 57 | 57 |
| 58 | 58 | 58 |
| 59 | 59 | 59 |
| 60 | 60 | 60 |
| 61 | 61 | 61 |
| 62 | 62 | 62 |
| 63 | 63 | 63 |
| 64 | 64 | 64 |
| 65 | 65 | 65 |
| 66 | 66 | 66 |
| 67 | 67 | 67 |
| 68 | 68 | 68 |
| 69 | 69 | 69 |
| 70 | 70 | 70 |
| 71 | 71 | 71 |
| 72 | 72 | 72 |
| 73 | 73 | 73 |
| 74 | 74 | 74 |
| 75 | 75 | 75 |
| 76 | 76 | 76 |
| 77 | 77 | 77 |
| 78 | 78 | 78 |
| 79 | 79 | 79 |
| 80 | 80 | 80 |
| 81 | 81 | 81 |
| 82 | 82 | 82 |
| 83 | 83 | 83 |
| 84 | 84 | 84 |
| 85 | 85 | 85 |
| 86 | 86 | 86 |
| 87 | 87 | 87 |
| 88 | 88 | 88 |
| 89 | 89 | 89 |
| 90 | 90 | 90 |
| 91 | 91 | 91 |
| 92 | 92 | 92 |
| 93 | 93 | 93 |
| 94 | 94 | 94 |
| 95 | 95 | 95 |
| 96 | 96 | 96 |
| 97 | 97 | 97 |
| 98 | 98 | 98 |
| 99 | 99 | 99 |
| 100 | 100 | 100 |



MLGW

WATER

PRODUCTION



1990

MLGW WATER PRODUCTION

| TOPIC | PAGE # |
|---------------------------------|--------|
| I. TREATMENT PLANT DATA | 1 |
| A. PUMPAGE | |
| B. AERATORS | |
| C. FILTERS | |
| II. LIFT SYSTEM DATA | 4 |
| A. NORTH COUNTY SYSTEM | |
| B. EAST COUNTY SYSTEM | |
| C. SOUTH COUNTY SYSTEM | |
| D. PRESIDENT ISLAND | |
| E. ROSEMARK | |
| F. INTERNAL BOOSTER STA. | |
| G. LOWER SYSTEM | |
| H. TANKS | |
| III. INTERCONNECTION VALVE DATA | 12 |
| A. MLGW & OTHER SYSTEMS | |
| B. UPPER & LOWER SYSTEMS | |
| IV. PRODUCTION WELL DATA | 16 |
| A. MALLORY | |
| B. SHEAHAN | |
| C. ALLEN | |
| D. MCCORD | |
| E. LICHTERMAN | |
| F. DAVIS | |
| G. MORTON | |
| H. SHAW | |
| I. LNG | |
| J. PALMER | |
| V. OBSERVATION WELL DATA | 35 |
| A. FLUVIAL (TERRACE) DEPOSITS | |
| B. MEMPHIS SAND | |
| C. FORT PILLOW SAND | |
| VI. WATER LAB DATA | 39 |
| A. WATER ANALYSIS | |
| B. WATER CHARACTERISTICS | |

TREATMENT PLANT

DATA

TREATMENT PLANT DATA

| STATION | PLANT FLOW (MGD) | AERATOR RISES (No.) | AERATOR FLOW RATE (GPM/50.FT.) | PUMP/NGE (RATE/) | | DISCHARGE PRESSURE (PSI) | H.S. PUMPS (No.) | PUMP/NGE (MGD) |
|--------------------------|------------------|---------------------|--------------------------------|------------------|-------------------------------|--------------------------|------------------|----------------|
| | | | | FILTER BOX (No.) | FILTER FLOW RATE (GPM/50.FT.) | | | |
| MILLORY | 35 | 16 | 23.74 | 8 | 3.68 | 87 | 4 | 1.0 |
| SHEPARD #1 | 35 | 17 | 12.61 | 10 | 2.95 | 72 | 4 | 1.0 |
| SHEPARD #2 | -- | 8 | 26.30 | -- | -- | -- | -- | -- |
| ALLEN | 30 | 14 | 23.25 | 10 | 2.55 | 76 | 4 | 6.0 |
| MCCORD | 35 | 14 | 27.13 | 4 | 7.45 | 76 | 5 | 6.0 |
| LICHTENMAN | 30 | 14 | 23.25 | 4 | 6.38 | 68 | 5 | 6.0 |
| LICHTENMAN (WITH BYPASS) | 35 | 14 | 27.13 | 4 | 7.45 | -- | -- | -- |
| PALMER | 5.5 | 2 | 15.91 | 6 | 3.18 | 60 | 3 | 8 |
| DAVIS | 15 | 4 | 25.00 | 4 | 2.89 | 77 | 2 | 1.5 |
| DAVIS #1 (FUTURE) | 32.5 | 4 | 25.00 | 4 | 6.26 | 77 | 4 | 6.5 |
| DAVIS #2 (FUTURE) | -- | 8 | 23.74 | -- | -- | -- | -- | -- |
| MORTON | 15 | 7 | 23.25 | 4 | 2.50 | 74 | 3 | 37.5 |
| MORTON (FUTURE) | 30 | 14 | 23.25 | 4 | 5.00 | 74 | 5 | 67.5 |
| SHAW | 15 | 8 | 20.35 | 4 | 2.50 | 57 | 3 | 31.5 |
| SHAW LOOP (FUTURE) | 30 | 16 | 20.35 | 4 | 5.00 | 57 | 4 | 42 |
| SHAW UPPER (FUTURE) | -- | -- | -- | -- | -- | 78 | 3 | 22.5 |
| UIG | 1.1 | 1 | 10.40 | 1 | 3.24 | 70 | 3 | 0.9 |

TREATMENT PLANT DATA


AERATORS

| | NO. OF RISERS | WIDTH IN FT. | LENGTH IN FT. | SECTIONS PER RISER | AREA SQ. FT. | TRAYS HIGH |
|-------------------|------------------|-----------------|------------------|-----------------------|-----------------|---------------|
| MALLORY | 16 | 4 | 8 | 2 | 64 | 9 |
| SHEAHAN #1 | 17 | 3 | 6.75 | 2 | 40.5 | 9 |
| SHEAHAN #2 | 8 | 4.5 | 8.25 | 2 | 74.25 | 9 |
| ALLEN | 14 | 4 | 8 | 2 | 64 | 9 |
| MCCORD | 14 | 4 | 8 | 2 | 64 | 9 |
| LICHTERMAN | 14 | 4 | 8 | 2 | 64 | 9 |
| DAVIS #1 | 4 | 5 | 10.417 | 2 | 104.17 | 9 |
| DAVIS #2 (FUTURE) | 8 | 4 | 8 | 2 | 64 | 9 |
| MORTON | 7 | 4 | 8 | 2 | 64 | 9 |
| MORTON (FUTURE) | 14 | 4 | 8 | 2 | 64 | 9 |
| SHAW | 8 | 4 | 8 | 2 | 64 | 9 |
| SHAW (FUTURE) | 16 | 4 | 8 | 2 | 64 | 9 |
| PALMER | 2 | 4 | 15 | 2 | 120 | 9 |
| L.N.G. | 1 | 4.5 | 16 | 21 | 72 | 6 |

FILTERS

| | NO. OF BOXES | WIDTH IN FT. | LENGTH IN FT. | SECTIONS PER BOX | AREA SQ. FT. | TYPE MEDIA |
|-----------------|-----------------|-----------------|------------------|---------------------|-----------------|---------------|
| MALLORY | 8 | 12.5 | 33 | 2 | 825 | mixed |
| SHEAHAN #1 | 10 | 12.5 | 33 | 2 | 825 | mixed |
| ALLEN | 10 | 12 | 34 | 2 | 816 | sand |
| MCCORD | 4 | 12 | 34 | 2 | 816 | mixed |
| LICHTERMAN | 4 | 12 | 34 | 2 | 816 | mixed |
| DAVIS #1 | 4 | 15 | 30 | 2 | 900 | mixed |
| MORTON | 4 | 13.167 | 39.5 | 2 | 1040.1 | mixed |
| MORTON (FUTURE) | 4 | 13.167 | 39.5 | 2 | 1040.1 | mixed |
| SHAW | 4 | 13.167 | 39.5 | 2 | 1040.1 | mixed |
| PALMER | 6 | 10 | 20 | 1 | 200 | sand |
| L.N.G. | 1 | 17.167 | DIA | 1 | 231.46 | mixed |

LIFT SYSTEM



LIFT SYSTEM DATA

NORTH COUNTY SYSTEM

PUMPING STATION

| RATED CAPACITIES | LNG |
|------------------------|--------|
| ----- | --- |
| NUMBER OF WELLS | 2 |
| CAPACITY (MGD) | |
| PUMP #1 | 0.4 |
| PUMP #2 | 0.4 |
| PUMP #3 | 0.3 |
| GROSS PUMPAGE | 1.1 |
| TREATMENT | 0.7 |
| STORAGE (MG) | 0.3 |
| PUMP ELEVATION (FT.) | 331 |
| HYDROSTATIC HEAD (FT.) | 493.5. |

LIFT STATIONS

| RATED CAPACITIES | ORGILL |
|---------------------|--------|
| ----- | ----- |
| CAPACITY (GPM) | |
| PUMP #1 | 500 |
| PUMP #2 | 500 |
| GROSS PUMPAGE (GPM) | 1000 |
| LIFT (FT.) | |
| PUMP #1 | 128 |
| PUMP #2 | 128 |

LIFT SYSTEM DATA

EAST COUNTY SYSTEM

PUMPING STATION

| <u>RATED CAPACITIES</u> | <u>SHAW (FUTURE)</u> |
|-------------------------|----------------------|
| NUMBER OF WELLS | 10 |
| CAPACITY (MGD) | |
| PUMP #1 | -- |
| PUMP #2 | 7.5 |
| PUMP #3 | -- |
| PUMP #4 | 7.5 |
| PUMP #5 | -- |
| PUMP #6 | 7.5 |
| PUMP #7 | -- |
| GROSS PUMPAGE | 22.5 |
| TREATMENT (MGD) | 15 |
| STORAGE (MG) | 15 |
| PUMP ELEVATION (FT.) | 364 |
| HYDROSTATIC HEAD (FT.) | 495 |

LIFT STATIONS

| <u>RATED CAPACITIES</u> | <u>ROCKY PT.</u> | <u>PISGAH</u> | <u>HOUSTON LEVEE</u> | <u>GERMANTOWN RD.</u> |
|-------------------------|------------------|---------------|----------------------|-----------------------|
| CAPACITY (GPM) | | | | |
| PUMP #1 | 440 | 750 | 600 | 800 |
| PUMP #2 | --- | 750 | 200 | 800 |
| PUMP #3 | --- | --- | --- | 2000 |
| PUMP #4 | --- | --- | --- | 2000 |
| GROSS PUMPAGE (GPM) | 440 | 1500 | 800 | 5600 |
| LIFT (FT.) | | | | |
| PUMP #1 | 127 | 80 | 210 | 164 |
| PUMP #2 | --- | 80 | 210 | 164 |
| PUMP #3 | --- | --- | --- | 125 |
| PUMP #4 | --- | --- | --- | 125 |

LIFT SYSTEM DATA

SOUTH COUNTY SYSTEM

LIFT STATIONS

| RATED CAPACITIES | CAPLEVILLE | ROSS RD. |
|---------------------|------------|----------|
| CAPACITY (GPM) | | |
| PUMP #1 | 350 | 2000 |
| PUMP #2 | --- | 825 |
| GROSS PUMPAGE (GPM) | 350 | 2825 |
| LIFT (FT.) | | |
| PUMP #1 | 110 | 108 |
| PUMP #2 | --- | 86 |

PRESIDENT ISLAND

| RATED CAPACITIES | PRESIDENT ISLAND |
|---------------------|------------------|
| CAPACITY (GPM) | |
| PUMP #1 | 3500 |
| PUMP #2 | 3500 |
| GROSS PUMPAGE (GPM) | 7000 |
| LIFT (FT.) | |
| PUMP #1 | 63 |
| PUMP #2 | 63 |

LIFT SYSTEM DATA

ROSMARK

| <u>RATED CAPACITIES</u> | <u>ROSMARK</u> |
|-------------------------|----------------|
| CAPACITY (GPM) | |
| PUMP #1 | 600 |
| PUMP #2 | 125 |
| GROSS PUMPAGE (GPM) | 725 |
| LIFT (FT.) | |
| PUMP #1 | 108 |
| PUMP #2 | 64 |

INTERNAL BOOSTER STATIONS

| <u>RATED CAPACITIES</u> | <u>BROOKS RD.</u> | <u>SHELBY DR.</u> | <u>PARK AVE.</u> |
|-------------------------|-------------------|-------------------|------------------|
| CAPACITY (GPM) | | | |
| PUMP #1 | 5500 | 3000 | 7500 |
| PUMP #2 | 5500 | 3000 | --- |
| GROSS PUMPAGE (GPM) | 11000 | 6000 | 7500 |
| LIFT (FT.) | | | |
| PUMP #1 | 82 | 60 | 90 |
| PUMP #2 | 82 | 60 | -- |

LIFT SYSTEM DATA

LOWER SYSTEM

| RATED CAPACITIES | MALLOY | SHEPARD | ALLEN | MCCORD | LICHTENMAN | DAVIS | MORTON | SIAM | PALMER | TOTAL |
|--------------------------|--------|---------|----------|--------|------------|--------|----------|----------|--------|-------|
| GENERATION (KW) | -- | -- | 1000 (E) | -- | -- | -- | -- | 1250 (E) | -- | 2250 |
| NUMBER OF WELLS | 25 | 23 | 26 | 24 | 23 | 14 | 10 | 10 | 4 | 199 |
| HIGH SERVICE PUMPS (MGD) | | | | | | | | | | |
| #1 | 15 | 15 (V) | 15 (V) | 5 | 10 | 10 (V) | 12.5 (F) | 10.5 | 2.2 | -- |
| #2 | 15 | 15 (V) | 15 (V) | 10 (V) | 10 (V) | 15 (F) | 12.5 (V) | -- | 2.4 | -- |
| #3 | 15 (V) | 15 | 15 | 15 | 15 | 15 (V) | 12.5 (V) | 10.5 (V) | 2.4 | -- |
| #4 | 15 (V) | 15 | 15 (V) | 15 (V) | 15 (V) | 15 (F) | 12.5 | -- | -- | -- |
| #5 | 15 (F) | 4 (E) | -- | 15 | 15 | -- | 12.5 (F) | 10.5 (V) | -- | -- |
| #6 | 4 (E) | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| #7 | -- | -- | -- | -- | -- | -- | -- | 10.5 (F) | -- | -- |
| TOTAL (MGD) | 64 | 64 | 60 | 60 | 65 | 25 | 37.5 | 31.5 | 8 | 383.5 |
| TOTAL (Future) | 79 | -- | -- | -- | -- | 55 | 62.5 | 42 | -- | -- |
| TREATMENT (MGD) | 35 | 35 | 30 | 30 | 35 | 15 | 15 | 15 | 5.5 | 200.5 |
| TREATMENT (Future) | -- | -- | -- | -- | -- | 30 | 30 | 30 | -- | -- |
| STORAGE (MG) | 23 | 18 | 20 | 10 | 10 | 10 | 10 | 15 | 2 | 118 |
| STORAGE (Future) | -- | -- | -- | 20 | 20 | 20 | 20 | 25 | -- | -- |
| PUMP ELEVATION (FT.) | 251 | 299 | 294.5 | 303 | 328 | 269 | 304 | 364 | 317 | -- |
| HYDROSTATIC HEAD (FT.) | 456 | 458.5 | 454 | 474 | 483 | 451 | 480 | 495 | 450 | -- |

NOTES: E = ENGINE DRIVEN UNIT; V = VARIABLE SPEED PUMP; F = FUTURE

LIFT STATION DATA

ELEVATED STORAGE TANKS

| TANK | STREET ADDRESS | OVERHEAD STORAGE (Gal.) | OVERFLOW ELEVATION (FT) | SYSTEM |
|--------------------|-----------------------------|-------------------------|-------------------------|---------------|
| PALMER | 1241 E. HOLMES | 300,000 | 451.5 | LOWER |
| FRAYSER | 655 WHITNEY | 500,000 | 415 | LOWER |
| RALEIGH MILLINGTON | 3704 RALEIGH-MILLINGTON | 300,000 | 452.48 | LOWER |
| EGYPT CENTRAL | 5384 EGYPT CENTRAL | 500,000 | 452.49 | LOWER |
| LUCY | 6440 CHASE | 300,000 | 406 | LOWER |
| CLOVERDAVEN | 7604 SLEDGE | 100,000 | 424 | LOWER |
| WILSON RD | 7685 WILSON RD. | 200,000 | 484 | LOWER |
| BAKER | 7707 DENJESTOWN | 500,000 | 493.5 | NORTH COUNTY |
| FARRIS | 6925 MUDVILLE | 100,000 | 493.5 | NORTH COUNTY |
| RAINEY | 9907 REDWOOD | 250,000 | 493.5 | NORTH COUNTY |
| CAPLEVILLE | 5234 E. HOLMES | 100,000 | 510 | SOUTH COUNTY |
| HOLMES RD. | 7599 HOLMES RD. | 500,000 | 530 | SOUTH COUNTY |
| STONEBRIDGE | 8894 HWY. 64 | 500,000 | 527 | EAST COUNTY |
| GALLAGHER | 2040 ARLINGTON-COLLIERVILLE | 500,000 | 527 | EAST COUNTY |
| PRESIDENT ISLAND | 1720 DOCK | 500,000 | 407 | PRESIDENT IS. |

LEGEND

- EXISTING PUMPING STATION
- PROPOSED PUMPING STATION
- EXISTING LIFT PUMP
- PROPOSED LIFT PUMP
- EXISTING ELEVATED STORAGE TANK
- PROPOSED ELEVATED STORAGE TANK

PUMPING STATIONS


- A-ALLEN
- D-DAVIS
- L-LICHTERMAN
- LNG-LIQUID NATURAL GAS PLANT
- M-MALLORY
- MC-MCCORD
- MO-MORTON
- P-PALMER
- S-SHEAHAN
- SW-SHAW
- SO-SOUTH

LIFT STATIONS

- O-ORIGILL
- BR-BROOKS ROAD
/>
- C-CAPLEVILLE
- GR-BERMANTOWN ROAD
- MC-HOUSTON LEVEE
- MP-ROCKY POINT
- PI-PRESIDENT ISLAND
- RR-ROSS ROAD
- SD-SHELBY DRIVE
- PA-PARK AVENUE
- WG-WALNUT GROVE
- PR-PISGAM ROAD
- RM-ROSEMARK


ELEVATED STORAGE TANKS

- F-FRAYSER
- R-RALEIGH
- PI-PRESIDENT ISLAND
- C-CAPLEVILLE
- HR-HOLMES ROAD
- P-PALMER
- EG-EGYPT CENTRAL
- B-BAKER
- LW-LUCY WOODSTOCK
- CC-FARRIS
- RW-RAINEY
- CH-CLOVERHAVEN
- MR-MACON ROAD
- SB-STONEBRIDGE
- G-GALLAGHER



MEMPHIS LIGHT, GAS, & WATER DIVISION
 GENERAL ENGINEERING DIVISION
 PLANNING SECTION
 OF
 SYSTEM ENGINEERING DEPARTMENT
 DRAWN BY: L.P.
 DATE: 10/1/60

INTERCONNECTION VALVE



DATA

WATER SYSTEM INTERCONNECTION VALVES BETWEEN MLGW AND OTHER SYSTEMS
GENERAL LOCATION

| ARLINGTON WATER SYSTEM | VALVE NO | PAGE NO | VALVE SIZE |
|--|-----------------|------------|---------------|
| 1. OLD AIR LINE ROAD & I-40 | 1 | 301 | 8" |
| BARTLETT WATER SYSTEM | | | |
| 1. CHARLES BRYAN RD. (METER BYPASS) | 7 | 39 | 6" |
| 2. BRUNSWICK & MEMPHIS-ARLINGTON | 2 | 237 | 8" |
| 3. HWY. 64 WEST OF BRUNSWICK ROAD | 1 | 97 | 8" |
| 4. COUNTRYHILL RD. & MEMPHIS-ARLINGTON RD. | 9 | 149 | 8" |
| COLLIERVILLE WATER SYSTEM | | | |
| 1. BAILEY STATION RD. & HWY. 72 | 2 | 1527 | 12" |
| 2. HOUSTON LEVEE RD. & HWY 72 | 1 | 1527 | 8" |
| 3. HOUSTON LEVEE RD. & FRANK RD. | 1 | 1391 | 8" |
| GERMANTOWN WATER SYSTEM | | | |
| 1. POPLAR AVE. & KIRBY RD. (METER BYPASS) | NOT NUMBERED | 1265 | 6" |
| 2. FORREST HILL-IRENE RD. SOUTH OF POPLAR PIKE | 1 | 1455 | 12" |
| 3. HOUSTON LEVEE RD. & DOGWOOD | 1 | 1269 | 8" |
| 4. TAMERLANE LN. EAST OF RIVERDALE ROAD | 25 | 1447 | 6" |
| 5. WOFFINGTON LN. NORTH OF CRESTRIDGE RD. | 51 | 1447 | 6" |
| MILLINGTON WATER SYSTEM | | | |
| 1. CUBA MILLINGTON RD. EAST OF QUITO RD. | 1 | 511 | 6" |
| 2. WILKINSVILLE RD. & WEST UNION RD. | 6 | 537 | 8" |



INTERCONNECTION VALVES BETWEEN HLGN
AND OTHER SYSTEMS

ABELINGTON WATER SYSTEM

AL OLD AIR LINE RD. & T-40

BARTLETT WATER SYSTEM

61 CHARLES BRON RD. (Water Hydrant)

62 BE JUICE & MEMPHIS-AR. JUNCTION

63 HWY 42, WEST OF BRUNSWICK RD

64 COMPTON RD. & MEMPHIS ARLINGTON RD.

COLLIERVILLE WATER SYSTEM

65 BARTLETT STATION RD. & HWY 72

66 HOUSTON LEWIS RD. & HWY 72

67 HOUSTON LEWIS RD. & FRANK RD.

GERMANTOWN WATER SYSTEM

68 POPULAR AVE. & EAST RD. (Water Hydrant)

69 FOREST HILL-ENGINE RD. SOUTH OF POPULAR

PIKE

70 HOUSTON LEWIS RD. & DOUGLASS

71 HANCOCK RD. EAST OF RIVERSIDE RD.

72 WASHINGTON LN. NORTH OF CRESTBROOK RD.

WILLINGTON WATER SYSTEM

73 CURA WILLINGTON RD. EAST OF HWY 72

74 WILKINSVILLE RD. & WEST UNION RD.

LEGEND

MUNICIPAL OR
BOARD BOUNDARY

MUNICIPALITIES

UTILITY BOARD

INTERCONNECTION
VALVE

MEMPHIS LIGHT, GAS & WATER DIVISION
- SYSTEMS & PLANTS
- DIVISIONS OF
- ENGINEERING DIVISION
MUNICIPAL & UTILITY BOARD
BOUNDARY
Drawn by L.P.



50th Anniversary



P.O. Box 430 Memphis, Tennessee 38101 Telephone (901) 528-4011

ANALYSIS OF WATER SUPPLIED BY THE CITY OF MEMPHIS

| | <u>Sheahan Station</u> | <u>Allen Station</u> | <u>McCord Station</u> | <u>Mallory Station</u> | <u>Lichterman Station</u> |
|--|----------------------------|--------------------------|---------------------------|----------------------------|-------------------------------|
| <u>Before Aeration</u> | | | | | |
| Iron (Fe) | 0.53 mg/L* | 0.44 | 0.46 | 0.43 | 0.14 |
| Manganese (Mn) | 0.012 | 0.013 | 0.014 | 0.013 | 0.003 |
| Fluoride (F ⁻) | 0.09 | 0.09 | 0.09 | 0.11 | 0.09 |
| pH | 6.5 | 6.5 | 6.4 | 6.4 | 6.3 |
| <u>After Aeration, Filtration and Fluoridation</u> | | | | | |
| Iron (Fe) | 0.03 | 0.02 | 0.06 | 0.03 | 0.03 |
| Manganese (Mn) | 0.001 | 0.001 | 0.003 | 0.001 | 0.005 |
| Fluoride (F ⁻) | 0.99 | 1.04 | 0.99 | 1.07 | 0.99 |
| pH | 7.3 | 7.4 | 7.4 | 7.4 | 7.4 |
| Alkalinity (CaCO ₃) | 43.0 | 66.0 | 49.0 | 64.0 | 37.0 |
| Hardness (CaCO ₃) | 39.0 | 62.0 | 44.0 | 58.0 | 32.0 |
| Calcium (CaCO ₃) | 19.0 | 31.5 | 22.8 | 27.8 | 18.0 |
| Magnesium (CaCO ₃) | 20.0 | 30.5 | 21.2 | 30.2 | 14.0 |
| Sodium (Na) | 7.94 | 9.83 | 8.40 | 9.16 | 7.14 |
| Potassium (K) | 0.84 | 0.93 | 0.88 | 0.82 | 0.72 |
| Sulfate (SO ₄) | 9.0 | 9.0 | 14.3 | 6.3 | 6.7 |
| Chloride (Cl) | 5.8 | 6.9 | 7.1 | 4.5 | 6.7 |
| Nitrate (NO ₃) | 0.10 | 0.08 | 0.08 | 0.26 | 0.20 |
| Phosphate (PO ₄) | 1.40 | 1.34 | 1.50 | 1.37 | 1.34 |
| Dissolved Solids | 68.0 | 104.0 | 80.0 | 68.0 | 66.0 |
| Silica (SiO ₂) | 13.7 | 15.2 | 12.8 | 14.7 | 14.0 |
| Temperature at Station (F°) | 65.0 | 63.0 | 63.0 | 65.0 | 63.0 |

pH is influenced by aeration efficiency which varies slightly with the pumping rate and wind velocity.

* mg/L is equal to parts per million

People You Can Count On
Since 1939



50th Anniversary



Analysis (con'd)

P.O. Box 430 Memphis, Tennessee 38101 Telephone (901) 528-4011

ANALYSIS OF WATER SUPPLIED BY THE CITY OF MEMPHIS

| | <u>LNG Plant</u> | <u>Davis Station</u> | <u>Morton Station</u> | <u>Palmer Station</u> | <u>Average of All Stations</u> |
|--|----------------------|--------------------------|---------------------------|---------------------------|------------------------------------|
| <u>Before Aeration</u> | | | | | |
| Iron (Fe) † | 0.75 mg/L* | 0.63 | 0.79 | 0.07 | 0.47 |
| Manganese (Mn) | 0.012 | 0.010 | 0.015 | 0.007 | 0.011 |
| Fluoride (F ⁻) | 0.13 | 0.10 | 0.10 | 0.10 | 0.10 |
| pH | 6.3 | 6.6 | 6.6 | 6.3 | 6.4 |
| <u>After Aeration, Filtration and Fluoridation</u> | | | | | |
| Iron (Fe) | 0.02 | 0.04 | 0.02 | 0.01 | 0.02 |
| Manganese (Mn) | 0.017 | 0.010 | 0.001 | 0.001 | 0.004 |
| Fluoride (F ⁻) | 1.05 | 1.02 | 1.02 | 1.05 | 1.02 |
| pH | 7.3 | 7.7 | 7.6 | 7.3 | 7.4 |
| Alkalinity(CaCO ₃) | 37.0 | 120.0 | 57.0 | 42.0 | 57.2 |
| Hardness(CaCO ₃) ³ | 32.0 | 110.0 | 55.0 | 35.0 | 51.9 |
| Calcium(CaCO ₃) | 17.8 | 63.5 | 30.3 | 17.0 | 27.5 |
| Magnesium(CaCO ₃) | 14.2 | 46.5 | 24.7 | 18.0 | 24.4 |
| Sodium (Na) | 6.92 | 9.04 | 6.22 | 8.43 | 8.12 |
| Potassium (K) | 0.80 | 1.18 | 1.24 | 0.84 | 0.92 |
| Sulfate (SO ₄) | 7.5 | 8.4 | 7.9 | 8.1 | 8.6 |
| Chloride (Cl) | 5.2 | 6.6 | 4.6 | 6.5 | 6.0 |
| Nitrate (NO ₃) | 0.07 | 0.16 | 0.16 | 0.07 | 0.13 |
| Phosphate (PO ₄) | 1.50 | 1.27 | 1.59 | 1.40 | 1.41 |
| Dissolved Solids | 68.0 | 148.0 | 68.0 | 52.0 | 80.2 |
| Silica (SiO ₂) | 10.9 | 14.1 | 10.0 | 12.2 | 13.1 |
| Temperature at Station (F°) | 65.0 | 62.0 | 64.0 | 64.0 | 64.0 |

pH is influenced by aeration efficiency which varies slightly with the pumping rate and wind velocity.

*mg/L is equal to parts per million

July 1989

J.H. Webb
Manager, Water Laboratory

People You Can Count On
Since 1939



50th Anniversary



P.O. Box 430 Memphis, Tennessee 38101 Telephone (901) 528-4011

ADDITIONAL CHARACTERISTICS OF WATER SUPPLIED BY THE CITY OF MEMPHIS

| | <u>Sheahan Station</u> | <u>Allen Station</u> | <u>McCord Station</u> | <u>Mallory Station</u> | <u>Lichterman Station</u> |
|--|----------------------------|--------------------------|---------------------------|----------------------------|-------------------------------|
| Color (Units-PCS) | <5 | <5 | <5 | <5 | <5 |
| Turbidity (NTU) | 0.14 | 0.11 | 0.18 | 0.18 | 0.13 |
| Specific Conductance (Micromhos / cm @25°C) | 113 | 160 | 122 | 133 | 94 |
| Aluminum (Al)* | 0.006 | 0.003 | 0.008 | 0.029 | 0.0039 |
| Arsenic (As) | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 |
| Barium (Ba) | 0.024 | 0.058 | 0.034 | 0.048 | 0.021 |
| Cadmium (Cd) | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Chromium (Cr) | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Copper (Cu) | 0.048 | 0.035 | 0.045 | 0.061 | 0.053 |
| Cyanide (CN ⁻²) | <0.010 | <0.010 | <0.010 | <0.010 | <0.010 |
| Detergents (MBAS) | <0.025 | <0.025 | <0.025 | <0.025 | <0.025 |
| Lead (Pb) | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Mercury (Hg) | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| Phenols | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Selenium (Se) | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 |
| Silver (Ag) | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Zinc (Zn) | <0.005 | <0.005 | <0.005 | <0.005 | <0.005 |
| Total Coliform (Colonies / 100ml) | <1.0 | <1.0 | <1.0 | <1.0 | <1.0 |
| Total Organic Carbon | 0.492 | 0.637 | 0.501 | 0.654 | 0.340 |
| Trihalomethanes | 0.002 | 0.006 | 0.004 | 0.004 | 0.004 |
| Volatile Organic Chemicals | ND | ND | ND | ND | ND |

People You Can Count On
Since 1939

Reference 25



MEMPHIS LIGHT, GAS AND WATER DIVISION

June 28, 1993

Mr. Christian J. Lavalley
B & V Waste Science and Technology Corporation
The Curtis Center, Suite 705
601 Walnut Street
Philadelphia, PA 19106-3307

RE: City of Memphis Water Production

Dear Mr. Lavalley:

In response to your above referenced inquiry, please find enclosed copies of maps containing our well fields (please note the revision date indicated on each map).

The total number of water customers MLGW supplies is 213,311, and each well produces approximately 344 million gallons of water per year.

The information concerning the depths of the wells can be located in the 1990 Production Book you obtained earlier from MLGW; this is the most recent information we have at this time.

If you have further questions, please contact Donna Robbins at (901) 528-4736.

Sincerely,

Paula Payne
Vice President
Support Services

dr

Enclosures

CENSUS '90



1990 Census of
Population and Housing
Summary Population and
Housing Characteristics
Tennessee




Table 5. Household, Family, and Group Quarters Characteristics: 1990—Con.

(For definitions of terms and meanings of symbols, see text.)

| State County County Subdivision Place | Family households | | | | | Nonfamily households | | | | Persons per— | | Persons in group quarters | | Other non- group quarters |
|--|--------------------------|---------------------|---------|-----------------------------|--|----------------------|--------------------------|-------------------|-----------|--------------|-------|---------------------------|--------|------------------------------------|
| | Persons in households | All house- holds | Total | Married couple family | Female house- holder, no husband present | Total | Householder living alone | | Household | Family | Total | Institutional persons | | |
| | | | | | | | Total | 65 years and over | | | | | | |
| | | | | | | | | | | | | | Total | |
| Sevier County | 18 189 | 6 534 | 5 128 | 4 150 | 765 | 1 406 | 1 311 | 684 | 553 | 2 78 | 3 21 | 169 | 69 | |
| Huntsville division | 4 928 | 1 718 | 1 387 | 1 134 | 201 | 331 | 296 | 154 | 125 | 2 87 | 3 25 | 114 | 14 | |
| Huntsville town | 546 | 215 | 148 | 119 | 22 | 67 | 62 | 44 | 37 | 2 54 | 3 14 | 114 | 14 | |
| Onondaga town (pt) | 19 | 5 | 4 | 3 | — | 1 | 1 | 1 | 1 | 3 80 | 4 50 | — | — | |
| Normal division | 2 226 | 719 | 617 | 516 | 75 | 102 | 95 | 49 | 42 | 3 10 | 3 38 | — | — | |
| Onondaga division | 5 522 | 2 121 | 1 568 | 1 224 | 275 | 553 | 531 | 290 | 237 | 2 60 | 3 12 | 55 | 55 | |
| Onondaga town (pt) | 3 977 | 1 224 | 826 | 594 | 190 | 398 | 383 | 215 | 183 | 2 43 | 3 07 | 55 | 55 | |
| Robbins division | 2 514 | 870 | 694 | 573 | 99 | 176 | 163 | 90 | 70 | 2 89 | 3 32 | — | — | |
| Winfield division | 2 999 | 1 106 | 862 | 703 | 115 | 244 | 226 | 101 | 79 | 2 7 | 3 11 | — | — | |
| Onondaga town (pt) | 451 | 196 | 131 | 99 | 26 | 65 | 62 | 17 | 12 | 2 30 | 2 88 | — | — | |
| Winfield town | 564 | 206 | 161 | 132 | 22 | 45 | 43 | 21 | 17 | 2 74 | 3 09 | — | — | |
| Seminole County | 8 778 | 3 287 | 2 555 | 2 087 | 353 | 732 | 656 | 322 | 252 | 2 67 | 3 06 | 85 | 85 | |
| Center Point division | 2 292 | 851 | 675 | 580 | 65 | 176 | 151 | 65 | 47 | 2 69 | 3 05 | — | — | |
| Dunwoody division | 6 486 | 2 436 | 1 880 | 1 507 | 298 | 556 | 505 | 257 | 205 | 2 66 | 3 06 | 85 | 85 | |
| Dunwoody city | 3 646 | 1 417 | 1 055 | 814 | 191 | 362 | 332 | 173 | 143 | 2 57 | 3 03 | 85 | 85 | |
| Sevier County | 50 394 | 19 520 | 15 091 | 12 706 | 1 853 | 4 429 | 3 858 | 1 561 | 1 239 | 2 58 | 2 96 | 649 | 582 | |
| Berea Springs division | 4 458 | 1 677 | 1 353 | 1 157 | 156 | 374 | 280 | 116 | 88 | 2 66 | 2 98 | — | — | |
| Sevierville town (pt) | 252 | 95 | 66 | 54 | 11 | 29 | 23 | 8 | 6 | 2 65 | 3 18 | — | — | |
| Chattanooga division | 8 628 | 3 185 | 2 703 | 2 381 | 257 | 482 | 430 | 179 | 149 | 2 77 | 3 04 | 77 | 77 | |
| Sevierville CDP (pt) | 5 027 | 1 837 | 1 550 | 1 356 | 168 | 287 | 255 | 100 | 87 | 2 74 | 3 01 | 77 | 77 | |
| Dunwoody division | 3 966 | 1 489 | 1 160 | 1 012 | 109 | 329 | 283 | 115 | 85 | 2 66 | 3 05 | 3 | — | |
| Division Center town | 475 | 206 | 162 | 123 | 10 | 64 | 58 | 29 | 23 | 2 31 | 2 81 | 3 | — | |
| Germanburg division | 4 335 | 1 668 | 1 308 | 1 071 | 178 | 560 | 487 | 197 | 167 | 2 32 | 2 78 | 60 | — | |
| Germanburg city | 3 357 | 1 484 | 1 007 | 822 | 139 | 477 | 414 | 170 | 145 | 2 26 | 2 75 | 60 | — | |
| Knox Creek division | 4 256 | 1 579 | 1 275 | 1 091 | 121 | 304 | 262 | 109 | 83 | 2 70 | 3 03 | — | — | |
| Sevierville division | 19 807 | 7 920 | 5 871 | 4 797 | 861 | 2 049 | 1 790 | 729 | 577 | 2 50 | 2 93 | 509 | 505 | |
| Pigeon Forge city (pt) | 2 602 | 1 075 | 764 | 618 | 121 | 311 | 263 | 93 | 73 | 2 42 | 2 90 | 113 | 106 | |
| Sevierville town (pt) | 6 126 | 2 885 | 1 961 | 1 507 | 382 | 924 | 841 | 382 | 314 | 2 33 | 2 87 | 200 | 200 | |
| Wear Valley division | 4 742 | 1 802 | 1 421 | 1 197 | 171 | 381 | 326 | 116 | 90 | 2 63 | 2 98 | — | — | |
| Pigeon Forge city (pt) | 312 | 120 | 98 | 87 | 10 | 22 | 21 | 6 | 5 | 2 60 | 2 94 | — | — | |
| Shelby County | 803 085 | 303 571 | 212 076 | 144 773 | 56 404 | 91 495 | 77 999 | 25 382 | 20 245 | 2 65 | 3 22 | 23 245 | 12 182 | |
| Arlington division | 9 012 | 2 990 | 2 569 | 2 198 | 300 | 421 | 372 | 143 | 106 | 3 01 | 3 29 | 661 | 650 | |
| Arlington town | 1 052 | 356 | 283 | 234 | 42 | 73 | 66 | 31 | 22 | 2 96 | 3 37 | 489 | 489 | |
| Bartlett town (pt) | 10 | 5 | 3 | — | — | 2 | 2 | 1 | 1 | 2 00 | 2 67 | 167 | 167 | |
| Lakeland city | 1 199 | 455 | 381 | 339 | 38 | 74 | 65 | 20 | 17 | 2 64 | 2 92 | 5 | — | |
| Collierville division | 17 385 | 5 448 | 4 787 | 4 208 | 455 | 661 | 586 | 222 | 176 | 3 19 | 3 45 | 114 | 114 | |
| Collierville town (pt) | 14 313 | 4 429 | 3 879 | 3 369 | 406 | 550 | 489 | 192 | 155 | 3 23 | 3 50 | 114 | 114 | |
| Memphis city (pt) | 3 653 | 1 192 | 1 025 | 913 | 77 | 167 | 153 | 76 | 56 | 3 06 | 3 37 | 5 | — | |
| Memphis division | 742 626 | 283 879 | 195 259 | 130 489 | 54 422 | 88 520 | 75 529 | 24 481 | 19 558 | 2 62 | 3 21 | 16 627 | 11 181 | |
| Bartlett town (pt) | 26 627 | 8 451 | 7 636 | 6 784 | 666 | 815 | 711 | 222 | 189 | 3 15 | 3 34 | 185 | 185 | |
| Collierville town (pt) | 32 893 | 10 713 | 9 414 | 8 620 | 634 | 1 299 | 1 167 | 281 | 233 | 3 07 | 3 33 | — | — | |
| Memphis city (pt) | 594 312 | 229 829 | 153 785 | 94 315 | 50 316 | 76 044 | 64 964 | 27 700 | 18 122 | 2 59 | 3 21 | 16 015 | 10 569 | |
| Willingboro division | 20 776 | 7 002 | 5 772 | 4 829 | 735 | 1 230 | 1 013 | 314 | 242 | 2 97 | 3 29 | 5 819 | 5 599 | |
| Memphis city (pt) | 12 225 | 4 168 | 3 412 | 2 911 | 387 | 756 | 606 | 152 | 115 | 2 93 | 3 27 | 5 64 | 5 599 | |
| Raymont division | 1 788 | 636 | 533 | 478 | 38 | 103 | 94 | 52 | 42 | 2 81 | 3 11 | — | — | |
| Shelby Forest division | 7 845 | 2 424 | 2 131 | 1 658 | 377 | 293 | 252 | 94 | 65 | 3 24 | 3 46 | 19 | — | |
| Memphis city (pt) | — | — | — | — | — | — | — | — | — | — | — | — | — | |
| Smith County | 13 998 | 5 358 | 4 151 | 3 579 | 447 | 1 207 | 1 127 | 643 | 512 | 2 61 | 3 03 | 145 | 134 | |
| Carthage division | 5 921 | 2 353 | 1 725 | 1 465 | 210 | 628 | 591 | 353 | 299 | 2 52 | 3 02 | 145 | 134 | |
| Carthage town | 2 241 | 993 | 626 | 477 | 131 | 367 | 350 | 203 | 180 | 2 56 | 2 94 | 145 | 134 | |
| Farms of the River division | 1 657 | 619 | 494 | 434 | 32 | 125 | 116 | 65 | 43 | 2 68 | 3 06 | — | — | |
| South Carthage division | 4 420 | 2 286 | 1 932 | 1 680 | 205 | 454 | 420 | 225 | 170 | 2 69 | 3 04 | — | — | |
| Carthage town | 851 | 343 | 276 | 220 | 49 | 71 | 67 | 42 | 33 | 2 57 | 2 95 | — | — | |
| South Carthage town | — | — | 252 | 205 | 42 | 91 | 89 | 44 | 34 | 2 48 | 2 96 | — | — | |
| Spartanburg County | 9 295 | 3 678 | 2 812 | 2 452 | 251 | 866 | 793 | 444 | 344 | 2 53 | 2 93 | 184 | 95 | |
| Cumtardland City Carthage division | 1 776 | 705 | 537 | 453 | 56 | 168 | 156 | 71 | 52 | 2 52 | 2 93 | — | — | |
| Cumtardland City town | 319 | 131 | 97 | 72 | 17 | 34 | 30 | 12 | 7 | 2 44 | 2 84 | — | — | |
| Dover division | 3 021 | 1 244 | 900 | 788 | 83 | 344 | 321 | 192 | 157 | 2 43 | 2 90 | 98 | 95 | |
| Dover city | 1 246 | 564 | 365 | 309 | 45 | 199 | 188 | 123 | 105 | 2 21 | 2 78 | 95 | 95 | |
| Indian Mound Burnside Hills division | 4 498 | 1 729 | 1 375 | 1 211 | 112 | 354 | 316 | 181 | 135 | 2 60 | 2 94 | — | — | |
| Modern division | — | — | — | — | — | — | — | — | — | — | — | 86 | — | |
| Sullivan County | 141 449 | 56 729 | 42 516 | 35 372 | 3 632 | 14 213 | 13 048 | 5 674 | 4 669 | 2 49 | 2 93 | 2 147 | 1 351 | |
| Blountville division | 13 846 | 5 246 | 4 166 | 3 600 | 412 | 1 080 | 955 | 354 | 276 | 2 64 | 3 01 | 485 | 464 | |
| Blountville CDP | 2 296 | 879 | 712 | 610 | 73 | 167 | 154 | 86 | 72 | 2 61 | 2 95 | 309 | 309 | |
| Bristol city (pt) | 76 | 31 | 20 | 17 | 3 | 11 | 7 | 1 | 1 | 2 45 | 3 05 | — | — | |
| Walton Hill CDP (pt) | 2 | 1 | 1 | — | — | — | — | — | — | 2 00 | 2 00 | — | — | |
| Bluff City-Piney Hills division | 16 483 | 6 212 | 4 990 | 4 252 | 530 | 1 222 | 1 115 | 469 | 368 | 2 45 | 3 00 | 11 | 10 | |
| Bluff City city | 1 390 | 544 | 414 | 330 | 57 | 130 | 121 | 57 | 51 | 2 56 | 2 97 | — | — | |
| Bristol city (pt) | 79 | 32 | 24 | 18 | 5 | 8 | 7 | 6 | 5 | 2 47 | 2 92 | — | — | |
| Johnson City city (pt) | 96 | 37 | 27 | 24 | 1 | 10 | 6 | 3 | 3 | 2 59 | 3 00 | — | — | |
| Bristol division | 29 434 | 12 191 | 8 622 | 6 965 | 1 315 | 3 569 | 3 258 | 1 297 | 1 140 | 2 41 | 2 93 | 715 | 265 | |
| Bristol city (pt) | 22 707 | 9 662 | 6 565 | 5 213 | 1 092 | 3 117 | 2 851 | 1 253 | 1 025 | 2 35 | 2 91 | 559 | 119 | |
| Walton Hill CDP (pt) | 3 332 | 1 242 | 1 024 | 881 | 108 | 218 | 198 | 80 | 64 | 2 68 | 2 99 | — | — | |
| Marion Valley division | 2 721 | 987 | 812 | 679 | 94 | 175 | 160 | 74 | 58 | 2 76 | 3 06 | 234 | 234 | |
| Bristol city (pt) | 78 965 | 32 093 | 23 926 | 19 876 | 3 281 | 8 167 | 7 560 | 3 380 | 2 827 | 2 46 | 2 91 | 702 | 61 | |
| Blountville CDP | 10 953 | 4 223 | 3 345 | 2 815 | 263 | 887 | 788 | 292 | 239 | 2 59 | 2 95 | — | — | |
| Cumtard Heights CDP | 6 711 | 2 538 | 2 080 | 1 868 | 164 | 458 | 418 | 143 | 120 | 2 64 | 2 96 | 5 | — | |
| Kingsport city (pt) | 33 510 | 14 692 | 9 983 | 7 830 | 1 828 | 4 709 | 4 419 | 2 186 | 1 865 | 2 28 | 2 83 | 649 | 589 | |
| Spartanburg CDP (pt) | 1 331 | 523 | 410 | 358 | 45 | 113 | 109 | 47 | 35 | 2 54 | 2 95 | — | — | |
| Sumner County | 102 065 | 36 850 | 29 511 | 24 907 | 3 545 | 7 339 | 6 384 | 2 579 | 2 093 | 2 77 | 3 13 | 1 216 | 637 | |
| Berthoud division | 3 073 | 1 078 | 899 | 784 | 75 | 179 | 154 | 71 | 52 | 2 65 | 3 15 | 21 | 21 | |
| Carlisle city (pt) | 411 | 132 | 122 | 112 | 4 | 10 | 9 | 3 | 2 | 3 11 | 3 27 | — | — | |
| Carlisle Springs division | 3 615 | 1 232 | 1 081 | 953 | 89 | 151 | 128 | 43 | 29 | 2 93 | 3 15 | 7 | 7 | |
| Carlisle city (pt) | — | — | — | — | — | — | — | — | — | — | — | — | — | |
| Carlisle division | 21 617 | 8 224 | 6 120 | 4 688 | 1 151 | 2 104 | 1 845 | 854 | 729 | 2 63 | 3 09 | 552 | 393 | |
| Carlisle city (pt) | 17 761 | 6 872 | 5 002 | 3 724 | 1 036 | 1 870 | 1 644 | 777 | 666 | 2 58 | 3 07 | 552 | 393 | |

U.S. Department of Commerce
Economics and Statistics Administration
BUREAU OF THE CENSUS

Reference 27

1990 CP-1-5

CENSUS '90



1990 Census of Population
General Population
Characteristics
Arkansas




Table 2. Summary of General Characteristics of Households and Families: 1990

(for definitions of terms and meanings of symbols, see text)

| State Urban and Rural and Size of Place Inside and Outside Metropolitan Area County Place and [In Selected States] County Subdivision (1,000 or More Persons) | Percent of all households | | | | | | | | | | | Persons per— | | | |
|--|---------------------------|-----------------------|---|--|---|-------|--------------------------|--------|-------------------|--------|------|---------------------------------------|----------------|--------|------|
| | All house- holds | Family households | | | | | Nonfamily households | | | | | house- holder 65 years and over | House- hold | Family | |
| | | Married-couple family | | Female householder no husband present | | Total | Householder living alone | | | | | | | | |
| | | Total | With own children under 18 years | Total | With own children under 18 years | | Total | Female | 65 years and over | | | | | | |
| | | | | | | | | | Total | Female | | | | | |
| The State | 891 179 | 72.1 | 34.3 | 59.2 | 26.5 | 11.1 | 6.5 | 26.9 | 24.6 | 15.0 | 11.6 | 9.2 | 25.9 | 2.57 | 1.06 |
| URBAN AND RURAL AND SIZE OF PLACE | | | | | | | | | | | | | | | |
| Urban | 488 323 | 68.9 | 32.9 | 52.7 | 23.3 | 13.5 | 8.3 | 31.1 | 27.4 | 17.6 | 12.4 | 10.1 | 25.7 | 2.48 | 1.04 |
| Inside urbanized area | 230 144 | 67.7 | 33.3 | 50.9 | 23.5 | 13.9 | 8.5 | 32.3 | 27.8 | 17.0 | 10.2 | 8.3 | 21.1 | 2.50 | 1.08 |
| Outside urbanized area | 204 836 | 66.3 | 32.2 | 49.4 | 22.3 | 14.1 | 8.5 | 33.7 | 28.9 | 17.7 | 10.6 | 8.6 | 21.7 | 2.46 | 1.07 |
| Urban fringe | 25 308 | 78.4 | 42.4 | 63.4 | 33.2 | 12.1 | 7.7 | 21.6 | 18.9 | 11.3 | 7.0 | 5.7 | 16.4 | 2.76 | 1.16 |
| Outside urbanized area | 258 179 | 70.0 | 32.5 | 54.2 | 23.2 | 13.2 | 8.1 | 30.0 | 27.0 | 18.2 | 14.4 | 11.8 | 29.7 | 2.47 | 1.07 |
| Place of 10,000 or more | 122 793 | 68.4 | 32.4 | 53.1 | 23.4 | 12.7 | 7.8 | 31.6 | 27.5 | 18.0 | 13.2 | 10.9 | 26.7 | 2.45 | 1.01 |
| Place of 2,500 to 9,999 | 135 386 | 71.4 | 32.7 | 55.3 | 22.9 | 13.6 | 8.5 | 28.6 | 26.5 | 18.3 | 15.4 | 12.5 | 32.5 | 2.49 | 1.01 |
| Rural | 402 856 | 78.2 | 36.1 | 67.1 | 30.3 | 8.2 | 4.4 | 21.8 | 19.9 | 11.8 | 10.6 | 8.0 | 26.2 | 2.68 | 1.08 |
| Place of 1,000 to 2,499 | 52 349 | 71.1 | 32.1 | 56.2 | 23.6 | 12.3 | 7.3 | 28.9 | 27.1 | 19.2 | 16.9 | 13.8 | 34.5 | 2.48 | 1.01 |
| Place of less than 1,000 | 42 101 | 73.0 | 33.6 | 58.4 | 26.0 | 11.4 | 6.2 | 27.0 | 25.3 | 16.6 | 15.5 | 12.2 | 32.4 | 2.59 | 1.10 |
| Other rural | 308 406 | 80.1 | 37.1 | 70.1 | 32.0 | 7.1 | 3.7 | 19.9 | 17.9 | 9.9 | 6.9 | 4.4 | 23.9 | 2.73 | 1.09 |
| INSIDE AND OUTSIDE METROPOLITAN AREA | | | | | | | | | | | | | | | |
| Inside metropolitan area | 354 752 | 71.6 | 35.4 | 56.7 | 26.8 | 12.0 | 7.2 | 28.4 | 24.4 | 14.7 | 9.6 | 7.7 | 20.9 | 2.59 | 1.11 |
| In central city | 204 520 | 66.3 | 32.1 | 49.3 | 22.3 | 14.1 | 8.6 | 33.7 | 28.9 | 17.7 | 10.6 | 8.6 | 21.7 | 2.46 | 1.07 |
| Not in central city | 150 232 | 78.9 | 39.9 | 66.7 | 32.9 | 9.2 | 5.4 | 21.1 | 18.4 | 10.7 | 8.2 | 6.4 | 19.7 | 2.76 | 1.15 |
| Urban | 58 137 | 75.8 | 39.9 | 61.7 | 31.2 | 11.4 | 7.3 | 24.2 | 20.7 | 13.1 | 8.9 | 7.4 | 19.6 | 2.68 | 1.12 |
| Inside urbanized area | 25 298 | 78.4 | 42.4 | 63.4 | 33.2 | 12.1 | 7.7 | 21.6 | 18.9 | 11.3 | 7.0 | 5.7 | 16.4 | 2.76 | 1.16 |
| Outside urbanized area | 32 839 | 73.7 | 37.9 | 60.4 | 29.7 | 10.9 | 7.0 | 26.3 | 22.1 | 14.4 | 10.4 | 8.6 | 22.0 | 2.62 | 1.08 |
| Rural | 92 095 | 80.9 | 39.9 | 69.9 | 34.0 | 7.9 | 4.3 | 19.1 | 16.9 | 9.3 | 7.7 | 5.8 | 19.9 | 2.80 | 1.16 |
| Outside metropolitan area | 534 427 | 74.1 | 33.6 | 60.8 | 26.2 | 10.5 | 6.1 | 25.9 | 23.7 | 15.1 | 12.9 | 10.2 | 29.2 | 2.56 | 1.04 |
| Urban | 225 666 | 69.5 | 31.8 | 53.3 | 22.2 | 13.5 | 8.3 | 30.5 | 27.7 | 18.7 | 14.9 | 12.2 | 30.8 | 2.45 | 1.00 |
| Inside urbanized area | 326 | 88.3 | 42.9 | 78.8 | 38.7 | 5.8 | 2.5 | 11.7 | 11.3 | 6.7 | 4.0 | 3.7 | 11.7 | 2.87 | 1.07 |
| Outside urbanized area | 225 340 | 69.5 | 31.8 | 53.3 | 22.2 | 13.5 | 8.3 | 30.5 | 27.7 | 18.7 | 14.9 | 12.2 | 30.9 | 2.45 | 1.00 |
| Place of 10,000 or more | 106 343 | 68.4 | 32.3 | 52.6 | 23.1 | 13.1 | 8.0 | 31.6 | 28.0 | 18.3 | 13.5 | 11.2 | 27.2 | 2.44 | 1.01 |
| Place of 2,500 to 9,999 | 118 977 | 70.4 | 31.3 | 54.0 | 21.5 | 13.9 | 8.6 | 29.6 | 27.4 | 19.1 | 16.2 | 13.2 | 34.1 | 2.46 | 1.09 |
| Rural | 310 761 | 77.4 | 34.9 | 66.2 | 29.1 | 8.3 | 4.4 | 22.6 | 20.8 | 12.5 | 11.5 | 8.7 | 28.0 | 2.64 | 1.06 |
| COUNTY | | | | | | | | | | | | | | | |
| Arkansas County | 8 389 | 72.1 | 34.8 | 56.9 | 25.8 | 12.1 | 7.4 | 27.9 | 25.8 | 16.2 | 13.9 | 11.0 | 28.5 | 2.54 | 1.06 |
| Asheley County | 8 890 | 76.7 | 37.0 | 61.7 | 28.7 | 11.9 | 6.7 | 23.3 | 21.9 | 13.5 | 11.8 | 9.6 | 26.4 | 2.70 | 1.16 |
| Benton County | 13 486 | 73.5 | 32.8 | 65.4 | 19.3 | 6.1 | 3.4 | 26.5 | 24.5 | 16.5 | 15.9 | 12.0 | 42.8 | 2.28 | 1.09 |
| Benton County | 37 555 | 77.2 | 32.5 | 67.9 | 27.2 | 6.9 | 4.1 | 22.8 | 20.0 | 12.7 | 10.0 | 8.2 | 29.0 | 2.55 | 1.03 |
| Benton County | 11 131 | 74.4 | 33.3 | 64.2 | 27.5 | 7.9 | 4.6 | 25.6 | 23.2 | 15.6 | 12.8 | 10.2 | 28.6 | 2.50 | 1.05 |
| Bradley County | 4 545 | 73.3 | 32.6 | 57.0 | 23.7 | 13.3 | 7.5 | 26.7 | 25.2 | 16.8 | 15.0 | 12.3 | 32.5 | 2.54 | 1.03 |
| Calhoun County | 2 185 | 74.0 | 33.7 | 60.9 | 27.1 | 10.5 | 5.6 | 26.0 | 24.0 | 14.4 | 13.8 | 10.7 | 29.8 | 2.63 | 1.13 |
| Carroll County | 7 550 | 72.0 | 30.4 | 61.0 | 24.4 | 8.4 | 4.6 | 26.0 | 24.4 | 15.6 | 12.4 | 9.7 | 29.7 | 2.45 | 1.02 |
| Chicot County | 5 557 | 71.2 | 34.7 | 65.8 | 20.1 | 21.7 | 13.2 | 28.8 | 26.8 | 17.8 | 16.5 | 12.8 | 32.6 | 2.81 | 1.44 |
| Clark County | 7 907 | 69.3 | 30.8 | 55.7 | 22.9 | 11.2 | 6.9 | 30.7 | 27.4 | 17.9 | 14.6 | 11.7 | 30.1 | 2.42 | 1.06 |
| City County | 7 504 | 71.7 | 29.8 | 61.4 | 24.8 | 7.7 | 3.8 | 28.3 | 26.5 | 18.0 | 16.4 | 13.1 | 34.1 | 2.38 | 1.27 |
| Cleveland County | 7 926 | 76.0 | 28.2 | 67.2 | 23.4 | 6.7 | 3.7 | 24.0 | 22.0 | 14.1 | 12.4 | 9.4 | 32.7 | 2.41 | 1.20 |
| Cleveland County | 2 668 | 79.0 | 37.3 | 66.7 | 30.7 | 9.5 | 5.3 | 21.0 | 19.5 | 12.2 | 12.2 | 9.5 | 26.7 | 2.69 | 1.09 |
| Columbia County | 9 638 | 71.1 | 32.7 | 64.4 | 24.0 | 13.8 | 7.5 | 28.9 | 26.8 | 17.4 | 15.3 | 12.0 | 30.7 | 2.57 | 1.13 |
| Cornwall County | 7 179 | 74.6 | 33.5 | 60.8 | 26.2 | 10.9 | 5.9 | 25.4 | 23.5 | 14.8 | 13.3 | 10.5 | 29.3 | 2.62 | 1.10 |
| Crawford County | 26 285 | 71.8 | 34.8 | 58.7 | 27.4 | 10.5 | 6.3 | 28.2 | 23.5 | 14.7 | 9.7 | 8.2 | 20.8 | 2.53 | 1.01 |
| Crawford County | 15 251 | 80.2 | 41.0 | 67.6 | 33.3 | 9.9 | 6.4 | 19.8 | 17.9 | 11.2 | 8.9 | 7.2 | 21.2 | 2.25 | 1.12 |
| Crawford County | 17 120 | 75.8 | 39.7 | 63.1 | 26.5 | 18.7 | 11.3 | 24.2 | 21.3 | 12.4 | 9.2 | 6.9 | 20.8 | 2.89 | 1.39 |
| Crawford County | 6 754 | 77.6 | 39.8 | 61.2 | 30.3 | 12.8 | 7.5 | 22.4 | 20.8 | 13.9 | 11.4 | 9.2 | 26.4 | 2.81 | 1.25 |
| Crawford County | 3 600 | 72.9 | 32.9 | 57.4 | 25.4 | 11.6 | 5.9 | 27.1 | 25.3 | 15.7 | 15.1 | 11.3 | 31.5 | 2.61 | 1.14 |
| Crawford County | 5 957 | 73.6 | 38.2 | 52.8 | 25.9 | 17.5 | 10.8 | 26.4 | 24.3 | 15.7 | 14.1 | 10.9 | 28.6 | 2.78 | 1.34 |
| Crawford County | 6 342 | 74.1 | 37.6 | 57.4 | 27.8 | 13.6 | 8.4 | 25.9 | 23.7 | 14.7 | 12.1 | 9.4 | 25.4 | 2.63 | 1.12 |
| Crawford County | 21 325 | 73.8 | 37.0 | 62.1 | 30.2 | 9.3 | 5.5 | 26.2 | 20.5 | 12.2 | 8.5 | 6.9 | 19.5 | 2.65 | 1.10 |
| Crawford County | 5 578 | 76.2 | 35.2 | 63.3 | 29.3 | 8.0 | 4.5 | 23.8 | 22.2 | 14.1 | 12.7 | 9.9 | 28.8 | 2.58 | 1.03 |
| Crawford County | 4 010 | 75.3 | 30.9 | 63.8 | 26.1 | 7.0 | 3.7 | 24.7 | 23.3 | 15.4 | 14.5 | 11.1 | 35.0 | 2.47 | 1.20 |
| Crawford County | 30 836 | 69.4 | 26.5 | 57.5 | 20.0 | 9.5 | 5.4 | 30.6 | 27.6 | 17.5 | 14.7 | 11.2 | 34.3 | 2.32 | 1.22 |
| Crawford County | 5 118 | 79.4 | 38.9 | 69.1 | 33.5 | 7.2 | 3.8 | 20.6 | 19.1 | 11.9 | 10.4 | 8.3 | 23.1 | 2.70 | 1.09 |
| Crawford County | 12 325 | 75.8 | 34.9 | 64.7 | 28.9 | 8.5 | 4.7 | 24.2 | 22.0 | 14.3 | 11.9 | 9.7 | 26.2 | 2.54 | 1.27 |
| Crawford County | 8 212 | 73.1 | 34.8 | 56.6 | 25.6 | 13.4 | 7.8 | 26.9 | 25.0 | 15.8 | 13.4 | 10.6 | 28.8 | 2.58 | 1.09 |
| Crawford County | 10 115 | 75.5 | 34.3 | 62.6 | 27.0 | 10.0 | 5.9 | 24.5 | 23.2 | 15.0 | 12.8 | 10.1 | 28.9 | 2.55 | 1.00 |
| Crawford County | 4 975 | 75.1 | 36.0 | 60.6 | 28.1 | 11.5 | 6.7 | 24.9 | 23.4 | 15.3 | 13.9 | 10.7 | 29.7 | 2.65 | 1.13 |
| Crawford County | 11 846 | 75.1 | 35.9 | 64.0 | 29.8 | 8.2 | 4.7 | 24.9 | 22.8 | 14.7 | 11.9 | 9.3 | 25.8 | 2.58 | 1.03 |
| Crawford County | 4 684 | 74.4 | 27.0 | 65.4 | 22.7 | 6.9 | 3.4 | 25.6 | 24.2 | 16.2 | 16.2 | 12.4 | 40.0 | 2.37 | 1.20 |
| Crawford County | 7 361 | 73.0 | 32.7 | 57.8 | 25.1 | 12.2 | 6.3 | 27.0 | 25.0 | 16.1 | 14.1 | 10.9 | 30.1 | 2.54 | 1.04 |
| Crawford County | 30 001 | 73.2 | 35.9 | 54.0 | 24.9 | 15.0 | 9.6 | 26.8 | 24.2 | 14.7 | 11.8 | 9.0 | 25.6 | 2.70 | 1.24 |
| Crawford County | 7 059 | 72.8 | 32.8 | 61.3 | 26.4 | 8.6 | 5.2 | 27.2 | 24.4 | 15.7 | 14.0 | 10.9 | 29.8 | 2.70 | 1.28 |
| Crawford County | 3 584 | 72.2 | 31.6 | 55.1 | 23.8 | 13.9 | 6.7 | 27.8 | 26.6 | 16.7 | 15.9 | 12.8 | 33.5 | 2.66 | 1.23 |
| Crawford County | 6 857 | 73.5 | 32.7 | 61.9 | 26.5 | 9.3 | 5.1 | 26.5 | 24.9 | 17.2 | 14.9 | 11.9 | 32.0 | 2.49 | 1.26 |
| Crawford County | 4 578 | 72.7 | 36.3 | 49.0 | 21.8 | 20.1 | 12.9 | 27.3 | 25.6 | 15.4 | 14.4 | 10.8 | 30.9 | 2.82 | 1.43 |
| Crawford County | 3 796 | 75.1 | 36.9 | 58.2 | 27.8 | 14.0 | 7.7 | 24.9 | 23.4 | 14.5 | 12.8 | 9.9 | 28.2 | 2.76 | 1.29 |
| Crawford County | 5 150 | 76.3 | 37.3 | 61.4 | 28.9 | 11.5 | 6.9 | 23.7 | 22.1 | 13.4 | 11.7 | 8.9 | 25.4 | 2.68 | 1.15 |
| Crawford County | 7 628 | 74.9 | 35.0 | 63.6 | 28.6 | 8.6 | 5.0 | 25.1 | 23.6 | 15.2 | 14.2 | 11.3 | 30.5 | 2.60 | 1.09 |
| Crawford County | 13 866 | 79.5 | 42.0 | 67.2 | 34.7 | 9.4 | 5.8 | 20.5 | 18.5 | | | | | | |



Reply to
Attention of:

DEPARTMENT OF THE ARMY
MEMPHIS DISTRICT, CORPS OF ENGINEERS
8-202 CLIFFORD DAVIS FEDERAL BUILDING
167 N. MID-AMERICA MALL
MEMPHIS, TENNESSEE 38103-1894

April 1, 1992

Engineering Division
Hydraulics and Hydrology Branch

Ms. Laura J. Morrisson, Project Scientist
B & V Waste Science & Technology Corporation
1117 Perimeter Center West, Suite W-212
Atlanta, Georgia 30338

Dear Ms. Morrisson:

Reference is made to your letter dated March 25, 1992, and follow-up telephone conversation with Ms. Jancie Hatcher on March 31, 1992, inquiring about water flow information in the Memphis, Tennessee, area.

Please find enclosed the following discharge data for 1990 at Corps of Engineers' gaging locations:

- a. Mississippi River at Memphis, Tennessee, River Mile 734.4
- b. Loosahatchie River at Brunswick, Tennessee, River Mile 25.3
- c. Wolf River at Raleigh, Tennessee, River Mile 9.4

Also enclosed are discharge data for USGS gaging locations from October, 1989, to September, 1990:

- a. Nonconnah Creek near Germantown, Tennessee, River Mile 17.3
- b. Wolf River at Walnut Grove Road at Memphis, Tennessee, River Mile 15.4
- c. Loosahatchie River near Arlington, Tennessee, River Mile 30.4

If we can be of further assistance, please feel free to contact us.

Sincerely,

A handwritten signature in cursive script, appearing to read "Dewey L. Jones", is written over the typed name and title.

Dewey L. Jones
Chief, Hydraulics and Hydrology Branch

Enclosures

WOLF RIVER BASIN

179

07031660 WOLF RIVER AT WALNUT GROVE ROAD AT MEMPHIS, TN

LOCATION.--Lat 35°07'58", long 89°31'18", Shelby County, Hydrologic Unit 08010210, on right bank at upstream end of bridge on Walnut Grove Road, 0.5 mi east of Interstate Highway 240, and at mile 15.4.

DRAINAGE AREA.--709 mi².

PERIOD OF RECORD.--October 1969 to current year. Prior to September 1977 published as "near Germantown" and Oct. 1978 to Sept. 1986 "at Germantown".

GAGE.--Water-stage recorder. Datum of gage is 225.82 ft above National Geodetic Vertical Datum of 1929. Prior to Apr. 21, 1986 water-stage recorder at site 2.1 mi upstream at datum 0.94 ft higher.

REMARKS.--Records poor. Periodic observations of water temperature and specific conductance are published in this report as miscellaneous water quality data.

AVERAGE DISCHARGE.--21 years, 1,023 ft³/s, 19.59 in/yr.

EXTREMES FOR PERIOD OF RECORD.--Maximum discharge, 33,400 ft³/s, Mar. 14, 1975; gage height, 27.98 ft, site and datum then in use; minimum, 184 ft³/s, Oct. 8, 9, 12, 13, 1987.

EXTREMES FOR CURRENT YEAR.--Peak discharges greater than base discharge of 7,000 ft³/s and maximum (*):

| Date | Time | Discharge (ft ³ /s) | Gage height (ft) | Date | Time | Discharge (ft ³ /s) | Gage height (ft) |
|--------|---------|--------------------------------|------------------|--------|------|--------------------------------|------------------|
| Feb. 5 | Unknown | *19,800 | *22.92 | May 20 | 1245 | 7,160 | 14.78 |

Minimum discharge, 251 ft³/s, Sept. 1-3.

DISCHARGE, CUBIC FEET PER SECOND, WATER YEAR OCTOBER 1989 TO SEPTEMBER 1990
MEAN VALUES

| DAY | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP |
|-------|-------|-------|-------|-------|--------|-------|-------|-------|-------|-------|------|------|
| 1 | 956 | 377 | 495 | *2400 | 1870 | 721 | 750 | *4100 | 700 | 392 | 291 | 253 |
| 2 | 951 | 377 | 470 | *2130 | 5090 | 690 | 697 | *4000 | *670 | 386 | 282 | 251 |
| 3 | 807 | 370 | 458 | *1700 | *8430 | 699 | 854 | 3710 | *680 | 372 | 284 | 271 |
| 4 | 710 | 373 | 439 | 1960 | *11800 | 691 | 618 | 3440 | *830 | 363 | 280 | 259 |
| 5 | 724 | 383 | 430 | *1510 | *17300 | 661 | 608 | 3120 | *1100 | 338 | 282 | 261 |
| 6 | 757 | 405 | 440 | *1410 | 13300 | 864 | 1210 | 2750 | *930 | 315 | 282 | 257 |
| 7 | 687 | 405 | 417 | *1310 | 6690 | 762 | 1120 | 1990 | *850 | 317 | 280 | 257 |
| 8 | 583 | 1950 | 411 | *1220 | 3990 | 4710 | 943 | 1290 | *690 | 320 | 277 | 262 |
| 9 | 514 | 1040 | 425 | 1020 | 2970 | 3510 | 745 | 887 | *590 | 319 | 274 | 265 |
| 10 | 469 | 1030 | 445 | 882 | 5760 | 3730 | 697 | 725 | *570 | 323 | 273 | 266 |
| 11 | 440 | 935 | 443 | 761 | 8620 | 3060 | 700 | 824 | *550 | 347 | 271 | 283 |
| 12 | 421 | 740 | 433 | 837 | 6460 | 2460 | 867 | 812 | *540 | 597 | 268 | *410 |
| 13 | 412 | 599 | 442 | *586 | 4380 | 1930 | 803 | 811 | *530 | 432 | 337 | 406 |
| 14 | 407 | 556 | 452 | 340 | 2910 | 1490 | 573 | 833 | *522 | 472 | 318 | 328 |
| 15 | 403 | 564 | 439 | 533 | 4020 | 3840 | 562 | 811 | *520 | 448 | 329 | 324 |
| 16 | 991 | 537 | 430 | 518 | 4290 | 2390 | 561 | 817 | *610 | 399 | 319 | 327 |
| 17 | 2810 | 594 | 403 | 623 | 3240 | 2440 | 1080 | 788 | *620 | 374 | 316 | 326 |
| 18 | 1370 | 627 | 389 | 1120 | 2200 | 2820 | 1300 | 806 | *550 | 349 | 309 | 316 |
| 19 | 1070 | *550 | 410 | 1020 | 1540 | 2620 | 1170 | 911 | *530 | 343 | 299 | 308 |
| 20 | 824 | *460 | 406 | 1140 | 1010 | 1860 | 903 | 5220 | *520 | 334 | 289 | 309 |
| 21 | 681 | *445 | *399 | 1110 | 804 | 1270 | 2730 | 4020 | *522 | 321 | 283 | 318 |
| 22 | 631 | *890 | *391 | 1100 | 1520 | 906 | 2380 | 4790 | *560 | 355 | 277 | 338 |
| 23 | 811 | *899 | *392 | 900 | 1520 | 744 | 2810 | 4730 | *580 | 378 | 271 | 343 |
| 24 | 558 | *740 | *397 | 800 | 1420 | 651 | 2470 | 3940 | *550 | 384 | 266 | 344 |
| 25 | 496 | *770 | *389 | 733 | 1270 | 608 | 2290 | 3160 | *490 | 411 | 261 | 350 |
| 26 | 447 | *690 | *395 | *872 | 1060 | 581 | *1800 | 2430 | *470 | 378 | 258 | 370 |
| 27 | *425 | *640 | *385 | 600 | 925 | 578 | *1780 | 1710 | *480 | 352 | 257 | 397 |
| 28 | *415 | *610 | *397 | *802 | 791 | 578 | *2600 | 1250 | 438 | 337 | 257 | 388 |
| 29 | *405 | 593 | 471 | *3780 | --- | 585 | *3350 | 981 | 422 | 321 | 257 | 329 |
| 30 | *390 | 532 | *2200 | *2440 | --- | 1510 | *4000 | 718 | 404 | 315 | 258 | 316 |
| 31 | 387 | --- | *2250 | *2460 | --- | 974 | --- | 685 | --- | 296 | 256 | --- |
| TOTAL | 21752 | 19683 | 16753 | 38417 | 123180 | 50731 | 41862 | 65839 | 17998 | 11388 | 8761 | 9432 |
| MEAN | 702 | 656 | 540 | 1239 | 4399 | 1636 | 1393 | 2124 | 600 | 367 | 283 | 314 |
| MAX | 2810 | 1950 | 2250 | 3780 | 17300 | 4710 | 4000 | 5220 | 1100 | 597 | 337 | 410 |
| MIN | 387 | 370 | 389 | 518 | 791 | 578 | 561 | 611 | 404 | 296 | 256 | 251 |
| CFSM | .99 | .93 | .76 | 1.75 | 6.20 | 2.31 | 1.87 | 3.00 | .85 | .52 | .40 | .44 |
| IN. | 1.14 | 1.03 | .88 | 2.02 | 6.46 | 2.66 | 2.20 | 3.45 | .94 | .60 | .46 | .49 |

CAL YR 1989 TOTAL 560214 MEAN 1535 MAX 14900 MIN 350 CFSM 2.16 IN. 29.39
WTR YR 1990 TOTAL 425796 MEAN 1167 MAX 17300 MIN 251 CFSM 1.65 IN. 22.34

* Estimated

2

LOOSAHATCHIE RIVER BASIN

07030240 LOOSAHATCHIE RIVER NEAR ARLINGTON, TN

LOCATION.--Lat 35°18'37", long 89°38'23", Shelby County, Hydrologic Unit 08010209, on left bank 20 ft downstream from bridge on U.S. Highways 70 and 79, 1.5 mi upstream from Beaver Creek, 1.5 mi northeast of Arlington, and at mile 30.4.

DRAINAGE AREA.--262 mi².

PERIOD OF RECORD.--October 1969 to current year.

GAGE.--Water-stage recorder. Datum of the gage is 246.43 ft above National Geodetic Vertical Datum of 1929.

REMARKS.--Records poor. Periodic observations of water temperature and specific conductance are published in this report as miscellaneous water quality data.

AVERAGE DISCHARGE.--21 years, 378 ft³/s, 19.59 in/yr.

EXTREMES FOR PERIOD OF RECORD.--Maximum discharge, 27,400 ft³/s, Dec. 25, 1987, gage height, 25.27 ft; minimum, 66 ft³/s, Apr. 6, 7, 1974.

EXTREMES FOR CURRENT YEAR.--Peak discharges greater than base discharge of 5,500 ft³/s and maximum (*):

| Date | Time | Discharge (ft ³ /s) | Gage height (ft) | Date | Time | Discharge (ft ³ /s) | Gage height (ft) |
|---------|---------|--------------------------------|------------------|---------|------|--------------------------------|------------------|
| Nov. 8 | 0900 | 6,850 | 17.15 | Feb. 15 | 2400 | 6,330 | 16.52 |
| Jan. 29 | Unknown | Unknown | Unknown | Mar. 8 | 1200 | 7,360 | 17.66 |
| Feb. 4 | Unknown | 14,500 | 22.11 | Apr. 21 | 1315 | 5,540 | 17.59 |
| Feb. 10 | Unknown | Unknown | Unknown | | | | |

Minimum discharge, 97 ft³/s, several days.

DISCHARGE, CUBIC FEET PER SECOND, WATER YEAR OCTOBER 1969 TO SEPTEMBER 1990
MEAN VALUES

| DAY | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP |
|-------|------|-------|------|-------|-------|-------|-------|-------|------|------|------|------|
| 1 | 334 | 128 | 115 | 486 | 273 | 353 | 172 | 235 | 150 | 107 | 101 | 97 |
| 2 | 225 | 124 | 115 | 232 | 5400 | 360 | 168 | 1660 | 150 | 105 | 101 | 97 |
| 3 | 183 | 123 | 111 | 197 | 8900 | 348 | 163 | 951 | 400 | 105 | 101 | 97 |
| 4 | 146 | 123 | 110 | 1120 | 12000 | 328 | 140 | 498 | 220 | 103 | 101 | 98 |
| 5 | 141 | 123 | 110 | 403 | 2350 | 316 | 134 | 190 | 170 | 100 | 101 | 98 |
| 6 | 137 | 138 | 110 | 216 | 820 | 312 | 228 | 173 | 145 | 100 | 101 | 98 |
| 7 | 134 | 304 | 114 | 172 | 634 | 320 | 232 | 170 | 140 | 100 | 101 | 98 |
| 8 | 131 | 5320 | 114 | 168 | 564 | 4840 | 159 | 168 | 135 | 99 | 101 | 98 |
| 9 | 130 | 2200 | 112 | 157 | 847 | 2810 | 146 | 155 | 132 | 99 | 101 | 98 |
| 10 | 128 | 398 | 110 | 141 | 6700 | 599 | 152 | 143 | 129 | 99 | 101 | 102 |
| 11 | 126 | 211 | 108 | 132 | 2330 | 306 | 179 | 147 | 128 | 103 | 101 | 129 |
| 12 | 125 | 176 | 106 | 125 | 732 | 508 | 151 | 175 | 127 | 140 | 101 | 108 |
| 13 | 124 | 164 | 105 | 117 | 545 | 687 | 140 | 163 | 125 | 157 | 102 | 102 |
| 14 | 124 | 159 | 104 | 116 | 456 | 271 | 138 | 141 | 122 | 117 | 102 | 100 |
| 15 | 123 | 169 | 103 | 115 | 2900 | 3340 | 138 | 139 | 121 | 108 | 102 | 103 |
| 16 | 304 | 182 | 100 | 113 | 4650 | 1550 | 138 | 138 | 120 | 106 | 102 | 100 |
| 17 | 2310 | 152 | 100 | 302 | 1100 | 427 | 1140 | 185 | 118 | 104 | 102 | 98 |
| 18 | 343 | 142 | 100 | 843 | 576 | 296 | 791 | 170 | 118 | 103 | 102 | 98 |
| 19 | 199 | 137 | 100 | 380 | 493 | 243 | 241 | 193 | 117 | 104 | 102 | 98 |
| 20 | 170 | 136 | 101 | 500 | 426 | 211 | 188 | 3570 | 116 | 104 | 102 | 98 |
| 21 | 154 | 133 | 100 | 323 | 396 | 198 | 3520 | 1600 | 114 | 103 | 101 | 99 |
| 22 | 148 | 327 | 97 | 185 | 1720 | 189 | 3140 | 700 | 160 | 103 | 100 | 100 |
| 23 | 141 | 480 | 97 | 152 | 856 | 182 | 526 | 400 | 130 | 103 | 100 | 99 |
| 24 | 138 | 182 | 97 | 137 | 515 | 175 | 246 | 250 | 119 | 102 | 100 | 97 |
| 25 | 134 | 153 | 97 | 144 | 409 | 170 | 203 | 217 | 112 | 102 | 99 | 97 |
| 26 | 131 | 140 | 99 | 126 | 375 | 165 | 181 | 193 | 112 | 102 | 99 | 97 |
| 27 | 130 | 133 | 99 | 114 | 362 | 160 | 326 | 187 | 111 | 102 | 99 | 97 |
| 28 | 128 | 127 | 98 | 346 | 352 | 158 | 5370 | 182 | 110 | 102 | 99 | 97 |
| 29 | 127 | 119 | 105 | 3910 | --- | 163 | 2580 | 162 | 109 | 102 | 98 | 97 |
| 30 | 127 | 117 | 898 | 1310 | --- | 754 | 396 | 161 | 108 | 102 | 98 | 97 |
| 31 | 127 | --- | 2180 | 392 | --- | 278 | --- | 143 | --- | 102 | 97 | --- |
| TOTAL | 7300 | 12539 | 5915 | 13275 | 57781 | 21027 | 21426 | 13559 | 4169 | 3288 | 3118 | 2992 |
| MEAN | 235 | 418 | 191 | 428 | 2064 | 676 | 714 | 437 | 139 | 106 | 101 | 99.7 |
| MAX | 2310 | 5320 | 2180 | 3910 | 12000 | 4840 | 5370 | 3570 | 400 | 157 | 102 | 129 |
| MIN | 123 | 117 | 97 | 113 | 273 | 158 | 134 | 138 | 108 | 99 | 97 | 97 |
| CFSM | .80 | 1.60 | .73 | 1.63 | 7.88 | 2.59 | 2.73 | 1.67 | .53 | .40 | .38 | .38 |
| IN. | 1.04 | 1.78 | .84 | 1.88 | 8.20 | 2.99 | 3.04 | 1.93 | .59 | .47 | .44 | .42 |

CAL YR 1989 TOTAL 227119 MEAN 622 MAX 13000 MIN 84 CFSM 2.37 IN. 32.25
WTR YR 1990 TOTAL 166389 MEAN 456 MAX 12000 MIN 97 CFSM 1.74 IN. 23.62

* Estimated

DAILY DISCHARGE FOR 1990

21

MISSISSIPPI RIVER AT MEMPHIS, TENN.

COMPUTED DAILY DISCHARGE IN THOUSAND CUBIC FEET PER SECOND

| DAY | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC |
|------------------------------|-----|------|------|--------|-----------------------------|------|-----|-----|-----|-----|-----|------|
| 1 | 196 | 601 | 1120 | 666 | 539 | 1113 | 669 | 452 | 409 | 258 | 435 | 325 |
| 2 | 203 | 621 | 1102 | 643 | 517 | 1106 | 654 | 422 | 408 | 249 | 422 | 336 |
| 3 | 222 | 664 | 1068 | 618 | 497 | 1103 | 635 | 406 | 407 | 240 | 394 | 358 |
| 4 | 270 | 715 | 1010 | 585 | 482 | 1104 | 614 | 409 | 401 | 238 | 357 | 372 |
| 5 | 349 | 766 | 922 | 557 | 483 | 1103 | 592 | 415 | 392 | 230 | 322 | 383 |
| 6 | 443 | 830 | 814 | 534 | 496 | 1101 | 577 | 406 | 379 | 225 | 293 | 406 |
| 7 | 527 | 885 | 722 | 503 | 511 | 1094 | 560 | 398 | 368 | 227 | 279 | 451 |
| 8 | 611 | 928 | 683 | 481 | 541 | 1081 | 542 | 395 | 363 | 240 | 272 | 503 |
| 9 | 642 | 963 | 676 | 464 | 601 | 1060 | 524 | 395 | 366 | 252 | 273 | 536 |
| 10 | 658 | 972 | 645 | 452 | 655 | 1036 | 514 | 402 | 362 | 260 | 276 | 550 |
| 11 | 661 | 1003 | 609 | 439 | 685 | 1010 | 510 | 410 | 352 | 263 | 275 | 551 |
| 12 | 648 | 1009 | 592 | 433 | 685 | 979 | 511 | 413 | 350 | 269 | 279 | 540 |
| 13 | 619 | 1015 | 580 | 444 | 664 | 947 | 507 | 406 | 352 | 286 | 285 | 519 |
| 14 | 580 | 1017 | 572 | 466 | 633 | 908 | 504 | 389 | 341 | 301 | 299 | 482 |
| 15 | 537 | 1029 | 585 | 487 | 611 | 869 | 509 | 375 | 321 | 311 | 319 | 444 |
| 16 | 504 | 1052 | 607 | 507 | 604 | 832 | 516 | 364 | 307 | 312 | 337 | 407 |
| 17 | 485 | 1066 | 623 | 525 | 618 | 794 | 521 | 352 | 303 | 321 | 347 | 380 |
| 18 | 471 | 1081 | 634 | 552 | 660 | 743 | 533 | 340 | 300 | 343 | 354 | 386 |
| 19 | 445 | 1103 | 723 | 564 | 743 | 688 | 555 | 334 | 293 | 371 | 351 | 398 |
| 20 | 418 | 1125 | 796 | 573 | 850 | 651 | 574 | 326 | 288 | 396 | 344 | 438 |
| 21 | 403 | 1141 | 852 | 573 | 933 | 649 | 582 | 318 | 283 | 410 | 333 | 574 |
| 22 | 428 | 1154 | 888 | 556 | 990 | 670 | 587 | 316 | 281 | 411 | 315 | 705 |
| 23 | 483 | 1155 | 917 | 532 | 1037 | 676 | 587 | 323 | 285 | 400 | 298 | 812 |
| 24 | 539 | 1150 | 925 | 514 | 1074 | 674 | 577 | 341 | 287 | 392 | 290 | 911 |
| 25 | 585 | 1142 | 923 | 516 | 1102 | 673 | 561 | 365 | 281 | 393 | 286 | 972 |
| 26 | 614 | 1134 | 912 | 527 | 1116 | 679 | 543 | 389 | 273 | 401 | 289 | 1021 |
| 27 | 625 | 1126 | 885 | 535 | 1121 | 682 | 534 | 411 | 268 | 413 | 298 | 1078 |
| 28 | 627 | 1124 | 841 | 552 | 1120 | 688 | 533 | 423 | 268 | 422 | 315 | 1131 |
| 29 | 634 | | 778 | 566 | 1118 | 689 | 527 | 428 | 267 | 427 | 320 | 1166 |
| 30 | 630 | | 722 | 560 | 1116 | 680 | 510 | 429 | 264 | 429 | 321 | 1198 |
| 31 | 615 | | 691 | | 1112 | | 484 | 423 | | 433 | | 1232 |
| MEAN | 505 | 985 | 788 | 530 | 771 | 869 | 593 | 386 | 327 | 326 | 319 | 631 |
| MAX | 661 | 1155 | 1120 | 666 | 1121 | 1113 | 669 | 452 | 409 | 433 | 435 | 1232 |
| MIN | 196 | 601 | 572 | 433 | 482 | 649 | 484 | 316 | 264 | 225 | 272 | 325 |
| TOTAL DISCHARGE FOR YEAR WAS | | | | 211827 | MEAN DISCHARGE FOR YEAR WAS | | | | 580 | | | |

MAXIMUM DISCHARGE WAS 1,242,243 CFS ON DEC. 31.
 MINIMUM DISCHARGE WAS 194,180 CFS ON JAN. 1.

MISSISSIPPI RIVER AT MEMPHIS, TENN.

LOCATION. LAT. 35-07-23, LONG. 90-04-36. MILE 734.4, APPROXIMATELY EIGHTEEN HUNDRED FEET DOWNSTREAM FROM HARAHAN BRIDGE.

GAGE. AUTOMATIC RECORDER ON SOUTHWEST CORNER OF AMERICAN COMMERCIAL LIQUID TERMINAL OIL DOCK AT 427 WEST ILLINOIS AVENUE.

GENERAL INFORMATION. DRAINAGE AREA (REVISED). 928,700 SQUARE MILES. BANKFULL STAGE. 34 FEET. LOW WATER REFERENCE PLANE, MINUS 2.6 FEET ON GAGE. THE AVERAGE RELATION BETWEEN BEALE STREET GAGE AND GAGE NEAR BRIDGE IS A STRAIGHT LINE YIELDING STAGES ON THE BRIDGE GAGE THE SAME AT ZERO STAGE, AND 1.6 FEET LOWER AT THE 50 FOOT STAGE.

RECORDS AVAILABLE. STAGE, OCT. 1934 TO SEPT. 1951 AND OCT. 1952 TO DATE IN REPORTS OF U. S. GEOLOGICAL SURVEY. DEC. 1934 TO DATE IN REPORTS OF THE NATIONAL WEATHER SERVICE. (WEATHER SERVICE STAGES FROM DEC. 1890 TO AUG. 1932 REFER TO BEALE ST. GAGE, AND FROM SEPT. 1932 TO DEC. 1934 TO GAGE AT SITE 1,000 FEET DOWNSTREAM.) SINCE 1950 IN REPORTS OF THE CORPS OF ENGINEERS. MEASURED DISCHARGE, INTERMITTENTLY FROM 1882 TO 1904, AND 1932 TO DATE. DAILY DISCHARGE, JAN. 1933 TO DATE. ALSO IN REPORTS OF THE GEOLOGICAL SURVEY.

EXTREMES. HIGHEST, 48.7 FEET ON FEB. 10, 1937. LOWEST, MINUS 10.70 FEET ON JUL. 10 AND 11, 1968. MAXIMUM, 2,020,000 CFS WAS MEASURED ON FEB. 7, 1937 (STAGE, 48.3). MINIMUM, 78,000 CFS ON AUG. 23, 1936 (STAGE, 0.0).

DAILY EIGHT A.M. STAGE IN FEET

GAGE ZERO, 183.91 FEET, N.C.V.D. OF 1929

| DAY | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC |
|-----|------|------|------|------|------|------|------|------|-----|------|-----|------|
| 1 | -3.4 | 16.5 | 31.1 | 18.3 | 14.7 | 30.2 | 18.4 | 11.3 | 8.3 | 1.6 | 9.4 | 3.8 |
| 2 | -2.9 | 17.1 | 30.6 | 17.6 | 13.9 | 30.2 | 18.1 | 9.9 | 8.1 | 1.2 | 9.1 | 4.5 |
| 3 | -1.9 | 18.1 | 29.9 | 16.8 | 13.1 | 30.4 | 17.6 | 9.0 | 8.2 | 0.6 | 8.1 | 5.5 |
| 4 | 0.7 | 19.7 | 28.7 | 15.7 | 12.3 | 30.8 | 17.0 | 9.0 | 7.9 | 0.6 | 6.5 | 6.5 |
| 5 | 4.4 | 21.0 | 26.6 | 14.8 | 12.3 | 30.7 | 16.3 | 9.4 | 7.5 | 0.0 | 4.7 | 7.0 |
| 6 | 8.6 | 22.7 | 23.9 | 14.1 | 12.6 | 30.6 | 15.9 | 9.1 | 7.0 | -0.4 | 3.1 | 7.8 |
| 7 | 11.5 | 24.1 | 21.2 | 13.1 | 13.2 | 30.4 | 15.5 | 8.6 | 6.6 | -0.5 | 2.3 | 9.8 |
| 8 | 14.4 | 25.2 | 19.5 | 12.1 | 14.0 | 30.1 | 14.9 | 8.4 | 6.2 | 0.6 | 1.9 | 12.2 |
| 9 | 15.5 | 26.1 | 19.1 | 11.4 | 16.1 | 29.5 | 14.4 | 8.3 | 6.3 | 1.5 | 1.8 | 13.4 |
| 10 | 16.3 | 26.9 | 19.1 | 10.9 | 18.2 | 29.0 | 13.9 | 8.5 | 6.3 | 2.2 | 2.0 | 14.3 |
| 11 | 16.6 | 27.3 | 16.9 | 10.5 | 19.4 | 28.3 | 13.6 | 8.8 | 5.8 | 2.5 | 1.9 | 14.5 |
| 12 | 16.5 | 27.5 | 16.2 | 10.1 | 19.7 | 27.6 | 13.5 | 9.0 | 5.6 | 2.8 | 2.0 | 14.2 |
| 13 | 15.7 | 27.8 | 15.7 | 10.6 | 19.1 | 26.9 | 13.3 | 8.8 | 5.9 | 3.7 | 2.2 | 13.7 |
| 14 | 14.6 | 27.9 | 15.2 | 11.4 | 18.2 | 26.0 | 12.9 | 7.8 | 5.5 | 4.4 | 2.7 | 12.4 |
| 15 | 13.2 | 28.1 | 15.3 | 12.1 | 17.2 | 25.1 | 13.0 | 7.2 | 4.5 | 5.0 | 3.6 | 10.8 |
| 16 | 12.2 | 28.9 | 16.1 | 12.6 | 16.8 | 24.3 | 13.1 | 6.6 | 3.6 | 4.9 | 4.6 | 9.2 |
| 17 | 11.6 | 29.1 | 16.6 | 13.2 | 17.1 | 23.4 | 13.2 | 5.9 | 3.4 | 5.1 | 5.1 | 7.8 |
| 18 | 11.2 | 29.3 | 17.2 | 14.3 | 18.1 | 22.1 | 13.4 | 5.3 | 3.4 | 6.0 | 5.5 | 7.7 |
| 19 | 10.0 | 29.8 | 19.3 | 14.8 | 20.4 | 20.5 | 14.0 | 5.1 | 3.0 | 7.3 | 5.3 | 8.3 |
| 20 | 8.8 | 30.2 | 21.4 | 15.3 | 23.4 | 19.3 | 14.6 | 4.8 | 2.8 | 8.4 | 4.9 | 9.4 |
| 21 | 7.9 | 30.6 | 22.9 | 15.4 | 25.4 | 18.8 | 14.8 | 4.4 | 2.5 | 9.0 | 4.3 | 14.1 |
| 22 | 8.6 | 31.0 | 23.8 | 15.2 | 26.9 | 19.3 | 14.9 | 4.3 | 2.3 | 9.0 | 3.3 | 19.0 |
| 23 | 11.1 | 31.2 | 24.5 | 14.3 | 28.1 | 19.2 | 14.8 | 4.6 | 2.6 | 8.9 | 2.1 | 21.9 |
| 24 | 13.4 | 31.3 | 24.8 | 13.6 | 29.1 | 18.9 | 14.6 | 5.6 | 2.8 | 7.9 | 1.7 | 24.7 |
| 25 | 15.2 | 31.2 | 24.9 | 13.6 | 29.8 | 18.5 | 14.3 | 6.6 | 2.5 | 7.8 | 1.3 | 26.2 |
| 26 | 16.3 | 31.1 | 24.7 | 14.0 | 30.2 | 18.4 | 13.7 | 7.5 | 2.1 | 8.0 | 1.2 | 27.4 |
| 27 | 16.9 | 31.1 | 24.2 | 14.3 | 30.3 | 18.4 | 13.5 | 8.3 | 1.8 | 8.5 | 1.7 | 28.7 |
| 28 | 17.3 | 31.1 | 23.2 | 14.9 | 30.3 | 18.7 | 13.6 | 8.9 | 1.8 | 8.8 | 2.8 | 29.9 |
| 29 | 17.7 | | 21.6 | 15.5 | 30.3 | 18.9 | 13.6 | 9.2 | 1.9 | 9.0 | 3.3 | 30.8 |
| 30 | 17.6 | | 20.1 | 15.4 | 30.2 | 18.7 | 13.3 | 9.2 | 1.8 | 9.1 | 3.5 | 31.3 |
| 31 | 17.2 | | 19.0 | | 30.2 | | 12.4 | 9.0 | | 9.3 | | 32.1 |

THE FOLLOWING REFER ONLY TO READINGS APPEARING IN THE TABLE ABOVE.

| | | | | | | | | | | | | |
|------|-------|-------|-------|-------|-------|-------|-------|------|------|------|------|-------|
| MEAN | 11.38 | 26.85 | 21.71 | 13.87 | 20.98 | 24.45 | 14.51 | 7.69 | 4.60 | 4.92 | 3.74 | 15.45 |
| MAX. | 17.7 | 31.3 | 31.1 | 18.3 | 30.3 | 30.8 | 18.4 | 11.3 | 8.3 | 9.3 | 9.6 | 32.1 |
| MIN. | -3.4 | 16.5 | 15.2 | 10.1 | 12.3 | 18.4 | 12.4 | 4.3 | 1.8 | -0.5 | 1.2 | 3.8 |

HIGHEST STAGE WAS 32.43 ON DEC 31.
LOWEST STAGE WAS -3.46 ON JAN 1.

5

DAILY DISCHARGE FOR 1990

91

LOOSAHATCHIE RIVER AT BRUNSWICK, TENN.

COMPUTED DAILY DISCHARGE IN CUBIC FEET PER SECOND

| DAY | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC |
|------|-----|-------|-----|------|------|-----|-----|-----|-----|-----|-----|------|
| 1 | | | | | 438 | | | | | | | |
| 2 | 493 | | | | | | | | | | | |
| 3 | | | | | | | | | | 79 | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | | 785 | | | | | | 113 | | | 126 | |
| 7 | | | | | 319 | | | | | | | |
| 8 | | | | | | | | 123 | | | | |
| 9 | | | | | | | 140 | | | 220 | | |
| 10 | | | | | | | | | 112 | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | 452 | | | | | | | | | |
| 13 | | 529 | | | | | | | | | | |
| 14 | | | | | 201 | | | | | | | |
| 15 | | | | | | | | | | | | |
| 16 | | 10100 | | 270 | | | | | | | | |
| 17 | 228 | | | | | | | | | | | 345 |
| 18 | | | | | | | | | 116 | | | |
| 19 | | | | | | | | | | | | 7016 |
| 20 | | | | | | | | | | | | |
| 21 | | 331 | | | 3173 | | | | | | | |
| 22 | | | | | | | | | | | | |
| 23 | | | | 1043 | | | 138 | | | | | |
| 24 | | | | | | | | 121 | | | | |
| 25 | | | | | | | | | | 109 | | |
| 26 | 283 | | | | | | | | | | | |
| 27 | | | | | | | | 122 | | | 142 | |
| 28 | | | | | | | | | | | | |
| 29 | | | | | 168 | | | | | | | |
| 30 | | | | | | | | | | 100 | | |
| 31 | | | | | | | | | | | | |
| MEAN | | | | | | | | | | | | |
| MAX. | | | | | | | | | | | | |
| MIN. | | | | | | | | | | | | |

A-NO RECORD.

YEARLY RECORD INCOMPLETE.

DISCHARGE VALUES SHOWN ARE ACTUAL DISCHARGE OBSERVATIONS.

DAILY STAGES FOR 1990

LOOSAHATCHIE RIVER AT BRUNSWICK, TENN.

LOCATION. LAT. 35-16-32, LONG. 89-43-50. MILE 25.3. HIGHWAY BRIDGE ABOUT A MILE NORTH OF BRUNSWICK. THE MOUTH OF LOOSAHATCHIE RIVER IS 740.6 MILES UPSTREAM ON THE MISSISSIPPI RIVER FROM HEAD OF PASSES.

CAGE. STAGE DETERMINED FROM MARK ON GUARDRAIL ON UPSTREAM SIDE OF BRIDGE.

GENERAL INFORMATION. DRAINAGE AREA, 506 SQUARE MILES. BANKFULL STAGE, 21 FEET. DUE TO CHANNEL IMPROVEMENTS IN 1976, USING AN AUTOMATIC RECORDER ON THIS BRIDGE BECAME IMPRACTICAL.

RECORDS AVAILABLE. STAGE, JAN. 12, 1939, TO JUN. 28, 1976. STAGES PUBLISHED FROM JUN. 28, 1976, TO DATE ARE MEAN STAGES FOR TIME OF DISCHARGE OBSERVATION. COMPUTED DAILY DISCHARGE, 1939 TO JUN. 28, 1976. DISCHARGE VALUES FROM JUN. 28, 1976 TO DATE ARE ACTUAL DISCHARGE OBSERVATIONS.

EXTREMES. HIGHEST, 28.5 FEET, FROM WATERMARK, IN JAN. 1935. LOWEST OBSERVED STAGE, 4.01 FEET ON AUG 15, 1988. MAXIMUM 39,700 CFS OBSERVED ON JAN. 9, 1946 (STAGE, 25.8). DISCHARGE NOT DETERMINED FOR RECORD HIGH STAGE. MINIMUM, 46 CFS COMPUTED FOR JUL. 16, 1944, AND SUBSEQUENT DAYS.

DAILY EIGHT A.M. STAGE IN FEET

CAGE ZERO, 227.25 FEET, N.C.V.D. OF 1929

| DAY | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC |
|-----|-----|------|-----|-----|------|-----|-----|-----|-----|-----|-----|------|
| 1 | A | A | A | A | 5.7 | A | A | A | A | A | A | A |
| 2 | 5.0 | A | A | A | A | A | A | A | A | A | A | A |
| 3 | A | A | A | A | A | A | A | A | A | 4.3 | A | A |
| 4 | A | A | A | A | A | A | A | A | A | A | A | A |
| 5 | A | A | A | A | A | A | A | A | A | A | A | A |
| 6 | A | 7.1 | A | A | A | A | A | 4.3 | A | A | 4.3 | A |
| 7 | A | A | A | A | 4.8 | A | A | A | A | A | A | A |
| 8 | A | A | A | A | A | A | A | 4.3 | A | A | A | A |
| 9 | A | A | A | A | A | A | 4.3 | A | A | 4.5 | A | A |
| 10 | A | A | A | A | A | A | A | A | 4.3 | A | A | A |
| 11 | A | A | A | A | A | A | A | A | A | A | A | A |
| 12 | A | A | 5.3 | A | A | A | A | A | A | A | A | A |
| 13 | A | 5.3 | A | A | A | A | A | A | A | A | A | A |
| 14 | A | A | A | A | 4.6 | A | A | A | A | A | A | A |
| 15 | A | A | A | A | A | A | A | A | A | A | A | A |
| 16 | A | 19.7 | A | 4.4 | A | A | A | A | A | A | A | A |
| 17 | 4.2 | A | A | A | A | A | A | A | A | A | A | 4.7 |
| 18 | A | A | A | A | A | A | A | A | 4.3 | A | A | A |
| 19 | A | A | A | A | A | A | A | A | A | A | A | 18.3 |
| 20 | A | A | A | A | A | A | A | A | A | A | A | A |
| 21 | A | 4.8 | A | A | 12.4 | A | A | A | A | A | A | A |
| 22 | A | A | A | A | A | A | A | A | A | A | A | A |
| 23 | A | A | A | 7.1 | A | A | 4.3 | A | A | A | A | A |
| 24 | A | A | A | A | A | A | A | 4.3 | A | A | A | A |
| 25 | A | A | A | A | A | A | A | A | A | 4.3 | A | A |
| 26 | 4.4 | A | A | A | A | A | A | A | A | A | 4.3 | A |
| 27 | A | A | A | A | A | A | A | 4.3 | A | A | A | A |
| 28 | A | A | A | A | A | A | A | A | A | A | A | A |
| 29 | A | A | A | A | 4.5 | A | A | A | A | 4.3 | A | A |
| 30 | A | A | A | A | A | A | A | A | A | A | A | A |
| 31 | | | | | | | | | | | | |

THE FOLLOWING REFER ONLY TO READINGS APPEARING IN THE TABLE ABOVE

MEAN
MAX.
MIN.

A-NO RECORD.

YEARLY RECORD INCOMPLETE.

STAGES SHOWN ARE MEAN STAGES FOR TIME OF DISCHARGE OBSERVATIONS.

93

MAXIMUM DISCHARGE WAS 17,538 CFS ON FEB. 4.
MINIMUM DISCHARGE WAS NOT DETERMINED.

[illegible]

WOLF RIVER AT RALEIGH, TENN.

LOCATION. LAT. 35-12-08, LONG. 89-55-24. MILE 9.4, AUSTIN PEAY HIGHWAY BRIDGE. THE MOUTH OF WOLF RIVER IS 738.6 MILES UPSTREAM ON THE MISSISSIPPI RIVER FROM HEAD OF PASSES.

GAGE. AUTOMATIC RECORDER ON BRIDGE.

GENERAL INFORMATION. DRAINAGE AREA, 770 SQUARE MILES. BANKFULL STAGE, 12 FEET. DISCHARGE IS AFFECTED BY BACKWATER DURING HIGH MISSISSIPPI RIVER STAGES. RIVER CONDITIONS HAVE CHANGED SINCE 1962 DUE TO CHANNEL ENLARGEMENT AND REALIGNMENT OPERATIONS.

RECORDS AVAILABLE. STAGE, MAY 12, 1936, TO DATE. PRIOR TO NOV. 22, 1940, GAGE WAS 700 FEET DOWNSTREAM. COMPUTED DAILY DISCHARGE, 1936 TO DATE.

EXTREMES. HIGHEST, 23.72 FEET, FROM WATERMARK, ON JAN. 20, 1935. LOWEST, MINUS 5.93 FEET ON OCT. 15, 1963. MAXIMUM, 41,400 CFS COMPUTED FOR JAN. 9, 1946 (STAGE 20.4). DISCHARGE NOT DETERMINED FOR RECORD HIGH STAGE. MINIMUM, NO FLOW FROM JAN. 30 TO FEB. 9, 1937, BECAUSE OF BACKWATER.

DAILY EIGHT A.M. STAGE IN FEET

GAGE ZERO, 217.22 FEET, N.C.V.D. OF 1929

| DAY | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP | OCT | NOV | DEC |
|-----|------|------|------|--------|------|--------|------|--------|------|--------|------|------|
| 1 | 0.1 | 0.5 | 0.7 | E 0.1 | 3.2 | A | A | -3.3 | A | A | A | A |
| 2 | 0.1 | 7.3 | 0.3 | E 0.0 | 2.8 | A | A | E -3.3 | A | A | A | A |
| 3 | -0.4 | 8.3 | 0.1 | E 0.0 | 3.1 | A | A | E -3.4 | A | -3.6 | A | 0.3 |
| 4 | 0.9 | 9.1 | -0.3 | E -0.1 | 2.7 | A | A | E -3.4 | A | 0.9 | A | A |
| 5 | -0.4 | 10.8 | -0.6 | E -0.2 | 2.3 | A | A | E -3.4 | A | -0.8 | -3.2 | A |
| 6 | -0.5 | 12.5 | -1.2 | -0.3 | 2.1 | A | A | -3.4 | A | E -1.0 | A | A |
| 7 | -0.8 | 8.6 | -1.3 | A | 1.3 | A | A | -3.4 | A | A | A | A |
| 8 | -0.9 | 5.3 | 4.8 | A | 0.2 | A | A | -3.4 | A | A | A | A |
| 9 | -1.4 | 3.5 | 1.5 | A | 0.0 | A | -3.2 | A | A | A | A | A |
| 10 | A | 8.3 | 2.3 | A | A | A | A | A | -3.6 | A | A | A |
| 11 | A | 6.7 | 2.0 | A | A | -1.1 | A | A | -3.4 | A | A | -3.0 |
| 12 | A | 7.3 | 1.7 | A | A | A | A | A | -3.3 | A | A | -2.0 |
| 13 | A | 5.5 | 1.2 | A | A | A | A | A | A | A | A | A |
| 14 | A | 3.0 | 0.5 | A | -2.1 | A | A | A | A | A | -2.9 | A |
| 15 | A | 3.4 | 3.1 | A | A | A | A | A | A | A | A | A |
| 16 | A | 6.2 | 1.7 | -2.9 | A | A | A | A | A | A | A | A |
| 17 | -2.7 | 3.3 | 1.6 | -0.9 | A | A | A | A | A | A | A | -1.5 |
| 18 | -0.8 | 2.3 | 1.8 | 0.3 | A | -2.5 | A | A | -3.5 | A | A | 2.1 |
| 19 | -1.4 | 1.6 | 1.9 | A | -2.0 | A | A | A | A | A | A | 0.6 |
| 20 | -1.2 | 1.2 | 1.0 | A | 3.1 | A | A | -3.4 | A | A | A | 3.9 |
| 21 | -1.4 | 0.8 | 0.5 | 0.2 | 1.1 | A | A | E -3.4 | A | A | A | 6.9 |
| 22 | A | 1.4 | 0.2 | 1.0 | 4.1 | -0.1 | A | E -3.5 | A | A | A | 9.7 |
| 23 | A | 1.4 | A | 1.6 | 4.2 | E -1.3 | -2.9 | E -3.5 | A | A | A | 9.5 |
| 24 | A | 1.4 | A | 1.2 | 3.5 | E -1.7 | A | -3.5 | A | A | A | 8.2 |
| 25 | A | 1.3 | A | 1.0 | 2.8 | E -2.1 | A | A | A | -3.2 | A | 5.4 |
| 26 | -2.5 | 1.0 | A | 0.5 | 2.1 | -2.5 | A | A | A | E -3.2 | -3.3 | 4.5 |
| 27 | -2.0 | 0.9 | A | 0.3 | 1.8 | A | A | A | A | E -3.3 | A | 4.0 |
| 28 | -1.6 | 0.7 | A | 5.6 | 1.7 | A | A | A | A | E -3.3 | A | 4.0 |
| 29 | 4.6 | A | A | 1.6 | 1.4 | A | A | A | A | -3.4 | A | 3.0 |
| 30 | 1.1 | A | 1.6 | 2.4 | -0.4 | A | A | A | A | A | A | 3.0 |
| 31 | 1.4 | A | 0.3 | A | A | A | A | A | A | A | A | 3.3 |

THE FOLLOWING REFER ONLY TO READINGS APPEARING IN THE TABLE ABOVE.

MEAN 4.40
MAX. 12.5
MIN. 0.5

A- NO RECORD.
E- ESTIMATED.

HIGHEST STAGE WAS 12.50 ON FEB. 6.
LOWEST STAGE WAS NOT DETERMINED.

MONCONNAE CREEK BASIN

183

07032200 MONCONNAE CREEK NEAR GERMANTOWN, TN

LOCATION.--Lat 35°02'59", long 89°49'08". Shelby County, Hydrologic Unit 08010211, on left bank at downstream side of bridge on Winchester Road, 2.6 mi south of Germantown, and at mile 17.3.

DRAINAGE AREA.--68.2 mi².

PERIOD OF RECORD.--Occasional low-flow measurements, water years 1959-1964, 1969; October 1969 to May 1985, October 1985 to current year.

REVISED RECORDS.--WRD TN-74-1: Drainage area, WRD TN-87-1 (P).

GAGE.--Water-stage recorder. Datum of gage is 262.92 ft above National Geodetic Vertical Datum of 1929 (levels by Soil Conservation Service).

REMARKS.--Records fair. Periodic observations of water temperature are published in this report as miscellaneous water quality data.

AVERAGE DISCHARGE.--20 years (water years 1970-84, 1985-90), 107 ft³/s, 21.29 in/yr.

EXTREMES FOR PERIOD OF RECORD.--Maximum discharge, 13,100 ft³/s, July 2, 1989, gage height 24.23 ft, maximum gage height 27.11 ft, Mar. 12, 1975; no flow at times most years.

EXTREMES FOR CURRENT YEAR.--Peak discharges greater than base discharge of 3,700 ft³/s and maximum (*):

| Date | Time | Discharge (ft ³ /s) | Gage height (ft) | Date | Time | Discharge (ft ³ /s) | Gage height (ft) |
|---------|---------|--------------------------------|------------------|---------|---------|--------------------------------|------------------|
| Oct. 16 | 2145 | 5,910 | 16.62 | Mar. 15 | Unknown | Unknown | Unknown |
| Feb. 3 | Unknown | Unknown | Unknown | Apr. 21 | 0615 | 5,070 | 15.41 |
| Feb. 10 | Unknown | Unknown | Unknown | Apr. 28 | 0230 | 4,260 | 14.17 |
| Feb. 15 | 2345 | 4,830 | 15.05 | May 20 | 0845 | 6,750 | 17.79 |
| Mar. 8 | Unknown | Unknown | Unknown | | | | |

Minimum discharge, .01 ft³/s, Sept. 28, 29, 30.

DISCHARGE, CUBIC FEET PER SECOND, WATER YEAR OCTOBER 1989 TO SEPTEMBER 1990 MEAN VALUES

| DAY | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP |
|-------|---------|--------|---------|--------|-------|-------|--------|--------|--------|--------|--------|-------|
| 1 | 21 | .62 | .64 | 100 | 78 | 126 | 52 | 47 | 2.0 | .36 | 1.7 | .43 |
| 2 | 8.6 | 4.7 | .76 | 34 | 2380 | 169 | 28 | 1140 | 3.0 | 2.2 | 1.4 | .34 |
| 3 | 3.2 | 3.8 | .83 | 49 | 4360 | 141 | *20 | 207 | 135 | 2.2 | 1.1 | .42 |
| 4 | 3.0 | 1.3 | .69 | 360 | 962 | 95 | *9.1 | 179 | 27 | .55 | 1.0 | .29 |
| 5 | 1.8 | 1.8 | .59 | 83 | 107 | 75 | *7.3 | 86 | 10 | 5.4 | 1.0 | .27 |
| 6 | 1.3 | 15 | .47 | 39 | 51 | 63 | *338 | 30 | 4.4 | .96 | .64 | .33 |
| 7 | 1.1 | 4.1 | .31 | 29 | 37 | *254 | *160 | 17 | 1.9 | .36 | .55 | .40 |
| 8 | 1.8 | 394 | 2.1 | 44 | 29 | *3660 | *64 | 12 | 1.1 | .49 | .58 | .65 |
| 9 | .93 | 59 | 2.2 | 31 | 368 | 565 | 31 | 9.1 | 2.7 | .41 | .68 | .99 |
| 10 | .96 | 17 | 1.2 | 19 | *2160 | 294 | *16 | 6.1 | 29 | .25 | .74 | .63 |
| 11 | 1.6 | 11 | .78 | 13 | 204 | 186 | *8.7 | 10 | 9.7 | .28 | .53 | .61 |
| 12 | 1.8 | 3.8 | .59 | 8.8 | 58 | 137 | *5.8 | 24 | 2.8 | 67 | .41 | 13 |
| 13 | 2.3 | 2.7 | .40 | 5.6 | 37 | 122 | *4.2 | 18 | .89 | 13 | 81 | 49 |
| 14 | 2.1 | 1.6 | .33 | 3.9 | 28 | 109 | *3.8 | 10 | .56 | 3.5 | 10 | 3.7 |
| 15 | 2.1 | 8.2 | .28 | 3.2 | 1520 | *2000 | *3.0 | 6.1 | 77 | 1.3 | 1.9 | .74 |
| 16 | 692 | 15 | .23 | 3.0 | *1260 | *281 | *3.0 | 3.7 | 22 | .77 | .68 | .48 |
| 17 | 1310 | 3.9 | .30 | 75 | 87 | 83 | *318 | 28 | 5.5 | .50 | .28 | .26 |
| 18 | 46 | 3.4 | .33 | 249 | 42 | 45 | 154 | 8.5 | 1.4 | .31 | .73 | .20 |
| 19 | 20 | 2.0 | 5.6 | 89 | 33 | 31 | 36 | 298 | .70 | .56 | .77 | 3.8 |
| 20 | 9.4 | 1.7 | 1.6 | 180 | 25 | 24 | 99 | 3360 | .46 | .59 | .75 | 1.1 |
| 21 | 5.1 | 1.0 | .87 | 77 | 20 | 20 | 2820 | 602 | .46 | .69 | .55 | 2.2 |
| 22 | 3.8 | 52 | .28 | 34 | *693 | 16 | 270 | 89 | 406 | 10 | .47 | 8.7 |
| 23 | 3.2 | 42 | .11 | 21 | 258 | 18 | 57 | 25 | 24 | 34 | .49 | .83 |
| 24 | 2.5 | 16 | .03 | 15 | 134 | 12 | 34 | 14 | 7.4 | 14 | .81 | .30 |
| 25 | 1.5 | 8.1 | .06 | 31 | 94 | 12 | 26 | 7.4 | 5.3 | 3.0 | .46 | .13 |
| 26 | 1.4 | 3.6 | .30 | 16 | 76 | 16 | 18 | 4.9 | 1.3 | .92 | .45 | .09 |
| 27 | 1.5 | 2.9 | .45 | 10 | 65 | 12 | 252 | 10 | .73 | .54 | .49 | .06 |
| 28 | .65 | 3.5 | .34 | 329 | 59 | 20 | 1650 | 15 | .57 | .55 | .39 | .02 |
| 29 | .56 | 1.3 | 8.4 | 1600 | --- | 25 | 136 | 8.0 | .50 | .76 | .40 | .01 |
| 30 | .76 | .74 | 400 | 171 | --- | 764 | 44 | 3.6 | .42 | 7.3 | .31 | .01 |
| 31 | .80 | --- | 707 | 47 | --- | 151 | --- | 2.0 | --- | 3.6 | .51 | --- |
| TOTAL | 2152.88 | 685.76 | 1138.07 | 3788.8 | 15226 | 9504 | 6467.7 | 6260.4 | 783.79 | 176.55 | 111.97 | 90.09 |
| MEAN | 69.4 | 22.9 | 36.7 | 122 | 544 | 307 | 218 | 203 | 26.1 | 5.70 | 3.61 | 3.00 |
| MAX | 1310 | 394 | 707 | 1600 | 4360 | 3660 | 2620 | 3360 | 406 | 67 | 81 | 49 |
| MIN | .56 | .62 | .03 | 3.0 | 20 | 12 | 3.0 | 2.0 | .42 | .25 | .28 | .01 |
| CFSM | 1.02 | .34 | .54 | 1.79 | 7.97 | 4.50 | 3.18 | 2.97 | .38 | .08 | .05 | .04 |
| IN. | 1.17 | .37 | .62 | 2.07 | 8.31 | 5.16 | 3.53 | 3.43 | .43 | .10 | .06 | .05 |

CAL YR 1989 TOTAL 62128.00 MEAN 178 MAX 5900 MIN .03 CFSM 2.50 IN. 33.89
WTR YR 1990 TOTAL 46407.01 MEAN 127 MAX 4360 MIN .01 CFSM 1.66 IN. 25.31

* Estimated

10

Reference 29

If flood insurance is available in this community, contact your insurance agent, or call the National Flood Insurance (800) 638-6620.

APPROXIMATE SCALE

NATIONAL FLOOD INSURANCE PROGRAM

FIRM

FLOOD INSURANCE RATE MAP

**CITY OF
MEMPHIS, TENNESSEE
SHELBY COUNTY**

PANEL 10 OF 30


**COMMUNITY-PANEL NUMBER
470177 0010 S**

**EFFECTIVE DATE:
DECEMBER 1, 1992**



Federal Emergency Management Agency

KEY TO MAP

| | |
|---|---|
| 500-Year Flood Boundary | — |
| 100-Year Flood Boundary | — |
| Zone Designations* |  |
| 100-Year Flood Boundary | — |
| 500-Year Flood Boundary | — |
| Base Flood Elevation Line With Elevation in Feet** | — 513 — |
| Base Flood Elevation in Feet Where Uniform Within Zone** | (EL 987) |
| Elevation Reference Mark | RM7x |
| Zone D Boundary | — |
| River Mile | • M1.5 |

**Referenced to the National Geodetic Vertical Datum of 1929

*EXPLANATION OF ZONE DESIGNATIONS


| ZONE | EXPLANATION |
|--------|--|
| A | Areas of 100-year flood; base flood elevations and flood hazard factors not determined. |
| A0 | Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; average depths of inundation are shown, but no flood hazard factors are determined. |
| AH | Areas of 100-year shallow flooding where depths are between one (1) and three (3) feet; base flood elevations are shown, but no flood hazard factors are determined. |
| A1-A30 | Areas of 100-year flood; base flood elevations and flood hazard factors determined. |
| A99 | Areas of 100-year flood to be protected by flood protection system under construction; base flood elevations and flood hazard factors not determined. |
| B | Areas between limits of the 100-year flood and 500-year flood; or certain areas subject to 100-year flooding with average depths less than one (1) foot or where the contributing drainage area is less than one square mile; or areas protected by levees from the base flood. (Medium shading) |
| C | Areas of minimal flooding. (No shading) |
| D | Areas of undetermined, but possible, flood hazards. |
| V | Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors not determined. |
| V1-V30 | Areas of 100-year coastal flood with velocity (wave action); base flood elevations and flood hazard factors determined. |

NOTES TO USER

Certain areas not in the special flood hazard areas (zones A and V) may be protected by flood control structures.

This map is for flood insurance purposes only; it does not necessarily show all areas subject to flooding in the community, or other metric features outside special flood hazard areas.

For all other map panels, see separately printed Index To Map Panels.



ZONE C

ZONE C

ZONE A13

RIVER

ZONE C

ILLINOIS


Sunrise

Horseier Ln

Ave

Klinker

Burlington St



Reference 30

B&V WASTE SCIENCE AND TECHNOLOGY CORP.

TELEPHONE MEMORANDUM

Site Assessment
Old Osmose Chemical Facility

BVWST Project 52012.022
October 18, 1991
2:35 p.m.

Surface Water Intakes on the Mississippi River
Groundwater Drinking Water Population

To: Jerry Collins
Company: Department of Memphis Public Works
Phone No.: (901) 576-6720

Recorded by: Laura Morrison *LM* 10-18-91

Surface Water Intakes on the Mississippi River

There are no surface water intakes on the Mississippi River. rivers, streams and lakes flowing into the Mississippi river in the Memphis area have no surface water intakes.

Reference 31

B&V WASTE SCIENCE AND TECHNOLOGY CORP.

TELEPHONE MEMORANDUM

US EPA Site Assessment
Memphis, Tennessee SIPs

Fishing and Recreation on Memphis area water bodies

BVWST Project 52012.xxx

BVWST File

July 1, 1992

9:15 a.m.

To: John Rayfield
Company: TN Wildlife Resource Agency, Shelby County office
Phone No.: (901) 753-1351

Recorded by: Paul Delphos *PD 6-1-92*

The following water bodies are the only Memphis area rivers which are monitored and/or evaluated by the TN Wildlife Resource Agency. All other creeks are not considered large enough to be monitored. These water bodies include:

Mississippi River
Loosahatchie River
Nonconnah Creek
Wolf River
Lake McKellar

There is a commercial fishing ban for all these water bodies, and it is recommended for recreational fishing that "no consumption of fish" occurs with fish caught from these rivers. This statement is made in the area's fishing guide and Mr. Rayfield only knows of signs posted on Lake McKellar as it is the most utilized water body in the area. He verified that recreational fishing occurs on the above mentioned rivers and caught fish are carried away, therefore, Mr. Rayfield assumes the fish are eaten. He also stated that boating, water skiing, and swimming occur on the above mentioned water bodies, with Lake McKellar being used the most and the Mississippi River being used the least.

B&V WASTE SCIENCE AND TECHNOLOGY CORP.

TELEPHONE MEMORANDUM

BVST Project 52012.003
December 23, 1991
12:50 p.m.

Recreational Fishing

To: John Condor, Wildlife Manager
Company: Wildlife Resources Agency
Phone No.: (901) 423-5725


Recorded by: Laura Morrisson *Jm* 12-23-91

There has been a commercial fishing ban on the Mississippi River and connecting streams from Tipton County to the Mississippi state line since 1985. Periodic fish sampling has shown chlordane in fish in the Mississippi River. There are warnings posted about eating the fish from the Mississippi River. Recreational fishing occurs despite these warnings.

Arkansas has never participated in the fishing bans on the Mississippi River, even though they are aware of the potential hazards.

/ms

Reference 33



NORTHWEST MEMPHIS, TENN - ARK

NOTES TO THE USER


- Wetlands which have been field examined are indicated on the map by an asterisk (*)
- Additions or corrections to the wetlands information displayed on this map are solicited. Please forward such information to the address indicated
- Subsystems, Classes, Subclasses, and Water Regimes in *italics* were developed specifically for NATIONAL WETLANDS INVENTORY mapping
- Some areas designated as R4SB, R4SBW, OR R4SB1 (INTERMITTENT STREAMS) may not meet the definition of wetland
- This map uses the class Unconsolidated Shore (US). On earlier NWI maps that class was designated Beach Bar (BB), or Flat (FL). Subclasses remain the same in both versions




U.S. DEPARTMENT OF THE INTERIOR


FISH AND WILDLIFE SERVICE

Prepared by National Wetlands Inventory



1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.





WEST MEMPHIS, ARK.-TENN.

NOTES TO THE USER

- Wetlands which have been field examined are indicated on the map by an asterisk (*).
- Additions or corrections to the wetlands information displayed on this map are solicited. Please forward such information to the address indicated.
- Ecosystems, Classes, Subclasses, and Water Regimes in *Rates* were developed specifically for NATIONAL WETLANDS INVENTORY mapping.
- Some areas designated as R4SB, R4S2W, or R4S3U (INTERMITTENT STREAMS) may not meet the definition of wetland.
- This map uses the class Unconsolidated Shore (US) for earlier NWI maps that class was designated both as R4S2B or R4S2U (R4) Subclass remains the same in both versions.



... 1940s and 1950s ...

FROM AND OFFICE SERVICE



- NOTES TO THE USER**
- Before we can have been examined are indicated on the map by an asterisk (*).
- Additions or corrections to the wetlands information reported on this map are solicited. Please forward such information to the address indicated.
- Subsystems, Classes, Subclasses, and Water Regimes in *Wetlands* were developed specifically for NATIONAL WETLANDS INVENTORY mapping.
- Some areas designated as RASB, RASBW, OR RASB (INTERMITTENT STREAMS) may not meet the definition of wetland.
- This map uses the class designation I (Shore Line US On either NAVI maps, that class was designated Beachy or 600B) or F (FL) and areas within the same symbol versions.

NOTES TO THE USER

[illegible]

ETLANDS INVENTORY

1. LOCATION OF ETLANDS



EXPLANATION OF FEDERAL STATUS DESIGNATIONS

FEDERAL STATUS, DETERMINED BY THE U. S. FISH AND WILDLIFE SERVICE¹

| | | |
|------|---|--|
| E/SA | - | Endangered by similarity of appearance |
| LE | - | Taxa formally listed as endangered |
| LT | - | Taxa formally listed as threatened |
| PE | - | Taxa proposed to be formally listed as endangered |
| PT | - | Taxa proposed to be formally listed as threatened |
| S | - | Synonyms |
| LTXN | - | Listed threatened, non-essential experimental population |

C1 - Taxa for which the Service has on file substantial information on biological vulnerability and threats to support the appropriateness to list them as endangered or threatened species. Included are those taxa whose status in recent past is known, but may have already become extinct. Such possibly extinct taxa are indicated by an asterisk (*). Double asterisk (**) indicate taxa believed to be extinct in the wild, but known to be extant in cultivation.

C2 - Taxa for which information now in possession of the Service indicated that proposing to list them as endangered or threatened is appropriate, but for which substantial data on biological vulnerability and threat(s) are not currently known or on file to support a proposed rule.

C3- Taxa that are no longer being considered for listing as threatened or endangered species. The following subcategories are used to further indicate the reason(s) for removal from consideration.

3A - Taxa for which the Service has persuasive evidence of extinction or being destroyed. If rediscovered, such taxa might acquire high priority for listing.

3B - Names that on the basis of current taxonomic understanding do not represent taxa meeting the Acts definition of "species." Such proposed taxa could be reevaluated in the future on the basis of subsequent research.

3C - Taxa that have proven to be more abundant or widespread than was previously believed and/or those that are not subject to any identifiable threat.

NOTE: The taxa listed in Categories 1 and 2 may be considered candidates for addition to the list of Endangered and Threatened plants, and, as such, consideration should be given them in environmental planning.

1. Federal Register, 50 (188), September 18, 1985, pp. 37958-37959, and September 27, 1985, pp. 39526-39527.

DEFINITIONS OF STATE STATUS FOR THE OFFICIAL LIST
OF
TENNESSEE'S RARE PLANTS¹

- E - ENDANGERED, Species now in danger of becoming extinct in Tennessee because of:
- (a) their rarity throughout their range, or
 - (b) their rarity in Tennessee as a result of sensitive habitat destruction or restricted area of distribution.
- E* - TAXA considered to be endangered in Tennessee due to evidence of large numbers being taken from the wild and lack of commercial success with propagation or transplantation.
- T - THREATENED, Species likely to become endangered in the immediately foreseeable future as a result of rapid habitat destruction or commercial exploitation.
- S - SPECIAL CONCERN, Species requiring special concern because of:
- (a) their rarity in Tennessee because the State represents the limit or near-limit of their geographic range, or
 - (b) their status is undetermined because of insufficient information.
- P - POSSIBLY EXTIRPATED, Species that have not been seen in Tennessee within the past 20 years.
1. Adapted from the Committee for Tennessee Rare Plants. 1978. The rare and vascular plants of Tennessee. J. Tenn. Acad. Sci. 53(4):128-133.

STATE STATUS OF TENNESSEE'S RARE WILDLIFE
(Designated by Tennessee Wildlife Resource Agency)

STATUS DESIGNATIONS

- | | | |
|-----|---|--|
| P | - | Possibly extirpated |
| E | - | Endangered |
| T | - | Threatened |
| S | - | Special Concern |
| I | - | Inactive |
| D | - | Deemed in Need of Management |
| * | - | <u>Species Proposed for Federal Protection</u> |
| ESD | - | Designated by the Ecological Services Division |

Reference 35

Graphical Exposure Modelling System (GEMS)

Data Download

September 2, 1993

9:30 a.m.

Data Compiled by Dane G. Pehrman

B&V Waste Science and Technology Corp.

1990 Census Data

International Harvester Landfill Site Inspection Prioritization

Population within 4 miles of the International Harvester Landfill Site


Latitude:35°12'24.08"

Longitude:90°03'03.64"

| <u>Distance</u> | <u>Population</u> | <u>Interval Pop.</u> |
|-----------------|-------------------|----------------------|
| 0 (km) | 0 | 0 |
| 0.4 (km) | 0 | 0 |
| 0.8 (km) | 0 | 2,599 |
| 1.6 (km) | 2,599 | 6,128 |
| 3.2 (km) | 8,727 | 20,234 |
| 4.8 (km) | 28,961 | 31,602 |
| 6.4 (km) | 60,563 | |

POOR LEGIBILITY

**PORTIONS OF THIS DOCUMENT
MAY BE UNREADABLE, DUE TO
THE QUALITY OF THE
ORIGINAL**



Potential Hazardous Waste Site

PRELIMINARY ASSESSMENT

INTERNATIONAL HARVESTER

MEMPHIS, SHELBY COUNTY, TENNESSEE

TND 007 02 4516

**PRELIMINARY ASSESSMENT
INTERNATIONAL HARVESTER
TND 007 02 4516**

I. HISTORY OF SITE

The International Harvester Company is located in Memphis, Tennessee, Shelby County approximately one-half mile from the Mississippi. The land in the area is mainly flat with some gently sloped hills.

This company manufactures farm equipment and the manufacturing process includes: casting shearing, machine, welding, assembly, washing, plating and painting.

International Harvester has been in operation since 1947. The company has been operating a disposal site on company property, adjacent to its manufacturing operation from the early 1940's to November 1983. At present the disposal site has been inactive four years, yet closure has not been documented or made available to state superfund file.

II. NATURE OF HAZARDOUS MATERIALS

According to the feasibility study of industrial waste fill site, a hazardous waste site investigation conducted by E.P.A. on October 20-21, 1980, at the International Harvester disposal site noted detectable quantities of lead, chromium and P.C.B's. chromium levels in water samples taken at the site noted the drinking water

standards for chromium limits its concentration to 0.05 mg/l. lead levels in water samples taken showed the concentration to be less than 0.04 mg. which is less than the DWS limits of 0.05 mg/l.

Soil and sediments samples taken at the site also indicate detectable levels of lead, chromium, and PCB's. Samples taken at five locations showed a chromium concentration range 30 to 278 mg/kg and a lead concentration ranging from 57 to 468 mg/kg. PCB's were detected in all soil and sediment samples with concentrations ranging from 180 ug/kg to 18,000 ug/kg quantity of hazardous waste is unknown at this time. International Harvester's landfill is located in a flood plain.

III. DESCRIPTION OF HAZARDOUS CONDITION, INCIDENTS, PERMIT VIOLATION

There is unstable containment due to the fact that the Landfill is located in a floodplain, and therefore requires protection from possible floodwaters.

IV. ROUTE'S FOR CONTAMINATION

Drainage ditches on site empty toward the Mississippi River.

The landfill lies in the flood plains of the Mississippi River and is not protected from possible flood waters.

The site drains also into fields that grow soybeans and wheat.

V. POSSIBLE AFFECTED POPULATION AND RESOURCES

There is a potential for surface water contamination due to possible floodwaters, possible groundwater contamination due to the aquifer of concern and possible food contaminations.

Approximately 2000,00 populus could be affected.

VI. RECOMMENDATION AND JUSTIFICATIONS

This site has become inactive as of November 1983. It is considered to be a RCRA facility. It should be noted for the DSWM that there exist the potential for existing irregularities in waste distribution and a determination of the potential harm of the hazardous waste alleged to be present should be looked into.

RCRA ASSESSMENT

In State Superfund estimation this site (International Harvester) is a RCRA facility.

Since the landfill was in full operation, storing hazardous waste over the allotted time and was considered an active site up until 1983.

The State Superfund Program has conducted remedial action, but at this time International Harvester is considered a RCRA facility and no further action will be taken on behalf of Site Investigation, Division of Superfund.

TH/lag SF #5

REFERENCES

1. Tennessee Department of Health and Environment State Superfund file # 79-525(1).
2. Tennessee Department of Health and Environment Solid Waste Management file # 79-525.
3. Feasibility study of industrial waste fill site. Prepared by: Environmental Management Planning & Engineering March 1982.
4. Tennessee Department of Health and Environment Division of Solid Waste Management Commissioners Orders.
5. Topographic Map of Northwest Memphis Quadrangle.



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION
01 STATE 02 SITE NUMBER
TN 0007-02-4516

II. SITE NAME AND LOCATION

| | | | |
|---|----------------|--|---------------------|
| 01 SITE NAME (Legal, common, or descriptive name of site) International Harvester Company EPIC #73 | | 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 3003 Harvester Lane | |
| 03 CITY Memphis | 04 STATE TN | 05 ZIP CODE 38127 | 06 COUNTY Shelby |
| 07 COUNTY CODE 157 | | 08 CONG DIST 8 | |
| 09 COORDINATES LATITUDE 35 12 23 | | LONGITUDE 90 03 05 | |

10 DIRECTIONS TO SITE (Starting from nearest public road)

I-240 west until road forks, go north on Thomas, to Marsch, turn west on Marsch to Sunrise North to Frayer then west to Harvester.

III. RESPONSIBLE PARTIES

| | | | |
|--|----------------|---|---------------------------------------|
| 01 OWNER (if owner) International Harvester Corporation | | 02 STREET (business, mailing, residential) 3003 Harvester Lane | |
| 03 CITY Memphis | 04 STATE TN | 05 ZIP CODE 38127 | 06 TELEPHONE NUMBER (901) 357-5311 |
| 07 OPERATOR (if owner and different from owner) International Harvester Corporation | | 08 STREET (business, mailing, residential) 3003 Harvester Lane | |
| 09 CITY Memphis | 10 STATE TN | 11 ZIP CODE 38127 | 12 TELEPHONE NUMBER (901) 357-5311 |
| 13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN | | | |
| 14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input type="checkbox"/> A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (RCRA 109 c) DATE RECEIVED: _____ MONTH DAY YEAR <input checked="" type="checkbox"/> C. NONE | | | |

IV. CHARACTERIZATION OF POTENTIAL HAZARD

| | | | |
|--|--|--|--|
| 01 ON SITE INSPECTION <input checked="" type="checkbox"/> YES DATE 10 20 80 MONTH DAY YEAR <input type="checkbox"/> NO | | BY (Check all that apply) <input checked="" type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): _____ | |
| 02 SITE STATUS (Check one) <input type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input checked="" type="checkbox"/> C. UNKNOWN | | 03 YEARS OF OPERATION BEGINNING YEAR 1947 ENDING YEAR 1983 <input type="checkbox"/> UNKNOWN | |

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Alleged chromium and lead, PCB's and some extractable/purgeable organic compounds.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION


Drainage ditches on site that empty toward the Mississippi River. The landfill lies in the flood plains of the Mississippi River and is not protected from possible flood water.

V. PRIORITY ASSESSMENT

| | | | |
|---|--|--|--|
| 01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste information and Part 3 - Description of Release Conditions and Incidents. <input type="checkbox"/> A. HIGH (Inspection required promptly) <input checked="" type="checkbox"/> B. MEDIUM (Inspection required) <input type="checkbox"/> C. LOW (Inspect on time available basis) <input type="checkbox"/> D. NONE (No further action needed. Complete current status report) | | | |
|---|--|--|--|

VI. INFORMATION AVAILABLE FROM

| | | |
|---|--|---------------------------------------|
| 01 CONTACT Z.S. Migot | 02 OF Agency Organization International Harvester | 03 TELEPHONE NUMBER (901) 357-5311 |
| 04 PERSON RESPONSIBLE FOR ASSESSMENT Robin Tanya Humphries | 05 AGENCY TDH&E | 06 ORGANIZATION Superfund |
| 07 TELEPHONE NUMBER 615-741-3424 | | 08 DATE 05 13 87 MONTH DAY YEAR |



☐ L1 HIGHLY VOLATILE
☐ L2 EXPLOSIVE
☐ L3 REACTIVE
☐ L4 INCOMPATIBLE
☐ L5 NOT APPLICABLE

EDA FORM 2070-12 (7-64)



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

| 1 IDENTIFICATION | |
|------------------|----------------|
| 01 STATE | 02 SITE NUMBER |
| TN | D 007-02-4516 |

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED 2000.00 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

Due to the variations of the Memphis sands, this aquifer has a possibility for ground water contamination.

01 ☒ B SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED 2000.00 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

The landfill lies in the flood plains of the Mississippi River and is not protected from possible flood waters.

01 ☐ C CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED: _____ 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ D FIRE/EXPLOSIVE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED: _____ 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☒ E DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED: 2000.00 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

Possible drinking water contamination.

01 ☒ F CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED 10 acres 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☒ ALLEGED
(ACRES) 04 NARRATIVE DESCRIPTION

Possible contamination of soil.

01 ☒ G DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED 2000.00 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☒ ALLEGED
04 NARRATIVE DESCRIPTION

Alleged chromium and lead were below or slightly above drinking water limits.

01 ☐ H WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED: _____ 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION

01 ☐ I POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED _____ 02 ☐ OBSERVED (DATE _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

1. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 0 007-02-4516

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include number(s) of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☒ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☒ ALLEGED

Site drains into fields tht grow soybeans and wheat.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES
(Spills, runs, leaking drums, leaking drums)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☒ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: 2000.00

04 NARRATIVE DESCRIPTION

Landfill is out of compliance with the flood plain criteria.

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

Chromium, lead, PCB's, other organic waste.

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Give specific references to all state files, reports, and records)

TDHE Superfund File

Feasibility study of industrial waste fill site prepared for International Harvester Co. by Environmental Management Planning and Engineering.

Site No. TND

Reference No. 77-525-(1)

INTERNATIONAL HARVESTER
3003 HARVESTER AVENUE
MEMPHIS, TENNESSEE

I. Site Identification

- A. Name - International Harvester
- B. County - Shelby
- C. Nearest Urban Area - Memphis
- D. Water Supplies Potentially Affected
 - 1. Public - Not affected
 - 2. Private - Not affected
 - 3. Other
 - a) Drainage ditches on site empty towards the Mississippi River
 - b) The landfill lies in the floodplains of the Mississippi River and is not protected from possible floodwaters.
 - c) The site also drains into fields that grow soybeans and wheat.
- E. Acreage - 10 acres

II. Site History

- A. Owner - International Harvester Corp.
- B. Operator - International Harvester Corp., G. W. Beadles, Manager
- C. Hazardous Waste Data
 - 1. Source - International Harvester
 - 2. Volume - approximately 1000-2000 tons
 - 3. Types of Wastes - Wood, paper, foundry sand, glass, metal scraps, cardboard, trash, paint and paint sludge, washing machine sludge, oils, greases, coolants, wastewater treatment sludge, spent transformer oil, varnish, sealing compound, caustics and acids, electroplating treatment sludge and miscellaneous industrial solid waste
- D. Period of Operation - 1947 to present
- E. Current Status - Feasibility study for closure submitted to SWM Superfund.

III. Investigations

A. Sampling Data

On October 20-21, 1980, EPA conducted a hazardous waste site investigation. During this investigation five sediment or soil samples and two water samples were collected. Chromium and lead were below or slightly above drinking water limits in water, but were very high in sediment/soil; high levels of PCBs were found in all soil samples, and

International Harvester
Page Two

moderate to low amounts of some extractable/purgeable organic compounds were also found in soil/sediment samples.

Although chromium and lead contamination may enter the Mississippi River, the flow of this river, 470,000 cu. ft/sec., is enough to dilute it. The metal, PCB and organic-contaminated soil may, however, be washed into adjacent fields, which grow food crops, and may also migrate in the event of flooding.

B. Other Investigating Work - None

C. Costs Incurred

| <u>Entity</u> | <u>Activity</u> | <u>Cost</u> |
|---------------|--------------------|-------------|
| EPA | Site Investigation | \$15,000 |

IV. Enforcement Action

1. TN

September 1, 1981 - (SWM & EPA) International Harvester informed that their landfill was out of compliance with the floodplain criteria and was on the EPA open dump inventory.

September 17, 1981 - March 17, 1982 - Extension granted for submittal of a feasibility study for correcting the floodplain problem. Feasibility study submitted March 17, 1982. International Harvester accepted recommendation to close the landfills but subsequently developed financial problems. SWM allowed sufficient time for them to recover financially before requiring closure.

May 6, 1983 (SWM) - Hazardous Waste inspection found no violations for hazardous waste generators.

November, 1983 SWM Superfund staff reviewed closure plan and developed recommendations.

2. EPA

October 20, 1980 - Conducted a hazardous waste site inspection.


October 23, 1981 - International Harvester informed of potential violations of RCRA.

3. Local - None

V. Remedial Action


| <u>Entity</u> | <u>Activity</u> | <u>Cost</u> |
|---------------|-----------------|-------------|
|---------------|-----------------|-------------|

None to date



LOCATION MAP
INTERNATIONAL HARVESTER

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE



Site No. TND

Reference No. # 79-525

79-5

CAP-
CGP-17



DEPARTMENT OF HEALTH AND ENVIRONMENT
SOUTHWEST TENNESSEE REGIONAL OFFICE
295 SUMMAR AVENUE
JACKSON, TENNESSEE 38301-3984

October 10, 1985

Mr. John Bandy
International Harvester Co., Inc.
3003 Harvester Lane
Memphis, TN 38127

Re: International Harvester
Acct. # 79525/Acct. #79526
Shelby County 11

5/e 79-525

Dear John:

Pursuant to our inspection on September 25th and October 2, 1985, implementation of the "Investigation Program and Remedial Action Selection and Implementation Report" appears to be proceeding as scheduled; specifically, the NPDES discharge pipe construction, the general grading of the site to a 4:1 slope and the segregation of the clay and cover materials.


On said dates the IH sites known as the Klinke Ave. Site (acct.#79525) and the S. Riverside Blvd. Site (acct. #79526), respectively were located, identified and catagorized. The Klinke Ave. Site (acct. #79525) is "one in the same" as the Harvester Ave. Site (acct. #79525) and is recorded as such. The Klinke Ave./Harvester Ave. Site is currently catagorized "Remedial Action Underway." The IH-Epic #73 located at 1356 S. Riverside Blvd. (acct. #79526) is the address for the GE/Memphis Lamp Plant (acct. #79524); the correct address for the IH, S. Riverside Blvd. site (acct. #79526) is 300 Olive Street, Memphis, TN. In accordance with our conversations and a site inspection, the IH, 300 Olive Street site (acct. #79526) has no hazardous material on site; therefore the site should not be listed on the Superfund Master list.

Confirmation of the aforementioned information must be submitted to this office in writing to assure the correct categorization and listing of both International Harvester sites. Upon receipt of the confirmation letter the correction will be made and the Division will be notified as such.

• Mr. John Bandy
Page 2
October 10, 1985

Your cooperation and expedience in this matter is greatly appreciated. Should you have any questions, please contact me at (901)424-9250, extension 318.

Sincerely,

A handwritten signature in black ink, appearing to read "Danny Brewer", with a stylized flourish at the end.

Danny Brewer
Environmental Engineer, Superfund
Division of Solid Waste Management

DAB/df 4-5

cc: DSWM, Don Shackelford, Superfund
DSWM, Paul Patterson, Memphis



STATE OF TENNESSEE
DEPARTMENT OF HEALTH AND ENVIRONMENT
SOUTHWEST TENNESSEE REGIONAL OFFICE
295 SUMMAR AVENUE
JACKSON, TENNESSEE 38301-3984

11/21/85

December 19, 1985

Mr. Tom Shaffer, Engineer
Velsicol Chemical Corporation
2603 Corporate Avenue
Suite 100
Memphis, Tennessee 38123

Re: Velsicol Chemical Dump
Hardeman County

Dear Mr. Shaffer:

An inspection of Velsicol's Dump in Hardeman County was conducted on December 9, 1985 by George Harvell, Danny Brewer and W. T. Blasingame of the Division of Solid Waste Management. In general the site was in good condition, but some areas of erosion were noted and marked on the attached maps.

The following items need to be addressed:

1. Severe erosion exists in the borrow pit areas of the north disposal site. Erosion is also taking place in the borrow pit area of the middle site.
2. It was understood that the slopes of the cap were to be mowed. This had not taken place at the time of inspection. It is also understood that the cap will be mowed on a regular basis during the forth-coming year.
3. Slight erosion is occurring in the area of the "deer lick". Discretion should be used as to whether this problem needs to be addressed at the present.
4. Pine trees could possibly be utilized for stabilization in steep areas of severe erosion.
5. The entire area should be adequately posted as a disposal site, and it is necessary that a sign be erected listing the dangers associated with the sand pit.

Should you have any questions regarding this letter, please feel free to contact me at 424-9200.

Sincerely,

W. T. Blasingame
W. T. Blasingame *OAB*
Environmental Specialist, Superfund
Division of Solid Waste Management

WTB/rc 5-3

Attachments

cc: DSWM, Nashville, Don Shackelford ✓
DSWM, Jackson, Randy Harris
Mr. Chuck Hanson

POND 12

POND 9

NORTH DISPOSAL AREA

SEVERE
EROSION
BORROW
PIT AREA

NOTE: GM 7 IS A PERMANENT
BENCH MARK.
TOP OF CASING EL. 510.84
GROUND EL. 508.11

POND 8

SEVERE
EROSION

BORROW
AREA

EROSION


EROSION

DEER
LICK
AREA

EROSION
OLD POND
AREA

POND 7

W.L.
436.9




MIDDLE D ARE

EROSION
BORROW
PIT AREA

PUGH I
434.18
← CULVER

AL



SOUTH
AF

NO EROSION
PROBLEMS WERE
IDENTIFIED @ THE
SOUTH DISPOSAL AREA

WQC PROTECT

Site No. TND

Reference No. Feasibility STUDY

SOLID WASTE DISPOSAL FACILITY
FEASIBILITY STUDY

Prepared for
INTERNATIONAL HARVESTER
Memphis, Tennessee



March 1982



ENVIRONMENTAL MANAGEMENT
PLANNING & ENGINEERING

METRO CENTER • 151 ATHENS WAY • NASHVILLE, TENNESSEE 37228

FOREWORD

State regulations issued under the authority of the "Tennessee Solid Waste Disposal Act" have been the primary guide for development of this feasibility study. However, the State's study requirements appear based on sanitary landfill disposal of municipal refuse and, as a result, are not necessarily applicable to industrial landfills.

Since this study considers a single industrial plant and only compares continued landfill operation with final closure, the following study requirements are considered inapplicable:

1. Population Density and Trends: Population trends in the Memphis area will have no effect on International Harvester's waste generation schedule.
2. Major Waste Producers in Area: Production of waste by other sources has no influence on International Harvester's operating procedure.
3. Existing Area Disposal Facilities and Collection Services: International Harvester's industrial fill does not compete with existing disposal facilities, and several local collection services are capable of handling the waste quantities generated if necessary.
4. Transportation System for Site Access: On site disposal of waste requires no use of public roads. Removal of trash by commercial contractor would occur on existing roads with negligible effects on traffic.
5. Site Evaluation of Proposed Disposal Area: The existing industrial fill site has been chosen for continued use, so an evaluation of alternative sites is unnecessary.

The State's sanitary landfill design criteria, again related primarily to municipal refuse, are not specifically related to the International Harvester landfill. As a result, several alternative design strategies have been considered in this report:

1. Closure with an impermeable soil cover and a dike to prevent flooding
2. Closure with an impermeable cover only
3. Continued operation with six inches of weekly cover
4. Continued operation with twelve inches of weekly cover

Final design criteria should be developed with the Division of Solid Waste Management before plans and specifications are prepared.

CONCLUSION

The most economical solution for International Harvester is to close and cover its existing landfill without the construction of a dike. Should construction of the dike be required, the option of continuing use becomes more favorable, depending on the amount of weekly cover required and the need for International Harvester to keep the fill open.

Estimated capital and operating expenses for the various design strategies are as follows:

| | <u>Initial Cost</u> | <u>Annual Costs</u> |
|--|---------------------|---------------------|
| Closure with Dike | \$407,000 | \$36,000 |
| Closure without Dike | 244,000 | 36,000 |
| Continued Operation with Six Inch Cover | 286,000 | 24,200 |
| Continued Operation with Twelve Inch Cover | 323,000 | 34,600 |

The above costs do not consider International Harvester's expenses for equipment and personnel if continued operation of the landfill is chosen.

Based on International Harvester's maximum anticipated waste generation rate of 200 cubic yards per day (uncompacted), remaining landfill life is 18 years.


INTRODUCTION

The International Harvester Corporation has been operating a waste disposal site on company property adjacent to its manufacturing operation since the 1940's. (See location map.) At one time, landfilled items included wood, paper, foundry sand, paint sludge, washing machine sludge, oils, greases, coolants, wastewater treatment sludge, and all miscellaneous solid waste generated by the manufacturing operation, with the exception of scrap metal. Before 1970 all combustible material was burned daily. In 1974, oils, coolants, and flowable grease were eliminated from the landfill and are now removed by oil scavengers. Washing machine sludge and paint sludge became a part of the wastewater treatment sludge in 1978, which is disposed of through Chemical Waste Management, Inc., in Marietta, Georgia, at their Emelle, Alabama facility. Their EPA ID Code is ALT000622464. The foundry was closed in February 1981, eliminating foundry sand from the landfilled items.

Material currently landfilled on-site includes only wood, metal banding and wire, cardboard, and other trash generated by plant operation. Past disposal practices, however, have left residues of lead, chromium, and polychlorinated biphenols (PCB's). (See Page 7.)

It has been determined that this disposal site lies in the floodplain and therefore requires protection from possible floodwaters. This feasibility study outlines the protective steps to be taken and will compare the cost of closing the fill to continuing its use.

The International Harvester site is located approximately one-half mile from the Mississippi River in Memphis, Tennessee. The land in this area is mainly flat with some gently sloped hills. A topographic map of the area is found in Appendix A.



LOCATION MAP
INTERNATIONAL HARVESTER

CLOSURE REQUIREMENTS

A determination has been made that the industrial fill site lies in the floodplain and it will be necessary to construct a levee around the site to a height of at least one foot above the 100-year flood level of 233.4 feet above sea level. The design of the levee will be such that it will have a 12-foot minimum crown and side slopes will be constructed at a 3:1 ratio. The levee will be machine compacted and seeded for stability and to aid in erosion prevention.

In addition to the construction of a levee, the existing fill site will receive two feet of compacted cover material to reduce infiltration and provide a surface for vegetation.

The graded areas will have sufficient slope so that ponding will not occur (minimum of two percent). Steep sections will be terraced to prevent erosion. Adequate drainage of surface water will be provided by ditching and berming to intercept and divert runoff from off-site sources.

CONTINUED USE REQUIREMENTS

In the event of continued use, a levee will be required as previously described. Site preparation consisting of grading existing irregularities in waste distribution will be necessary. Cover material should be placed and grading will be done over the entire 10-acre area. The site will initially be divided into two approximately equal five-acre portions. One area will be covered with one foot of compacted soil and seeded and saved for future use. The remaining tract will be developed as the landfill. When capacity is reached, the site will be closed and the remaining section will be developed. Weekly cover will be applied and areas left unworked for greater than 90 days will be seeded.

During operation, sufficient slope (minimum two percent) and drainage shall be maintained to prevent infiltration into fill area. Steep sections shall be terraced to prevent erosion.

Disposal into the fill area will continue until the elevation of the top of the fill is approximately equal to the elevation of the plant site (Elevation 274). Slope of the fill sides should be no greater than 3:1. Upon closure of the fill, two feet of compacted cover material will be applied and seeded.

CHEMICAL CONTAMINATION

A hazardous waste site investigation conducted by EPA on October 20-21, 1980, at the Internatioal Harvester disposal site noted detectable quantities of lead, chromium, and PCB's. Chromium levels in two water samples taken at the site were measured at 0.058 mg/l and 0.104 mg/l. The Drinking Water Standards for chromium limits its concentration to 0.05 mg/l. Lead levels in water samples taken showed the concentration to be less than 0.04 mg/l which is less than the DWS limits of 0.05 mg/l.

Soil and sediment samples taken at the site also indicate detectable levels of lead, chromium, and PCB's. Samples taken at five locations showed a chromium concentration range of 30 to 278 mg/kg and a lead concentration ranging from 57 to 468 mg/kg. PCB's were detected in all soil and sediment samples with concentrations ranging from 180 ug/kg to 18,000 ug/kg.

Review of past disposal practices has found that lead and chromium most likely originated from disposal of paint sludges while the source of PCB's is spent transformer oil. These disposal practices have been discontinued.-

Analysis of the EPA water and soil data indicates no significant impact from these hazardous constituents. This conclusion is based on the following observations:

1. Chromium and lead concentrations in the water samples are below or slightly above drinking water standards. Impact on downstream water quality is insignificant considering potential runoff from this site into the Mississippi River (average flow of river at Memphis is reported as 470,000 cubic feet per second). Furthermore, the company's NPDES permit establishes a chromium standard of 1.0 mg/l for discharge from the wastewater treatment facility; no standard has been set for lead.

2. While PCB's are found in the soil in relatively high concentrations, PCB's are insoluble in water and therefore are unlikely to leave the disposal facility. The EPA study did not analyze PCB in the water.
3. Proposed continued operation or closure techniques will better ensure prevention of water leaching through the landfill by cover, capping, and drainage practices.

PROPOSED LEACHATE CONTROL MEASURES

Minimizing surface infiltration is a primary purpose of either continued landfill operation or closure. Typically, a properly designed landfill accomplishes this requirement through two primary methods:

1. Surface waters which might run onto the landfill are routed around the waste facility; precipitation which falls onto the landfill is caused to run off the surface as soon as possible.
2. A relatively impermeable cover is placed over the fill which minimizes the amount of water which may infiltrate through the waste.

Soil available on-site appears suitable for cover materials. The material will be of generally the same type as that used by the City of Memphis to line the sludge lagoons for the North Wastewater Treatment Plant. The coefficient of permeability is estimated as 1×10^{-5} cm/sec. which should be adequate for levee construction, intermediate and final cover. Drainage will be routed around the fill and on-site drainage will be constructed to maximize runoff through sloping and minimize erosion by terracing.

APPENDIX B CLOSURE COST

| <u>Plans</u> | <u>Initial Cost</u> | <u>Annual Cost</u> |
|--|---------------------|--------------------|
| 1. Close and Contract Waste Removal (Without Dike) | | |
| A. Cover and Stabilize Existing Landfill | | |
| 1. Site Preparation | \$ 2,500 | |
| 2. Earthwork | 148,400 | |
| 3. Seeding | 10,000 | |
| B. Cover and Stabilize Unused Area (5 Acres) | | |
| 1. Earthwork | 55,700 | |
| 2. Seeding | 5,000 | |
| C. Contract Waste Removal | | \$36,000 |
| D. Contingency (10%) | <u>22,400</u> | |
| | \$244,000 | |
| 2. Close and Contract Waste Removal (With Dike) | | |
| A. Dike Construction | | |
| 1. Earthwork | \$145,000 | |
| 2. Seeding | 3,000 | |
| B. Cover and Stabilize Existing Fill | | |
| 1. Site Preparation | 2,500 | |
| 2. Earthwork | 148,840 | |
| 3. Seeding | 10,000 | |
| C. Cover and Stabilize Unused Area (5 Acres) | | |
| 1. Earthwork | 55,660 | |
| 2. Seeding | 5,000 | |
| D. Contract Waste Removal | | \$36,000 |
| E. Contingency | <u>37,000</u> | |
| | \$407,000 | |

Difference in initial cost is \$163,000.

By closing the fill, the annual cost of operating the fill (equipment and man-hours) would be eliminated.

APPENDIX C

COST OF CONSTRUCTING DIKE AND CONTINUING USE IN PRESENT FILL AREA (LIFE ESTIMATED - 18 YEARS)

Plan 2 (6" Intermediate Cover)

| | <u>Initial Cost</u> | <u>Annual Cost</u> |
|---|---------------------|--------------------|
| 1. Construct Dike | | |
| a. Earthwork | \$145,000 | |
| b. Seeding | 3,000 | |
| 2. Initial Earthwork | | |
| a. Cover and Close Unused 5-Acre Area (18") | 55,700 | |
| b. Seeding | 5,000 | |
| 3. Site Preparation | 2,500 | |
| 4. 6" Intermediate Cover for 10 Acres | 32,300 | |
| 5. Seeding 5 Acres | 5,000 | |
| 6. Annual Cover | | \$10,400 |
| 7. Annual Seeding | | 5,000 |
| 8. Eventual Closure Cost | | <u>8,800</u> |
| | | \$24,200 |
| 9. Contingency | <u>37,500</u> | |
| | \$286,000 | |

To be added is the cost of an operator and equipment for spreading waste.

APPENDIX D

COST OF CONSTRUCTING DIKE AND CONTINUING USE IN PRESENT FILLA REA (LIFE ESTIMATED - 18 YEARS)

Plan 1 (1' Intermediate Cover)

| | <u>Initial Cost</u> | <u>Annual Cost</u> |
|---|---------------------|--------------------|
| 1. Construct Dike | | |
| a. Earthwork | \$ 145,000 | |
| b. Seeding | 3,000 | |
| 2. Initial Earthwork | | |
| a. Cover and Close 5-Acre Unused Area (18") | 55,700 | |
| b. Seeding | 5,000 | |
| 3. Site Preparation | 2,500 | |
| 4. 1' Intermediate Cover for 10 Acres | 64,500 | |
| 5. Seeding 5 Acres | 5,000 | |
| 6. Annual Cover | | \$ 20,800 |
| 7. Annual Seeding | | 5,000 |
| 8. Eventual Closure Cost | <u> </u> | <u>8,800</u> |
| | \$ 280,700 | \$ 34,600 |
| 9. Contingency (15%) | <u>42,300</u> | |
| | \$ 323,000 | |

To be added is the cost of an operator and equipment for spreading waste.

Site No. TND

Reference No. Commissioners order

March 14, 1984


International Harvester Company
c/o C. T. Corporation System
530 Gay Street
Knoxville, Tennessee 37902

Dear Sir:

Enclosed please find a document entitled Commissioner's Order issued by James E. Word against International Harvester Company. I would particularly direct your attention to the Notice of Rights section.

If you have any questions please call me at (615) 741-3657.

Sincerely,



William L. Penny
Assistant General Counsel

Enclosure

cc: Don Shackelford ✓
Tom Blankenship, Jr.
Jean Inman

3012 file

Identify, contain, and clean up, including monitoring and maintenance, inactive hazardous substance sites which pose or may pose a danger to public health, safety or the environment because of the release or threatened release of hazardous substances. Pursuant to T.C.A. Section 68-46-215 the Commissioner may issue an order for correction to the appropriate person, and this order shall be complied with within the time limit specified in the order.

COMMISSIONER'S ORDER

Comes now, James E. Word, Commissioner of the Tennessee Department of Health and Environment, and states that:

PARTIES

I.

James E. Word is the duly appointed Commissioner of the Tennessee Department of Health and Environment (the "Department").

II.

The International Harvester Company (the "Respondent") is a Maryland Corporation qualified to do business in Tennessee. It is doing business at 3003 Harvester Lane, Memphis, Tennessee 38127. Its registered agent for service of process is: C. T. Corporation Systems, 530 Gay Street, Knoxville, Tennessee 37902. The Company manufactures farm equipment and the manufacturing processes include casting, shearing, machining, welding, assembly, washing, plating and painting.

JURISDICTION

III.

Pursuant to T.C.A. Sections 68-46-111 and 68-46-206, the Commissioner is authorized to issue an order to any liable party requiring such party to investigate, identify, contain, and clean up, including monitoring and maintenance, inactive hazardous substance sites which pose or may pose a danger to public health, safety or the environment because of the release or threatened release of hazardous substances. Pursuant to T.C.A. Section 68-46-215 the Commissioner may issue an order for correction to the appropriate person, and this order shall be complied with within the time limit specified in the order.

As part of the Respondents manufacturing process, it produces metal plating wastes containing lead, chromium and other elements. This liquid waste is a hazardous substance as defined in T.C.A. Section 68-46-202. The waste is also a listed hazardous waste as defined in the Tennessee Hazardous Waste Regulation 1200-1-11-.02(4).

VI.

The existence of this inactive hazardous substance site poses or may be reasonably anticipated to pose a danger to public health, safety, and environment. This inactive hazardous substance site appears on the proposed list of such sites (pursuant to T.C.A. Section 68-46-206) eligible for investigation, identification, containment and clean up.

VII.

The Respondent reported that it has disposed of hazardous waste at a disposal site owned by International Harvester Company and located at latitude and longitude coordinates 35°12'23" and 90°03'05" respectively. The Respondent has reported the disposal of wood, paper, foundry sand, glass metal scraps, cardboard, trash, paint and paint sludge, washing machine sludge, oils, grease, coolants, wastewater treatment sludge, spent transformer oil, varnishes, sealing compounds, caustics and acids, electroplating treatment sludge and miscellaneous industrial solid waste. The disposal site has been inactive since at least November, 1983.

VIII.

On October 20-21, 1980 EPA conducted a hazardous waste site investigation of International Harvester. Analysis of samples taken during this inspection revealed

By operating this disposal site and generating the hazardous substances disposed of in the site, Respondent is a "liable party" as defined in T.C.A. Section 68-46-202 which is defined as:

"(a.) The owner or operator of an inactive hazardous substance site;

(b.) Any person who at the time of disposal was the owner or operator of an inactive hazardous substance site;

(c.) Any generator of hazardous substance who at the time of disposal caused such substance to be disposed of at an inactive hazardous substance site; . . ."

This site is a hazardous substance site within the meaning of T.C.A. Section 68-46-202 which is defined as "any site or area where hazardous substance disposal has occurred."

X.

PREMISES CONSIDERED, I, James E. Word, hereby ORDER the Respondent, International Harvester Company to comply with the following:

A. INITIAL ASSESSMENT

1. Within sixty (60) days of receipt of this Order, the Respondent shall submit to the Department any existing data available to the Respondent which is pertinent to the assessment of the hazard that the specified site may pose to public health and the environment. This information shall include available data listed in paragraph X.B.2 of this Order and shall be submitted in duplicate.

and maintenance. A schedule for future activities, deemed necessary by the Department, shall be established at this conference. Depending on existing data, the Department may determine that no further action is necessary. In all other cases, the schedule established in this conference will provide the dates by which the activities enumerated herein must be completed.

B. INVESTIGATION PROGRAM

1. According to the schedule established in the initial assessment conference, the Respondent shall submit to the Department a proposed Investigation Plan.

2. In order to provide an accurate assessment of the hazard posed by the site to public health and the environment and to develop design data for remedial action, the Investigation Plan shall include, but not be limited to, assessment of the following factors:

- a. Types and quantities of hazardous substances disposed at the site.
- b. Physical state, analytical summary, toxicological characteristics and other pertinent data defining hazardous substances present at the site.
- c. Methods and extent of the disposal operation including containment methods used, plans and/or photographs of site operation, perimeter and depth of disposal area, and type of disposal operation conducted (open burning, trench, surface impoundment, etc.).
- d. Observed release of contaminants to groundwater, surface water or air, including sampling, to determine contaminant concentrations and extent of contaminant migration.

(1.) Groundwater use and population served by groundwater sources within a three (3) mile radius of the perimeter of contaminant migration.

(2.) Surface water use and population served within a three (3) mile reach downstream of the perimeter of contaminant migration.

(3.) Population potentially affected by contaminant releases to the air within a four (4) mile radius of the perimeter of contaminant migration.

(4.) Distance from the site to sensitive environments such as a natural wetland, critical habitat for an endangered species or a National Wildlife Refuge.

g. Fire and explosion hazard assessment of the site.

h. Direct contact hazard assessment of the site.

3. The Investigation Plan must include cost estimates and a proposed schedule for completion of activities involved in the investigation. Following a review of the Plan, the Department may schedule a meeting which Respondent shall attend to discuss any revisions required by the Department. The Respondent will be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a revised Investigation Plan shall be submitted by the Respondent to the Department. Upon approval by the Department of the revised Investigation Plan, the Respondent shall begin required activities according to the revised Investigation Plan.

schedule. This report will be referred to as a Hazard Assessment/Remedial Action report (herein after referred to as "HA/RA"). Remedial action alternatives must include cost estimates and proposed schedules for completion of activities involved in remedial action implementation.

2. Assessment of each remedial action alternative must include consideration of the following factors:

- a. The technological feasibility of each alternative;
- b. The cost-effectiveness of each alternative;
- c. The nature of the danger to the public health, safety, and the environment posed by the hazardous substances at the site; and
- d. The extent to which each alternative would achieve the goal of T.C.A. Section 68-46-206(d) which states, in part, ". . . The goal of any such action shall be cleanup and containment of the site through the elimination of the threat to public health, safety and the environment posed by the hazardous substance."

3. Following the Department review of the HA/RA Report, the Department will schedule a meeting which the Respondent shall attend, to discuss any revisions required by the Department. The Respondent shall be given seven (7) days notice prior to the meeting. On or before a deadline date established in this review meeting, a revised HA/RA Report shall be submitted to the Department. Upon receipt of approval by the Department of the revised HA/RA Report, the Respondent shall begin activities required by the revised HA/RA Report, unless the Department determines no further action is necessary.

1. Where the Department determines a need for site monitoring and maintenance, the Respondent shall provide a Site Monitoring and Maintenance Plan (herein after referred to as "M/M Plan") which shall include a proposed schedule for completion of required activities and cost estimates within ninety (90) days of receipt of a request for said Plan by the Department.

2. Within forty-five (45) days of receipt of this M/M Plan by the Department, the Respondent shall attend a meeting with the Department to discuss any required revisions. On or before a deadline established in this review meeting, a revised M/M Plan shall be submitted by the Respondent to the Department. Upon receipt of approval by the Department, the revised M/M Plan will go into effect.


E. To the extent practicable, any investigation, identification, containment and clean-up, including monitoring and maintenance, shall be consistent with the national contingency plan promulgated pursuant to Section 105 of Public Law 96-510.

F. Certain activities may be deemed critical by the Department and shall require observation by the Department. The Respondent shall provide sufficient notice to the Department to allow scheduling of personnel for these activities. The Department also reserves the right to observe any other activities required pursuant to this Order.

G. Any failure to comply with approved schedules of activities required under this Order shall be a failure to comply with this Order.

H. In this Order, any reference to the singular includes the plural.


Health and Environment this 14th day of March, 1984.


JAMES E. WORD, Commissioner
Tennessee Department of Health
and Environment

NOTICE OF RIGHTS

International Harvester Company is hereby advised that in accordance with T.C.A. Section 68-46-215 it may secure a review of the necessity for or reasonableness of this Order by filing with the Commissioner, a written petition setting forth the grounds and reason for objection and asking for a hearing in the matter involved before the Solid Waste Disposal Control Board. The Order shall become final and not subject to review unless the person or persons named herein shall file such petition for a hearing no later than thirty (30) days after the date such Order is secured. Hearings will be conducted in accordance with the Tennessee Uniform Administrative Procedures Act.


Correspondence regarding this Order should be addressed to William L. Penny, Assistant General Counsel, 150 9th Avenue, North, Nashville, Tennessee 37203 or telephone (615)741-3657.


William L. Penny
Assistant General Counsel

WLP/bec/Intern Harv

Site No. TND

Reference No. Topo map #5



Chickasaw Bluff No 3

LOOSAATCHIE

MISSISSIPPI


NORTHWEST MEMPHIS QUADRANGLE
TENNESSEE-ARKANSAS
7.5 MINUTE SERIES (TOPOGRAPHIC)
NE 1/4 MEMPHIS 15 QUADRANGLE

N

* Update Del'te - same as Int. Yarr.

TND 980558670
TND 007024516

| | | | |
|--|---------------------------------|---|---|
| POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT PART 1 - SITE INFORMATION AND ASSESSMENT | | I. IDENTIFICATION 01 STATE: TND 02 SITE NUMBER: 98-055-8670 | |
| II. SITE NAME AND LOCATION | | | |
| 01 SITE NAME (Legal, common, or descriptive name of site) International Harvester | | 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Klinke Ave | |
| 03 CITY Klinke Ave. Memphis | 04 STATE TN | 05 ZIP CODE 38053 | 06 COUNTY Shelby |
| 08 COORDINATES LATITUDE 35° 12' 35" | LONGITUDE 90° 02' 20" | | |
| 10 DIRECTIONS TO SITE (Starting from nearest public road) | | | |
| III. RESPONSIBLE PARTIES | | | |
| 01 OWNER (If known) International Harvester | | 02 STREET (Business, mailing, residential) Klinke | |
| 03 CITY Memphis | 04 STATE TN | 05 ZIP CODE | 06 TELEPHONE NUMBER |
| 07 OPERATOR (If known and different from owner) International Harvester | | 08 STREET (Business, mailing, residential) 3003 Harvester Lane | |
| 09 CITY Memphis | 10 STATE TN | 11 ZIP CODE 3805 | 12 TELEPHONE NUMBER (901) 357-5311 |
| 13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ (Agency name) <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER: _____ (Specify) <input type="checkbox"/> G. UNKNOWN | | | |
| 14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input type="checkbox"/> A. RCRA 3001 DATE RECEIVED: _____ MONTH DAY YEAR <input checked="" type="checkbox"/> B. UNCONTROLLED WASTE SITE (RCRA 103) DATE RECEIVED: _____ MONTH DAY YEAR <input type="checkbox"/> C. NONE | | | |
| IV. CHARACTERIZATION OF POTENTIAL HAZARD | | | |
| 01 ON SITE INSPECTION <input type="checkbox"/> YES DATE _____ MONTH DAY YEAR <input checked="" type="checkbox"/> NO | | BY (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): _____ | |
| 02 SITE STATUS (Check one) <input type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input checked="" type="checkbox"/> C. UNKNOWN | | 03 YEARS OF OPERATION BEGINNING YEAR _____ ENDING YEAR _____ <input checked="" type="checkbox"/> UNKNOWN | |
| 04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED Drum Storage - unknown materials | | | |
| 05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION Drum Storage - Unknown | | | |
| V. PRIORITY ASSESSMENT | | | |
| 01 PRIORITY FOR INSPECTION (Check one, if high or medium is selected, complete Part 2 - Waste information and Part 3 - Observation of Hazardous Conditions and Incidents) <input checked="" type="checkbox"/> A. HIGH (Immediate response required) <input type="checkbox"/> B. MEDIUM (Intermediate response) <input type="checkbox"/> C. LOW (Respond on next available basis) <input type="checkbox"/> D. NONE (No further action needed, complete current inspection form) | | | |
| VI. INFORMATION AVAILABLE FROM | | | |
| 01 CONTACT Z. S. M. get | | 02 OF (Agency, Organization) International Harvester | |
| 04 PERSON RESPONSIBLE FOR ASSESSMENT [Signature] | | 05 AGENCY Dpt Health Environ. | 06 ORGANIZATION DSWH 3012 |
| | | 07 TELEPHONE NUMBER (615) 741-6287 | 08 DATE 1. 12. 89 MONTH DAY YEAR |



☐ I. HIGHLY VOLATILE
☐ J. EXPLOSIVE
☐ K. REACTIVE
☐ L. INCOMPATIBLE
☐ M. NOT APPLICABLE

EPA FORM 2070-12 (7-81)



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ B. SURFACE WATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ C. CONTAMINATION OF AIR

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ E. DIRECT CONTACT

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ F. CONTAMINATION OF SOIL

03 AREA POTENTIALLY AFFECTED: _____
(Acres)

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ G. DRINKING WATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ H. WORKER EXPOSURE/INJURY

03 WORKERS POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ I. POPULATION EXPOSURE/INJURY

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE 02 SITE NUMBER

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include names of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES

(Spill/leak/dumping/discharging errors)

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Can specify references, e. g., state files, agency records, reports)

Mile
743

SHELBY CO
PITTTENDEN CO

Light
an Point
Bar

ARKANSAS
TENNESSEE

MISSISSIPPI

LOOSA HATCHIE
BAR

Chickasaw E

Slough


ROAD
BILLION
AND BENJESTOWN RD

LOOSA HATCHIE

Radio
Towers
(WMPs)

Klinke
Park

Substation



BENJESTOWN
MORNINGSIDE

Mile
740

INC

Light

WOLF

FLOODWALL



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT
PART 1 - SITE INFORMATION AND ASSESSMENT

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
TN 007-02-4516

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site)

International Harvester - Epic #73

02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER

3003 Harvester Lane

03 CITY

Memphis

04 STATE

TN

05 ZIP CODE

06 COUNTY

Shelby

07 COUNTY CODE

157

08 CONG DIST

08

09 COORDINATES LATITUDE

35 12 23.0

LONGITUDE

090 03 05.0

10 DIRECTIONS TO SITE (Starting from nearest public road)

III. RESPONSIBLE PARTIES

01 OWNER (If known)

International Harvester Corp

02 STREET (Business, mailing, residential)

03 CITY

04 STATE

05 ZIP CODE

06 TELEPHONE NUMBER

(312) 836-2340

07 OPERATOR (If known and different from owner)

08 STREET (Business, mailing, residential)

09 CITY

10 STATE

11 ZIP CODE

12 TELEPHONE NUMBER

13 TYPE OF OWNERSHIP (Check one)

☒ A. PRIVATE

☐ B. FEDERAL

(Agency name)

☐ C. STATE

☐ D. COUNTY

☐ E. MUNICIPAL

☐ F. OTHER

(Specify)

☐ G. UNKNOWN

14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply)

☒ A. RCRA 3001 DATE RECEIVED: 6/1/81
MONTH DAY YEAR

☐ B. UNCONTROLLED WASTE SITE (CERCLA 103(c)) DATE RECEIVED: _____
MONTH DAY YEAR

☐ NONE

IV. CHARACTERIZATION OF POTENTIAL HAZARD

01 ON SITE INSPECTION

☒ YES

DATE

5/6/83
MONTH DAY YEAR

☐ NO

BY (Check all that apply)

☒ A. EPA

☐ B. EPA CONTRACTOR

☐ C. STATE

☐ D. OTHER CONTRACTOR

☐ E. LOCAL HEALTH OFFICIAL

☐ F. OTHER

(Specify)

CONTRACTOR NAME(S):

02 SITE STATUS (Check one)

☒ A. ACTIVE

☐ B. INACTIVE

☐ C. UNKNOWN

03 YEARS OF OPERATION

BEGINNING YEAR

ENDING YEAR

☐ UNKNOWN

04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED

Chrom on steel electroplating process - wastes include lead & Cr VI

International Harvester has submitted a feasibility study for plant closure to be reviewed by Superfund.

05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION

V. PRIORITY ASSESSMENT

01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous Conditions and Incidents)

☐ A. HIGH

(Inspection required promptly)

☐ B. MEDIUM

(Inspection required)

☒ C. LOW

(Inspect on time available basis)

☐ D. NONE

(No further action needed, complete current disposition form)

VI. INFORMATION AVAILABLE FROM

01 CONTACT

Z. S. Migot

02 OF Agency Organization

International Harvester

03 TELEPHONE NUMBER

(901) 357-5311

04 PERSON RESPONSIBLE FOR ASSESSMENT

Skipp Wrightson

05 AGENCY

Dept Health

06 ORGANIZATION


Sec. 3012

07 TELEPHONE NUMBER

(615) 741-6287

08 DATE

11/21/83
MONTH DAY YEAR





POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE

02 SITE NUMBER

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☐ A. GROUNDWATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ B. SURFACE WATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ C. CONTAMINATION OF AIR

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ E. DIRECT CONTACT

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ F. CONTAMINATION OF SOIL

03 AREA POTENTIALLY AFFECTED: _____
(Acres)

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ G. DRINKING WATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ H. WORKER EXPOSURE/INJURY

03 WORKERS POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

01 ☐ I. POPULATION EXPOSURE/INJURY

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED



POTENTIAL HAZARDOUS WASTE SITE
PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

I. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include names of species)

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ M. UNSTABLE CONTAINMENT OF WASTES
(Spills/runoff/standing liquids/leaking drums)

03 POPULATION POTENTIALLY AFFECTED: _____

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

01 ☐ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

II. TOTAL POPULATION POTENTIALLY AFFECTED: _____

V. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g., State Dept. Sampling Analysis Reports)

Site No. 73

EPIC Description: Dump and fill of industrial waste behind factory. Several piles of leaking drums. Leachate ponds.

Facility Name & Location: *IND 007024514*
International Harvester - *EPIC #73*
3003 Harvester Lane
Shelby Memphis, Tennessee 38127
Contact: Gene Cutrell, Plant Engineer; 901/357-3511

EPA Inspectors: Richard Green & Andrew Kromis

Date & Time of Inspection: 2 MAY 80, 1000

Summary of Field Observations:

International Harvester in Memphis fabricates farm equipment. The plant processes include casting, shearing, machining, welding, assembly, washing, plating, and painting. In addition to manufacturing complete pieces of equipment, the plant also manufactures parts to be shipped to other International Harvester plants.

Site No. 73 is approximately 30 acres located on International Harvester property east of the plant. There were about 1,000 empty drums stacked along the western edge of the site. The original contents of these drums were oil, paint, varnish, sealing compound, caustics, and hydrochloric acid. Most of the drums are sold to Memphis Drum Service to be reconditioned or they are returned to the product manufacturer. Those drums that cannot be sold are supposed to be crushed (but not cleaned) and dumped empty into the landfill. The ground surface down gradient from the drums was oily and black foundry sand is spread out in an area northeast of the drums.

The western edge of site No. 73 is the working face of the International Harvester landfill. The material landfilled consists of wood, pallets, crates, metal, paper trash, glass, and some drums. With the exception of yellow drums filled with trash, the drums in the landfill were supposed to be empty. One drum, originally containing grease, was about three-fourths full, capped and sealed. It was located at the top of the highwall at the edge of the landfill. Other drums originally labelled for oil, paint, cooling compound, and sealant were on the working face of the landfill. These drums were not accessible; therefore, it is not known if they were empty. Other unlabelled drums were seen of which Mr. Cutrell could not identify the contents (or former contents).


Runoff from the landfill probably flows into the area of the plant discharge (see diagram) and then on to the Mississippi River. The plant effluent is sampled for NPDES permit requirements prior to receiving any runoff from the landfill. The plant discharge flows about one half mile through land which is actively being farmed on its way to the Mississippi River. Mr. Cutrell said that the landfill had recently appeared on the front page of the local newspaper with a caption noting

leaking chemical drums."

Preliminary Sampling and Coordinating Recommendations:

Sampling of water and sediment in outfall channel below dump, runoff and soils on top of dump, and selected drums in the dump. Coordination with NPDES/Water Sources Team (should NPDES sampling point be moved downstream of dump?)

Site No. 73



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

DATE:

APR 15 1981

SUBJECT: International Harvester Company, Hazardous Waste Site Investigation, Memphis, TN.
October 20, 1980

FROM: Director, Surveillance and Analysis Division

TO: Howard Zeller, Acting Director
Enforcement Division


Attached is a copy of the subject report. Would you please see that a copy of the report and sample analyses are sent to the International Harvester Company. The plant contact and his address is:

Mr. Gene Cutrell, Plant Engineer
International Harvester
3003 Harvester Lane
Memphis, Tennessee 38127

Billy H. Adams for
James H. Finger

Attachments

cc: Finger/Adams
Lair/Carter
Bennett/Carroll
✓ Wilburn
Al Smith/Wayne Mathis
Newton/Turnipseed
Hall/Till



HAZARDOUS WASTE SITE INVESTIGATION
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE
MARCH, 1981

INTRODUCTION

A hazardous waste site investigation was conducted at the International Harvester Company, Memphis, TN, during October 20-21, 1980 by J. S. Hall and Charles A. Till of the US Environmental Protection Agency (US-EPA), Region IV, Surveillance and Analysis Division (SAD). This investigation was initiated following a preliminary inspection by personnel of the US-EPA, Region IV, Enforcement Division in May 1980 (1). During the May 1980 inspection, US-EPA, investigators observed wood, pallets, crates, metal, paper, trash, glass, and drums in a landfill adjacent to the plant. The drums in the landfill were alleged to be empty (with the exception of some yellow drums filled with trash), and could not be sold or reconditioned. These drums were not accessible, so their contents or lack thereof were not verified by the US-EPA. The drums that were not sold or reconditioned were supposed to be crushed. There were also approximately 1000 empty drums stacked along the northeastern side of the landfill near the back entrance gate of the plant. The original contents of these drums were reported to be oil, paint, varnish, sealing compound, caustics, and hydrochloric acid.

STUDY AREA

The International Harvester Plant is located at 3003 Harvester Lane on the northwestern side of Memphis (see figure 1). The plant manufactures farm equipment. The manufacturing processes include casting, shearing, machining, welding, assembly, washing, plating, and painting. In addition to manufacturing complete pieces of equipment, the plant also manufactures parts to be shipped to other International Harvester Plants.

The subject landfill is located to the west of the plant. The landfill and adjacent area are situated on the Mississippi River floodplain. All runoff from the landfill drains toward the Mississippi River via a large drainage ditch. The soils around the landfill are floodplain alluvium that consist of materials formed from silts and clays washed from the adjacent uplands, and from silts, clays, sands and gravels deposited by the Mississippi River. The area immediately downgradient from the landfill is presently being farmed. The topography of the area consists of gently sloping uplands to nearly flat to flat bottom lands. (See figure 2 for site map)

During this investigation, four sediment, one soil, and two water samples were collected. Three sediment samples (IH-2, IH-3, IH-4) were collected in depositional areas downgradient from the landfill. A composite soil sample (IH-5) was collected from random locations on top of the landfill. The two water samples IH-6 and IH-001, and another sediment sample IH-7 were collected in the drainage ditch that conveys wastewater from the plant and surface runoff from the landfill to the Mississippi River (see figure 2 for sampling locations). All sampling points were located on International Harvester Company property.

DISCUSSIONS AND RESULTS

The soil and sediment samples were analyzed for organic compounds and metals. Water sample IH-6 was analyzed for organic compounds, metals, and cyanide. Water sample IH-001 was collected for an NPDES inspection so it was analyzed only for metals and other permitted parameters. Results of the NPDES investigation were forwarded January 29, 1981, and are not discussed in this report.

Sampling station locations are included in Table 1. All data included in tables 2 and 3 include only metals and organic compounds that were positively identified and quantified by laboratory analyses. Several organic compounds were tentatively identified and concentrations were estimated; also, some trace concentrations (below the minimum detection level (MDL) of organic compounds and metals were detected but were too low to be quantified. These data, along with all of the analytical results, are included with the analytical data sheets in Attachment 1. Attachment 2 contains all of the field data record sheets.

Extractable and Purgeable Organic Compounds

3,4-benzofluoranthene and/or 11,12-benzofluoranthene was detected at a concentration of 1,500 ug/kg in the sediment sample (IH-3) collected in the small drainage ditch on the western side of the landfill. This sample would have been affected by runoff from most of the landfill area except for the northwest portion. Trace concentrations of eight other extractable organic compounds were detected, but were too low to be quantified (<1,000 ug/kg), including: naphthalene, phenanthrene and/or anthracene, fluoranthene, pyrene, chrysene and/or 1,2-benzanthracene, 3,4-benzopyrene, 1,12-benzoperylene, and phenol (<2,200 ug/kg). Also, 13 other extractable organic compounds were tentatively identified in this sample with estimated concentrations or concentrations too low to be quantified. (See Attachment 1).

Sediment sample IH-2, collected in a depositional area collected at the southern part of the site, contained trace concentrations of nine extractable organic compounds but were too low to be quantified (<1,000 ug/kg). These were: naphthalene, phenanthrene and/or anthracene, fluoranthene, pyrene, 1,2-benzanthracene, 3,4-benzofluoranthene and/or 11,12-benzofluoranthene, 3,4-benzopyrene, 1,12-benzoperylene, and phenol (<500 ug/kg). Ten other extractable organic compounds were tentatively identified with estimated concentrations or concentrations too low to be quantified.

Sediment sample IH-4, collected in a depositional area of the northern part of the site, contained a trace concentration of phenol (<1,000 ug/kg). There were also four other extractable organic compounds tentatively identified with estimated concentrations or concentrations too low to be quantified.

Soil sample IH-5 collected on the landfill, contained trace concentrations of fluoranthene (<15,000 ug/kg) and pyrene (<15,000 ug/kg). Also, one other extractable organic compound was tentatively identified in IH-5, but the concentration was too low to be quantified.

Sediment sample IH-7, collected from the large drainage ditch below the site, contained seven extractable organic compounds that were tentatively identified with estimated concentrations, or concentrations too low to be quantified.

The water sample IH-6, collected from the large drainage ditch below the site, contained no detectable extractable organic compounds.

The only purgeable organic compound detected in any of the soil and sediment or water samples collected during this investigation was dichlorodifluoromethane at a trace concentration (<5 ug/kg) in soil sample IH-4.

Chlorinated Organic Compounds

Polychlorinated biphenyls (PCB's) were detected in all of the soil and sediment samples. The concentrations and compounds were as follows: (IH-2), PCB (Aroclor 1248, 18,000 ug/kg); (IH-3), PCB (Aroclor 1248, 5,500 ug/kg); (IH-4), PCB (Aroclor 1248, 8,900 ug/kg); (IH-5), PCB (Aroclor 1254, 3,800 ug/kg); and (IH-7); PCB (Aroclor 1254, 180 ug/kg). These data indicate that PCB concentrations were higher in the landfill area than in the drainage ditch sediments downgradient from the landfill (see figure 2 and table 2). PCB's have been used in numerous commercial applications such as plasticizers, heat transfer fluids, hydraulic fluids, fluids in vacuum pumps and compressors, lubricants, and wax extenders. (2)

Metals

Iron was detected in all of the soil and sediment samples ranging in concentration from 21,360 ug/kg to 41,000 ug/kg. Sediment sample IH-3 contained lead at a concentration of 112 ug/kg, and zinc at a concentration of 147 ug/kg. Sediment sample IH-4 contained chromium, 141 ug/kg; lead, 468 ug/kg, and zinc, 175 ug/kg. Sediment sample IH-7 contained chromium, 278 ug/kg; lead 210 ug/kg; and zinc, 174 ug/kg. Soil sample IH-5 contained chromium at a concentration of 104 ug/kg. Chromium was detected in water sample IH-6 at a concentration of 104 ug/L. None of the other metals detected in the soil, sediment or water samples displayed high concentrations (3) (See table 2 for concentrations).

METHODOLOGY

All sampling and preservation methods used during this investigation were in accordance with the Water Surveillance Branch Standard Operating Procedures and Quality Assurance Manual, August 29, 1980 (4). Chain-of-custody was maintained from time of collection until samples were relinquished to Laboratory Services Branch (LSB) personnel at the North Treatment Plant in Memphis.

Analyses were conducted by the US-EPA, SAD, Laboratory Services Branch (LSB) and Mead Technology (contract laboratory). The soil, sediment and water samples were analyzed for organic compounds and metals by the (LSB). Water sample IH-6 was analyzed by Mead Technology for organic compounds. The (LSB) analyzed water sample IH-6 for metals and cyanide. Water sample IH-001 was analyzed by the (LSB) for NPDES parameters.

REFERENCES

1. "Report - Hazardous Waste Site Investigation - Memphis, Tennessee - First Phase", US Environmental Protection Agency, Region IV, Enforcement Division; June 1980.
2. Ambient Water Quality Criteria for Polychlorinated Biphenyls United States Environmental Protection Agency, EPA-440/5-80-068, 1980.
3. Hazardous Waste Site Investigation, Frayser Pond Site, Memphis, TN. US Environmental Protection Agency, Region IV, Surveillance and Analysis Division, September 17, 1980.
4. Water Surveillance Branch Standard Operating Procedures and Quality Assurance Manual. (Draft); US Environmental Protection Agency Region IV, Surveillance and Analysis Division, August 29, 1980.

Table 1
Sampling Locations
International Harvester Company
Memphis, Tennessee
March, 1981

| Field Identification | SAD No. | Date | Time | Description | Type Sample |
|----------------------|----------|-------|--------------|--|-------------|
| IH-2 | 81C 0103 | 10/20 | 1045 | Depositional area below the southern most part of landfill. | Sediment |
| IH-3 | 81C 0104 | 10/20 | 1100 | Depositional area below landfill in drainage ditch on western side of site | Sediment |
| IH-4 | 81C 0106 | 10/20 | 1120 | Area below landfill on northern most part of dump. | Sediment |
| IH-5 | 81C 0105 | 10/20 | 1130 1145 | Composite sample from several locations on top of landfill. | Soil |
| IH-6 | 81C 0108 | 10/20 | 1420 | Effluent ditch at culvert and field rd. Approx. 1000 ft. below NPDES discharge pipe. | Water |
| IH-7 | 81C 0107 | 10/20 | 1425 | Effluent ditch at culvert and field rd. Approx. 1000 ft. below NPDES discharge pipe. | Sediment |
| IH-001 | 81C 0150 | 10/21 | 0935 | NPDES outfall in ditch discharging from the plant. | Water |

Table 2
Analytical Results
Soil Samples
International Harvester Company
Memphis, Tennessee
March, 1981


| Parameter | Sample Locations | | | | |
|-----------------------------------|------------------|--------|--------|--------|--------|
| | IH-2 | IH-3 | IH-4 | IH-5 | IH-7 |
| 3,4 - benzofluoranthene and/or | | | | | |
| 11,12 - benzofluoranthene (ug/kg) | ND | 1500 | ND | ND | ND |
| Barium (mg/kg) | 111 | 199 | 316 | 68 | 221 |
| Cadmium (mg/kg) | ND | ND | ND | ND | 4 |
| Chromium (mg/kg) | 30 | 44 | 141 | 104 | 278 |
| Copper (mg/kg) | 26 | 40 | 74 | 50 | 37 |
| Nickel (mg/kg) | 18 | 31 | 35 | 29 | 33 |
| Lead (mg/kg) | 70 | 112 | 468 | 57 | 210 |
| Strontium (mg/kg) | 37 | 48 | 92 | 46 | 41 |
| Titanium (mg/kg) | 275 | 533 | 320 | 112 | 224 |
| Vanadium (mg/kg) | 19 | 49 | 27 | 17 | 55 |
| Yttrium (mg/kg) | 5 | 11 | 8 | 4 | 14 |
| Zinc (mg/kg) | 83 | 147 | 175 | 54 | 174 |
| Zirconium (mg/kg) | 4 | ND | 5 | ND | ND |
| Mercury (mg/kg) | ND | ND | ND | ND | 0.1 |
| Calcium (mg/kg) | 17,638 | 13,170 | 19,300 | 6,591 | 6,050 |
| Magnesium (mg/kg) | 5,176 | 7,497 | 6,800 | 2,977 | 5,350 |
| Aluminum (mg/kg) | 7,282 | 20,985 | 15,900 | 6,200 | 23,750 |
| Iron (mg/kg) | 21,360 | 30,990 | 41,100 | 29,680 | 31,050 |
| Manganese (mg/kg) | 502 | 786 | 665 | 426 | 875 |
| Sodium (mg/kg) | ND | ND | 545 | 390 | ND |
| PCB, (Aroclor 1248) (ug/kg) | 18,000 | 5,500 | 8,900 | ND | ND |
| PCB, (Aroclor 1254) (ug/kg) | ND | ND | ND | 3,800 | 180 |


Note: ND - Indicates material was analyzed for but not detected at or above the minimum detection limit.

Table 3
 Analytical Results
 Water Sample (IH-6) and NPDES Discharge Sample (IH-001)
 International Harvester Company
 Memphis, Tennessee
 March, 1981

| Parameter | IH-6 | IH-001 |
|------------|--------|--------|
| | (ug/L) | (ug/L) |
| Barium | 41 | 38 |
| Chromium | 104 | 58 |
| Copper | 14 | 11 |
| Molybdenum | 215 | 68 |
| Strontium | 44 | 38 |
| Aluminum | 300 | 154 |
| Calcium | 13 | 13 |
| Magnesium | 5.9 | 6 |
| Iron | 1.0 | 0.6 |
| Sodium | 17.0 | 12 |

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE





ATTACHMENT 1

EPA, SAD, RCN. IV
Athens, GA 4/80

COMPL'D. 1-26-81

[illegible]

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected, The number is the Minimum Detection Limit.
I/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RCN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 1-26-8

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0103 | | |
|--|--|------------------------|------------------------|
| SOURCE & STATION | IH-2 Depositional area below So. most part of dump. | | |
| DATE/TIME | 10-20-80 @ 1045 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 1000U | |
| 26. 1,3-dichlorobenzene | 34569 | 1000U | |
| 27. 1,4-dichlorobenzene | 34574 | 1000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 1000U | |
| 12. hexachloroethane | 34399 | 1000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 1000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 2000U | |
| 56. nitrobenzene | 34450 | 1000U | |
| 52. hexachlorobutadiene | 39705 | 1000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 1000U | |
| 55. naphthalene | 34445 | 1000K | |
| 43. bis(2-chloroethoxy) methane | 34281 | 1000U | |
| 54. isophorone | 34411 | 2000U | |
| 53. hexachlorocyclopentadiene | 34389 | 1000U | |
| 20. 2-chloronaphthalene | 34584 | 1000U | |
| 77. acenaphthylene | 34203 | 1000U | |
| 1. acenaphthene | 34208 | 1000U | |
| 71. dimethyl phthalate | 34344 | 1000U | |
| 35. 2,4-dinitrotoluene | 34614 | 1000U | |
| 36. 2,6-dinitrotoluene | 34629 | 1000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 1000U | |
| 80. fluorene | 34384 | 1000U | |
| 70. diethyl phthalate | 34339 | 1000U | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 1000U | |
| 62. N-nitrosodiphenylamine 2/ | 34436 | 1000U | |
| 9. hexachlorobenzene | 39701 | 1000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 1000U | |
| 81. phenanthrene 4/ | 34464 | | |
| 78. anthracene 4/ | 34223 | 1000K | |
| 68. di-n-butyl phthalate | 39112 | 1000U | |
| 39. fluoranthene | 34379 | 1000K | |
| 84. pyrene | 34472 | 1000K | |
| 67. butyl benzyl phthalate | 34295 | 1000U | |
| 5. benzidine | 39121 | 2000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 1000U | |
| 76. chrysene 2/ | 34323 | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 1000K | |
| 28. 3,3'-dichlorobenzidine | 34634 | 1000U | |
| 69. di-n-octyl phthalate | 34599 | 1000U | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 1000K | |
| 73. 3,4-benzopyrene | 34250 | 1000K | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 1000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 1000U | |
| 79. 1,12-benzoperylene | 34524 | 1000K | |
| 24. 2-chlorophenol | 34589 | 500U | |
| 57. 2-nitrophenol | 34594 | 500U | |
| 65a. phenol (GC/MS) | 34695 | 500K | |
| 34. 2,4-dimethylphenol | 34609 | 500U | |
| 31. 2,4-dichlorophenol | 34604 | 500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 500U | |
| 22. parachlorometacresol | 34455 | 500U | |
| 59. 2,4-dinitrophenol | 34619 | 4000U | |
| 60. 4,6-dinitro-o-cresol | 34660 | 500U | |
| 64. pentachlorophenol | 39061 | 500U | |
| 58. 4-nitrophenol | 34649 | 1000U | |

A - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine.

5/ - Chrysene and/or 1,2-benzanthracene

6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E.W. Loy, Jr.

REC'D. 10-20-80 COMPL'D. 1-26-81

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0104 | | |
|--|--|------------------------|------------------------|
| SOURCE & STATION | IH-3 Area below dump ditch on Western side of site. | | |
| DATE/TIME | 10-20-80 @ 1100 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 1000U | |
| 26. 1,3-dichlorobenzene | 34569 | 1000U | |
| 27. 1,4-dichlorobenzene | 34574 | 1000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 1000U | |
| 12. hexachloroethane | 34399 | 1000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 1000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 2000U | |
| 56. nitrobenzene | 34450 | 1000U | |
| 52. hexachlorobutadiene | 39705 | 1000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 1000U | |
| 55. naphthalene | 34445 | 1000K | |
| 43. bis(2-chloroethoxy) methane | 34281 | 1000U | |
| 54. isophorone | 34411 | 2000U | |
| 53. hexachlorocyclopentadiene | 34389 | 1000U | |
| 20. 2-chloronaphthalene | 34584 | 1000U | |
| 77. acenaphthylene | 34203 | 1000U | |
| 1. acenaphthene | 34208 | 1000U | |
| 71. dimethyl phthalate | 34344 | 1000U | |
| 35. 2,4-dinitrotoluene | 34614 | 1000U | |
| 36. 2,6-dinitrotoluene | 34629 | 1000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 1000U | |
| 80. fluorene | 34384 | 1000U | |
| 70. diethyl phthalate | 34339 | 1000U | |
| 37. 1,2-diphenylhydrazine ^{2/} | 34349 | 1000U | |
| 62. N-nitrosodiphenylamine ^{3/} | 34436 | 1000U | |
| 9. hexachlorobenzene | 39701 | 1000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 1000U | |
| 81. phenanthrene ^{4/} | 34464 | | |
| 78. anthracene ^{5/} | 34223 | 1000K | |
| 68. di-n-butyl phthalate | 39112 | 1000U | |
| 39. fluoranthene | 34379 | 1000K | |
| 84. pyrene | 34472 | 1000K | |
| 67. butyl benzyl phthalate | 34295 | 1000U | |
| 5. benzidine | 39121 | 2000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 1000U | |
| 76. chrysene ^{2/} | 34323 | | |
| 72. 1,2-benzanthracene ^{2/} | 34529 | 1000K | |
| 28. 3,3'-dichlorobenzidine | 34634 | 1000U | |
| 69. di-n-octyl phthalate | 34599 | 1000U | |
| 74. 3,4-benzofluoranthene ^{6/} | 34233 | | |
| 75. 11,12-benzofluoranthene ^{6/} | 34245 | 1500 | |
| 73. 3,4-benzopyrene | 34250 | 1000K | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 1000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 1000U | |
| 79. 1,12-benzoperylene | 34524 | 1000K | |
| 24. 2-chlorophenol | 34589 | 2200U | |
| 57. 2-nitrophenol | 34594 | 2200U | |
| 65a. phenol (GC/MS) | 34695 | 2200K | |
| 34. 2,4-dimethylphenol | 34609 | 2200U | |
| 31. 2,4-dichlorophenol | 34604 | 2200U | |
| 21. 2,4,6-trichlorophenol | 34624 | 2200U | |
| 22. parachlorometa cresol | 34455 | 2200U | |
| 59. 2,4-dinitrophenol | 34619 | 11,000U | |
| 60. 4,6-dinitro-o-cresol | 34660 | 2200U | |
| 64. pentachlorophenol | 39061 | 2200U | |
| 58. 4-nitrophenol | 34649 | 4400U | |

A - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/- Tentative identification.

2/- and/or azobenzene.

3/- and/or diphenylamine.

5/- Chrysene and/or 1,2-benzanthracene
6/- 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 4/80

RESULTS ON DRY WEIGHT BASIS

No other organic compounds detected with an estimated minimum detection limit of 2500 ug/kg

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN
Athens, GA 4

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 1-1

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0105 | | |
|--|--|------------------------|------------------------|
| SOURCE & STATION | IH-5 Composite of 4 sites from top of dump. 10-20-80 @ 1130 | | |
| DATE/TIME | 10-20-80 @ 1145 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloroethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 15000U | |
| 26. 1,3-dichlorobenzene | 34569 | 15000U | |
| 27. 1,4-dichlorobenzene | 34574 | 15000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 15000U | |
| 12. hexachloroethane | 34399 | 15000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 15000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 30000U | |
| 56. nitrobenzene | 34450 | 15000U | |
| 52. hexachlorobutadiene | 39705 | 15000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 15000U | |
| 55. naphthalene | 34445 | 15000U | |
| 43. bis(2-chloroethoxy) methane | 34281 | 15000U | |
| 54. isophorone | 34411 | 30000U | |
| 53. hexachlorocyclopentadiene | 34389 | 15000U | |
| 20. 2-chloronaphthalene | 34564 | 15000U | |
| 77. acenaphthylene | 34203 | 15000U | |
| 1. acenaphthene | 34203 | 15000U | |
| 71. dimethyl phthalate | 34344 | 15000U | |
| 35. 2,4-dinitrotoluene | 34614 | 15000U | |
| 36. 2,6-dinitrotoluene | 34629 | 15000U | |
| 40. 4-chlorobenzyl phenyl ether | 34644 | 15000U | |
| 80. fluorene | 34384 | 15000U | |
| 70. diethyl phthalate | 34339 | 15000U | |
| 37. 1,2-diphenylhydrazine ^{2/} | 34349 | 15000U | |
| 62. N-nitrosodiphenylamine ^{3/} | 34436 | 15000U | |
| 9. hexachlorobenzene | 39701 | 15000U | |
| 41. 4-bromobenzyl phenyl ether | 34639 | 15000U | |
| 81. phenanthrene ^{4/} | 34464 | | |
| 78. anthracene ^{4/} | 34223 | 15000U | |
| 68. di-n-butyl phthalate | 39112 | 15000U | |
| 39. fluoranthene | 34379 | 15000U | |
| 84. pyrene | 34472 | 15000U | |
| 67. butyl benzyl phthalate | 34295 | 15000U | |
| 5. benzidine | 39121 | 30000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 15000U | |
| 76. chrysene ^{5/} | 34323 | | |
| 72. 1,2-benzanthracene ^{2/} | 34529 | 15000U | |
| 28. 3,3'-dichlorobenzidine | 34634 | 15000U | |
| 69. di-n-octyl phthalate | 34599 | 15000U | |
| 74. 3,4-benzofluoranthene ^{6/} | 34233 | | |
| 75. 11,12-benzofluoranthene ^{6/} | 34245 | 15000U | |
| 73. 3,4-benzopyrene | 34250 | 15000U | |
| 83. indeno (1,2,3-cd) pyrene | 34405 | 15000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 15000U | |
| 79. 1,12-benzoperylene | 34524 | 15000U | |
| 24. 2-chlorophenol | 34589 | 500U | |
| 57. 2-nitrophenol | 34594 | 500U | |
| 65a. phenol (GC/MS) | 34695 | 500U | |
| 34. 2,4-dichlorophenol | 34609 | 500U | |
| 31. 2,4-dichlorophenol | 34604 | 500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 500U | |
| 22. parachlorometa cresol | 34455 | 500U | |
| 59. 2,4-dinitrophenol | 34619 | 5000U | |
| 60. 4,6-dinitro-cresol | 34660 | 500U | |
| 64. pentachlorophenol | 39061 | 500U | |
| 58. 4-nitrophenol | 34649 | 1000U | |

A - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

2/ - Tentative identification.

5/ - Chrysene and/or 1,2-benza.

6/ - 3,4-benzofluoranthene and

11,12-benzofluoranthene.

EPA, SAD, RCN. IV
Athens, GA 4/8

RESULTS ON DRY WEIGHT BASIS

No other organic compounds detected with an estimated minimum detection limit of .15,000 ug/

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/- Tentative identification.

LEA-SAD, RONA-20
ATHENS, GA
4/80

BASED ON WET WEIGHT BASIS

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
NA - Not analyzed.
1/- Tentative identification.
2/- On NRDC List of Priority Pollutants.

LEADS, 100-44
ATHENS, GA
4/80

REC'D. 10-20-80 COMPLET'D. 12-19-80

| SAD NO. | 81C 0103 | 81C 0104 | 81C 0105 |
|---|--|---|--------------------------------|
| SOURCE & STATION | IH-2 Depositional area below dump. | IH-3 Below dump ditch western side. | IH-5 composite of 4 top. |
| DATE/TIME | 10-20-80 @ 1045 | 10-20-80 @ 1100 | 10-20-80 @ 1130-1 |
| Compound | ug/kg | ug/kg | ug/kg |
| dichlorodifluoromethane ^{2/} | 34334 5U | 5U | 5U |
| methyl chloride ^{2/} | 34421 5U | 5U | 5U |
| methyl bromide ^{2/} | 34416 5U | 5U | 5U |
| vinyl chloride ^{2/} | 34495 5U | 5U | 5U |
| chloroethane ^{2/} | 34314 5U | 5U | 5U |
| methylene chloride ^{2/} | 34426 5U | 5U | 5U |
| trichlorofluoromethane ^{2/} | 34491 5U | 5U | 5U |
| 1,1-dichloroethylene ^{2/} | 34504 5U | 5U | 5U |
| 1,1-dichloroethane ^{2/} | 34499 5U | 5U | 5U |
| 1,2-trans-dichloroethylene ^{2/} | 34549 5U | 5U | 5U |
| chloroform ^{2/} | 34318 5U | 5U | 5U |
| 1,2-dichloroethane ^{2/} | 34534 5U | 5U | 5U |
| 1,1,1-trichloroethane ^{2/} | 34509 5U | 5U | 5U |
| carbon tetrachloride ^{2/} | 34299 5U | 5U | 5U |
| dichlorobromomethane ^{2/} | 34330 5U | 5U | 5U |
| 1,2-dichloropropane ^{2/} | 34544 5U | 5U | 5U |
| 1,3-dichloropropylene ^{2/} | 34564 5U | 5U | 5U |
| trichloroethylene ^{2/} | 34487 5U | 5U | 5U |
| benzene ^{2/} | 34237 5U | 5U | 5U |
| chlorodibromomethane ^{2/} | 34309 5U | 5U | 5U |
| 1,1,2-trichloroethane ^{2/} | 34514 5U | 5U | 5U |
| 2-chloroethyl vinyl ether (mixed) ^{2/} | 34579 5U | 5U | 5U |
| bromoform ^{2/} | 34290 5U | 5U | 5U |
| 1,1,2,2-tetrachloroethane ^{2/} | 34519 5U | 5U | 5U |
| tetrachloroethylene ^{2/} | 34478 5U | 5U | 5U |
| toluene ^{2/} | 34483 5U | 5U | 5U |
| chlorobenzene ^{2/} | 34304 5U | 5U | 5U |
| ethylbenzene ^{2/} | 34374 5U | 5U | 5U |
| acrolein ^{2/} | 34213 100U | 100U | 100U |
| acrylonitrile ^{2/} | 34218 100U | 100U | 100U |
| dihydrothiophene 1/ | 5U | 5U | 8J |

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
NA - Not analyzed.

1/- Tentative identification.
2/- On NRDC List of Priority Pollutants.

ATHENS, GA
4/80

REC'D. 10-20-80 COMPLET'D. 12-10

| SAD NO. | 81C 0106 | 81C 0107 |
|---|--------------------------------|---------------------------------|
| SOURCE & STATION | IH-4 Below dump northern part. | IH-7 Effluent ditch at Culvert. |
| DATE/TIME | 10-20-80 1120-1145 | 10-20-80 1125-1145 |
| Compound | ug/kg | ug/kg |
| dichlorodifluoromethane ^{2/} | 34334 5U | 5U |
| methyl chloride ^{2/} | 34421 5U | 5U |
| methyl bromide ^{2/} | 34416 5U | 5U |
| vinyl chloride ^{2/} | 34495 5U | 5U |
| chloroethane ^{2/} | 34314 5U | 5U |
| methylene chloride ^{2/} | 34426 5U | 5U |
| trichlorofluoromethane ^{2/} | 34491 5U | 5U |
| 1,1-dichloroethylene ^{2/} | 34504 5U | 5U |
| 1,1-dichloroethane ^{2/} | 34499 5U | 5U |
| 1,2-trans-dichloroethylene ^{2/} | 34549 5U | 5U |
| chloroform ^{2/} | 34318 5U | 5U |
| 1,2-dichloroethane ^{2/} | 34534 5U | 5U |
| 1,1,1-trichloroethane ^{2/} | 34509 5U | 5U |
| carbon tetrachloride ^{2/} | 34299 5U | 5U |
| dichlorobromomethane ^{2/} | 34330 5U | 5U |
| 1,2-dichloropropane ^{2/} | 34544 5U | 5U |
| 1,3-dichloropropylene ^{2/} | 34564 5U | 5U |
| trichloroethylene ^{2/} | 34487 5U | 5U |
| benzene ^{2/} | 34237 5U | 5U |
| chlorodibromomethane ^{2/} | 34309 5U | 5U |
| 1,1,2-trichloroethane ^{2/} | 34514 5U | 5U |
| 2-chloroethyl vinyl ether (mixed) ^{2/} | 34579 5U | 5U |
| bromoform ^{2/} | 34290 5U | 5U |
| 1,1,2,2-tetrachloroethane ^{2/} | 34519 5U | 5U |
| tetrachloroethylene ^{2/} | 34478 5U | 5U |
| toluene ^{2/} | 34483 5U | 5U |
| chlorobenzene ^{2/} | 34304 5U | 5U |
| ethylbenzene ^{2/} | 34374 5U | 5U |
| acrolein ^{2/} | 34213 100U | 100U |
| acrylonitrile ^{2/} | 34218 100U | 100U |

2/- On NRDC List of Priority Pollutants.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 2-3-80

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0106 | | |
|--|--|------------------------|------------------------|
| SOURCE & STATION | IH-4 Area below dump on Northern most part of dump. | | |
| DATE/TIME | 10-20-80 @ 1120 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34741 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 40000U | |
| 26. 1,3-dichlorobenzene | 34569 | 40000U | |
| 27. 1,4-dichlorobenzene | 34574 | 40000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 40000U | |
| 12. hexachloroethane | 34399 | 40000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 40000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 80000U | |
| 56. nitrobenzene | 34450 | 40000U | |
| 52. hexachlorobutadiene | 39705 | 40000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 40000U | |
| 55. naphthalene | 34445 | 40000U | |
| 43. bis(2-chloroethoxy) methane | 34281 | 40000U | |
| 54. isophorone | 34411 | 80000U | |
| 53. hexachlorocyclopentadiene | 34389 | 40000U | |
| 20. 2-chloronaphthalene | 34584 | 40000U | |
| 77. acenaphthylene | 34203 | 40000U | |
| 1. acenaphthene | 34208 | 40000U | |
| 71. dimethyl phthalate | 34344 | 40000U | |
| 35. 2,4-dinitrotoluene | 34614 | 40000U | |
| 36. 2,6-dinitrotoluene | 34629 | 40000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 40000U | |
| 80. fluorene | 34384 | 40000U | |
| 70. diethyl phthalate | 34339 | 40000U | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 40000U | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 40000U | |
| 9. hexachlorobenzene | 39701 | 40000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 40000U | |
| 81. chrysene 4/ | 34464 | | |
| 78. anthracene 5/ | 34223 | 40000U | |
| 68. di-n-butyl phthalate | 39112 | 40000U | |
| 39. fluoranthene | 34379 | 40000U | |
| 84. pyrene | 34472 | 40000U | |
| 67. butyl benzyl phthalate | 34295 | 40000U | |
| 5. benzidine | 39121 | 80000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 40000U | |
| 76. chrysene 5/ | 34323 | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 40000U | |
| 28. 3,3'-dichlorobenzidine | 34634 | 40000U | |
| 69. di-n-octyl phthalate | 34599 | 40000U | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 40000U | |
| 73. 3,4-benzopyrene | 34250 | 40000U | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 40000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 40000U | |
| 79. 1,12-benzoperylene | 34524 | 40000U | |
| 24. 2-chlorophenol | 34589 | 7500U | |
| 57. 2-nitrophenol | 34594 | 7500U | |
| 65a. phenol (GC/MS) | 34695 | 7500K | |
| 34. 2,4-dimethylphenol | 34609 | 7500U | |
| 31. 2,4-dichlorophenol | 34604 | 7500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 7500U | |
| 22. parachlorometa cresol | 34455 | 7500U | |
| 59. 2,4-dinitrophenol | 34619 | 60000U | |
| 60. 4,6-dinitro-o-cresol | 34660 | 7500U | |
| 64. pentachlorophenol | 34061 | 7500U | |
| 58. 4-nitrophenol | 34649 | 15000U | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine

5/ - Chrysene and/or 1,2-benzanthra

6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 4/

RESULTS ON DRY WEIGHT BASIS

No other organic compounds detected with an estimated minimum detection limit of . 40000 u.

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit

1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAG, RCN, I:
Athens, GA 4/81

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr.

REC'D. 10-20-80 COMPL'D. 2-17-

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | | BIC 0107 | | |
|--|-------|---|------------------------|------------------------|
| SOURCE & STATION | | IH-7 Eff. ditch at Culvert at field Rd. below pipe | | |
| DATE/TIME | | 10-20-80 @ 1426 | | |
| Compounds on NRDC List of Priority Pollutants | | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 5000U | | |
| 26. 1,3-dichlorobenzene | 34569 | 5000U | | |
| 27. 1,4-dichlorobenzene | 34574 | 5000U | | |
| 18. bis(2-chloroethyl) ether | 34276 | 5000U | | |
| 12. hexachloroethane | 34399 | 5000U | | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 5000U | | |
| 61. N-nitrosodi-n-propylamine | 34431 | 10000U | | |
| 36. nitrobenzene | 34450 | 5000U | | |
| 52. hexachlorobutadiene | 39705 | 5000U | | |
| 8. 1,2,4-trichlorobenzene | 34554 | 5000U | | |
| 55. naphthalene | 34445 | 5000U | | |
| 43. bis(2-chloroethoxy) methane | 34281 | 5000U | | |
| 54. isophorone | 34411 | 10000U | | |
| 53. hexachlorocyclopentadiene | 34389 | 5000U | | |
| 20. 2-chloronaphthalene | 34584 | 5000U | | |
| 77. acenaphthylene | 34203 | 5000U | | |
| 1. acenaphthene | 34205 | 5000U | | |
| 71. dimethyl phthalate | 34344 | 5000U | | |
| 35. 2,4-dinitrotoluene | 34614 | 5000U | | |
| 36. 2,6-dinitrotoluene | 34629 | 5000U | | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 5000U | | |
| 80. fluorene | 34384 | 5000U | | |
| 70. diethyl phthalate | 34339 | 5000U | | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 5000U | | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 5000U | | |
| 9. hexachlorobenzene | 39701 | 5000U | | |
| 41. 4-bromophenyl phenyl ether | 34639 | 5000U | | |
| 81. phenanthrene 4/ | 34464 | | | |
| 78. anthracene 5/ | 34223 | 5000U | | |
| 68. di-n-butyl phthalate | 39112 | 5000U | | |
| 39. fluoranthene | 34379 | 5000U | | |
| 84. pyrene | 34472 | 5000U | | |
| 67. butyl benzyl phthalate | 34295 | 5000U | | |
| 5. benzidine | 39121 | 10000U | | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 5000U | | |
| 76. chrysene 2/ | 34323 | | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 5000U | | |
| 28. 3,3'-dichlorobenzidine | 34634 | 5000U | | |
| 69. di-n-octyl phthalate | 34599 | 5000U | | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 5000U | | |
| 73. 3,4-benzopyrene | 34250 | 5000U | | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 5000U | | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 5000U | | |
| 79. 1,12-benzoperylene | 34524 | 5000U | | |
| 24. 2-chlorophenol | 34589 | 2100U | | |
| 57. 2-nitrophenol | 34594 | 2100U | | |
| 65a. phenol (GC/MS) | 34695 | 2100U | | |
| 34. 2,4-dimethylphenol | 34609 | 2100U | | |
| 31. 2,4-dichlorophenol | 34604 | 2100U | | |
| 21. 2,4,6-trichlorophenol | 34624 | 2100U | | |
| 22. parachlorometa cresol | 34455 | 2100U | | |
| 59. 2,4-dinitrophenol | 34619 | 17000U | | |
| 60. 4,6-dinitro-o-cresol | 34660 | 2100U | | |
| 64. pentachlorophenol | 39061 | 2100U | | |
| 58. 4-nitrophenol | 34649 | 4200U | | |

A - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine.

4/ - Phenanthrene and/or anthracene.

5/ - Chrysene and/or 1,2-benzanth

6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 41

RESULTS ON DRY WEIGHT BASIS

THE CHROMATOGRAM INDICATES THE PRESENCE OF
A PETROLEUM TYPE PRODUCT.

.J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

DATA REPORTING SHEET
SEDIMENT

EPA-SAD-L58-4-10-8

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-20-80 COMPL'D 12-17-80
Memphis, TN

PROJECT NUMBER 81-6 RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C | 0107 | | | |
|-------------------|-------|--|--|--|--|
| SOURCE & STATION: | | IH-7 Eff. ditch at Culvert at field Rd. below pipe. | | | |
| DATE/TIME | | 10-20-80/1425-1145 | | | |
| ELEMENT (mg/kg) | | | | | |
| Silver* | 01078 | 3K | | | |
| Arsenic* | 01003 | 14K | | | |
| Boron | 01023 | | | | |
| Barium | 01008 | 221 | | | |
| Beryllium* | 01013 | 4K | | | |
| Cadmium* | 01028 | 4 | | | |
| Cobalt | 01038 | 8K | | | |
| Chromium* | 01029 | 278 | | | |
| Copper* | 01043 | 37 | | | |
| Molybdenum | 01063 | 8K | | | |
| Nickel* | 01068 | 33 | | | |
| Lead* | 01052 | 210 | | | |
| Antimony* | 01098 | 10K | | | |
| Selenium* | 01148 | 16K | | | |
| Tin | 01103 | 24K | | | |
| Strontium | 01083 | 41 | | | |
| Tellurium | 45513 | 16K | | | |
| Titanium | 01153 | 224 | | | |
| Thallium* | 34480 | 40K | | | |
| Vanadium | 01088 | 55 | | | |
| Yttrium | 45514 | 14 | | | |
| Zinc* | 01093 | 174 | | | |
| Zirconium | 01163 | 4K | | | |
| Mercury* | 71921 | 0.1 | | | |
| Calcium | 00917 | 6050 | | | |
| Magnesium | 00924 | 5350 | | | |

- CONTINUED ON BACK -

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

EPA-SAD-LSE -4-10.

COMPL'D 12-17-80

RESULTS ON DRY WEIGHT BASIS

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

WATER
 DATA REPORTING SHEET

SAG NO. RIC 0108 CONTRACT LAB NO. D0212 CONTRACT LAB Method Technology
 PROJECT International Harvester SOURCE & STATION M-6 EFF. DITCH AT Culvert at
Memphis, TN Field Road below pipe.
 DATE/TIME SAMPLED 10-20-80 @ 1420 SAMPLE RECEIVED 10-20-80 DATA RECEIVED 12-17-80

| VOLATILE COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | | ug/L | TENTATIVELY-IDENTIFIED COMPOUNDS | ug/L |
|--|--|-------|-------|--|------|
| 2V | Acrolein | 34210 | 100U | The chromatogram indicates the presence of a petroleum-type product. | |
| 3V | Acrylonitrile | 34215 | 100U | | |
| 4V | Benzene | 34030 | 10U | | |
| 6V | Carbon Tetrachloride | 32102 | 10U | | |
| 7V | Chlorobenzene | 34301 | 10U | | |
| 10V | 1,2-Dichloroethane | 32103 | 10U | | |
| 11V | 1,1,1-Trichloroethane | 34506 | 10U | | |
| 13V | 1,1-Dichloroethane | 34496 | 10U | | |
| 14V | 1,1,2-Trichloroethane | 34511 | 10U | | |
| 15V | 1,1,2,2-Tetrachloroethane | 34516 | 10U | | |
| 16V | Chloroethane | 34311 | 10U | | |
| 19V | 2-Chloroethylvinyl Ether | 34576 | 10U | | |
| 23V | Chloroform | 32106 | 10U | | |
| 29V | 1,1-Dichloroethylene | 34501 | 10U | | |
| 30V | 1,2-Trans-Dichloroethylene | 34546 | 10U | | |
| 32V | 1,2-Dichloropropane | 34541 | 10U | | |
| 33V | 1,3-Dichloropropane | 34551 | 10U | | |
| 38V | Ethylbenzene | 34371 | 10U | | |
| 44V | Methylene Chloride | 34423 | 10U | | |
| 45V | Methyl Chloride | 34418 | 10U | | |
| 46V | Methyl Bromide | 34413 | 10U | | |
| 47V | Bromoform | 32104 | 10U | | |
| 48V | Dichlorobromomethane | 32101 | 10U | | |
| 49V | Trichlorofluoromethane | 34488 | 10U | | |
| 50V | Dichlorodifluoromethane | 34658 | 10U | | |
| 51V | Chlorodibromomethane | 34305 | 10U | | |
| 85V | Tetrachloroethylene | 34475 | 10U | | |
| 86V | Toluene | 34010 | 10U | | |
| 87V | Trichloroethylene | 39180 | 10U | | |
| 88V | Vinyl Chloride | 39175 | 10U | | |
| PESTICIDES/PCB'S ON NRDC LIST OF PRIORITY POLLUTANTS | | | ug/L | | |
| 89P | Aldrin | 39330 | 0.10U | | |
| 90P | Dieldrin | 39330 | 0.10U | | |
| 91P | Chlordane (Tech. Mixture & Metabolites) | 39350 | 0.10U | | |
| 92P | 4,4'-DDT (p,p'-DDT) | 39300 | 0.10U | | |
| 93P | 4,4'-DDE (p,p'-DDE) | 39320 | 0.10U | | |
| 94P | 4,4'-DDD (p,p'-TDE) | 39310 | 0.10U | | |
| 95P | a-Endosulfan-Alpha | 34361 | 0.10U | | |
| 96P | b-Endosulfan-Beta | 34356 | 0.10U | | |
| 97P | Endosulfan Sulfate | 34351 | 0.10U | | |
| 98P | Endrin | 39390 | 0.10U | | |
| 99P | Endrin Aldehyde | 34356 | 0.10U | | |
| 100P | Heptachlor | 39410 | 0.10U | | |
| 101P | Heptachlor Epoxide | 39420 | 0.10U | | |
| 102P | a-BHC-Alpha | 39337 | 0.10U | | |
| 103P | b-BHC-Beta | 39338 | 0.10U | | |
| 104P | gamma-BHC-(Lindane)-Gamma | 39340 | 0.10U | | |
| 105P | delta-BHC-Delta | 34259 | 0.10U | | |
| 106P | PCB-1242 (Aroclor 1242) | 39495 | 0.10U | | |
| 107P | PCB-1254 (Aroclor 1254) | 39504 | 0.10U | | |
| 108P | PCB-1221 (Aroclor 1221) | 39483 | 0.10U | | |
| 109P | PCB-1232 (Aroclor 1232) | 39492 | 0.10U | | |
| 110P | PCB-1248 (Aroclor 1248) | 39500 | 0.10U | | |
| 111P | PCB-1260 (Aroclor 1260) | 39508 | 0.15U | | |
| 112P | PCB-1016 (Aroclor 1016) | 34671 | 0.10U | | |
| 113P | Toxaphene | 39400 | 0.40U | | |
| 129P | 2,3,7,8-Tetrachlorodibenzo-p-dioxin (TCDD) | 34675 | NA | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

8/22/80

WATER
DATA REPORTING SHEET

SAD NO. 81C0108 CONTRACT LAB NO. D0212 CONTRACT LAB Mead Technology
 PROJECT International Harvester SOURCE & STATION IR-6 EFF. Ditch at Culvert at
Memphis, TN Field Road below pipe.
 DATE/TIME SAMPLED 10-20-80 @ 1420 SAMPLE RECEIVED 10-20-80 DATA RECEIVED 12-17-80

| PAH/NEUTRAL COMPOUNDS ON NEDC LIST OF PRIORITY POLLUTANTS | | ug/L |
|--|-------|------|
| 1B Acenaphthene | 34205 | 10U |
| 5B Benzidine | 39120 | 10U |
| 8B 1,2,4-Trichlorobenzene | 34551 | 10U |
| 9B Hexachlorobenzene | 39700 | 10U |
| 12B Hexachloroethane | 34396 | 10U |
| 17B Bis(Chloromethyl) Ether | 34268 | NA |
| 18B Bis(2-Chloroethyl) Ether | 34273 | 10U |
| 20B 2-Chloronaphthalene | 34581 | 10U |
| 25B 1,2-Dichlorobenzene | 34536 | 10U |
| 26B 1,3-Dichlorobenzene | 34566 | 10U |
| 27B 1,4-Dichlorobenzene | 34571 | 10U |
| 28B 3,3'-Dichlorobenzidine | 34631 | 10U |
| 35B 2,4-Dinitrotoluene | 34611 | 10U |
| 36B 2,6-Dinitrotoluene | 34626 | 10U |
| 37B 1,2-Diphenylhydrazine ^{1/} | 34346 | 10U |
| 39B Fluoranthene | 34376 | 10U |
| 40B 4-Chlorophenyl Phenyl Ether | 34641 | 10U |
| 41B 4-Bromophenyl Phenyl Ether | 34636 | 10U |
| 42B Bis(2-Chloroisopropyl) Ether | 34283 | 10U |
| 43B Bis(2-Chloroethoxy) Methane | 34278 | 10U |
| 52B Hexachlorobutadiene | 39702 | 10U |
| 53B Hexachlorocyclopentadiene | 34386 | 10U |
| 54B Isophorone | 34408 | 10U |
| 55B Naphthalene | 34696 | 10U |
| 56B Nitrobenzene | 34447 | 10U |
| 61B N-Nitrosodimethylamine ^{2/} | 34438 | NA |
| 62B N-Nitrosodiphenylamine ^{2/} | 34433 | 10U |
| 63B N-Nitrosodi-N-Propylamine | 34428 | 10U |
| 66B Bis(2-Ethylhexyl) Phthalate | 39100 | 50U |
| 67B Butyl Benzyl Phthalate | 34292 | 10U |
| 68B Di-N-Butylphthalate | 39110 | 10U |
| 69B Di-N-Octylphthalate | 34596 | 10U |
| 70B Diethylphthalate | 34336 | 10U |
| 71B Dimethylphthalate | 34341 | 10U |
| 72B Benzo (A) Anthracene ^{4/} | 34526 | 10U |
| 73B Benzo(A) Pyrene ^{5/} | 34247 | 10U |
| 74B 3,4-Benzofluoranthene ^{5/} | 34230 | 10U |
| 75B Benzo(K) Fluoranthene ^{5/} | 34242 | 10U |
| 76B Chrysene ^{5/} | 34320 | 10U |
| 77B Acenaphthylene | 34200 | 10U |
| 78B Anthracene ^{3/} | 34220 | 10U |
| 79B Benzo(GHI) Perylene | 34521 | 25U |
| 80B Fluorene | 34381 | 10U |
| 81B Phenanthrene ^{3/} | 34461 | 10U |
| 82B Dibenzo(A, H) Anthracene | 34556 | 25U |
| 83B Indeno (1,2,3-CD) Pyrene | 34403 | 25U |
| 84B Pyrene | 34469 | 25U |

| ACID COMPOUNDS ON NEDC LIST OF PRIORITY POLLUTANTS | | ug/L |
|---|-------|------|
| 21A 2,4,6-Trichlorophenol | 34621 | 25U |
| 22A p-Chloro-m-Cresol | 34452 | 25U |
| 24A 2-Chlorophenol | 34586 | 25U |
| 31A 2,4-Dichlorophenol | 34601 | 25U |
| 34A 2,4-Dimethylphenol | 34606 | 25U |
| 57A 2-Nitrophenol | 34591 | 25U |
| 58A 4-Nitrophenol | 34646 | 25U |
| 59A 2,4-Dinitrophenol | 34616 | 250U |
| 60A 4,6-Dinitro-o-Cresol | 34657 | 250U |
| 64A Pentachlorophenol | 39032 | 25U |
| 65A Phenol (GC/MS) | 34994 | 25U |

K - Actual value is known to be less than value given.

U - Material was analyzed for but not detected. The number is the minimum detection limit.

1/ - And/or Azobenzene.

2/ - And/or Diphenylamine.

3/ - 813 Phenanthrene and/or 783 Anthracene.

DATA REPORTING SHEET
WATER

EPA-823-158 4-10-80

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-20-80 COMPL'D 11-20-80
Memphis, TN
PROJECT No. 81-6

| | | | | | |
|------------------|-------|--|--|--|--|
| SAD NO. | 81-C | 0103 | | | |
| SOURCE & STATION | | IH-6 EFF Ditch at Culvert and Field Rd. Below Pipe. | | | |
| DATE/TIME | | 10-20-80 @ 1420-1145 | | | |
| ELEMENT (ug/l.) | | | | | |
| Silver * | 01077 | 10K | | | |
| Arsenic * | 01002 | 45K | | | |
| Boron | 01022 | --- | | | |
| Barium | 01007 | 41 | | | |
| Beryllium * | 01012 | 10K | | | |
| Cadmium * | 01027 | 10K | | | |
| Cobalt | 01037 | 20K | | | |
| Chromium * | 01034 | 104 | | | |
| Copper * | 01042 | 14 | | | |
| Molybdenum | 01062 | 215 | | | |
| Nickel * | 01067 | 35K | | | |
| Lead * | 01051 | 40K | | | |
| Antimony * | 01097 | 25K | | | |
| Selenium * | 01147 | 40K | | | |
| Tin | 01102 | 60K | | | |
| Strontium | 01082 | 44 | | | |
| Tellurium | 01064 | 40K | | | |
| Titanium | 01152 | 10K | | | |
| Thallium * | 01059 | 100K | | | |
| Vanadium | 01087 | 10K | | | |
| Yttrium | 01203 | 10K | | | |
| Zinc * | 01092 | --- | | | |
| Zirconium | 01162 | 10K | | | |
| Mercury * | 71900 | 0.2K | | | |
| Aluminum | 01105 | 300 | | | |
| Manganese | 01055 | 50K | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

* - Priority Pollutant.

(Continued on Back)

67A-849-123 7-29-64

[illegible]

* - Priority Pollutant.

DATA REPORTING SHEET
WATER

LRN-330-153 4-10-80

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-21-80 COMPL'D 11-20-80
Memphis, TN
 PROJECT No. 81-6

| SAD NO. | 81C | 0150 | | | |
|------------------|-------|---|--|--|--|
| SOURCE & STATION | | IH-001 NPDES Outfall in ditch downstream. | | | |
| DATE/TIME | | 10-21-80 @ 0935 | | | |
| ELEMENT (ug/L) | | | | | |
| Silver * | 01077 | 10K | | | |
| Arsenic * | 01002 | 45K | | | |
| Boron | 01022 | --- | | | |
| Barium | 01007 | 38 | | | |
| Beryllium * | 01012 | 10K | | | |
| Cadmium * | 01027 | 10K | | | |
| Cobalt | 01037 | 20K | | | |
| Chromium * | 01034 | 58 | | | |
| Copper * | 01042 | 11 | | | |
| Molybdenum | 01062 | 68 | | | |
| Nickel * | 01067 | 35K | | | |
| Lead * | 01051 | 40K | | | |
| Antimony * | 01097 | 25K | | | |
| Selenium * | 01147 | 40K | | | |
| Tin | 01102 | 60K | | | |
| Strontium | 01082 | 38 | | | |
| Tellurium | 01064 | 40K | | | |
| Titanium | 01152 | 10K | | | |
| Thallium * | 01059 | 100K | | | |
| Vanadium | 01087 | 10K | | | |
| Yttrium | 01203 | 10K | | | |
| Zinc * | 01092 | --- | | | |
| Zirconium | 01162 | 10K | | | |
| Mercury * | 71900 | 0.2K | | | |
| Aluminum | 01105 | 154 | | | |
| Manganese | 01055 | 50K | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

K - Actual value is known to be less than value given.
 L - Actual value is known to be greater than value given.
 * - Priority Pollutant.

44-38861-100-1

[illegible]

* - Priority Pollutant.

1190

US EPA REGION IV S&A DIVISION
LABORATORY SERVICES BRANCH
DATA REPORTING SHEET
GIC0103 - BIC0100

NATIONAL HARVESTER

PROJECT # 01-6 ***PROG ELEMENT # CSI

SAMPLE RECEIVED DATE 10/20/80 1530

MEMPHIS

STATE: TN

COMPLETED: 12/15/80

| DATE | TIME | SAMPLE TYPE | ANALYSES TO BE RUN |
|----------|------|-------------|--------------------|
| 10/20/80 | 1420 | ANBWA | MG UG/L : METSC |
| 10/20/80 | 1145 | | MG/L : TOC |
| | | | PH : PH |
| | | | ITEM : 25.0 |
| | | | DEG C : |

ATTACHMENT 2

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|---|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Murphy, TN</u> CONTACT _____ | SAMPLING STATION NO. <u>T-11-001</u> SAMPLING LOCATION <u>NPDES outfall</u> <u>COI in ditch downstream</u> <u>Excess sampling; failed contact</u> <u>containing 4 more to contact cooling</u> |
|---|---|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☒ IND. ☐ INF. ☒ EFF. ☐ _____ ☒ 24 HR. COMP. AT 30 MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☒ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☒ TYPE 1510 1680 11 163022 (6:30)
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------------------|--------------------------|-----------------|------------------|
| DATE | <u>0150</u> | <u>0150</u> | BACTERIAL 0 |
| TIME | <u>10/24/80 10:21/80</u> | <u>10/21/80</u> | BOD, COD, TOC 1 |
| FLOW (avg) L | <u>1000 109.0</u> | <u>0935</u> | CYANIDE 2 |
| TEMPERATURE °C | <u>16.4</u> | <u>25</u> | METALS 3 |
| pH | <u>7.3</u> | | N, P 4 |
| TOT. Cl ₂ RES, mg/l | | | ORG, O&G, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| | | | |
| | | | |
| SAMPLE CODE | <u>2c water</u> | | |
| SAMPLED BY (Sig) | <u>STH, L. H. Till</u> | | |
| SEALED BY (Sig) | <u>STH</u> | | |
| DATE AND TIME | <u>10/22/80 7:00</u> | | |
| | | | PRESERVED P |

11 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>B. Quinn</u> | <u>10/21/80</u> | <u>11:30</u> | <u>1</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

R1 - 1 pt 9 pers metals
 PH Bufferd
 4 4.2
 7 6.8
 10 9.9
 1,440,000 gal / 24 hrs period
 (pH meter bufferd @ 7.0, reads on 4 and 10)

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

DISCHARGER International Harvester

SAMPLING STATION NO. I H-2

ADDRESS _____

SAMPLING LOCATION Dr. position at area below southern end of part of dump

CONTACT Gene Cantrell

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT SAMPLE HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.
SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
COMPUTED FROM _____

SAMPLE COLLECTION

| | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------------------|----------------------|--------------|------------------|
| SAD NO. | | | BACTERIAL 0 |
| DATE | <u>10/20/80</u> | | BOD, COD, TOC 1 |
| TIME | <u>1045</u> | | CYANIDE 2 |
| FLOW () L | | | METALS 3 |
| TEMPERATURE °C | | | N, P 4 |
| pH | | | ORG, O&G, PEST 5 |
| TOT. Cl ₂ RES. mg/l | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| | | | 8 |
| SAMPLE CODE | <u>See below</u> | | 9 |
| SAMPLED BY (Sig) | <u>JSF</u> | | A |
| SEALED BY (Sig) | <u>JSF</u> | | B |
| DATE AND TIME | <u>10/20/80 1200</u> | | PRESERVED P |

11 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|-------------|-----------|-----------|-------------|
| <u>Bob Brown</u> | <u>10/20/80</u> | <u>1530</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1-1qt glass - organics ^{ext R}
1-1qt glass - metals ^{ext R}
plastic - dup. metals sample collected for I H; ~~see separate card~~
start

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|--|--|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Memphis, TN</u> CONTACT _____ | SAMPLING STATION NO. <u>T-11-3</u> SAMPLING LOCATION <u>Depositional area below dump - 4 in. hole on western side of site</u> |
|--|--|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ HR. COMP AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | DATE | TIME | FLOW () <input type="checkbox"/> | TEMPERATURE °C | pH | TOT. C12 RES, mg/l | SAMPLE CODE ¹² |
|------------------|-----------|----------|------|-----------------------------------|----------------|----|--------------------|---------------------------|
| | / | 10/20/80 | 1100 | | | | | BACTERIAL 0 |
| | / | | | | | | | BOD, COD, TOC 1 |
| | | | | | | | | CYANIDE 2 |
| | | | | | | | | METALS 3 |
| | | | | | | | | N, P 4 |
| | | | | | | | | ORG, O&G, PEST 5 |
| | | | | | | | | PHENOLS 6 |
| | | | | | | | | SOLIDS 7 |
| | | | | | | | | 8 |
| SAMPLE CODE | | | | | | | | 9 |
| SAMPLED BY (Sig) | | | | | | | | A |
| SEALED BY (Sig) | | | | | | | | B |
| DATE AND TIME | | | | | | | | PRESERVED P |

¹¹ Use Avg. Flow for Composites and Inst. Flow for Grabs ¹² Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|----------|------|-----------|-----------|-------------|
| <u>Bob Gorman</u> | 10/20/80 | 1530 | 2 | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1 - 1 qt glass - organics ^{ext R} _{von R}
 1 - 1 pt plastic - metals _R (metals dupl. collected for TH)

**U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION**

REGION **IV**

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>IH-4</u> |
| ADDRESS <u>Memphis TN</u> | SAMPLING LOCATION <u>Depositional area</u> |
| CONTACT <u>Gene Cartmell</u> | <u>below dump on northernmost part of</u> |
| | <u>dump (South of NDDPS ditch), sample</u> |
| | <u>area flows to NDDPS ditch</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------------------|----------------------|--------------|------------------|
| DATE | <u>10/20/80</u> | | BACTERIAL 0 |
| TIME | <u>1120</u> | | BOD, COD, TOC 1 |
| FLOW () L | | | CYANIDE 2 |
| TEMPERATURE °C | | | METALS 3 |
| pH | | | N, P 4 |
| TOT. Cl ₂ RES, mg/l | | | ORG, OAG, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| SAMPLE CODE | <u>See below</u> | | 8 |
| SAMPLED BY (Sig) | <u>Gene Cartmell</u> | | 9 |
| SEALED BY (Sig) | <u>Gene</u> | | A |
| DATE AND TIME | <u>10/20/80 1120</u> | | B |
| | | | PRESERVED P |

1 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Bob Riden</u> | <u>10/20/80</u> | <u>15:30</u> | <u>7</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1 - 1qt glass - organics ^{ext. p} _{VOF p}

1 - 1pt plastic - metals _p (dept metals collected for IH)

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Memphis TN</u> CONTACT <u>Gene Ethel</u> | SAMPLING STATION NO. <u>IH-5</u> SAMPLING LOCATION <u>Composite of</u> <u>Several (4) locations on site</u> <u>from top of dump</u> |
|---|--|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT HR. COMP AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE ¹² |
|--------------------------------|----------------------|--------------|---------------------------|
| DATE | <u>10/20/80</u> | | BACTERIAL 0 |
| TIME | <u>1130-1145</u> | | BOD, COD, TOC 1 |
| FLOW () L | | | CYANIDE 2 |
| TEMPERATURE °C | | | METALS 3 |
| pH | | | N, P 4 |
| TOT. Cl ₂ RES. mg/l | | | ORG, O&G, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| SAMPLE CODE | <u>See below</u> | | |
| SAMPLED BY (Sig) | <u>SLB, G. H. H.</u> | | |
| SEALED BY (Sig) | <u>SLB</u> | | |
| DATE AND TIME | <u>10/20/80 1200</u> | | |
| | | | PRESERVED P |

¹¹ Use Avg. Flow for Composites and Inst. Flow for Grabs ¹² Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Bob Brown</u> | <u>10/20/80</u> | <u>13:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1- "lower pile" - 1130
 2- "upper pile" - 1140
 3- " " - 1142
 4- " " - 1145
 1- 1qt glass - organics (24/8)
 1- 1pt plastic - metals (10/12)
 (dupl. metals collected for IH)

U.S. ENVIRONMENTAL PROTECTION SURVEILLANCE AND ANALYSIS D

D 0212

REGION IV

ATHENS, GEORGIA

| | |
|--|--|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Memphis, TN</u> CONTACT <u>Gene Cuddeback</u> | SAMPLING STATION NO. <u>TH-6</u> SAMPLING LOCATION <u>Elkhorn discharge</u> <u>Culvert @ Field Road - Locust</u> <u>Willow discharge (HIDES) pond</u> |
|--|--|

SAMPLE AND WASTE FLOW INFORMATION

WATER

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☐ _____ HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------------------|----------------------|--------------|------------------|
| DATE | <u>10/24/80</u> | | BACTERIAL Q |
| TIME | <u>1420</u> | | BOD, COD, TOC 1 |
| FLOW () L | | | CYANIDE 2 |
| TEMPERATURE °C | <u>25.0</u> | | METALS 3 |
| pH | <u>6.4</u> | | N, P 4 |
| TOT. Cl ₂ RES. mg/l | | | ORG. ORG. PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| | | | 8 |
| SAMPLE CODE | <u>see below</u> | | 9 |
| SAMPLED BY (Sig) | <u>STL-011/11</u> | | A |
| SEALED BY (Sig) | <u>STL</u> | | B |
| DATE AND TIME | <u>10/24/80 1500</u> | | P |

11 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|------------|-----------|-------------|
| <u>B. C. Cuddeback</u> | <u>10/28/80</u> | <u>15:30</u> | <u>2/5</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

D - 0212

1 - 1 gal glass - organics
 1 - 1 pt glass - metals
 1 - VIAL - VOA
 1 - 1/2 gal plastic - CN
 1 - TOC

- metals dupl. collected
for IH

**U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION**

REGION IV

ATHENS, GEORGIA

| | |
|---|---|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>IH-7</u> |
| ADDRESS <u>Memphis, TN</u> | SAMPLING LOCATION <u>Effluent ditch @</u> |
| CONTACT <u>Gene C. Huff</u> | <u>Culvert @ field road ~1000 ft</u> |
| | <u>below NPDES discharge pipe</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ EQUIP _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | | SAMPLE CODE 12 |
|--------------------------------|------------|-------------------|-----------------|------------------|
| | | DATE | TIME | |
| | <u>1/1</u> | <u>0107</u> | <u>10/20/83</u> | BACTERIAL 0 |
| | <u>1/1</u> | <u>1425</u> | | BOD, COD, TOC 1 |
| | | | | CYANIDE 2 |
| FLOW () LL | | | | METALS 3 |
| TEMPERATURE °C | | | | N, P 4 |
| pH | | | | ORG, O&G, PEST 5 |
| TOT. Cl ₂ RES, mg/l | | | | PHENOLS 6 |
| | | | | SOLIDS 7 |
| SAMPLE CODE | | <u>See below</u> | | 8 |
| SAMPLED BY (Sig) | | <u>JSH:GA:111</u> | | 9 |
| SEALED BY (Sig) | | <u>CD/124</u> | | A |
| DATE AND TIME | | <u>10/20/83</u> | | B |
| | | | | PRESERVED P |

LL Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>As follows</u> | <u>10/20/83</u> | <u>15:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

VSA 12

1-1 qt glass - organic - ext. R

1-1 pt plastic - metals R (dupl. metals collected for IH)

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

ATHENS, GEORGIA 30613

DATE: MAY 05 1981

SUBJECT Supplemental Report -- Hazardous Waste Site Investigation -- International Harvester Company -- Memphis, Tennessee

FROM Director, Surveillance and Analysis Division

TO Howard Zeller, Acting Director
Enforcement Division

Attached is a copy of the subject report. A copy of this report should be sent to:


Mr. Gene Cutrell, Plant Engineer
International Harvester
3003 Harvester Lane
Memphis, Tennessee 38127

Billy H. Adams/for
James H. Finger

Attachment

cc: Wilburn
Scarborough/Mathis
Newton/Turnipseed
Adams
Carroll/Bennett
Carter/Lair
Hall/Till

EPA/Region IV
Atlanta, GA



EPA/Region IV
Atlanta, GA
MAY 11 1981
ENFORCEMENT DIVISION

SUPPLEMENTAL REPORT
HAZARDOUS WASTE SITE INVESTIGATION
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE
APRIL 29, 1981


A hazardous waste site investigation report for International Harvester Company was issued April 7, 1981, by the U. S. Environmental Protection Agency, Surveillance and Analysis Division (SAD). At the time the report was issued, cyanide data were not available for the soil and sediment samples collected at the International Harvester Company. Cyanide analyses were reported on April 20, 1981, by the Laboratory Services Branch. These data are included in Table 1; general site location and sampling locations are included in Figures 1 and 2.

The cyanide concentration in sediment sample IH-3 (0.68 mg/kg) collected at the southern portion of the landfill appears to be higher than the concentrations in the other soil and sediment samples. The sediment sample (IH-7) taken from the drainage ditch that carries runoff to the Mississippi River contained a concentration of 0.27 mg/kg. The water sample (IH-6) contained a trace concentration (<0.002 mg/l) but was too low to be quantified (see April 7, 1981 report).

TABLE 1
CYANIDE CONCENTRATIONS IN SOIL AND SEDIMENT SAMPLES
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

| <u>Sample Number</u> | <u>Location</u> | <u>Cyanide Concentration mg/kg (dry weight)</u> |
|----------------------|--|---|
| IH-2 | Depositional area below the southern most part of landfill | 0.68 |
| IH-3 | Depositional area below landfill in drainage ditch on western side of landfill | 0.25 |
| IH-4 | Area below landfill on northern part of dump | 0.37 |
| IH-5 | Composite sample collected on top of landfill | 0.21 |
| IH-7 | Effluent and drainage ditch at culvert and field road | 0.27 |

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE






FIGURE 2
SITE MAP & SAMPLING LOCATIONS
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

← DRAINAGE FLOW DIRECTION

● SAMPLING LOCATION

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
ATHENS, GEORGIA 30613

DATE: MAY 05 1981

SUBJECT Supplemental Report -- Hazardous Waste Site Investigation -- International Harvester Company -- Memphis, Tennessee

FROM Director, Surveillance and Analysis Division

TO Howard Zeller, Acting Director
Enforcement Division

Attached is a copy of the subject report. A copy of this report should be sent to:

Mr. Gene Cutrell, Plant Engineer
International Harvester
3003 Harvester Lane
Memphis, Tennessee 38127

Billy H. Adams/for
James H. Finger

Attachment

cc: ✓ Wilburn
Scarborough/Mathis
Newton/Turnipseed
Adams
Carroll/Bennett
Carter/Lair
Hall/Till

3240
Compliance Branch

SUPPLEMENTAL REPORT
HAZARDOUS WASTE SITE INVESTIGATION
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE
APRIL 29, 1981


A hazardous waste site investigation report for International Harvester Company was issued April 7, 1981, by the U. S. Environmental Protection Agency, Surveillance and Analysis Division (SAD). At the time the report was issued, cyanide data were not available for the soil and sediment samples collected at the International Harvester Company. Cyanide analyses were reported on April 20, 1981, by the Laboratory Services Branch. These data are included in Table 1; general site location and sampling locations are included in Figures 1 and 2.


The cyanide concentration in sediment sample IH-3 (0.68 mg/kg) collected at the southern portion of the landfill appears to be higher than the concentrations in the other soil and sediment samples. The sediment sample (IH-7) taken from the drainage ditch that carries runoff to the Mississippi River contained a concentration of 0.27 mg/kg. The water sample (IH-6) contained a trace concentration (<0.002 mg/l) but was too low to be quantified (see April 7, 1981 report).

TABLE 1
CYANIDE CONCENTRATIONS IN SOIL AND SEDIMENT SAMPLES
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

| <u>Sample Number</u> | <u>Location</u> | <u>Cyanide Concentration mg/kg (dry weight)</u> |
|----------------------|--|---|
| IH-2 | Depositional area below the southern most part of landfill | 0.68 |
| IH-3 | Depositional area below landfill in drainage ditch on western side of landfill | 0.25 |
| IH-4 | Area below landfill on northern part of dump | 0.37 |
| IH-5 | Composite sample collected on top of landfill | 0.21 |
| IH-7 | Effluent and drainage ditch at culvert and field road | 0.27 |

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

ATLANTA, GEORGIA 30333


DATE: MAY 27 1981

SUBJECT: Drums in Wooded Area Near International Harvester Company, Memphis, Tennessee

FROM: Environmental Engineer
Water Surveillance Branch

TO: Jim Wilburn, Chief
Compliance Branch


On April 6, 1981 while conducting a hazardous waste site field investigation (HWSI) in the Wolf River/2nd Street area of Memphis, Tennessee, Messrs. R. J. Bruner III, US-EPA/SAD and Neil Strickland, Ecology and Environment, Inc. were contacted by Mr. George Perkins. Mr. Perkins owned several tracts of land involved in the Wolf River/2nd Street area HWSI, and he requested that the investigators accompany him on a tour of the area so that he could point out the boundaries of his property. During the tour of his property, Mr. Perkins indicated that several drums were located in a small wooded area between the southwest corner of International Harvester Company and the DeWitt Spain Airport (see attached map). Enlargements of Enviropod photographs of the area were obtained from EPIC on August 24, 1981. These photographs (copies attached) confirm the location of approximately 50 drums in the wooded area. International Harvester Company should be contacted to determine what information the company has regarding the drums.



R. J. Bruner III, P.E.

cc: Wallace/Green
Newton/Turnipseed
✓Smith/Stonebraker/Mathis
Finger/Adams
Carter/Lair/Hill

Enviropod Aerial Photograph
2X Enlargement - Frame No. 153
Mission Flown Over Memphis, TN
December 3-4, 1980



HAZARDOUS WASTE SITE INVESTIGATION
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE
MARCH, 1981

INTRODUCTION

A hazardous waste site investigation was conducted at the International Harvester Company, Memphis, TN, during October 20-21, 1980 by J. S. Hall and Charles A. Till of the US Environmental Protection Agency (US-EPA), Region IV, Surveillance and Analysis Division (SAD). This investigation was initiated following a preliminary inspection by personnel of the US-EPA, Region IV, Enforcement Division in May 1980 (1). During the May 1980 inspection, US-EPA, investigators observed wood, pallets, crates, metal, paper, trash, glass, and drums in a landfill adjacent to the plant. The drums in the landfill were alleged to be empty (with the exception of some yellow drums filled with trash), and could not be sold or reconditioned. These drums were not accessible, so their contents or lack thereof were not verified by the US-EPA. The drums that were not sold or reconditioned were supposed to be crushed. There were also approximately 1000 empty drums stacked along the northeastern side of the landfill near the back entrance gate of the plant. The original contents of these drums were reported to be oil, paint, varnish, sealing compound, caustics, and hydrochloric acid.

STUDY AREA

The International Harvester Plant is located at 3003 Harvester Lane on the northwestern side of Memphis (see figure 1). The plant manufactures farm equipment. The manufacturing processes include casting, shearing, machining, welding, assembly, washing, plating, and painting. In addition to manufacturing complete pieces of equipment, the plant also manufactures parts to be shipped to other International Harvester Plants.

The subject landfill is located to the west of the plant. The landfill and adjacent area are situated on the Mississippi River floodplain. All runoff from the landfill drains toward the Mississippi River via a large drainage ditch. The soils around the landfill are floodplain alluvium that consist of materials formed from silts and clays washed from the adjacent uplands, and from silts, clays, sands and gravels deposited by the Mississippi River. The area immediately downgradient from the landfill is presently being farmed. The topography of the area consists of gently sloping uplands to nearly flat to flat bottom lands. (See figure 2 for site map)

During this investigation, four sediment, one soil, and two water samples were collected. Three sediment samples (IH-2, IH-3, IH-4) were collected in depositional areas downgradient from the landfill. A composite soil sample (IH-5) was collected from random locations on top of the landfill. The two water samples IH-6 and IH-001, and another sediment sample IH-7 were collected in the drainage ditch that conveys wastewater from the plant and surface runoff from the landfill to the Mississippi River (see figure 2 for sampling locations). All sampling points were located on International Harvester Company property.

DISCUSSIONS AND RESULTS

The soil and sediment samples were analyzed for organic compounds and metals. Water sample IH-6 was analyzed for organic compounds, metals, and cyanide. Water sample IH-001 was collected for an NPDES inspection so it was analyzed only for metals and other permitted parameters. Results of the NPDES investigation were forwarded January 29, 1981, and are not discussed in this report.

Sampling station locations are included in Table 1. All data included in tables 2 and 3 include only metals and organic compounds that were positively identified and quantified by laboratory analyses. Several organic compounds were tentatively identified and concentrations were estimated; also, some trace concentrations (below the minimum detection level (MDL) of organic compounds and metals were detected but were too low to be quantified. These data, along with all of the analytical results, are included with the analytical data sheets in Attachment 1. Attachment 2 contains all of the field data record sheets.

Extractable and Purgeable Organic Compounds

3,4-benzofluoranthene and/or 11,12-benzofluoranthene was detected at a concentration of 1,500 ug/kg in the sediment sample (IH-3) collected in the small drainage ditch on the western side of the landfill. This sample would have been affected by runoff from most of the landfill area except for the northwest portion. Trace concentrations of eight other extractable organic compounds were detected, but were too low to be quantified (<1,000 ug/kg), including: naphthalene, phenanthrene and/or anthracene, fluoranthene, pyrene, chrysene and/or 1,2-benzanthracene, 3,4-benzopyrene, 1,12-benzoperylene, and phenol (<2,200 ug/kg). Also, 13 other extractable organic compounds were tentatively identified in this sample with estimated concentrations or concentrations too low to be quantified. (See Attachment 1).

Sediment sample IH-2, collected in a depositional area collected at the southern part of the site, contained trace concentrations of nine extractable organic compounds but were too low to be quantified (<1,000 ug/kg). These were: naphthalene, phenanthrene and/or anthracene, fluoranthene, pyrene, 1,2-benzanthracene, 3,4-benzofluoranthene and/or 11,12-benzofluoranthene, 3,4-benzopyrene, 1,12-benzoperylene, and phenol (<500 ug/kg). Ten other extractable organic compounds were tentatively identified with estimated concentrations or concentrations too low to be quantified.

Sediment sample IH-4, collected in a depositional area of the northern part of the site, contained a trace concentration of phenol (<1,000 ug/kg). There were also four other extractable organic compounds tentatively identified with estimated concentrations or concentrations too low to be quantified.

Soil sample IH-5 collected on the landfill, contained trace concentrations of fluoranthene (<15,000 ug/kg) and pyrene (<15,000 ug/kg). Also, one other extractable organic compound was tentatively identified in IH-5, but the concentration was too low to be quantified.

Sediment sample IH-7, collected from the large drainage ditch below the site, contained seven extractable organic compounds that were tentatively identified with estimated concentrations, or concentrations too low to be quantified.

The water sample IH-6, collected from the large drainage ditch below the site, contained no detectable extractable organic compounds.

The only purgeable organic compound detected in any of the soil and sediment or water samples collected during this investigation was dichlorodifluoromethane at a trace concentration (<5 ug/kg) in soil sample IH-4.

Chlorinated Organic Compounds

Polychlorinated biphenyls (PCB's) were detected in all of the soil and sediment samples. The concentrations and compounds were as follows: (IH-2), PCB (Aroclor 1248, 18,000 ug/kg); (IH-3), PCB (Aroclor 1248, 5,500 ug/kg); (IH-4), PCB (Aroclor 1248, 8,900 ug/kg); (IH-5), PCB (Aroclor 1254, 3,800 ug/kg); and (IH-7); PCB (Aroclor 1254, 180 ug/kg). These data indicate that PCB concentrations were higher in the landfill area than in the drainage ditch sediments downgradient from the landfill (see figure 2 and table 2). PCB's have been used in numerous commercial applications such as plasticizers, heat transfer fluids, hydraulic fluids, fluids in vacuum pumps and compressors, lubricants, and wax extenders. (2)

Metals

Iron was detected in all of the soil and sediment samples ranging in concentration from 21,360 ug/kg to 41,000 ug/kg. Sediment sample IH-3 contained lead at a concentration of 112 ug/kg, and zinc at a concentration of 147 ug/kg. Sediment sample IH-4 contained chromium, 141 ug/kg; lead, 468 ug/kg, and zinc, 175 ug/kg. Sediment sample IH-7 contained chromium, 278 ug/kg; lead 210 ug/kg; and zinc, 174 ug/kg. Soil sample IH-5 contained chromium at a concentration of 104 ug/kg. Chromium was detected in water sample IH-6 at a concentration of 104 ug/L. None of the other metals detected in the soil, sediment or water samples displayed high concentrations (3) (See table 2 for concentrations).

METHODOLOGY

All sampling and preservation methods used during this investigation were in accordance with the Water Surveillance Branch Standard Operating Procedures and Quality Assurance Manual, August 29, 1980 (4). Chain-of-custody was maintained from time of collection until samples were relinquished to Laboratory Services Branch (LSB) personnel at the North Treatment Plant in Memphis.

Analyses were conducted by the US-EPA, SAD, Laboratory Services Branch (LSB) and Mead Technology (contract laboratory). The soil, sediment and water samples were analyzed for organic compounds and metals by the (LSB). Water sample IH-6 was analyzed by Mead Technology for organic compounds. The (LSB) analyzed water sample IH-6 for metals and cyanide. Water sample IH-001 was analyzed by the (LSB) for NPDES parameters.

REFERENCES

1. "Report - Hazardous Waste Site Investigation - Memphis, Tennessee - First Phase", US Environmental Protection Agency, Region IV, Enforcement Division; June 1980.
2. Ambient Water Quality Criteria for Polychlorinated Biphenyls United States Environmental Protection Agency, EPA-440/5-80-068, 1980.
3. Hazardous Waste Site Investigation, Frayser Pond Site, Memphis, TN. US Environmental Protection Agency, Region IV, Surveillance and Analysis Division, September 17, 1980.
4. Water Surveillance Branch Standard Operating Procedures and Quality Assurance Manual. (Draft); US Environmental Protection Agency Region IV, Surveillance and Analysis Division, August 29, 1980.

Table 1
Sampling Locations
International Harvester Company
Memphis, Tennessee
March, 1981

| Field Identification | SAD No. | Date | Time | Description | Type Sample |
|----------------------|----------|-------|--------------|--|-------------|
| IH-2 | 81C 0103 | 10/20 | 1045 | Depositional area below the southern most part of landfill. | Sediment |
| IH-3 | 81C 0104 | 10/20 | 1100 | Depositional area below landfill in drainage ditch on western side of site | Sediment |
| IH-4 | 81C 0106 | 10/20 | 1120 | Area below landfill on northern most part of dump. | Sediment |
| IH-5 | 81C 0105 | 10/20 | 1130 1145 | Composite sample from several locations on top of landfill. | Soil |
| IH-6 | 81C 0108 | 10/20 | 1420 | Effluent ditch at culvert and field rd. Approx. 1000 ft. below NPDES discharge pipe. | Water |
| IH-7 | 81C 0107 | 10/20 | 1425 | Effluent ditch at culvert and field rd. Approx. 1000 ft. below NPDES discharge pipe. | Sediment |
| IH-001 | 81C 0150 | 10/21 | 0935 | NPDES outfall in ditch discharging from the plant. | Water |

Table 2
Analytical Results
Soil Samples
International Harvester Company
Memphis, Tennessee
March, 1981


| Parameter | Sample Locations | | | | |
|---|------------------|--------|--------|--------|--------|
| | IH-2 | IH-3 | IH-4 | IH-5 | IH-7 |
| 3,4 - benzofluoranthene and/or 11,12 - benzofluoranthene (ug/kg) | ND | 1500 | ND | ND | ND |
| Barium (mg/kg) | 111 | 199 | 316 | 68 | 221 |
| Cadmium (mg/kg) | ND | ND | ND | ND | 4 |
| Chromium (mg/kg) | 30 | 44 | 141 | 104 | 278 |
| Copper (mg/kg) | 26 | 40 | 74 | 50 | 37 |
| Nickel (mg/kg) | 18 | 31 | 35 | 29 | 33 |
| Lead (mg/kg) | 70 | 112 | 468 | 57 | 210 |
| Strontium (mg/kg) | 37 | 48 | 92 | 46 | 41 |
| Titanium (mg/kg) | 275 | 533 | 320 | 112 | 224 |
| Vanadium (mg/kg) | 19 | 49 | 27 | 17 | 55 |
| Yttrium (mg/kg) | 5 | 11 | 8 | 4 | 14 |
| Zinc (mg/kg) | 83 | 147 | 175 | 54 | 174 |
| Zirconium (mg/kg) | 4 | ND | 5 | ND | ND |
| Mercury (mg/kg) | ND | ND | ND | ND | 0.1 |
| Calcium (mg/kg) | 17,638 | 13,170 | 19,300 | 6,591 | 6,050 |
| Magnesium (mg/kg) | 5,176 | 7,497 | 6,800 | 2,977 | 5,350 |
| Aluminum (mg/kg) | 7,282 | 20,985 | 15,900 | 6,200 | 23,750 |
| Iron (mg/kg) | 21,360 | 30,990 | 41,100 | 29,680 | 31,050 |
| Manganese (mg/kg) | 502 | 786 | 665 | 426 | 875 |
| Sodium (mg/kg) | ND | ND | 545 | 390 | ND |
| PCB, (Aroclor 1248) (ug/kg) | 18,000 | 5,500 | 8,900 | ND | ND |
| PCB, (Aroclor 1254) (ug/kg) | ND | ND | ND | 3,800 | 180 |


Note: ND - Indicates material was analyzed for but not detected at or above the minimum detection limit.

Table 3
 Analytical Results
 Water Sample (IH-6) and NPDES Discharge Sample (IH-001)
 International Harvester Company
 Memphis, Tennessee
 March, 1981

| Parameter | IH-6 | IH-001 |
|------------|--------|--------|
| | (ug/L) | (ug/L) |
| Barium | 41 | 38 |
| Chromium | 104 | 58 |
| Copper | 14 | 11 |
| Molybdenum | 215 | 68 |
| Strontium | 44 | 38 |
| Aluminum | 300 | 154 |
| Calcium | 13 | 13 |
| Magnesium | 5.9 | 6 |
| Iron | 1.0 | 0.6 |
| Sodium | 17.0 | 12 |

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE





ATTACHMENT 1

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RCN, IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 1-26-81

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0103 | | |
|--|--|------------------------|------------------------|
| SOURCE & STATION | IH-2 Depositional area below So. most part of dump. | | |
| DATE/TIME | 10-20-80 @ 1045 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 1000U | |
| 26. 1,3-dichlorobenzene | 34569 | 1000U | |
| 27. 1,4-dichlorobenzene | 34574 | 1000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 1000U | |
| 12. hexachloroethane | 34399 | 1000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 1000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 2000U | |
| 56. nitrobenzene | 34450 | 1000U | |
| 52. hexachlorobutadiene | 39705 | 1000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 1000U | |
| 55. naphthalene | 34445 | 1000K | |
| 43. bis(2-chloroethoxy) methane | 34281 | 1000U | |
| 54. isophorone | 34411 | 2000U | |
| 53. hexachlorocyclopentadiene | 34389 | 1000U | |
| 20. 2-chloronaphthalene | 34584 | 1000U | |
| 77. acenaphthylene | 34203 | 1000U | |
| 1. acenaphthene | 34208 | 1000U | |
| 71. dimethyl phthalate | 34344 | 1000U | |
| 35. 2,4-dinitrotoluene | 34614 | 1000U | |
| 36. 2,6-dinitrotoluene | 34629 | 1000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 1000U | |
| 80. fluorene | 34384 | 1000U | |
| 70. diethyl phthalate | 34339 | 1000U | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 1000U | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 1000U | |
| 9. hexachlorobenzene | 39701 | 1000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 1000U | |
| 81. phenanthrene 4/ | 34464 | | |
| 78. anthracene 4/ | 34223 | 1000K | |
| 68. di-n-butyl phthalate | 39112 | 1000U | |
| 39. fluoranthene | 34379 | 1000K | |
| 84. pyrene | 34472 | 1000K | |
| 67. butyl benzyl phthalate | 34295 | 1000U | |
| 5. benzidine | 39121 | 2000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 1000U | |
| 76. chrysene 2/ | 34323 | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 1000K | |
| 28. 3,3'-dichlorobenzidine | 34634 | 1000U | |
| 69. di-n-octyl phthalate | 34599 | 1000U | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 1000K | |
| 73. 3,4-benzopyrene | 34250 | 1000K | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 1000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 1000U | |
| 79. 1,12-benzoperylene | 34524 | 1000K | |
| 24. 2-chlorophenol | 34589 | 500U | |
| 57. 2-nitrophenol | 34594 | 500U | |
| 65a. phenol (GC/MS) | 34695 | 500K | |
| 34. 2,4-dimethylphenol | 34609 | 500U | |
| 31. 2,4-dichlorophenol | 34604 | 500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 500U | |
| 22. parachlorometa cresol | 34455 | 500U | |
| 59. 2,4-dinitrophenol | 34619 | 4000U | |
| 60. 4,6-dinitro-o-cresol | 34660 | 500U | |
| 64. pentachlorophenol | 39061 | 500U | |
| 58. 4-nitrophenol | 34649 | 1000U | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/- Tentative identification.

2/- and/or azobenzene.

3/- and/or diphenylamine.

5/- Chrysene and/or 1,2-benzanthracene
6/- 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 4/80

RESULTS ON DRY WEIGHT BASIS

THE CHROMATOGRAM INDICATES THE PRESENCE OF
A PETROLEUM TYPE PRODUCT.

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected, The number is the Minimum Detection Limit.

1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E.W. Loy, Jr.

REC'D. 10-20-80 COMPL'D. 1-26-81

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | | 81C 0104 | | |
|--|-------|--|------------------------|------------------------|
| SOURCE & STATION | | IH-3 Area below dump ditch on Western side of site. | | |
| DATE/TIME | | 10-20-80 @ 1100 | | |
| Compounds on NRDC List of Priority Pollutants | | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 1000U | | |
| 26. 1,3-dichlorobenzene | 34569 | 1000U | | |
| 27. 1,4-dichlorobenzene | 34574 | 1000U | | |
| 18. bis(2-chloroethyl) ether | 34276 | 1000U | | |
| 12. hexachloroethane | 34399 | 1000U | | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 1000U | | |
| 63. N-nitrosodi-n-propylamine | 34431 | 2000U | | |
| 56. nitrobenzene | 34450 | 1000U | | |
| 52. hexachlorobutadiene | 39705 | 1000U | | |
| 8. 1,2,4-trichlorobenzene | 34554 | 1000U | | |
| 55. naphthalene | 34445 | 1000K | | |
| 43. bis(2-chloroethoxy) methane | 34281 | 1000U | | |
| 54. isophorone | 34411 | 2000U | | |
| 53. hexachlorocyclopentadiene | 34389 | 1000U | | |
| 20. 2-chloronaphthalene | 34584 | 1000U | | |
| 77. acenaphthylene | 34203 | 1000U | | |
| 1. acenaphthene | 34208 | 1000U | | |
| 71. dimethyl phthalate | 34344 | 1000U | | |
| 35. 2,4-dinitrotoluene | 34614 | 1000U | | |
| 36. 2,6-dinitrotoluene | 34629 | 1000U | | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 1000U | | |
| 80. fluorene | 34384 | 1000U | | |
| 70. diethyl phthalate | 34339 | 1000U | | |
| 37. 1,2-diphenylhydrazine ^{2/} | 34349 | 1000U | | |
| 62. N-nitrosodiphenylamine ^{2/} | 34436 | 1000U | | |
| 9. hexachlorobenzene | 39701 | 1000U | | |
| 41. 4-bromophenyl phenyl ether | 34639 | 1000U | | |
| 81. phenanthrene ^{4/} | 34464 | | | |
| 78. anthracene ^{2/} | 34223 | 1000K | | |
| 68. di-n-butyl phthalate | 39112 | 1000U | | |
| 39. fluoranthene | 34379 | 1000K | | |
| 84. pyrene | 34472 | 1000K | | |
| 67. butyl benzyl phthalate | 34295 | 1000U | | |
| 5. benzidine | 39121 | 2000U | | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 1000U | | |
| 76. chrysene ^{2/} | 34323 | | | |
| 72. 1,2-benzanthracene ^{2/} | 34529 | 1000K | | |
| 28. 3,3'-dichlorobenzidine | 34634 | 1000U | | |
| 69. di-n-octyl phthalate | 34599 | 1000U | | |
| 74. 3,4-benzofluoranthene ^{6/} | 34233 | | | |
| 75. 11,12-benzofluoranthene ^{6/} | 34245 | 1500 | | |
| 73. 3,4-benzopyrene | 34250 | 1000K | | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 1000U | | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 1000U | | |
| 79. 1,12-benzoperylene | 34524 | 1000K | | |
| 24. 2-chlorophenol | 34589 | 2200U | | |
| 57. 2-nitrophenol | 34594 | 2200U | | |
| 65a. phenol (GC/MS) | 34695 | 2200K | | |
| 34. 2,4-dimethylphenol | 34609 | 2200U | | |
| 31. 2,4-dichlorophenol | 34604 | 2200U | | |
| 21. 2,4,6-trichlorophenol | 34624 | 2200U | | |
| 22. parachlorometa cresol | 34655 | 2200U | | |
| 59. 2,4-dinitrophenol | 34619 | 11,000U | | |
| 60. 4,6-dinitro-o-cresol | 34660 | 2200U | | |
| 64. pentachlorophenol | 39061 | 2200U | | |
| 58. 4-nitrophenol | 34649 | 4400U | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine.

5/ - Chrysene and/or 1,2-benzanthracene
6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 4/80

COMPL'D. 1-26-

[illegible]

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN. IV
Athens, GA 4/80

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 2-3-8

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0106 | | |
|--|--|------------------------|------------------------|
| SOURCE & STATION | IR-4 Area below dump on Northern most part of dump. | | |
| DATE/TIME | 10-20-80 @ 1120 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 40000U | |
| 26. 1,3-dichlorobenzene | 34569 | 40000U | |
| 27. 1,4-dichlorobenzene | 34574 | 40000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 40000U | |
| 12. hexachloroethane | 34399 | 40000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 40000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 80000U | |
| 56. nitrobenzene | 34450 | 40000U | |
| 52. hexachlorobutadiene | 39705 | 40000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 40000U | |
| 55. naphthalene | 34445 | 40000U | |
| 43. bis(2-chloroethoxy) methane | 34281 | 40000U | |
| 54. isophorone | 34411 | 80000U | |
| 53. hexachlorocyclopentadiene | 34389 | 40000U | |
| 20. 2-chloronaphthalene | 34584 | 40000U | |
| 77. acenaphthylene | 34203 | 40000U | |
| 1. acenaphthene | 34208 | 40000U | |
| 71. dimethyl phthalate | 34314 | 40000U | |
| 35. 2,4-dinitrotoluene | 34614 | 40000U | |
| 36. 2,6-dinitrotoluene | 34629 | 40000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 40000U | |
| 80. fluorene | 34384 | 40000U | |
| 70. diethyl phthalate | 34339 | 40000U | |
| 37. 1,2-diphenylhydrazine 4/ | 34349 | 40000U | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 40000U | |
| 9. hexachlorobenzene | 39701 | 40000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 40000U | |
| 81. phenanthrene 4/ | 34464 | | |
| 78. anthracene 5/ | 34223 | 40000U | |
| 68. di-n-butyl phthalate | 39112 | 40000U | |
| 39. fluoranthene | 34379 | 40000U | |
| 84. pyrene | 34472 | 40000U | |
| 67. butyl benzyl phthalate | 34295 | 40000U | |
| 5. benzidine | 39121 | 80000U | |
| 66. bis(7-ethylhexyl) phthalate | 39102 | 40000U | |
| 76. chrysene 2/ | 34323 | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 40000U | |
| 28. 3,3'-dichlorobenzidine | 34634 | 40000U | |
| 69. di-n-octyl phthalate | 34599 | 40000U | |
| 74. 3,4-benzofluoranthene 5/ | 34233 | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 40000U | |
| 73. 3,4-benzopyrene | 34250 | 40000U | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 40000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 40000U | |
| 79. 1,12-benzoperylene | 34524 | 40000U | |
| 24. 2-chlorophenol | 34589 | 7500U | |
| 57. 2-nitrophenol | 34594 | 7500U | |
| 65a. phenol (GC/MS) | 34695 | 7500K | |
| 34. 2,4-dimethylphenol | 34609 | 7500U | |
| 31. 2,4-dichlorophenol | 34604 | 7500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 7500U | |
| 22. parachlorometa cresol | 34455 | 7500U | |
| 59. 2,4-dinitrophenol | 34619 | 60000U | |
| 60. 4,6-dinitro-o-cresol | 34660 | 7500U | |
| 64. pentachlorophenol | 35061 | 7500U | |
| 58. 4-nitrophenol | 34649 | 15000U | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or azobenzene.

3/ - and/or diphenylamine.

5/ - Chrysene and/or 1,2-benzanthr.

6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 4/1

RESULTS ON DRY WEIGHT BASIS

THE CHROMATOGRAM INDICATES THE PRESENCE
OF A PETROLEUM TYPE PRODUCT.

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit
1/- Tentative identification.

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RGN
Athens, GA 4

PROJECT International Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr. REC'D. 10-20-80 COMPL'D. 11-1

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0105 | | |
|--|---|------------------------|------------------------|
| SOURCE & STATION | 1H-5 Composite of 4 sites from top of dump. | | |
| DATE/TIME | 10-20-80 @ 1130 | | |
| Compounds on NRDC List of Priority Pollutants | 10-20-80 @ 1145 | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloroethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34539 | 15000U | |
| 26. 1,3-dichlorobenzene | 34569 | 15000U | |
| 27. 1,4-dichlorobenzene | 34574 | 15000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 15000U | |
| 12. hexachloroethane | 34399 | 15000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 15000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 30000U | |
| 56. nitrobenzene | 34450 | 15000U | |
| 52. hexachlorobutadiene | 39705 | 15000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 15000U | |
| 55. naphthalene | 34445 | 15000U | |
| 43. bis(2-chloroethoxy) methane | 34281 | 15000U | |
| 54. isophorone | 34411 | 30000U | |
| 53. hexachlorocyclopentadiene | 34389 | 15000U | |
| 20. 2-chloronaphthalene | 34584 | 15000U | |
| 77. acenaphthylene | 34203 | 15000U | |
| 1. acenaphthene | 34208 | 15000U | |
| 71. dimethyl phthalate | 34344 | 15000U | |
| 35. 2,4-dinitrotoluene | 34614 | 15000U | |
| 36. 2,6-dinitrotoluene | 34629 | 15000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 15000U | |
| 80. fluorene | 34384 | 15000U | |
| 70. diethyl phthalate | 34339 | 15000U | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 15000U | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 15000U | |
| 9. hexachlorobenzene | 39701 | 15000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 15000U | |
| 81. phenanthrene 4/ | 34664 | | |
| 78. anthracene 4/ | 34223 | 15000U | |
| 68. di-n-butyl phthalate | 39112 | 15000U | |
| 39. fluoranthene | 34329 | 15000U | |
| 84. pyrene | 34472 | 15000U | |
| 67. butyl benzyl phthalate | 34295 | 15000U | |
| 5. benzidine | 39121 | 30000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 15000U | |
| 76. chrysene 5/ | 34323 | | |
| 72. 1,2-benzanthracene 5/ | 34529 | 15000U | |
| 28. 3,3'-dichlorobenzidine | 34634 | 15000U | |
| 69. di-n-octyl phthalate | 34599 | 15000U | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 15000U | |
| 73. 3,4-benzopyrene | 34250 | 15000U | |
| 83. indeno (1,2,3-cd) pyrene | 34405 | 15000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 15000U | |
| 79. 1,12-benzoperylene | 34524 | 15000U | |
| 24. 2-chlorophenol | 34589 | 500U | |
| 57. 2-nitrophenol | 34594 | 500U | |
| 65a. phenol (GC/MS) | 34695 | 500U | |
| 34. 2,4-dichlorophenol | 34609 | 500U | |
| 31. 2,4-dichlorophenol | 34604 | 500U | |
| 21. 2,4,6-trichlorophenol | 34624 | 500U | |
| 22. parachlorometa cresol | 34455 | 500U | |
| 59. 2,4-dinitrophenol | 34619 | 500U | |
| 60. 4,6-dinitro-p-cresol | 34660 | 500U | |
| 64. pentachlorophenol | 39061 | 500U | |
| 58. 4-nitrophenol | 34649 | 1000U | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

2/ - Tentative identification.

5/ - Chrysene and/or 1,2-benza.

6/ - 3,4-benzofluoranthene and
11,12-benzofluoranthene.

EPA, SAD, RCN. IV
Athens, GA 4/81

RESULTS ON DRY WEIGHT BASIS

No other organic compounds detected with an estimated minimum detection limit of .15,000 ug/

1/- Tentative identification:

SEDIMENT
DATA REPORTING SHEET
EXTRACTABLE ORGANIC ANALYSIS

EPA, SAD, RCN, I:
Athens, GA 4/30

PROJECT Internation Harvester
Memphis, TN

CHEMIST E. W. Loy, Jr.

REC'D. 10-20-80 COMPL'D. 2-17-

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 81C 0107 | | |
|--|---|------------------------|------------------------|
| SOURCE & STATION | IH-7 Eff. ditch at Culvert at field Rd. below pipe | | |
| DATE/TIME | 10-20-80 @ 1426 | | |
| Compounds on NRDC List of Priority Pollutants | Concentration ug/kg | Concentration ug/kg | Concentration ug/kg |
| 17. bis(chloromethyl) ether | 34271 | NA | NA |
| 61. N-nitrosodimethylamine | 34441 | NA | NA |
| 25. 1,2-dichlorobenzene | 34339 | 5000U | |
| 26. 1,3-dichlorobenzene | 34369 | 5000U | |
| 27. 1,4-dichlorobenzene | 34374 | 5000U | |
| 18. bis(2-chloroethyl) ether | 34276 | 5000U | |
| 12. hexachloroethane | 34399 | 5000U | |
| 42. bis(2-chloroisopropyl) ether | 34286 | 5000U | |
| 63. N-nitrosodi-n-propylamine | 34431 | 10000U | |
| 56. nitrobenzene | 34450 | 5000U | |
| 52. hexachlorobutadiene | 39705 | 5000U | |
| 8. 1,2,4-trichlorobenzene | 34554 | 5000U | |
| 55. naphthalene | 34445 | 5000U | |
| 43. bis(2-chloroethoxy) methane | 34281 | 5000U | |
| 54. isophorone | 34411 | 10000U | |
| 53. hexachlorocyclopentadiene | 34289 | 5000U | |
| 20. 2-chloronaphthalene | 34584 | 5000U | |
| 77. acenaphthylene | 34203 | 5000U | |
| 1. acenaphthene | 34205 | 5000U | |
| 71. dimethyl phthalate | 34344 | 5000U | |
| 35. 2,4-dinitrotoluene | 34614 | 5000U | |
| 36. 2,6-dinitrotoluene | 34629 | 5000U | |
| 40. 4-chlorophenyl phenyl ether | 34644 | 5000U | |
| 80. fluorene | 34384 | 5000U | |
| 70. diethyl phthalate | 34339 | 5000U | |
| 37. 1,2-diphenylhydrazine 2/ | 34349 | 5000U | |
| 62. N-nitrosodiphenylamine 3/ | 34436 | 5000U | |
| 9. hexachlorobenzene | 39701 | 5000U | |
| 41. 4-bromophenyl phenyl ether | 34639 | 5000U | |
| 81. phenanthrene 4/ | 34464 | | |
| 78. anthracene 4/ | 34223 | 5000U | |
| 68. di-n-butyl phthalate | 39112 | 5000U | |
| 39. fluoranthene | 34379 | 5000U | |
| 84. pyrene | 34472 | 5000U | |
| 67. butyl benzyl phthalate | 34295 | 5000U | |
| 5. benzidine | 39121 | 10000U | |
| 66. bis(2-ethylhexyl) phthalate | 39102 | 5000U | |
| 76. chrysene 2/ | 34323 | | |
| 72. 1,2-benzanthracene 2/ | 34529 | 5000U | |
| 28. 3,3'-dichlorobenzidine | 34634 | 5000U | |
| 69. di-n-octyl phthalate | 34599 | 5000U | |
| 74. 3,4-benzofluoranthene 6/ | 34233 | | |
| 75. 11,12-benzofluoranthene 6/ | 34245 | 5000U | |
| 73. 3,4-benzopyrene | 34250 | 5000U | |
| 83. indeno (1,2,3-cd) pyrene | 34406 | 5000U | |
| 82. 1,2,5,6-dibenzanthracene | 34559 | 5000U | |
| 79. 1,12-benzoperylene | 34574 | 5000U | |
| 24. 2-chlorophenol | 34589 | 2100U | |
| 57. 2-nitrophenol | 34594 | 2100U | |
| 65a. phenol (GC/MS) | 34695 | 2100U | |
| 34. 2,4-dimethylphenol | 34609 | 2100U | |
| 31. 2,4-dichlorophenol | 34604 | 2100U | |
| 21. 2,4,6-trichlorophenol | 34674 | 2100U | |
| 22. parachlorometa cresol | 34455 | 2100U | |
| 59. 2,4-dinitrophenol | 34619 | 17000U | |
| 60. 4,6-dinitro-o-cresol | 34660 | 2100U | |
| 64. pentachlorophenol | 39061 | 2100U | |
| 58. 4-nitrophenol | 34649 | 4200U | |

A - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.

1/ - Tentative identification.

2/ - and/or acobenzene.

3/ - and/or diphenylamine.

4/ - Phenanthrene and/or anthracene.

5/ - Chrysene and/or 1,2-benzanth

6/ - 3,4-benzofluoranthene and/or
11,12-benzofluoranthene.

(OVER)

EPA, SAD, RCN. IV
Athens, GA 47

RESULTS ON DRY WEIGHT BASIS

THE CHROMATOGRAM INDICATES THE PRESENCE OF
A PETROLEUM TYPE PRODUCT.

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
1/- Tentative identification.

ATHENS, GA
4/80

BASED ON WET WEIGHT BASIS

J - Estimated value.
K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
U - Material was analyzed for but not detected. The number is the Minimum Detection Limit.
NA - Not analyzed.
1/- Tentative identification.
2/- On NRDC List of Priority Pollutants.

ATHENS, GA
4/80

REC'D. 10-20-80 COMPLET'D. 12-10

| SAD NO. | 81C 0106 | 81C 0107 |
|---|--------------------------------|---------------------------------|
| SOURCE & STATION | IH-4 Below dump northern part. | IH-7 Effluent ditch at Culvert. |
| DATE/TIME | 10-20-80 1120-1145 | 10-20-80 1125-1145 |
| Compound | ug/kg | ug/kg |
| dichlorodifluoromethane ^{2/} | 34334 | 5U |
| methyl chloride ^{2/} | 34421 | 5U |
| methyl bromide ^{2/} | 34416 | 5U |
| vinyl chloride ^{2/} | 34495 | 5U |
| chloroethane ^{2/} | 34314 | 5U |
| methylene chloride ^{2/} | 34426 | 5U |
| trichlorofluoromethane ^{2/} | 34491 | 5U |
| 1,1-dichloroethylene ^{2/} | 34504 | 5U |
| 1,1-dichloroethane ^{2/} | 34499 | 5U |
| 1,2-trans-dichloroethylene ^{2/} | 34549 | 5U |
| chloroform ^{2/} | 34318 | 5U |
| 1,2-dichloroethane ^{2/} | 34534 | 5U |
| 1,1,1-trichloroethane ^{2/} | 34509 | 5U |
| carbon tetrachloride ^{2/} | 34299 | 5U |
| dichlorobromomethane ^{2/} | 34330 | 5U |
| 1,2-dichloropropane ^{2/} | 34544 | 5U |
| 1,3-dichloropropylene ^{2/} | 34564 | 5U |
| trichloroethylene ^{2/} | 34487 | 5U |
| benzene ^{2/} | 34237 | 5U |
| chlorodibromomethane ^{2/} | 34309 | 5U |
| 1,1,2-trichloroethane ^{2/} | 34514 | 5U |
| 2-chloroethyl vinyl ether (mixed) ^{2/} | 34579 | 5U |
| bromoform ^{2/} | 34290 | 5U |
| 1,1,2,2-tetrachloroethane ^{2/} | 34519 | 5U |
| tetrachloroethylene ^{2/} | 34478 | 5U |
| toluene ^{2/} | 34483 | 5U |
| chlorobenzene ^{2/} | 34304 | 5U |
| ethylbenzene ^{2/} | 34374 | 5U |
| acrolein ^{2/} | 34213 | 100U |
| acrylonitrile ^{2/} | 34218 | 100U |

- J - Estimated value.
- K - Actual value is known to be less than value given.
- L - Actual value is known to be greater than value given.
- U - Material was analyzed for but not detected. The number is the Minimum Detection Limit
- NA - Not analyzed.
- 1/ - Tentative identification.
- 2/ - On NRDC List of Priority Pollutants.

DATA REPORTING SHEET
SEDIMENT

EPA-SAD-LSB-4-10-5

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-20-80 COMPI'D 12-17-80
Memphis, TN

PROJECT NUMBER 81-6 RESULTS ON DRY WEIGHT BASIS

| SAD NO. | | 81C 0103 | 81C 0104 | 81C 0105 | 81C 0106 |
|------------------|-------|---|---|---|--|
| SOURCE & STATION | | IH-2 Deposition at area below SO most part of dump. | IH-3 Area below dump ditch on western side of site. | IH-5 Composite of 4 sites from top of dump. | IH-4 Area below dump on north most part of dump. |
| DATE/TIME | | 10-20-80 @ 1045 | 10-20-80 @ 1100 | 10-20-80 @ 1130/1145 | 10-20-80 @ 1120-1 |
| ELEMENT (mg/kg) | | | | | |
| Silver* | 01078 | 2K | 3K | 3K | 4K |
| Arsenic* | 01003 | 9K | 14K | 14K | 16K |
| Boron | 01023 | | | | |
| Barium | 01008 | 111 | 199 | 68 | 316 |
| Beryllium* | 01013 | 2K | 3K | 3K | 4K |
| Cadmium* | 01028 | 2K | 3K | 3K | 4K |
| Cobalt | 01038 | 4K | 6K | 6K | 7K |
| Chromium* | 01029 | 30 | 44 | 104 | 141 |
| Copper* | 01043 | 26 | 40 | 50 | 74 |
| Molybdenum | 01063 | 4K | 6K | 6K | 7K |
| Nickel* | 01068 | 18 | 31 | 29 | 35 |
| Lead* | 01052 | 70 | 112 | 57 | 468 |
| Antimony* | 01098 | 5K | 8K | 8K | 9K |
| Selenium* | 01148 | 8K | 12K | 12K | 14K |
| Tin | 01103 | 12K | 18K | 18K | 21K |
| Strontium | 01083 | 37 | 48 | 46 | 92 |
| Tellurium | 45513 | 8K | 12K | 12K | 14K |
| Titanium | 01153 | 275 | 533 | 112 | 320 |
| Thallium* | 34480 | 20K | 30K | 30K | 35K |
| Vanadium | 01088 | 19 | 49 | 17 | 27 |
| Yttrium | 45514 | 5 | 11 | 4 | 8 |
| Zinc* | 01093 | 83 | 147 | 54 | 175 |
| Zirconium | 01163 | 4 | 3K | 3K | 5 |
| Mercury* | 71921 | 0.05K | 0.05K | 0.05K | 0.05K |
| Calcium | 00917 | 17638 | 13170 | 6591 | 19300 |
| Magnesium | 00924 | 5176 | 7497 | 2977 | 6800 |

- CONTINUED ON BACK -

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

EPA-SAD-LSB-4-10-

CHEMIST B. McDaniel REC'D 10-20-80 COMPL'D 12-17-80

[illegible]

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

EPA-SAD-LSB-4-10-3
8

COMPL'D 12-17-80

RESULTS ON DRY WEIGHT BASIS

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

DATA REPORTING SHEET
SEDIMENT

EPA-SAD-LGR-4-10

PROJECT International Harvester
Memphis, TN

CHEMIST S. McDaniel

REC'D 10-20-80

COMPL'D 12-17-

PROJECT NUMBER 81-6

RESULTS ON DRY WEIGHT BASIS

| SAD NO. | 810 | 0107 | | | |
|------------------|-------|--|-----------|--|--|
| SOURCE & STATION | | IN-7 EFF. ditch at Culvert at field Rd. below pipe. | | | |
| DATE/TIME | | 10-20-80 | 1425-1145 | | |
| ELEMENT (ng/kg) | | | | | |
| Silver* | 01078 | 3K | | | |
| Arsenic* | 01003 | 14K | | | |
| Boron | 01023 | | | | |
| Barium | 01008 | 221 | | | |
| Beryllium* | 01013 | 4K | | | |
| Cadmium* | 01028 | 4 | | | |
| Cobalt | 01038 | 8K | | | |
| Chromium* | 01029 | 278 | | | |
| Copper* | 01043 | 37 | | | |
| Molybdenum | 01063 | 8K | | | |
| Nickel* | 01068 | 33 | | | |
| Lead* | 01052 | 210 | | | |
| Antimony* | 01098 | 10K | | | |
| Selenium* | 01148 | 16K | | | |
| Tin | 01103 | 24K | | | |
| Strontium | 01083 | 41 | | | |
| Tellurium | 45513 | 16K | | | |
| Titanium | 01153 | 224 | | | |
| Thallium* | 34480 | 40K | | | |
| Vanadium | 01088 | 55 | | | |
| Yttrium | 45514 | 14 | | | |
| Zinc* | 01093 | 174 | | | |
| Zirconium | 01163 | 4K | | | |
| Mercury* | 71921 | 0.1 | | | |
| Calcium | 00917 | 6050 | | | |
| Magnesium | 00924 | 5350 | | | |

- CONTINUED ON BACK -

K - Actual value is known to be less than value given.

L - Actual value is known to be greater than value given.

* - Priority Pollutant.

WATER
DATA REPORTING SHEET

SAD NO. RIC 0108 CONTRACT LAB NO. D0212 CONTRACT LAB Lead Technology
 PROJECT International Harvester SOURCE & STATION M-6 Eff. Ditch at Culvert at
Memphis, TN Field Road below pipe.
 DATE/TIME SAMPLED 10-20-80 @ 1420 SAMPLE RECEIVED 10-20-80 DATA RECEIVED 12-17-80

| VOLATILE COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | | ug/L | TENTATIVELY-IDENTIFIED COMPOUNDS | ug/L |
|---|--|-------|-------|--|------|
| 2V | Acrolein | 34210 | 100U | The chromatogram indicates the presence of a petroleum-type product. | |
| 3V | Acrylonitrile | 34215 | 100U | | |
| 4V | Benzene | 34030 | 10U | | |
| 6V | Carbon Tetrachloride | 32102 | 10U | | |
| 7V | Chlorobenzene | 34301 | 10U | | |
| 10V | 1,2-Dichloroethane | 32103 | 10U | | |
| 11V | 1,1,1-Trichloroethane | 34506 | 10U | | |
| 13V | 1,1-Dichloroethane | 34496 | 10U | | |
| 14V | 1,1,2-Trichloroethane | 34511 | 10U | | |
| 15V | 1,1,2,2-Tetrachloroethane | 34516 | 10U | | |
| 16V | Chloroethane | 34311 | 10U | | |
| 19V | 2-Chloroethylvinyl Ether | 34576 | 10U | | |
| 23V | Chloroform | 32106 | 10U | | |
| 29V | 1,1-Dichloroethylene | 34501 | 10U | | |
| 30V | 1,2-Trans-Dichloroethylene | 34546 | 10U | | |
| 32V | 1,2-Dichloropropane | 34541 | 10U | | |
| 33V | 1,3-Dichloropropylene | 34551 | 10U | | |
| 38V | Ethylbenzene | 34371 | 10U | | |
| 44V | Methylene Chloride | 34423 | 10U | | |
| 45V | Methyl Chloride | 34418 | 10U | | |
| 46V | Methyl Bromide | 34413 | 10U | | |
| 47V | Bromoform | 32104 | 10U | | |
| 48V | Dichlorobromomethane | 32101 | 10U | | |
| 49V | Trichlorofluoromethane | 34483 | 10U | | |
| 50V | Dichlorodifluoromethane | 34668 | 10U | | |
| 51V | Chlorodibromomethane | 34305 | 10U | | |
| 85V | Tetrachloroethylene | 34475 | 10U | | |
| 86V | Toluene | 34010 | 10U | | |
| 87V | Trichloroethylene | 39150 | 10U | | |
| 88V | Vinyl Chloride | 39175 | 10U | | |
| PESTICIDES/PCB'S ON NRDC LIST OF PRIORITY POLLUTANTS | | | ug/L | | |
| 89P | Aldrin | 39330 | 0.10U | | |
| 90P | Dieldrin | 39380 | 0.10U | | |
| 91P | Chlordane (Tech. Mixture & Metabolites) | 39350 | 0.10U | | |
| 92P | 4,4'-DDT (p,p'-DDT) | 39300 | 0.10U | | |
| 93P | 4,4'-DDE (p,p'-DDE) | 39320 | 0.10U | | |
| 94P | 4,4'-DDD (p,p'-TDE) | 39310 | 0.10U | | |
| 95P | a-Endosulfan-Alpha | 34361 | 0.10U | | |
| 96P | b-Endosulfan-Beta | 34356 | 0.10U | | |
| 97P | Endosulfan Sulfate | 34351 | 0.10U | | |
| 98P | Endrin | 39390 | 0.10U | | |
| 99P | Endrin Aldehyde | 34366 | 0.10U | | |
| 100P | Heptachlor | 39410 | 0.10U | | |
| 101P | Heptachlor Epoxide | 39420 | 0.10U | | |
| 102P | a-BHC-Alpha | 39337 | 0.10U | | |
| 103P | b-BHC-Beta | 39338 | 0.10U | | |
| 104P | gamma-BHC-(Lindane)-Gamma | 39340 | 0.10U | | |
| 105P | delta-BHC-Delta | 34259 | 0.10U | | |
| 106P | PCB-1242 (Aroclor 1242) | 39496 | 0.10U | | |
| 107P | PCB-1254 (Aroclor 1254) | 39504 | 0.10U | | |
| 108P | PCB-1221 (Aroclor 1221) | 39488 | 0.10U | | |
| 109P | PCB-1222 (Aroclor 1222) | 39492 | 0.10U | | |
| 110P | PCB-1248 (Aroclor 1248) | 39500 | 0.10U | | |
| 111P | PCB-1260 (Aroclor 1260) | 39508 | 0.15U | | |
| 112P | PCB-1016 (Aroclor 1016) | 34671 | 0.10U | | |
| 113P | Toxaphene | 39400 | 0.40U | | |
| 129P | 2,3,7,8-Tetrachlorodibenzo-p-dioxin (TCDD) | 34675 | NA | | |

NA - Not analyzed.

J - Estimated value.

K - Actual value is known to be less than value given.

5/22/80

WATER
DATA REPORTING SHEET

SAD NO. 81C0108 CONTRACT LAB NO. D0212 CONTRACT LAB Mead Technology
 PROJECT International Harvester SOURCE & STATION IH-6 EFF. Ditch at Culvert at
 Memphis, TN Field Road below pipe.
 DATE/TIME SAMPLED 10-20-80 @ 1420 SAMPLE RECEIVED 10-20-80 DATA RECEIVED 12-17-80

| BASE/NEUTRAL COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | ug/L |
|---|-------|------|
| 1B Acenaphthene | 34205 | 10U |
| 5B Benzidine | 39120 | 10U |
| 8B 1,2,4-Trichlorobenzene | 34551 | 10U |
| 9B Hexachlorobenzene | 39700 | 10U |
| 12B Hexachloroethane | 34396 | 10U |
| 17B Bis(Chloromethyl) Ether | 34268 | NA |
| 18B Bis(2-Chloroethyl) Ether | 34273 | 10U |
| 20B 2-Chloronaphthalene | 34531 | 10U |
| 25B 1,2-Dichlorobenzene | 34536 | 10U |
| 26B 1,3-Dichlorobenzene | 34566 | 10U |
| 27B 1,4-Dichlorobenzene | 34571 | 10U |
| 28B 3,3'-Dichlorobenzidine | 34631 | 10U |
| 35B 2,4-Dinitrotoluene | 34611 | 10U |
| 36B 2,6-Dinitrotoluene | 34626 | 10U |
| 37B 1,2-Diphenylhydrazine | 34346 | 10U |
| 39B Fluoranthene | 34376 | 10U |
| 40B 4-Chlorophenyl Phenyl Ether | 34641 | 10U |
| 41B 4-Bromophenyl Phenyl Ether | 34636 | 10U |
| 42B Bis(2-Chloroisopropyl) Ether | 34283 | 10U |
| 43B Bis(2-Chloroethoxy) Methane | 34278 | 10U |
| 52B Hexachlorobutadiene | 39702 | 10U |
| 53B Hexachlorocyclopentadiene | 34386 | 10U |
| 54B Isophorone | 34408 | 10U |
| 55B Naphthalene | 34696 | 10U |
| 56B Nitrobenzene | 34447 | 10U |
| 61B N-Nitrosodimethylamine | 34438 | NA |
| 62B N-Nitrosodiphenylamine | 34433 | 10U |
| 63B N-Nitrosodi-N-Propylamine | 34428 | 10U |
| 66B Bis(2-Ethylhexyl) Phthalate | 39100 | 50U |
| 67B Butyl Benzyl Phthalate | 34292 | 10U |
| 68B Di-N-Butylphthalate | 39110 | 10U |
| 69B Di-N-Octylphthalate | 34596 | 10U |
| 70B Diethylphthalate | 34336 | 10U |
| 71B Dimethylphthalate | 34341 | 10U |
| 72B Benzo (A) Anthracene | 34526 | 10U |
| 73B Benzo(A) Pyrene | 34247 | 10U |
| 74B 3,4-Benzofluoranthene | 34230 | 10U |
| 75B Benzo(K) Fluoranthene | 34242 | 10U |
| 76B Chrysene | 34320 | 10U |
| 77B Acenaphthylene | 34200 | 10U |
| 78B Anthracene | 34220 | 10U |
| 79B Benzo(GHI) Perylene | 34521 | 25U |
| 80B Fluorene | 34381 | 10U |
| 81B Phenanthrene | 34461 | 10U |
| 82B Dibenzo(A, H) Anthracene | 34556 | 25U |
| 83B Indeno (1,2,3-CD) Pyrene | 34403 | 25U |
| 84B Pyrene | 34469 | 25U |
| ACID COMPOUNDS ON NRDC LIST OF PRIORITY POLLUTANTS | | ug/L |
| 21A 2,4,6-Trichlorophenol | 34621 | 25U |
| 22A p-Chloro-m-Cresol | 34452 | 25U |
| 24A 2-Chlorophenol | 34586 | 25U |
| 31A 2,4-Dichlorophenol | 34601 | 25U |
| 34A 2,4-Dimethylphenol | 34606 | 25U |
| 57A 2-Nitrophenol | 34591 | 25U |
| 58A 4-Nitrophenol | 34646 | 25U |
| 59A 2,4-Dinitrophenol | 34616 | 250U |
| 60A 4,6-Dinitro-o-Cresol | 34657 | 250U |
| 64A Pentachlorophenol | 39032 | 25U |
| 65A Phenol (GC/MS) | 34694 | 25U |

K - Actual value is known to be less than value given.

U - Material was analyzed for but not detected. The number is the minimum detection limit.

1/ - And/or Azobenzene.

2/ - And/or Diphenylamine.

3/ - 813 Phenanthrene and/or 783 Anthracene.

DATA REPORTING SHEET
WATER

EPA-SAD-15B 4-10-80

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-20-80 COMPL'D 11-20-80
Memphis, TN
 PROJECT No. 81-6

| SAD NO. | 81- C | 0103 | | | |
|------------------|-------|--|--|--|--|
| SOURCE & STATION | | TH-6 EFF Ditch at Culvert and Field Rd. Below Pipe. | | | |
| DATE/TIME | | 10-20-80 @ 1420-1145 | | | |
| ELEMENT (ug/L) | | | | | |
| Silver * | 01077 | 10K | | | |
| Arsenic * | 01002 | 45K | | | |
| Boron | 01022 | --- | | | |
| Barium | 01007 | 41 | | | |
| Beryllium * | 01012 | 10K | | | |
| Cadmium * | 01027 | 10K | | | |
| Cobalt | 01037 | 20K | | | |
| Chromium * | 01034 | 104 | | | |
| Copper * | 01042 | 14 | | | |
| Molybdenum | 01062 | 215 | | | |
| Nickel * | 01067 | 35K | | | |
| Lead * | 01051 | 40K | | | |
| Antimony * | 01097 | 25K | | | |
| Selenium * | 01147 | 40K | | | |
| Tin | 01102 | 60K | | | |
| Strontium | 01082 | 44 | | | |
| Tellurium | 01064 | 40K | | | |
| Titanium | 01152 | 10K | | | |
| Thallium * | 01059 | 100K | | | |
| Vanadium | 01087 | 10K | | | |
| Yttrium | 01203 | 10K | | | |
| Zinc * | 01092 | --- | | | |
| Zirconium | 01162 | 10K | | | |
| Mercury * | 71900 | 0.2K | | | |
| Aluminum | 01105 | 300 | | | |
| Manganese | 01055 | 50K | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

K - Actual value is known to be less than value given.
 L - Actual value is known to be greater than value given.
 * - Priority Pollutant.

(Continued on Back)

22A-349-156 4-29-64

[illegible]

* - Priority Pollutant.

DATA REPORTING SHEET
WATER

EPA-SAD-153 4-10-80

PROJECT International Harvester CHEMIST B. McDaniel REC'D 10-21-80 COMPL'D 11-20-80
Memphis, TN
 PROJECT No. 81-6

| | | | | |
|------------------|-------|---|--|--|
| SAD NO. | 81C | 0150 | | |
| SOURCE & STATION | | IH-001 NPDES Outfall in ditch downstream. | | |
| DATE/TIME | | 10-21-80 @ 0935 | | |
| ELEMENT (ug/L) | | | | |
| Silver * | 01077 | 10K | | |
| Arsenic * | 01002 | 45K | | |
| Boron | 01022 | --- | | |
| Barium | 01007 | 38 | | |
| Beryllium * | 01012 | 10K | | |
| Cadmium * | 01027 | 10K | | |
| Cobalt | 01037 | 20K | | |
| Chromium * | 01034 | 58 | | |
| Copper * | 01042 | 11 | | |
| Molybdenum | 01062 | 68 | | |
| Nickel * | 01067 | 35K | | |
| Lead * | 01051 | 40K | | |
| Antimony * | 01097 | 25K | | |
| Selenium * | 01147 | 40K | | |
| Tin | 01102 | 60K | | |
| Strontium | 01082 | 38 | | |
| Tellurium | 01064 | 40K | | |
| Titanium | 01152 | 10K | | |
| Thallium * | 01059 | 100K | | |
| Vanadium | 01037 | 10K | | |
| Yttrium | 01203 | 10K | | |
| Zinc * | 01092 | --- | | |
| Zirconium | 01162 | 10K | | |
| Mercury * | 71900 | 0.2K | | |
| Aluminum | 01105 | 154 | | |
| Manganese | 01055 | 50K | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

K - Actual value is known to be less than value given.
 L - Actual value is known to be greater than value given.
 * - Priority Pollutant.

(Continued on Back)

000-500-000 - 20-

[illegible]

K - Actual value is known to be less than value given.
L - Actual value is known to be greater than value given.
* - Priority Pollutant.

SAMPLE RECEIVED DATE 10/20/80 1530

12.1.15/55

ANALYSES TO BE RUN

| DATE | TIME | LOCATION | DEPTH | WIND | WAVE | TEMP | DEG | DEG |
|----------|------|---------------------------|-------|------|------|------|-----|-----|
| 10/20/80 | 1420 | IM-9, EFF DITCH & CULVERT | | | | | | |
| 10/20/80 | 1145 | & FIELD RD BELOW PIPE | | | | | | |

STATE: TN

Siri

ATTACHMENT 2

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|---|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Murphy, TN</u> CONTACT _____ | SAMPLING STATION NO. <u>IH-001</u> SAMPLING LOCATION <u>NPDES outfall</u> <u>exl in ditch downstream</u> <u>from sanitary toilet contact</u> <u>containing & possible contact cooling</u> |
|---|---|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☒ IND. ☐ INF. ☒ EFF. ☐ _____ ☒ 24 HR. COMP. AT 30 MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☒ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☒ TYPE 1510 1680 # 163022 (330)
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE ¹² |
|--------------------------------|----------------------|-----------------|---------------------------|
| DATE | <u>10/21/80</u> | <u>10/21/80</u> | 0 BACTERIAL |
| TIME | <u>1000 1045</u> | <u>0935</u> | 1 BOD, COD, TOC |
| FLOW (cfs) ¹¹ | <u>1.44</u> | | 2 CYANIDE |
| TEMPERATURE °C | | <u>7.5</u> | 3 METALS |
| pH | | <u>7.3</u> | 4 N, P |
| TOT. Cl ₂ RES, mg/l | | | 5 ORG. O&G, PEST |
| | | | 6 PHENOLS |
| | | | 7 SOLIDS |
| | | | 8 |
| SAMPLE CODE | <u>3c below</u> | | 9 |
| SAMPLED BY (Sig) | <u>BSH, L.H.H.</u> | | A |
| SEALED BY (Sig) | <u>BSH</u> | | B |
| DATE AND TIME | <u>10/21/80 7230</u> | | P PRESERVED |

¹¹ Use Avg. Flow for Composites and Inst. Flow for Grabs ¹² Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>B. Green</u> | <u>10/21/80</u> | <u>10:30</u> | <u>1</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

pH 1 - 1 pt glass metals
 PH Bufferd
 4 4.2
 7 6.8
 10 9.9
 1,440,000 gal / 24 hr period
 PH meters upfield @ 7.0 p.m. on 4
 & on 18

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION **IV**

ATHENS, GEORGIA

| | |
|--|---|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Memphis, TN</u> CONTACT <u>Gene Cartledge</u> | SAMPLING STATION NO. <u>I H-2</u> SAMPLING LOCATION <u>area below southern end of dump</u> |
|--|---|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT SAMPLE H.R. COMP. AT MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ EQUIP.
 COMPUTED FROM

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | DATE | TIME | FLOW () LL | TEMPERATURE °C | PH | TOT. Cl ₂ RES. mg/l | SAMPLE CODE 12 |
|---------|-----------|-----------------|-------------|-------------|----------------|----|--------------------------------|------------------|
| | | <u>10/20/70</u> | <u>1045</u> | | | | | BACTERIAL 0 |
| | | | | | | | | BOD, COD, TOC 1 |
| | | | | | | | | CYANIDE 2 |
| | | | | | | | | METALS 3 |
| | | | | | | | | N, P 4 |
| | | | | | | | | ORG, ORG, PEST 5 |
| | | | | | | | | PHENOLS 6 |
| | | | | | | | | SOLIDS 7 |
| | | | | | | | | 8 |
| | | | | | | | | 9 |
| | | | | | | | | A |
| | | | | | | | | B |
| | | | | | | | | P |

SAMPLE CODE See below
 SAMPLED BY (Sig) EST U/PLH
 SEALED BY (Sig) EST
 DATE AND TIME 10/20/70 1200

LL Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Del. Return</u> | <u>10/20/70</u> | <u>15:20</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1-1qt glass - organics ent R
 1-1qt glass - metals not R
 plastic - dup. metals sample collected for I H; see separate sheet
Sheet

**U.S. ENVIRONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION**

REGION IV

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>T-11-3</u> |
| ADDRESS <u>11 samples TN</u> | SAMPLING LOCATION <u>Depositional area</u> |
| CONTACT <u></u> | <u>below dump - 4 in. hole on</u> |
| | <u>western side of site</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ HR. COMP. AT MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ EQUIP

COMPUTED FROM

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE ¹² |
|--------------------------------|-----------|----------------------|---------------------------|
| DATE | <u>1</u> | <u>0104</u> | BACTERIAL 0 |
| TIME | <u>1</u> | <u>10/20/80</u> | BOD, COD, TOC 1 |
| FLOW () L | | <u>1100</u> | CYANIDE 2 |
| TEMPERATURE °C | | | METALS 3 |
| pH | | | N, P 4 |
| TOT. Cl ₂ RES, mg/l | | | ORG, OBG, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| | | | |
| SAMPLE CODE | | <u>sediment</u> | |
| SAMPLED BY (Sig) | | <u>ALL G.A. TH</u> | |
| SEALED BY (Sig) | | <u>1/21</u> | |
| DATE AND TIME | | <u>10/20/80 1200</u> | |
| | | | PRESERVED P |

¹¹ Use Avg. Flow for Composites and Inst. Flow for Grabs ¹² Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Bob G. G. G.</u> | <u>10/20/80</u> | <u>15:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1 - 1 qt glass - organics ^{544 R} _{100 R}

1 - 1 pt plastic - metals & (metals dupl. collected for TH)

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|---|---|
| DISCHARGER <u>International Harvester</u> ADDRESS <u>Memphis, TN</u> CONTACT <u>Gene Cartmell</u> | SAMPLING STATION NO. <u>IH-4</u> SAMPLING LOCATION <u>Deposition area below dump on northwestern part of dump (South of NPDES ditch), sample area (close to NPDES ditch)</u> |
|---|---|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE 12 |
|--------------------------------|----------------------|--------------|------------------|
| DATE | <u>10/20/80</u> | | BACTERIAL 0 |
| TIME | <u>1120</u> | | BOD, COD, TOC 1 |
| FLOW () L | | | CYANIDE 2 |
| TEMPERATURE °C | | | METALS 3 |
| pH | | | N, P 4 |
| TOT. Cl ₂ RES. mg/l | | | ORG, OBG, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| SAMPLE CODE | <u>Sediment</u> | | 8 |
| SAMPLED BY (Sig) | <u>Gene Cartmell</u> | | 9 |
| SEALED BY (Sig) | <u>Gene</u> | | A |
| DATE AND TIME | <u>10/20/80 1200</u> | | B |
| | | | P |

1 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Gene Cartmell</u> | <u>10/20/80</u> | <u>15:30</u> | <u>7-</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1 - 1 qt glass - organics ^{ext. P} _{VOF P}
 1 - 1 qt plastic - metals _P (dept metals collected for IH)

U.S. ENVIRONMENTAL PROTECTION AGENCY SURVEILLANCE AND ANALYSIS DIVISION

REGION IV

ATHENS, GEORGIA

| | |
|--|--|
| DISCHARGER <u>International Flavors</u> ADDRESS <u>Memphis TN</u> CONTACT <u>Gene Cuthrell</u> | SAMPLING STATION NO. <u>IH-5</u> SAMPLING LOCATION <u>Composite of</u> <u>Several (4) locations on site</u> <u>from top of dump</u> |
|--|--|

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ _____ HR. COMP AT _____ MIN. INTERVALS ☐ FLOW PRO.
 SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____
 FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP _____
 COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE ¹² |
|--------------------------------|------------------------|--------------|---------------------------|
| DATE | <u>10/20/80</u> | | BACTERIAL 0 |
| TIME | <u>1130-1145</u> | | BOD, COD, TOC 1 |
| FLOW () L | | | CYANIDE 2 |
| TEMPERATURE °C | | | METALS 3 |
| pH | | | N, P 4 |
| TOT. Cl ₂ RES. mg/l | | | ORG, O&G, PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| | | | 8 |
| SAMPLE CODE | <u>See below</u> | | 9 |
| SAMPLED BY (Sig) | <u>SLH, G. G. Hill</u> | | A |
| SEALED BY (Sig) | <u>SLH</u> | | B |
| DATE AND TIME | <u>11/2/80 1200</u> | | PRESERVED P |

¹ Use Avg. Flow for Composites and Inst. Flow for Grabs ¹² Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO CONT. | NO CART. | RECEIPT NO. |
|--|----------------|--------------|----------|----------|-------------|
| <u>Bob G. Hill</u> | <u>11/2/80</u> | <u>15:20</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

1- "lower pile" - 1130
 2- "upper pile" - 1140
 3- " " " 1142
 4- " " " 1145
 1- 1qt glass - organics ext. p
 1- 1pt plastic - metals not R
(dupl. metals collected for IH)

**U.S. ENVIRONMENTAL PROTECTION D 0212
SURVEILLANCE AND ANALYSIS D**

REGION IV

ATHENS, GEORGIA

| | |
|---|--|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>37H-6</u> |
| ADDRESS <u>Memphis TN</u> | SAMPLING LOCATION <u>Effluent discharge</u> |
| CONTACT <u>Gene Cudde</u> | <u>Calvert Co. Rd 5.1000 ft</u> <u>below discharge (HIDOS) pipe</u> |

SAMPLE AND WASTE FLOW INFORMATION

WATER

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☐ _____ HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ _____ EQUIP. _____

COMPUTED FROM _____

SAMPLE COLLECTION

| SAD NO. | COMPOSITE | GRAB SAMPLES | SAMPLE CODE ^{L2} |
|--------------------------------|----------------------|--------------|---------------------------|
| DATE | <u>10/20/80</u> | | SACTERIAL 0 |
| TIME | <u>1420</u> | | BOD, COD, TOC 1 |
| FLOW () ^{L1} | | | CYANIDE 2 |
| TEMPERATURE °C | <u>25.0</u> | | METALS 3 |
| pH | <u>6.4</u> | | H ₂ P 4 |
| TOT. Cl ₂ RES. mg/l | | | ORG. ORG. PEST 5 |
| | | | PHENOLS 6 |
| | | | SOLIDS 7 |
| | | | |
| SAMPLE CODE | <u>see below</u> | | |
| SAMPLED BY (Sig) | <u>W. G. D. H.</u> | | |
| SEALED BY (Sig) | <u>W. G. D. H.</u> | | |
| DATE AND TIME | <u>10/20/80 1540</u> | | |
| | | | PRESERVED P |

^{L1} Use Avg. Flow for Composites and Inst. Flow for Grabs ^{L2} Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>B. G. D. H.</u> | <u>10/20/80</u> | <u>15:30</u> | <u>5</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

D - 0212

2 - 1 - 1 gal glass - organics

2 - 1 - 1 pt glass - metals

2 - 1 - VIAL - VOA

2 - 1 - 1/2 gal plastic - CN

2 - 1 - TOC

- metals dupl. collected for I H

**U.S. ENV. ONMENTAL PROTECTION AGENCY
SURVEILLANCE AND ANALYSIS DIVISION**

REGION IV

ATHENS, GEORGIA

| | |
|---|---|
| DISCHARGER <u>International Harvester</u> | SAMPLING STATION NO. <u>IH-7</u> |
| ADDRESS <u>Memphis, TN</u> | SAMPLING LOCATION <u>Effluent ditch @</u> |
| CONTACT <u>Gene Car Huff</u> | <u>Subvent @ field took 7:00 a.m.</u> |
| | <u>below NPET discharge pipe</u> |

SAMPLE AND WASTE FLOW INFORMATION

SAMPLE ☐ MUN. ☐ IND. ☐ INF. ☐ EFF. ☒ SEDIMENT ☐ HR. COMP. AT _____ MIN. INTERVALS ☐ FLOW PRO.

SAMPLER ☐ EPA ☐ DISCHARGER ☐ MAN. ☐ AUTO. ☐ TYPE _____

FLOW ☐ EPA ☐ DISCHARGER ☐ AVG. ☐ INST. ☐ EST. ☐ EQUIP _____

COMPUTED FROM _____

SAMPLE COLLECTION

| COMPOSITE | | GRAB SAMPLES | | SAMPLE CODE 12 | |
|--------------------------------|----|---------------|--|----------------|---|
| SAD NO. | | 0107 | | BACTERIAL | 0 |
| DATE | 11 | 10/20/82 | | BOD, COD, TOC | 1 |
| TIME | 11 | 1425 | | CYANIDE | 2 |
| FLOW () L | | | | METALS | 3 |
| TEMPERATURE °C | | | | N, P | 4 |
| pH | | | | ORG, O&G, PEST | 5 |
| TOT. Cl ₂ RES, mg/l | | | | PHENOLS | 6 |
| | | | | SOLIDS | 7 |
| | | | | | 8 |
| SAMPLE CODE | | See below | | | 9 |
| SAMPLED BY (Sig) | | JSH, CA, TLL | | | A |
| SEALED BY (Sig) | | CDP/24 | | | B |
| DATE AND TIME | | 10/20/82 1500 | | PRESERVED | P |

11 Use Avg. Flow for Composites and Inst. Flow for Grabs 12 Circle or Indicate Analysis and Enter Numerical Code

SAMPLE CUSTODY AND SHIPPING INFORMATION

| SAMPLES RELEASED TO (SIG) OR SHIPPED VIA | DATE | TIME | NO. CONT. | NO. CART. | RECEIPT NO. |
|--|-----------------|--------------|-----------|-----------|-------------|
| <u>Bob Gannon</u> | <u>10/20/82</u> | <u>15:30</u> | <u>2</u> | | |
| | | | | | |
| | | | | | |

REMARKS AND SKETCHES

VGA 12

1-1 qt glass - organic - evap. 2

1-.pt plastic - metals 2 (dupl. metals collected for IH)

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
ATHENS, GEORGIA 30613

DATE MAY 05 1981

SUBJECT Supplemental Report -- Hazardous Waste Site Investigation -- International Harvester Company -- Memphis, Tennessee

FROM Director, Surveillance and Analysis Division

TO Howard Zeller, Acting Director
Enforcement Division

Attached is a copy of the subject report. A copy of this report should be sent to:


Mr. Gene Cutrell, Plant Engineer
International Harvester
3003 Harvester Lane
Memphis, Tennessee 38127


Billy H. Adams/fm
James H. Finger

Attachment

cc: Wilburn
✓ Scarbrough/Mathis
Newton/Turnipseed
Adams
Carroll/Bennett
Carter/Lair
Hall/Till

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE





INTERNATIONAL HARVESTER
3003 HARVESTER AVENUE
MEMPHIS, TENNESSEE

I. Site Identification

- A. Name - International Harvester
- B. County - Shelby
- C. Nearest Urban Area - Memphis
- D. Water Supplies Potentially Affected
 - 1. Public - Not affected
 - 2. Private - Not affected
 - 3. Other
 - a) Drainage ditches on site empty towards the Mississippi River
 - b) The landfill lies in the floodplains of the Mississippi River and is not protected from possible floodwaters.
 - c) The site also drains into fields that grow soybeans and wheat.
- E. Acreage - 10 acres

II. Site History

- A. Owner - International Harvester Corp.
- B. Operator - International Harvester Corp., G. W. Beadles, Manager
- C. Hazardous Waste Data
 - 1. Source - International Harvester
 - 2. Volume - approximately 1000-2000 tons
 - 3. Types of Wastes - Wood, paper, foundry sand, glass, metal scraps, cardboard, trash, paint and paint sludge, washing machine sludge, oils, greases, coolants, wastewater treatment sludge, spent transformer oil, varnish, sealing compound, caustics and acids, electroplating treatment sludge and miscellaneous industrial solid waste
- D. Period of Operation - 1947 to present
- E. Current Status - Feasibility study for closure submitted to SWM Superfund.

III. Investigations

A. Sampling Data

On October 20-21, 1980, EPA conducted a hazardous waste site investigation. During this investigation five sediment or soil samples and two water samples were collected. Chromium and lead were below or slightly above drinking water limits in water, but were very high in sediment/soil; high levels of PCBs were found in all soil samples, and

moderate to low amounts of some extractable/purgeable organic compounds were also found in soil/sediment samples.

Although chromium and lead contamination may enter the Mississippi River, the flow of this river, 470,000 cu. ft/sec., is enough to dilute it. The metal, PCB and organic-contaminated soil may, however, be washed into adjacent fields, which grow food crops, and may also migrate in the event of flooding.

B. Other Investigating Work - None

C. Costs Incurred

| <u>Entity</u> | <u>Activity</u> | <u>Cost</u> |
|---------------|--------------------|-------------|
| EPA | Site Investigation | \$15,000 |

IV. Enforcement Action

1. TN

September 1, 1981 - (SWM & EPA) International Harvester informed that their landfill was out of compliance with the floodplain criteria and was on the EPA open dump inventory.

September 17, 1981 - March 17, 1982 - Extension granted for submittal of a feasibility study for correcting the floodplain problem. Feasibility study submitted March 17, 1982. International Harvester accepted recommendation to close the landfills but subsequently developed financial problems. SWM allowed sufficient time for them to recover financially before requiring closure.

May 6, 1983 (SWM) - Hazardous Waste inspection found no violations for hazardous waste generators.

November, 1983 SWM Superfund staff reviewed closure plan and developed recommendations.

2. EPA

October 20, 1980 - Conducted a hazardous waste site inspection.


October 23, 1981 - International Harvester informed of potential violations of RCRA.

3. Local - None

V. Remedial Action

| <u>Entity</u> | <u>Activity</u> | <u>Cost</u> |
|---------------|-----------------|-------------|
|---------------|-----------------|-------------|

None to date



LOCATION MAP
INTERNATIONAL HARVESTER

FIGURE 1
GENERAL LOCATION MAP
INTERNATIONAL HARVESTER COMPANY
MEMPHIS, TENNESSEE

